

KEY

Site ownership boundary

For detailed sections refer to drawings **252194-LPP-90-SW-L00-DSE-L-0100** series

Surfaces:
See detail drawing 252194-LPP-95-SW-L00-DET-L-0210
S01: Concrete paving as **Q25/315**
S02: Concrete paving as **Q25/316**
S03: Linear lighting feature
S04: Tactile paving as **Q25/320**
S05: Standard bitmac to MCC adoptable standards. See Curtins drawings for information.
S06: Scoutmoor Yorkstone - refer to Curtin's S278 information and Q25/311
Type S06a 50mm thick
Type S06b 75mm thick
S07: Concrete blister tactile paving see Curtin's drawing **061639-701** for details
S09: Existing Yorkstone surfacing to be retained as existing - refer to Curtin's S278 information
S10: Existing Yorkstone surfacing to be retained. To be lifted and re-laid where required to give even crossfall across entire width of footway see Curtin's drawing **061639-701** for details
S13: Loose gravel mulch to planting beds as **Q23/170**

Kerbs & edgings
K01: Existing wide Yorkstone kerb removed and replaced with BN2 kerb 50mm upstand.- refer to Curtin's S278 information
K02: Flush road kerb detail BN2 on Curtins' drawing **061639-702**
K03: Upstand kerb with 125mm upstand as HB2 detail on Curtins' drawing **061639-702**
K04: Steps: Concrete step units as **L37/315** and detail drawings **252194-LPP-95-SW-L00-DET-L-0210** & **252194-LPP-95-SW-L00-DET-L-0460/0461**
K05: Steel edging as **Q10/100**

Walls / Boundaries
W01: Low wall as **F21/120** and drawing **252194-LPP-95-SW-L00-DET-L-0400**
W02: Proposed wall to screen concrete ramp and balustrade to canal access as **F21/110** and drawing **252194-LPP-95-SW-L00-DET-L-0430**
W03: New wall to boundary of Princess Street as **F21/110** and **252194-LPP-95-SW-L00-DET-L-0430**
W04: Existing canal wall with existing stone base retained with new stone coping as detail drawing **252194-LPP-95-SW-L00-DET-L-0430**
W05: Existing canal wall retained with existing stone coping as detail drawing **252194-LPP-95-SW-L00-DET-L-0430**
W06: New retaining wall as detail drawing as **F21/110** and **252194-LPP-95-SW-L00-DET-L-0411**
B01: Glass balustrade as **L37/350** and detail drawing **252194-LPP-95-SW-L00-DET-L-0430 and 0431**
B02: Steel handrail to steps as **L37/150** and detail drawing **252194-LPP-95-SW-L00-DET-L-0460**
B03: Glazed gate to match balustrade as **L37/150**
B04: Steel railings as **L27/155**

Furniture / Structures:
F01: Stainless steel bollard as **Q50/190**
F03: Cycle hoops as **Q50/211**
F06: Tree planter bench as drawing **252194-LPP-95-SW-L00-DET-L-0441**
F07: Bench top to wall as **Q50/220** and detail drawing **252194-LPP-95-SW-L00-DET-L-0431**
F08: Feature boulders as **Q50/250**
For door protection bollards see drawing **252194-LPP-95-SW-L00-DPL-0014**

Lighting:
Proposed lighting: refer to drawing refer to detail drawing **252194-LPP-95-SW-L00-DET-L-0480** for details

Drainage:
Proposed drainage: refer to drawing **252194-LPP-52-SW-L00-DPL-L-0007** for details

Soft Landscape:
Proposed trees and planting to soft landscape: refer to drawing **252194-LPP-94-SW-L00-DPL-L-0020** for species details & **252194-LPP-95-SW-L00-DET-L-0470** for typical tree planting details

NOTES
1. For landscape specification refer to document: **252194-LPP-90-SW-L00-SSP-L-0600**

N

C11	RD	2021-04-14	Final Construction Issue
C10	RD	2020-10-06	Final Construction Issue
C9	RD	2020-02-17	Typos in annotations amended. Curtins' ref added
C8	RD	2020-02-12	Yorkstone channel to back edge Princess Street omitted
C7	RD	2020-01-13	S07 and S10 added.
C6	RD	2019-08-29	Updates in line with agreed VE 13-8-19
C5	RD	2019-05-15	Door swing protection added. Wall moved. Give Way markings shown on Venice Street
C4	RD	2019-05-08	Updates to annotations
C3	RD	2019-02-22	General updates and NBS clauses added to key
C2	RD	2018-10-02	Updates as latest drawings 0010 & 0011
C1	RD	2018-03-15	For Construction. Updates as drawing 0010 & 0011

© All information contained within this document remains copyright of Landscape Projects Ltd. and shall not be reproduced without prior consent.

(1) Do not scale from drawings - use written dimensions only. (2) All dimensions are in millimeters unless noted. (3) All dimensions shall be verified on site before proceeding with the work. (4) Landscape Projects shall be notified of any discrepancies. (5) Engineer to specify all sub-bases. Any below ground construction is indicative.

Project Title: **Manchester New Square**, Manchester			Drawing Title: **Landscape Proposal Plan** Ground Floor
Drawn Date: 2015-06-04	Drawn: RD	Checked: NCS	
Scale: 1:200 @ A1	Status: Final		Revision: **C11**

Drawing No.: **252194 | LPP | 90 | SW | L00 | DPL | L | 0001**

landscapeprojects
Landscape Architecture & Design
31 Blackfriars Road Salford Manchester M3 7AQ
PHONE: 0161 839 8336 FAX: 0161 839 7155
EMAIL: post@landscapeprojects.co.uk