

Project North Stand Manchester

Drainage Strategy

0053810-BHE-XX-XX-RP-X-0001

0053810

17 April 2023

Revision P01

Revision	Description	Issued by	Date	Checked
P01	Issued For Planning	AM	17/04/23	CM

https://burohappold.sharepoint.com/sites/053810/02_Documents/04_Reports/Civil Engineering Reports/20230309 Detailed Planning Report/230417 Project North Stand Manchester Drainage Strategy.docx

Report Disclaimer

This Report was prepared by Buro Happold Limited ("BH") for the sole benefit, use and information of Manchester City Football Club for submission for Planning. BH assumes no liability or responsibility for any reliance placed on this Report by any third party for any actions taken by any third party in reliance of the information contained herein. BH's responsibility regarding the contents of the Report shall be limited to the purpose for which the Report was produced and shall be subject to the express contract terms with Manchester City Football Club. The Report shall not be construed as investment or financial advice. The findings of this Report are based on the available information as set out in this Report.

author **Alex Mulroy**

date **17/04/2023**

approved **Chris Moore**

signature **Chris Moore**

Digitally signed by Chris Moore
DN: C=US,
E=Christopher.Moore@BuroHappold.com,
O=Buro Happold, OU=Infrastructure,
CN=Chris Moore
Location: Leeds
Reason: I am approving this document
Date: 2023.04.17 09:17:05+01'00'

date **17/04/2023**

Contents

1	Executive Summary	6
2	Introduction	7
2.1	Appointment and Brief	7
2.2	Limitations	7
3	Existing Site	8
3.1	Site Location and Description	8
3.2	Topography and Existing Levels	9
3.3	Geology	9
3.4	Flood Risk	9
3.5	Existing Drainage Regime	10
3.6	Watercourse	12
3.7	Local stakeholders and approving authorities	12
4	Proposed Development	13
5	Proposed Surface Water Drainage Strategy	14
5.1	Existing Site	14
5.2	Drainage Hierarchy	17
5.3	Climate Change	18
5.4	SuDS selection	18
	Permeable Paving	18
	Bioretention Systems	18
	Geocellular Storage System	18
	SuDs Operation and Maintenance Manual	18
5.5	Surface Water Drainage Network	19
5.6	Pollution Control	20
5.7	Designing for Exceedance	22
6	Proposed Foul Water Drainage Strategy	24
	Appendix A	26

Table of Tables

Table 3-1 Full Bore Pipe Analysis	15
Table 3-2 Attenuation Volumes	20
Table 5—3 Pollution Hazard Indices and Proposed Mitigation Methods	20
Table 5—4 Mitigation Indices of Proposed SuDS Components	2120

Table of Figures

Figure 1-1 Site Location Plan	8
Figure 1-2 Flood Map for Planning extract	9
Figure 1-3 Flood Risk from Surface Water Mapping Extract	10
Figure 2-1 Local Existing Public Sewer Network	11
Figure 2-2- Existing Impermeable Area	14
Figure 3-1 Pipe Catchment Plan	17

Glossary

Term	Definition
BH	Buro Happold
MCC	Manchester City Council
EA	Environmental Agency
UU	United Utilities
LLFA	Lead Local Flood Authority
BGS	British Geological Society
FRA	Flood Risk Assessment
SuDS	Sustainable Drainage Systems
DU	Discharge Unit
MH	Manhole
RWP	Rain Water Pipe

1 Executive Summary

Buro Happold has been instructed by Manchester City Football Club to prepare a stormwater drainage strategy in support of a detailed planning application to Manchester City Council (MCC) for the proposed Project North Stand Manchester development at the Etihad Campus

The drainage strategy has been undertaken in accordance with local and national standards, best practice and the requirements of MCC and United Utilities.

The site area is currently occupied by the existing club shop and city square open space, an existing car park associated with the Etihad Campus and existing hardstanding areas. The immediate surrounding area comprises mainly of the Etihad Campus including Sports infrastructure, the Metrolink Tram Line and Ashton Canal. The majority of the existing site is drained via an existing private drainage network which discharges into a public sewer in the north of the site.

The proposed development comprises of an expanded North Stand, an expanded and covered 'City Square' fan zone adjacent to the North Stand with associated food and drink facilities workspace, a new club shop, club museum and a hotel. A new vehicular access route is proposed from Alan Turing Way, to provide a drop-offpoint as required for the operation of the hotel.

The surface water drainage strategy will comprise a traditional gravity drainage network sized to convey flows from hardstanding areas and buildings to a geocellular storage tank, located in the northern area of the City Square, prior to being discharged offsite at an agreed allowable discharge rate. SuDS are incorporated into the landscape plan and used for water quality, conveyance and attenuation where possible.

The foul water drainage strategy will comprise a traditional gravity drainage network sized to convey flows from connection points within the hotel building, commercial building and expanded North Stand to a private onsite sewer. This existing private foul water network has been diverted as part of the site improvement works undertaken onsite but maintains its connection to the UU sewer in the north of the site.

2 Introduction

2.1 Appointment and Brief

Buro Happold has been instructed by Manchester City Football Club to prepare a stormwater drainage strategy in support of a detailed planning application to Manchester City Council (MCC) for the proposed Project North Stand Manchester development at the Etihad Campus, herein referred to as the site. This report is to be read in conjunction with the Buro Happold Flood Risk Assessment (FRA) and Structural and Ground Engineering Report also prepared in support of the planning application.

This report will review and document the following;

- Site constraints;
- Existing drainage regime; and
- Proposed surface and foul water drainage strategy.

The drainage strategy has been undertaken in accordance with local and national standards, best practice and the requirements of MCC and United Utilities.

2.2 Limitations

This report is based on the interpretation and assessment of data provided by third parties. It should be noted that the detailed design of the drainage and associated Sustainable Drainage Systems (SuDS) features for the site has not been finalised and the assumptions and information presented herein is subject to design development and outcomes from consultation with relative authorities. Operation and maintenance of all SuDS (including proprietary systems) will need to be considered once the proposed development has been finalised with all specific information being presented to those responsible for the maintenance of the facility. Buro Happold cannot be held responsible for the accuracy of third-party data or the conclusions that come from this information or as a result of changes arising from the developing design. The conclusions and findings of this report may change if the proposed development is amended or updated after the date of publishing.

3 Existing Site

3.1 Site Location and Description

The site is located within the Etihad Campus in the east of Manchester. It is approximately 3.5ha and is bordered by the Etihad Stadium to the south, the National Squash Centre to the west, the Metrolink Tram Line to the north and Alan Turing Way to the east.

The site area is currently occupied by the existing club shop and city square open space, an existing car park associated with the Etihad Campus and existing hardstanding areas. The immediate surrounding area comprises mainly of the Etihad Campus including Sports infrastructure, the Metrolink Tram Line and Ashton Canal. The majority of the existing site is drained via an existing private drainage network which discharges into separate foul and surface water sewers in the north of the site.

Figure 3-1 shows the boundary of the site and its relative location.



Figure 3-1 Site Location Plan

3.2 Topography and Existing Levels

The site is relatively flat. The highest point of the site is located in the eastern side of the site within the existing gravel car park with an approximate level of +62.64mAOD. The site slopes down towards the southwest to a low point adjacent to the Etihad Stadium at a level of approximate +60.44m AOD. The site levels reduce approximately 2.20m over a distance of approximately 150m (east to west); giving an average gradient of 1:75. Refer to **Appendix A** for Topographical survey.

3.3 Geology

British Geological Survey (BGS) England and Wales (Sheet No. 085 - Manchester, 1:50 000, 2011) and the BGS online geology (1:50,000) indicate the site is underlain by Made Ground over till deposits and the Pennine Upper Coal Measures Formation (mudstone, siltstone and sandstone).

Boreholes, undertaken as part of the ground investigation, shows that the ground make up in the area the attenuation tank consists of approximately 4.40m of made ground on top of clay. See **Appendix B** for borehole logs.

3.4 Flood Risk

The site is located entirely within Flood Zone 1 as designated by the Environment Agency (EA) and shown in Figure 3-2. The site is considered to be at low risk of flooding from rivers and the sea.




Figure 3-2 Flood Map for Planning extract

Multiple areas of the site are at risk from surface water flooding as per EA Flood Risk from Surface Water Mapping, as shown in Figure 3-3. These areas include the radial footway around the Etihad Stadium and the vehicular access to the

proposed development at Gibbon Street / Alan Turing Way. However, the vast majority of the flooding extents are considered low risk with an annual chance of occurring between 1 in 100 and 1 in 1000 in any given year.



Figure 3-3 Flood Risk from Surface Water Mapping Extract

Further information can be found in the accompanying Flood Risk Assessment (FRA) (see Environmental Statement Appendix 8.1).

3.5 Existing Drainage Regime

Record information obtained from UU (see Figure 3-4) indicates the following drainage systems are present in the vicinity of the site:

- 850mm diameter surface water sewer running east to west through the north of the site;
- 900mm diameter combined sewer running from south to north on the east side of the site;
- 375mm diameter concrete sewer running from south to north on the west side of the site; and
- 375mm diameter vitrified clay sewer running along the northern boundary of the site, and;
- 550mm x 950mm running along the northern boundary of the site.




Figure 3-4 Local Existing Public Sewer Network

Alignments shown in UU asset records conflict with onsite CCTV surveys in places. Discussions with UU regarding conflicting record information are ongoing.

3.5.1 Existing Private Foul Water Drainage

Foul water flows from the existing stadium and associated infrastructure drain via private drains running north, discharging into a UU sewer.

CCTV surveys indicate the following private foul water sewers are present within the site boundary:

1. A 225mm foul sewer running from the existing North Stand to the existing UU sewer in the north west of the site;
2. A 150mm foul sewer running from the north east of the site into the existing 225mm foul sewer (1) in the centre of the site;
3. A 150mm foul sewer running from toilets in the north west of the site into the existing 225mm foul sewer (1) in the south west of the site;

3.5.2 Existing Private Surface Water Drainage

Surface water flows from the existing stadium and associated infrastructure drain via private surface water drains running north, discharging into the UU Work 6 combined overflow sewer, ultimately discharging to the River Medlock west of the site.

CCTV surveys indicate the following private surface water sewers are present within the site boundary:

- 450mm and 600mm sewers convey flows from the stadium roof and adjacent hardstanding to a point outside the centre of the existing North Stand;
- A 600mm sewer conveys flows north to a 4m diameter manhole north east of the stadium shop, and onwards unrestricted to the United Utilities Works 6 overflow sewer.
- Other areas of hardstanding within the site boundary are drained to the 4m diameter manhole, and onwards unrestricted to the UU sewer, via private surface water sewers of varying diameters (150mm-750mm).

3.6 Watercourse

The nearest watercourses to the site are the Ashton Canal, approximately 35m to the north of the site and the River Medlock approximately 170m to the northwest which is designated as a Main River. The River Medlock is culverted below the car parks on the far side of Ashton canal to the north of the site.

3.7 Local stakeholders and approving authorities

With regard to development planning and permissions, and residual flood risk and drainage related matters, there are two principal stakeholders and/or approving authorities associated with the site. They are as follows:

Manchester City Council are the local governing planning authority and Lead Local Flood Authority (LLFA), having responsibility for:

- Leading the management of risk of flooding from ordinary watercourses, canals, ponds and reservoirs in its area; and
- Surface water flood risk in relation to planning applications, under The Flood and Water Management Act.

United Utilities (UU) are the statutory sewerage undertaker with powers under The Water Industry Act 1991.

Preliminary enquiries have been made to MCC and UU and are reported on herein. Consultation with the Environment Agency has not been deemed necessary as the site does not lie within a Groundwater Protection Zone and discharge is not to the ground or a main river. For further details, refer to the FRA submitted alongside this Drainage Strategy.

4 Proposed Development

The proposed development comprises of an expanded North Stand, an expanded and covered 'City Square' fan zone adjacent to the North Stand with associated food and drink facilities workspace, a new club shop and club museum, and a hotel. A new vehicular access route is proposed from Alan Turing Way, to provide a drop-off point as required for the operation of the hotel. See Figure 4-1 below for a plan of the proposed development.




Figure 4-1 Proposed Development

5 Proposed Surface Water Drainage Strategy

The proposed surface water strategy is presented within this section. It will set out the existing site catchments and the associated brownfield and greenfield runoff rates, the discharge methodology in line with the discharge hierarchy, the climate change allowances to be used within the drainage design, an explanation of the SuDS to be used onsite, where they will be located and how they will be utilised, a summary of the surface water strategy for the site, the water quality management design methods and calculations for the site and the exceedance flow strategy.

5.1 Existing Site

The existing site area measures 3.5ha. Approximately 2.46ha is positively drained hardstanding and buildings, of which 1.87ha is proposed to be modified by this project and 0.59ha is to remain unchanged.

An additional 0.91ha is a gravel car park with no positive drainage system and therefore considered greenfield land. The remaining 0.11ha is soft landscaping, consisting of steep grass banks leading down to the National Squash Centre and the Metrolink tram stop platform, and which likewise are to remain unchanged. These areas are shown in Figure 5-1 below.




Figure 5-1- Existing Surface Water Catchment Areas

The existing brownfield discharge rate for the positively drained hardstanding has been calculated using the modified rational method, where;

$$Q_{peak} = 2.78CIA$$

Q_{peak} = Peak runoff

C = Co-efficient $C = C_v * C_r$

C_v = Volumetric Co-efficient = 0.84

C_r = Routing Co-efficient = 1.3

I = Rainfall Intensity = 11.376mm/hr (60 min 1 in 1 year event)

A = Area = 1.87ha

$$Q_{peak} = 2.78 * 0.84 * 1.3 * 11.376 * 1.87$$

$$Q_{peak} = 64.6l/s$$

The runoff rate for the non-positively drained gravel car park (Q_{bar}) has been calculated as 5.9l/s. This was calculated at greenfield rates via the HR Wallingford Greenfield Runoff Rate Estimation tool. Please refer to **Appendix C** for the results.

It is considered the existing total runoff rate from site is therefore;

$$Q_{Tpeak} = 64.6 + 5.9 = 70.5l/s$$

As per the Manchester, Salford and Trafford Strategic Flood Risk Assessment new developments are to reduce brownfield runoff rates by 50%.

Therefore, the total allowable discharge rate from the site = 50% of positively drained hardstanding + Non-positively Drained Car Park Greenfield Rate;

$$Allowable Discharge Rate = \left(\frac{64.6}{2}\right) + 5.9 = 38.2l/s$$

However, even though the modified rational method provides a reasonable method of calculating flow it does not consider limitations on flow due to constraints such as pipe capacities. The limitation on this flow is calculated based upon the theoretical pipe full capacity of existing incoming connections from the site into the UU Sewerage Network, as shown in Table 5-1 below. See Figure 5-2 below for the Pipe Catchment Plan.

Table 5-1 Full Bore Pipe Analysis

Catchment	Area (m2)	Cum. Area (m2)	Flow (l/s)	Pipe Diameter	Capacity	Flows to	Flow Restricted
1	4017.53	4017.53	13.9	600	306	5	NO
2	545.02	545.02	1.9	225	40.4	10	NO
3	1278.56	1278.56	4.4	150	17.8	4	NO

4	1084.69	2363.25	8.2	300	71.2	8	NO
5	2940.9	6958.43	24.0	300	71.2	8	NO
6	2664.57	2664.57	9.2	600	306	8	NO
7	988.63	988.63	3.4	3x150	53.4	10	NO
8	540.14	14077.26	48.6	600	306	13	NO
9	1550.87	1550.87	5.4	300	71.2	8	NO
10	1277.2	2810.85	9.7	300	71.2	13	NO
11	1159.86	1159.86	4.0	150	17.8	13	NO
12	418.44	418.44	1.4	450	160.7	13	NO
13	239.85	18706.26	64.6	600	306	offsite	NO

The theoretical pipe full capacity check has been undertaken based on individual runs within the site and checking against cumulative area as the run progresses through the site. This check has shown that the flow discharging offsite is limited to 306l/s.

As shown within Table 5-1 it is not considered that the existing pipe sizes restrict the flow offsite. It is therefore proposed that the allowable Surface Water discharge rate is 38.2l/s.




Figure 5-2 Pipe Catchment Plan

5.2 Drainage Hierarchy

Planning guidance requires drainage strategies for new developments to discharge surface water in line with the following hierarchy:

1. Infiltration
2. Existing Watercourse
3. Existing sewer

Infiltration is not considered suitable on site due to the ground conditions identified within the ground investigation. Boreholes, undertaken as part of the ground investigation, shows that the ground make up in the area of the attenuation tank consists of approximately 4.40m of made ground on top of clay. This strategy has been agreed with United Utilities. See **Appendix B** for borehole logs.

There are no existing watercourses onsite to receive flows from the development. It is therefore proposed to utilise the existing surface water connection to the public UU overflow sewer, running east-west through the north of the site, which discharges into the River Medlock.

5.3 Climate Change

The stormwater network will ensure no flooding in the 1 in 100 year rainfall event. The site is modelled using FEH13 rainfall data.

In accordance with the Irwell Management Catchment peak rainfall allowance, for a 1% annual exceedance event, an uplift in rainfall intensity of 45% is proposed to account for the future effects of climate change across the lifespan of the development.

5.4 SuDS selection

The following Sustainable Drainage Systems (SuDS) are considered appropriate for the development.

Permeable Paving

Permeable paving provides a pavement suitable for pedestrian and/or vehicular traffic, while allowing rainfall to infiltrate through the surface and into the underlying structural layers. The water is temporarily stored beneath the overlying surface before being discharged downstream. As part of the Etihad North Stand development, permeable paving will be considered to provide conveyance, attenuation and water treatment within hardstanding areas across the development. Due to the relatively flat nature of the site the storage provided within the underlying structure can be used to reduce the required volume of the attenuation tank.

Bioretention Systems

Bioretention systems are shallow landscaped depressions that can reduce runoff rates and volumes and treat pollution through the use of engineered soils and vegetation. As part of the Etihad North Stand development, Bioretention systems will be considered as a collection and attenuation feature to provide water quality treatment for the car loop within the north east of the site.

Geocellular Storage System

Geocellular storage systems are modular plastic units with a high porosity (approx. 95%) that can be used to efficiently create a below ground structure for the temporary storage of surface water before controlled release. Due to the restricted external space and abundance of existing underground utilities within the site, geocellular storage structures will be the main form of attenuation.

SuDs Operation and Maintenance Manual

Regular maintenance of the sustainable drainage system is essential to maintain its performance. An Operation and Maintenance Manual will be prepared in accordance with the CIRIA guidance C753 section 32. This manual will be collated during the detailed design stage and will be included as part of the H&S File and Building Manual for the development. Maintenance will be in accordance with the specific requirements of each feature and the chosen attenuation supplier.

The Operation and Maintenance Manual will set out the location of all SuDS components on-site as well as a brief summary of their design intent, how the SuDS components work, their purpose and performance risks. It will also include

a maintenance plan and record pro forma, an explanation of the objectives of the maintenance proposed and the potential implications of not meeting those objectives.

It is currently understood that all drainage, including SuDS features, will remain within the ownership of the developer.

5.5 Surface Water Drainage Network

As there will be an increase in positively drained impermeable area within the site, there will be an increase in the likelihood and magnitude of standing water and surface water runoff occurring. The surface water strategy below has been devised to mitigate this and provide betterment to the existing surface water flows discharging from the site. Refer to drawing NSE-BHE-ZX-XX-DR-C-003101 in **Appendix D** for more details.

SuDS will be implemented within this development scheme. The conceptual SuDS strategy for the proposed development has been derived using the principles outlined within the CIRIA C753 SuDS Manual along with BS 8582:2013 – Code of Practice for Surface Water Management for Development Sites.

The scheme will utilise the existing topography and natural drainage catchments. Minor re-profiling of the site is proposed to direct surface water runoff away from proposed structures, however, it is expected the resultant flood flow paths will replicate the existing and direct exceedance flows to the stadium raceway to the south around the stadium.

The anticipated impermeable area of the catchment is based upon all redeveloped areas being utilised as hardstanding. With limited possibility of further hardstanding being implemented no allowance has been made for urban creep.

The proposed piped drainage system should be designed such that there is no surcharging in the 1 in 2 year probability event, and no flooding in the 1 in 30 year probability event. The piped system should be designed to Building Regulations Part H standards.

The surface water drainage strategy will comprise a traditional gravity drainage network sized to convey flows from hardstanding areas and buildings to a geocellular storage tank, located in the northern area of the City Square, prior to being discharged offsite at an agreed allowable discharge rate. Pipe gradients are set to achieve the self-cleansing velocity of 1m/s.

Porous paving will be used within the south of the site adjacent to the proposed north stand to provide attenuation, delay and mitigate the peak flood flows from the site, and offer treatment to the runoff. The porous paving will be supplemented with linear drainage and/or gullies to ensure all runoff is captured within the site boundary. The hardstanding will slope towards the linear drains with gullies located at low points where required.

The commercial roof, hotel roof and expanded north stand roof will discharge via multiple rain water pipes (RWPs). These RWPs will connect into the proposed gravity drainage network and be conveyed to the attenuation tank.

The drainage of the existing stadium roof retains the status quo as it drains into the existing drainage infrastructure within the Etihad Campus. The development of the site will not impact the discharge of the existing roof.

The hotel drop off will drain into a bioretention system within the adjacent green areas. The stadium raceway will be drained via permeable paving where possible. Where it is not possible to drain the onsite highways via SuDS, gullies and channel drains will be used to convey water directly into the gravity drainage network. A petrol interceptor may be required if it is not possible to treat all relevant areas of the site via SuDS.

The geocellular tank is sized based on 95% porosity and is designed to accommodate rainfall events up to and including the critical 1 in 100 year plus 45% allowance for climate change rainfall event (see Table 5-2 for required attenuation volumes). Hydraulic Calculations are available in **Appendix E**.

Table 5-2 Attenuation Volumes

Catchment	Catchment Area (ha)	Proposed Discharge Rate (l/s)	Approximate Total Volume (m ³)	Void Ratio
Etihad North Stand Development	2.480	38.2	1440	0.95

The surface water will discharge to an existing private manhole in the north of the site at a rate of 38.2l/s before being conveyed through the private network into a UU surface water sewer.

5.6 Pollution Control

The appropriateness of proposed SuDS for the proposed development has been evaluated based on the CIRIA SuDS Manual 2015 Simple Index Approach. The pollution hazard indices for different land uses within the proposed development have been taken from table 26.2 of the CIRIA SuDS Manual 2015 and pollution mitigation indices have been determined using table 26.3 of the CIRIA SuDS Manual 2015. The mitigation index must be equal to or exceed the pollution hazard index. Two components or more will be required if the mitigation index of an individual component is insufficient. As there will be reduced inflow concentrations for secondary or tertiary components a factor of 0.5 is used to account for this.

$$\begin{aligned} \text{Total SuDS mitigation index} &\geq \text{pollution hazard index} \\ (\text{for each contaminant type}) &\quad (\text{for each contaminant type}) \end{aligned}$$

$$\text{Total SuDS mitigation index} = \text{mitigation index}_1 + 0.5(\text{mitigation index}_2)$$

Where;

$$\text{mitigation index}_n = \text{mitigation index for component } n$$

Table 5—3 Pollution Hazard Indices and Proposed Mitigation Methods

Land Use	Pollution Hazard Level	Total Suspended Solids	Metals	Hydrocarbons
Residential roofs	Very low	0.2	0.2	0.05
Other roofs	Low	0.3	0.2	0.05
Individual property driveways	Low	0.5	0.4	0.4
Residential car parks	Low	0.5	0.4	0.4
Low traffic roads	Low	0.5	0.4	0.4
Commercial yard and delivery areas	Medium	0.7	0.6	0.7
Non-residential car parking with frequent change	Medium	0.7	0.6	0.7

Table 5—4 Mitigation Indices of Proposed SuDS Components

Type of SuDS	Mitigation Indices		
	TSS	Metals	Hydrocarbons
Porous Pavement	0.7	0.6	0.7
Bioretention System	0.8	0.8	0.8

To provide sufficient levels of treatment prior to discharge offsite appropriate water quality management design has been undertaken to satisfy Section 26 of the Ciria C753 SuDS Manual.

It is considered that the onsite hotel drop off will average less than 300 traffic movements per day. Table 26.2 of the Ciria C753 SuDS notes that pollution hazard levels for low traffic roads are as follows:

- TSS = 0.5;
- Metals = 0.4;
- Hydrocarbons = 0.4.

Treatment will be provided via a bioretention system which provide the following mitigation indices

- TSS = 0.8;
- Metals = 0.8;
- Hydrocarbons = 0.8.

It is considered that the stadium raceway will average less than 300 traffic movements per day. Table 26.2 of the Ciria C753 SuDS notes that pollution hazard levels for low traffic roads are as follows:

- TSS is 0.5;
- Metals is 0.4;
- Hydrocarbons is 0.4

Treatment will be provided via porous paving which provide the following mitigation indices

- TSS = 0.7;
- Metals = 0.6;
- Hydrocarbons = 0.7.

It is considered that the goods drop off to the east of the hotel will average less than 300 traffic movements per day. Table 26.2 of the Ciria C753 SuDS notes that pollution hazard levels for low traffic roads are as follows:

- TSS is 0.5;
- Metals is 0.4;
- Hydrocarbons is 0.4

Treatment will be provided via porous paving which provide the following mitigation indices

- TSS = 0.7;
- Metals = 0.6;
- Hydrocarbons = 0.7.

Each of the above is beyond the level of pollutants expected from the proposed usage therefore the use of the bioretention system and permeable paving will provide an adequate level of pre-treatment for the site where it can be applied. As stated in Section 5.5 it is envisaged a petrol interceptor may also be required if these SuDS cannot be implemented due to proposed levels or site constraints. A proprietary device, or devices, will be incorporated if appropriate based on the calculated mitigation indices.

The pollution hazard of the pedestrianised areas of the site and the stadium, commercial and hotel roofs have been considered. Due to the finish, treatment and design of the roofs and hardstanding it is not considered that metals or hydrocarbons will occur to a sufficient level to require treatment. It is considered that minor amounts of suspended solids will occur across the hardstanding and roofs, catchpit manholes are to be used across the site to capture and mitigate the occurrence of suspended solids.

5.7 Designing for Exceedance

The proposed site levels are designed to allow exceedance flow paths to safely convey overland surface water. Levels are designed to direct flows towards green areas or other areas where they will have no or limited impact. The scheme will utilize the existing topography and natural drainage catchments. Minor re-profiling of the site is proposed however the resultant flood flow paths will replicate the existing and direct flows flow paths onto the stadium raceway to the south.




Figure 5—3 Exceedance Flow Routes

6 Proposed Foul Water Drainage Strategy

A foul water strategy drawing, NSE-BHE-ZX-XX-DR-C-003102, has been prepared for the proposed development and can be found in **Appendix F**.

All internal and external areas of the site will be served by a private foul water network which will be designed in accordance with Part H of the Building Regulations.

The network will comprise a traditional gravity drainage network sized to convey flows from connection points within the hotel building, commercial building and expanded North Stand to a private onsite sewer. This existing private foul water network has been diverted as part of the site improvement works undertaken onsite but maintains its connection to the UU network in the north of the site.

Calculations have shown that the private network has the capacity to accept the additional flows. Please see foul water calculations in **Appendix E**.

Estimated Discharge Units (DUs) for these building have been provided by the public health engineer. These discharge units have been converted into a litre per second flow rate based on the expected frequency factor and have been used to inform communication with UU. Calculations are shown below:

$$Q_{peak} = K_{DU} \sqrt{DU}$$

Where:

- Q_{peak} = Peak Flow
- K_{DU} = Frequency Factor
 - 0.5 for Dwellings, Guest houses, offices (Intermittent use)
 - 0.7 for Hospitals, schools, restaurants, hotels (Frequent use)
 - 1 for Toilets open to the public (Congested Use)
 - 1.2 for Laboratory buildings (Special Use)
- DU = Discharge Units

A DU value of 109 was provided for the proposed commercial building. It is considered that there will be intermittent use of the public facilities in this building and therefore a frequency factor of 0.5 has been used.

$$\text{Commercial Building } Q_{peak} = K_{DU} \sqrt{DU}$$

$$\text{Commercial Building } Q_{peak} = 0.5 \sqrt{109} = 5.22 \text{ l/s}$$

A DU value of 1071 was provided for the proposed hotel. It is considered that there will be frequent use of the public facilities in this building and therefore a frequency factor of 0.7 has been used.

$$\text{Hotel } Q_{peak} = K_{DU} \sqrt{DU}$$

$$\text{Hotel } Q_{peak} = 0.7 \sqrt{1071} = 22.91 \text{ l/s}$$

A DU value of 287 was provided for the proposed North Stand. It is considered that there will be congested use of the public facilities in this building and therefore a frequency factor of 1.0 has been used.

$$\text{North Stand } Q_{peak} = K_{DU} \sqrt{DU}$$

$$\text{North Stand } Q_{peak} = 1.0\sqrt{287} = 16.94\text{l/s}$$

Based on the above calculations the total site discharge for the site is:

$$\text{Total Site Discharge} = 5.22\text{l/s} + 22.91\text{l/s} + 16.94\text{l/s} = 45.07\text{l/s}$$

The above calculations are considered industry standard for calculating total site; however, for this development it can be reasonably assumed that the individual buildings will not be concurrently discharging at peak flow and therefore the calculated total site discharge is likely to be conservative.

UU have agreed to accept flows from the site at an unrestricted rate to their network – refer to **Appendix G** for correspondence.

Appendix A Topographic Survey

Appendix B Borehole Logs



Key.

- Borehole
- Inspection Pit
- Observation Pit
- Trial Pit
- Window Sample

Notes:

Microsoft product screen shot(s) reprinted with permission from Microsoft Corporation

Centurion House, Olympus Park, Quedgeley,
Gloucester GL2 4NF
Telephone: (01452) 527743 Facsimile: (01452) 729314
E-mail: geotech@geoeng.co.uk
Web: www.geoeng.co.uk

Client:

CITY FOOTBALL GROUP LIMITED

Site:

ETIHAD GROUND INVESTIGATION

Title:

EXPLORATORY HOLE LOCATION PLAN

Drawn By:	AC	Checked By:	TH	Paper Size:	A3
Scale:	1:1000			Date:	February 2023
Contract:	37349			Figure:	1



APPENDIX A

FIELDWORK DATA

KEY TO EXPLORATORY HOLE LOGS



Sample type

D Small disturbed	U Undisturbed	L Dynamic	ES Environmental - soil	CS Core subsample (prepared)
B Bulk disturbed	UT Undisturbed thin wall	C Core	EW Environmental - water	LS Dynamic subsample (prepared)
LB Large bulk disturbed	P Piston	W Water		

Test type

S	SPT - Split spoon sampler followed by uncorrected SPT 'N' Value
C	SPT - Solid cone followed by uncorrected SPT 'N' Value
(*250 - Where full test drive not completed, linearly extrapolated 'N' value reported, ** - Denotes no effective penetration). Arrow length reflects test depth range.	
H	Hand vane - direct reading in kPa - not corrected for BS1377 (1990). Re* denotes refusal. Where the limit of the equipment is reached during a test, the reported value is the minimum recorded shear strength of the material.
M	Mackintosh probe - number of blows to achieve 100mm penetration
Mx	Mexco cone - average reading of equivalent CBR value in %
PP	Pocket penetrometer - calculated reading in kPa
Vo	Headspace vapour reading, uncorrected peak values in ppm, using a PID (calibrated with isobutylene, using a 10.6eV bulb)
TR	In situ thermal resistivity by needle probe in mK/W

Sample/core range/I_f

	Dynamic sample		Undisturbed sample - open drive including thin wall. Symbol length reflects recovery
--	----------------	--	--

x x = Total Core Recovery (TCR) as percentage of core run

y y = Solid Core Recovery (SCR) as percentage of core run. Assessment of core is based on full diameter

z z = Rock Quality Designation (RQD). The amount of solid core greater than 100mm expressed as percentage of core run

Where SPT has been carried out at the beginning of core run, disturbed section of core excluded from SCR and RQD assessment

I_f - fracture spacing - the modal fracture spacing (mm) over the indicated length of core. Where spacing varies significantly, the minimum, mode and maximum values are also given. NI = non-intact core NA = not applicable NR = no recovery

Instrumentation

	Porous tip		Perforated standpipe		Inclinometer		Extensometer
--	------------	--	----------------------	--	--------------	--	--------------

Backfill

	Granular response zone		Bentonite seal		Cement/bentonite grout		Soil backfill		Concrete	Cover	Raised cover		Stopcock cover
--	------------------------	--	----------------	--	------------------------	--	---------------	--	----------	--------------	--------------	--	----------------

Stratum boundaries

	Estimated boundary		Grading boundary
--	--------------------	--	------------------

Logging

The logging of soils and rocks has been carried out in general accordance with BS 5930:2015+A1:2020

Chalk is logged in general accordance with Lord et al (2002) CIRIA C574. Where possible, dynamic samples in chalk have been logged in accordance with CIRIA C574; descriptions and gradings (if presented) should be treated with caution given the potential for sample disturbance.

For rocks the term fracture has been used to identify a mechanical break within the core. Where possible incipient and drilling induced fractures have been excluded from the assessment of fracture state. Where doubt exists, a note has been made in the descriptions. All fractures are considered to be continuous unless otherwise reported.

Made Ground is readily identified when, within the natural make up, man made constituents are evident. Where Made Ground appears to be reworked natural material the differentiation between in situ natural deposits and Made Ground is much more difficult to ascertain. The interpretation of Made Ground within the logs should therefore be treated with caution.

The descriptors "topsoil" and "tarmacadam" are used as generic terms and do not imply conformation to any particular standard or composition.

Rootlets are defined as being less than 2mm in diameter, roots are defined as in excess of 2mm diameter.

General comments

The process of drilling and sampling will inevitably lead to sample disturbance, mixing or loss of material in some soil and rocks.

Indicated water levels are those recorded during the process of drilling or excavating exploratory holes and may not represent standing water levels.

All depths are measured along the axis of the borehole and are related to ground level at the point of entry. All inclinations are measured normal to the axis of the core.

Where provided, the stratigraphical names/geological rock units are for guidance only and may not be wholly accurate.

BOREHOLE LOG



BH22/02

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 1 of 8

Start Date 15 November 2022 Easting 386777

Scale 1:50

End Date 08 December 2022 Northing 398641 Ground Level 60.55mOD Depth 60.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
C	0.00 - 0.10						Vo 10.8	Black TARMAACADAM.	0.10	60.45	
1B	0.10 - 0.30							Light grey subangular and subrounded limestone COBBLES with some sandy fine to coarse gravel. Gravel is angular to subrounded fine to coarse limestone. (MADE GROUND)	0.30	60.25	
1ES	0.50 - 0.70						Vo 11.3				
2B	0.50 - 0.70							Greyish brown slightly clayey sandy locally very sandy angular to subrounded fine to coarse limestone and brick GRAVEL with a low subangular brick cobble content. (MADE GROUND)	1.20	59.35	
3D	0.50 - 0.70										
2ES	0.90 - 1.10						Vo 10.7				
4B	0.90 - 1.10										
5D	0.90 - 1.10										
6B	1.20 - 1.70						Vo 1.5	Firm greyish brown slightly sandy slightly gravelly CLAY with a low angular brick and concrete cobble content. Gravel is angular to subrounded fine to coarse brick and concrete. (MADE GROUND)			
3ES	1.50										
7D	2.00										
8B	2.00 - 2.50										
4ES	2.50	2.00					S 17	2.50m: Stiff.			
9D	2.50 - 2.95						Vo 1.1				
10B	2.50 - 2.95										
11D	3.00	3.00					S 13		3.00	57.55	
12D	3.00 - 3.45							Firm greyish brown locally mottled grey slightly sandy slightly gravelly CLAY. Gravel is angular and subangular fine and medium sandstone and coal.			
13B	3.00 - 3.45						Vo 0.6				
14UT	3.50 - 3.95										
5ES	3.50										
16D	4.00 - 4.45	4.00					S 14				
17B	4.00 - 4.45										
18UT	4.50 - 4.95	4.00									
19D	5.00	5.00					S 13				
20D	5.00 - 5.45										
21B	5.00 - 5.45										
22D	6.00	6.00									
23UT	6.00 - 6.45										
24B	6.50 - 7.00										
25D	7.00	7.00					S 18	7.00m: Becoming stiff.			
26D	7.00 - 7.45										
27B	7.00 - 7.45										
28D	8.00										

Continued Next Page

HOLE CONSTRUCTION

TOP (m)	BASE (m)	TYPE	PLANT USED
0.00	0.10	Rotary Core	Geotechnical Pioneer Rig
0.10	1.20	Inspection Pit	Hand Tools
1.20	14.00	Cable Percussion	Cable Percussion Rig

WATER STRIKE Groundwater not encountered prior to use of flush
DEPTH (m) CASING (m) ROSE TO (m) AFTER (min) REMARKS

CASING DEPTH		BARREL DIAMETER		BACKFILL			INSTRUMENTATION	
DIAM (mm)	BASE (m)	DIAM (mm)	BASE (m)	TOP (m)	BASE (m)	MATERIAL	DEPTH (m)	TYPE
200	13.50	300	0.10	0.00	0.50	Concrete	3.00	Standpipe (50mm)
168	24.00	200	14.00	0.50	0.60	Gravel	40.00	Standpipe (35mm) with geosock
140	60.00	128	14.20	0.60	0.90	Bentonite		
		146	60.00	0.90	3.10	Gravel		

HOLE PROGRESS

DATE TIME	DEPTH (m)	CASING (m)	WATER (m)
15-11-2022 07:00	0.00	Nil	
15-11-2022 17:00	0.10	Nil	Dry
17-11-2022 07:00	0.10	Nil	Dry
17-11-2022 17:00	1.20	Nil	1.15
22-11-2022 12:00	1.20	Nil	NR
22-11-2022 16:00	4.00	4.00	NR

REMARKS

Water flush used 14.20-15.00m. Polymer flush used 15.00-60.00m. Driller notes reduced flush returns (20%) 21.00-22.50m and 45.00-46.50m and (10%) 46.50-48.00m. Driller notes loss of flush returns 22.50-24.00m and 48.00-60.00m.

CONTRACT	CHECKED
37349	CT

BOREHOLE LOG



BH22/02

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 2 of 8

Start Date 15 November 2022 Easting 386777

Scale 1:50

End Date 08 December 2022 Northing 398641 Ground Level 60.55mOD Depth 60.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
29UT	8.00 - 8.45	8.00									
30B	8.50 - 9.00										
31D 32D 33B	9.00 9.00 - 9.45 9.00 - 9.45	9.00					S 23				
34D UT	10.00 10.00 - 10.45	10.00						Stiff grey slightly gravelly slightly sandy locally sandy silty CLAY. Gravel is subangular and subrounded fine to coarse siltstone, mudstone and sandstone.	10.00	50.55	
35D	10.30										
36B	10.50 - 11.00										
37D 38D	11.00 11.00 - 11.50										
39B	11.50 - 12.00										
40D 41D 42B	12.00 12.00 - 12.45 12.00 - 12.45	12.00					S 17				
43D 44UT	13.00 13.00 - 13.45	13.00						13.00 - 14.00m: Becoming very stiff. Rare thin and thick laminae of orangish brown fine and medium sand.			
45B	13.50 - 14.00										
46D 48L 49C	14.00 14.00 - 14.20 14.20 - 15.00	13.50 14.20	100	NA			S 42	Very stiff locally stiff brown slightly sandy locally sandy slightly gravelly CLAY. Gravel is angular to rounded fine and medium siltstone, mudstone, sandstone and rare limestone and quartzite.	14.00	46.55	
50D 51D 52C	14.90 - 15.00 15.00 - 15.40 15.00 - 16.50	14.20 15.00	100 0 0				S *60	15.00 - 15.50m: Gravel is fine to coarse. Extremely weak grey MUDSTONE with frequent thin laminae of grey siltstone. Frequently tending to very stiff fissured grey silty clay. Relict bedding fractures are subhorizontal to 10° extremely closely and very closely spaced planar rarely stepped smooth and 80° to subvertical planar smooth.	15.50	45.05	
53D	15.40 - 15.50			NI							

Continued Next Page

HOLE CONSTRUCTION

TOP (m) BASE (m) TYPE
 14.00 14.20 Windowless Sample
 14.20 60.00 Rotary Core

PLANT USED
 Geotechnical Pioneer Rig
 Geotechnical Pioneer Rig

WATER STRIKE Groundwater not encountered prior to use of flush
 DEPTH (m) CASING (m) ROSE TO (m) AFTER (min) REMARKS

CASING DEPTH

DIAM (mm) BASE (m)

BARREL DIAMETER

DIAM (mm) BASE (m)

BACKFILL

TOP (m) BASE (m) MATERIAL
 3.10 29.90 Bentonite
 29.90 40.00 Gravel
 40.00 60.00 Bentonite

INSTRUMENTATION

DEPTH (m) TYPE

HOLE PROGRESS

DATE TIME	DEPTH (m)	CASING (m)	WATER (m)
23-11-2022 07:00	4.00	4.00	NR
23-11-2022 12:00	9.00	9.00	NR
24-11-2022 07:00	9.00	9.00	NR
24-11-2022 14:30	14.00	13.50	NR
02-12-2022 10:30	14.00	13.50	Dry
02-12-2022 13:45	15.00	14.20	3.40

REMARKS

CONTRACT
37349

CHECKED
CT



BOREHOLE LOG



BH22/02

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 3 of 8

Start Date 15 November 2022 Easting 386777

Scale 1:50

End Date 08 December 2022 Northing 398641

Ground Level 60.55mOD

Depth 60.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
54D 55C	16.40 - 16.50 16.50 - 18.00	16.50	100 0 0								
56D 57C	18.00 - 18.13 18.00 - 19.50	18.00	100 63 37	NI 80 220			S *273	17.40 - 17.45m: Moderately weak thin bed of grey siltstone. Extremely weak to weak grey MUDSTONE with frequent extremely closely and very closely spaced thin laminae of siltstone. Bedding fractures are 10-20° extremely closely to medium spaced planar smooth and 80° to subvertical undulating and stepped smooth.	17.70	42.85	
58D 59D	18.60 - 18.70 18.80 - 18.90										
60C 61CS	19.50 - 21.00 19.50 - 19.72	19.50	100 53 26								
62D 63D 64C	20.90 - 21.00 21.00 - 21.45 21.00 - 22.50	21.00	85 23 0				S 11	21.00 - 21.70m: Disintegrated to clayey sandy angular fine to coarse gravel.			
65D	21.85 - 21.95			NI NI				Extremely weak black pyritic COAL recovered as angular fine to coarse gravel. Extremely weak to very weak grey, dark grey and black MUDSTONE disintegrated to very stiff sandy gravelly clay with rare coal gravel. Relict fractures are subhorizontal very closely to medium spaced planar smooth.	21.75 22.05	38.80 38.50	
66C 67D	22.50 - 24.00 22.90 - 23.00	22.50	100 0 0								
68D 69D	23.90 - 24.00 24.00 - 24.12	24.00					S *300	Very weak to moderately weak thinly laminated to thinly bedded grey MUDSTONE locally thinly interlaminated with siltstone. Bedding fractures are subhorizontal very closely to medium spaced planar and undulating smooth.	23.90	36.65	

Continued Next Page

HOLE CONSTRUCTION

TOP (m) BASE (m) TYPE

PLANT USED

WATER STRIKE Groundwater not encountered prior to use of flush
DEPTH (m) CASING (m) ROSE TO (m) AFTER (min) REMARKS

CASING DEPTH

DIAM (mm) BASE (m)

BARREL DIAMETER

DIAM (mm) BASE (m)

BACKFILL

TOP (m) BASE (m) MATERIAL

INSTRUMENTATION

DEPTH (m) TYPE

HOLE PROGRESS

DATE TIME	DEPTH (m)	CASING (m)	WATER (m)
05-12-2022 10:40	15.00	14.20	3.60
05-12-2022 17:40	22.50	22.50	Dry
06-12-2022 08:00	22.50	22.50	Dry
06-12-2022 17:10	34.50	34.50	0.90
07-12-2022 08:00	34.50	34.50	0.90
07-12-2022 17:15	52.50	52.50	22.00

REMARKS

CONTRACT
37349

CHECKED
CT

BOREHOLE LOG**BH22/02**

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 4 of 8

Start Date 15 November 2022 Easting 386777

Scale 1:50

End Date 08 December 2022 Northing 398641 Ground Level 60.55mOD Depth 60.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
70C	24.00 - 25.50		100 82 75	NI 100 300							
71D	24.90 - 25.00							24.75 - 24.85m: Disintegrated to angular medium and coarse gravel. 25.05 - 25.35m: Dark grey carbonaceous mudstone locally tending to extremely weak black coal.			
72C	25.50 - 27.00	25.50	80 100 100 100	90 140 760				25.70 - 26.45m: Fractures are widely spaced.			
73CS	26.55 - 26.80			140 170 300							
74C 75CS	27.00 - 28.50 27.00 - 27.50	27.00	93 93 74	570							
			50 100 240								
76C	28.50 - 30.00	28.50	100 52 27	NI 40 150				Weak dark grey and black carbonaceous MUDSTONE with medium spaced moderately weak thinly interbedded grey mudstone and siltstone and closely to widely spaced very thinly and thinly bedded extremely weak black coal frequently disintegrated to angular fine to coarse gravel. Fractures are 10-30° very closely to medium spaced planar rarely undulating and stepped smooth and 80° to subvertical planar smooth. (CHARLOTTE LOWER LEAF COAL SEAM). 28.90 - 29.20m: Non intact. Subvertical undulating smooth fracture.	28.50	32.05	
77CS	29.20 - 29.40			250 300							
78D 79C	29.90 - 30.00 30.00 - 31.50	30.00	NI 40 100 73 49								
80CS	31.00 - 31.30			NI 250 530				Weak locally extremely weak fossiliferous grey MUDSTONE. Bedding fractures are subhorizontal to 20° closely and medium spaced planar smooth.	30.85	29.70	
81D 82C	31.40 - 31.50 31.50 - 33.00	31.50	100 97 66								
Continued Next Page											

HOLE CONSTRUCTION

TOP (m) BASE (m) TYPE

PLANT USED

WATER STRIKE Groundwater not encountered prior to use of flush

DEPTH (m) CASING (m) ROSE TO (m) AFTER (min) REMARKS

CASING DEPTH

DIAM (mm) BASE (m)

BARREL DIAMETER

DIAM (mm) BASE (m)

BACKFILL

TOP (m) BASE (m) MATERIAL

INSTRUMENTATION

DEPTH (m) TYPE

HOLE PROGRESS

DATE TIME	DEPTH (m)	CASING (m)	WATER (m)
08-12-2022 08:15	52.50	52.50	19.70
08-12-2022 14:30	60.00	60.00	19.00

REMARKS

CONTRACT

37349

CHECKED

CT

BOREHOLE LOG



BH22/02

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 6 of 8

Start Date 15 November 2022 Easting 386777

Scale 1:50

End Date 08 December 2022 Northing 398641 Ground Level 60.55mOD Depth 60.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
98D 99C	40.40 - 40.50 40.50 - 42.00	40.50	90 76 63					40.15 - 40.35m: 80° planar smooth fracture.			
								40.80 - 40.90m: Locally gravel sized brown limestone.	41.00	19.55	
								40.95 - 41.50m: Subvertical to 80° undulating rough fracture.			
100CS	41.45 - 41.65			NI 250 360				Moderately weak thinly laminated to very thinly bedded grey SILTSTONE with extremely closely to closely spaced thinly and thickly interlaminated dark grey mudstone. Fractures are subhorizontal to 30° very closely to medium spaced planar rarely undulating smooth.			
101D 102C	41.90 - 42.00 42.00 - 43.50	42.00	93 83 73					42.00 - 42.40m: 50° undulating smooth fracture.			
103D	42.90 - 43.00										
104CS	43.23 - 43.50										
105C 106CS	43.50 - 45.00 43.60 - 43.95	43.50	100 91 84					43.50 - 44.15m: Mudstone is thinly laminated to medium bedded.			
								43.95 - 44.05m: 60° planar smooth fracture.	44.15	16.40	
107CS	44.25 - 44.50			130 270 290				Moderately weak thickly laminated to thinly bedded grey fine SANDSTONE with extremely closely and very closely spaced thinly and thickly laminated grey siltstone and rare thinly laminated mudstone. Laminae are subhorizontal to 10° planar rarely undulating smooth. Fractures are subhorizontal to 20° medium and widely spaced rarely very closely spaced planar smooth.			
108C	45.00 - 46.50	45.00	100 100 99	560							
109CS	46.10 - 46.50										
110C 111CS	46.50 - 48.00 46.50 - 47.00	46.50	93 66 46	470				Medium strong grey frequently stained reddish brown fine and medium SANDSTONE with rare thinly laminated black coal and mudstone. Fractures are 10-30° very closely and medium spaced planar smooth.	47.00	13.55	
								47.00 - 47.10m: Extremely closely and very closely spaced thinly interlaminated coal.			
								47.00 - 47.25m: 70° planar smooth locally rough fracture.			
								47.20 - 47.40m: Subvertical undulating smooth incipient fracture.			
								47.55 - 48.30m: Fractures are very closely and closely spaced with 70° to subvertical intersecting planar smooth fractures.			
112C	48.00 - 49.50	48.00									

Continued Next Page

HOLE CONSTRUCTION				WATER STRIKE Groundwater not encountered prior to use of flush			
TOP (m)	BASE (m)	TYPE	PLANT USED	DEPTH (m)	CASING (m)	ROSE TO (m)	AFTER (min) REMARKS

CASING DEPTH		BARREL DIAMETER		BACKFILL		INSTRUMENTATION	
DIAM (mm)	BASE (m)	DIAM (mm)	BASE (m)	TOP (m)	BASE (m) MATERIAL	DEPTH (m)	TYPE

HOLE PROGRESS				REMARKS				
DATE	TIME	DEPTH (m)	CASING (m)		WATER (m)			
					CONTRACT		CHECKED	
					37349		CT	

BOREHOLE LOG



BH22/02

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 7 of 8

Start Date 15 November 2022 Easting 386777

Scale 1:50

End Date 08 December 2022 Northing 398641 Ground Level 60.55mOD

Depth 60.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
113CS	49.10 - 49.50		100 85 70								
114C	49.50 - 51.00	49.50	100 85 71								
115CS	50.20 - 50.55		30 35 190 790					Moderately weak reddish brown fine and medium SANDSTONE with rare thinly laminated coal. Fractures are subhorizontal to 20° very closely to widely spaced planar smooth and 60-80° medium spaced planar smooth.	49.75	10.80	
116C	51.00 - 52.50	51.00	NI 120 160 100 85 83					50.80 - 51.10m: 80° to subvertical intersecting planar smooth fractures.			
117CS	51.86 - 52.17		770								
118C	52.50 - 54.00	52.50	NI 70 200 100 99 89					52.05 - 52.50m: Subvertical planar smooth incipient fracture.			
119CS	53.60 - 54.00		20 350 560					53.20 - 53.70m: Locally light grey.			
120C	54.00 - 55.50	54.00	53.70 - 54.25m: Light grey.								
121CS	55.30 - 55.43		100 79 25					Very weak to weak thickly laminated to medium bedded dark grey MUDSTONE with thinly interlaminated to very thinly interbedded greyish brown siltstone. Fractures are 5-20° very closely and closely spaced planar smooth. Bedding fractures are 5-20° extremely closely and very closely spaced planar smooth.	54.25	6.30	
122C	55.50 - 57.00	55.50	NI 20 120								
123D	55.50 - 55.60		90 46 32					Very weak dark grey carbonaceous MUDSTONE. Fractures are randomly orientated very closely and closely spaced planar polished.	55.50	5.05	

Continued Next Page

HOLE CONSTRUCTION				WATER STRIKE			
TOP (m)	BASE (m)	TYPE	PLANT USED	DEPTH (m)	CASING (m)	ROSE TO (m)	AFTER (min) REMARKS
							Groundwater not encountered prior to use of flush

CASING DEPTH		BARREL DIAMETER		BACKFILL		INSTRUMENTATION	
DIAM (mm)	BASE (m)	DIAM (mm)	BASE (m)	TOP (m)	BASE (m) MATERIAL	DEPTH (m)	TYPE

HOLE PROGRESS				REMARKS	AGS
DATE TIME	DEPTH (m)	CASING (m)	WATER (m)		
				CONTRACT	CHECKED
				37349	CT

BOREHOLE LOG



BH22/07

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 1 of 6

Start Date 15 November 2022 Easting 386804

Scale 1:50

End Date 19 December 2022 Northing 398696 Ground Level 61.00mOD Depth 45.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru-	test type & value	description	depth (m)	reduced level (m)	legend
C	0.00 - 0.10							Black TARMACADAM.	0.10	60.90	
1B	0.10 - 0.30						Vo 6.9	Light grey sandy angular to subrounded fine to coarse limestone and rare concrete GRAVEL. (MADE GROUND)	0.30	60.70	
2D	0.10 - 0.30						Vo 7.2	Greyish brown slightly clayey locally clayey very sandy angular and subangular fine to coarse brick, siltstone, limestone, concrete and rare tarmacadam GRAVEL with a low angular and subangular brick and concrete cobble content. (MADE GROUND)	1.15	59.85	
1ES	0.30 - 0.50						C 17	Firm to stiff dark grey and grey slightly sandy gravelly CLAY. Gravel is angular fine to coarse sandstone, brick and concrete. Strong hydrocarbon odour. (MADE GROUND)	2.00	59.00	
3B	0.30 - 0.50						Vo 3.0		2.30	58.70	
4D	0.30 - 0.50						C *200		2.40	58.60	
2ES	0.90 - 1.10						Vo 1.0	Brown clayey sandy angular to subrounded fine to coarse brick, concrete, sandstone, quartzite, mudstone and limestone GRAVEL. Faint hydrocarbon odour. (MADE GROUND)	2.80	58.20	
5B	0.90 - 1.10						Vo 3.0				
6D	0.90 - 1.10						S *67	Dark brownish grey locally dark grey and reddish brown slightly sandy angular to subrounded fine to coarse brick, limestone, quartzite and rare concrete GRAVEL. Faint hydrocarbon odour. (MADE GROUND)			
7B	1.20 - 1.65	Nil					S 34	Very stiff dark brownish grey slightly sandy gravelly clayey SILT. Gravel is angular to subrounded fine to coarse brick, quartzite and clinker. (MADE GROUND)			
3ES	1.50						S 10	Stiff becoming firm brown slightly sandy gravelly silty CLAY locally tending to clayey very sandy gravel. Gravel is angular to subrounded fine to coarse brick and quartzite. (MADE GROUND)			
8D	2.00	2.00					Vo 0.0				
9B	2.00 - 2.50	Nil					S 2	4.00 - 4.50m: Very soft slightly gravelly slightly sandy. Stiff becoming very stiff brown locally tending to dark brown slightly gravelly slightly sandy locally sandy silty CLAY. Gravel is angular to subrounded fine and medium sandstone, siltstone, mudstone and rare coal.			
10L	2.00 - 2.30						S 27				
4ES	2.10 - 2.20	2.30	100	NA			S 32				
11D	2.20 - 2.30	2.30	100	NA			S 24				
12C	2.30 - 2.50						S 24				
13D	2.40 - 2.50						S 24				
5ES	2.40						S 24				
14D	2.50 - 2.88	3.00					S 24				
15C	2.50 - 3.00						S 24				
6ES	2.80 - 3.00						S 24				
16D	3.00 - 3.45						S 24				
17L	3.00 - 3.50	3.50					S 24				
18D	3.50 - 3.95						S 24				
19L	3.50 - 4.00						S 24				
7ES	3.70 - 3.90						S 24				
20D	3.90 - 4.00	4.00					S 24				
21D	4.00 - 4.45						S 24				
22L	4.00 - 4.50						S 24				
23UT	4.50 - 4.95	4.50					S 24				
24D	4.95 - 5.05						S 24				
25D	5.05 - 5.10	4.50					S 24				
26D	5.10 - 5.55						S 24				
27L	5.10 - 6.00						S 24				
28D	5.20 - 5.30						S 24				
29D	5.90 - 6.00	4.50					S 24				
30D	6.00 - 6.45	6.00					S 24				
31L	6.00 - 6.60	6.00					S 24				
32D	6.60 - 7.05	6.00	100	NA			S 24				
33C	6.60 - 7.50	6.60					S 24				
34D	6.90 - 7.00						S 24				
35D	7.50 - 7.95	7.50	100				S 24				
36C	7.50 - 9.00						S 24				
37D	7.90 - 8.00						S 24				

Continued Next Page

HOLE CONSTRUCTION

TOP (m)	BASE (m)	TYPE	PLANT USED
0.00	0.10	Rotary Core	Geotechnical Pioneer Rig
0.10	1.20	Inspection Pit	Hand Tools
1.20	2.50	Cable Percussion	Cable Percussion Rig

WATER STRIKE Groundwater not encountered prior to use of flush
DEPTH (m) **CASING (m)** **ROSE TO (m)** **AFTER (min)** **REMARKS**

CASING DEPTH

DIAM (mm)	BASE (m)
200	3.00
168	14.00
140	45.00

BARREL DIAMETER

DIAM (mm)	BASE (m)
300	0.10
200	2.50
128	2.50
146	3.00

BACKFILL

TOP (m)	BASE (m)	MATERIAL
0.00	0.50	Concrete
0.50	0.60	Gravel
0.60	0.90	Bentonite
0.90	4.20	Gravel

INSTRUMENTATION

DEPTH (m)	TYPE
4.00	Standpipe (50mm)
40.00	Standpipe (35mm) with geosock

HOLE PROGRESS

DATE TIME	DEPTH (m)	CASING (m)	WATER (m)
15-11-2022 09:00	0.00	Nil	
15-11-2022 09:10	0.10	Nil	Dry
17-11-2022 15:50	0.10	Nil	Dry
17-11-2022 17:55	1.20	Nil	Dry
29-11-2022 12:00	1.20	Nil	NR
29-11-2022 14:00	2.50	2.50	NR

REMARKS

Partial collapse of borehole 2.50-2.00m prior to commencing dynamic sampling. Water flush used 2.30-3.00m. Polymer flush used 6.60-45.00m. Driller notes reduced flush returns (40%) 31.50-33.00m. Driller notes loss of flush returns 33.00-45.00m.



CONTRACT
37349

CHECKED
CT

BOREHOLE LOG



BH22/07

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 2 of 6

Start Date 15 November 2022 Easting 386804

Scale 1:50

End Date 19 December 2022

Northing 398696

Ground Level 61.00mOD

Depth 45.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
38D 39D 40C	8.90 - 9.00 9.00 - 9.45 9.00 - 10.50	9.00	100				S 26				
41D	9.90 - 10.00										
42D 43C	10.50 - 10.95 10.50 - 12.00	10.50	100				S 34				
44D	10.90 - 11.00										
45D 46D 47C	11.90 - 12.00 12.00 - 12.45 12.00 - 13.50	12.00	100				S 33				
48D	12.90 - 13.00										
49D 50C	13.50 - 13.95 13.50 - 15.00	13.50	100				S 44				
51D	14.50 - 14.60										
52D 53C	15.00 - 15.45 15.00 - 16.50	15.00	100				S 48				
54D	16.00 - 16.10							15.80 - 15.90m: Dark grey.			

Continued Next Page

HOLE CONSTRUCTION				WATER STRIKE			
TOP (m)	BASE (m)	TYPE	PLANT USED	DEPTH (m)	CASING (m)	ROSE TO (m)	AFTER (min)
2.00	2.30	Windowless Sample	Geotechnical Pioneer Rig				
2.30	3.00	Rotary Core	Geotechnical Pioneer Rig				
3.00	6.60	Windowless Sample	Geotechnical Pioneer Rig				

CASING DEPTH		BARREL DIAMETER		BACKFILL		INSTRUMENTATION	
DIAM (mm)	BASE (m)	DIAM (mm)	BASE (m)	TOP (m)	BASE (m)	DEPTH (m)	TYPE
		128	6.60	4.20	29.90		Bentonite
		146	45.00	29.90	40.00		Gravel
				40.00	45.00		Bentonite

HOLE PROGRESS				REMARKS	
DATE TIME	DEPTH (m)	CASING (m)	WATER (m)		
12-12-2022 13:50	2.00	Nil	0.90		
12-12-2022 17:20	3.00	3.00	0.20		
13-12-2022 08:15	3.00	3.00	0.40		
13-12-2022 17:15	13.50	13.50	1.10		
14-12-2022 14:20	13.50	13.50	0.40		
14-12-2022 17:45	19.50	19.50	0.70		

CONTRACT	CHECKED
37349	CT

BOREHOLE LOG**BH22/07**

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 3 of 6

Start Date 15 November 2022 Easting 386804

Scale 1:50

End Date 19 December 2022 Northing 398696 Ground Level 61.00mOD Depth 45.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
55D 56C	16.50 - 16.83 16.50 - 18.00	16.50	100 86 86	NI 840			S *136	Stiff becoming very stiff brown locally tending to dark brown slightly gravelly slightly sandy locally sandy silty CLAY. Gravel is angular to subrounded fine and medium sandstone, siltstone, mudstone and rare coal. 5.90 - 16.40m: Light bluish grey mottled light brown. Extremely weak thinly laminated light brownish grey MUDSTONE locally tending to very stiff slightly gravelly locally gravelly silty clay. Laminae are subhorizontal extremely closely spaced planar smooth. Bedding fractures are subhorizontal to 20° very closely and closely spaced planar smooth rarely stained brown. 16.70 - 17.55m: Fractures are widely spaced. 17.15 - 17.25m: 30° planar smooth lamination. 17.40 - 17.55m: Two very closely spaced thin beds of very weak brown and light reddish brown siltstone. Extremely weak to very weak thinly and thickly laminated grey locally dark grey MUDSTONE locally disintegrated to very stiff gravelly clay with medium spaced thin beds of light brown siltstone. Bedding fractures are subhorizontal to 20° closely and medium spaced planar smooth.	16.40	44.60	
57D 58C	17.90 - 18.00 18.00 - 19.50	18.00	100 90 87	NI 250 320					17.55	43.45	
59CS	19.02 - 19.27										
60C	19.50 - 21.00	19.50	100 60 50	NI 80 100				19.85 - 19.95m: Thin bed of weak grey mudstone. 20.40 - 21.00m: Fractures are widely spaced.			
61CS 62D 63D 64C	20.80 - 21.00 20.90 - 21.00 21.00 - 21.11 21.00 - 22.50	21.00	100 98 90	NI 60 150			S *429	Extremely weak to weak thinly interlaminated to thinly interbedded grey and light grey MUDSTONE and SILTSTONE. Bedding fractures are subhorizontal to 20° very closely and closely spaced planar and undulating smooth.	21.05	39.95	
65CS 66D 67D 68C 69CS	22.13 - 22.38 22.40 - 22.50 22.50 - 22.63 22.50 - 24.00 22.80 - 22.91	22.50	100 83 60	60 240 370			S *333	Very weak to weak locally moderately weak grey SILTSTONE with medium and widely spaced thin beds of thinly interlaminated mudstone. Fractures are subhorizontal to 20° very closely to medium spaced planar smooth. 23.00 - 23.10m: Subvertical planar smooth fracture. 23.40 - 23.80m: Fractures are 30-40° locally intersecting planar smooth.	22.60	38.40	
70D 71C	23.90 - 24.00 24.00 - 25.50	24.00						Continued Next Page			

HOLE CONSTRUCTIONTOP (m) BASE (m) TYPE
6.60 45.00 Rotary CorePLANT USED
Geotechnical Pioneer Rig**WATER STRIKE** Groundwater not encountered prior to use of flush
DEPTH (m) CASING (m) ROSE TO (m) AFTER (min) REMARKS**CASING DEPTH**

DIAM (mm) BASE (m)

BARREL DIAMETER

DIAM (mm) BASE (m)

BACKFILL

TOP (m) BASE (m) MATERIAL

INSTRUMENTATION

DEPTH (m) TYPE

HOLE PROGRESS

DATE TIME	DEPTH (m)	CASING (m)	WATER (m)
15-12-2022 08:00	19.50	19.50	0.60
15-12-2022 17:30	30.00	30.00	1.50
16-12-2022 08:15	30.00	30.00	18.90
16-12-2022 13:15	37.50	37.50	13.60
19-12-2022 10:00	37.50	37.50	20.65
19-12-2022 15:15	45.00	45.00	20.65

REMARKS
CONTRACT
37349
CHECKED
CT

BOREHOLE LOG



BH22/07

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 4 of 6

Start Date 15 November 2022 Easting 386804

Scale 1:50

End Date 19 December 2022 Northing 398696 Ground Level 61.00mOD Depth 45.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
72CS	25.15 - 25.43		100 86 81					24.70 - 24.85m: Extremely weak. 60° undulating rough fracture.			
73C 74CS	25.50 - 27.00 25.50 - 25.89	25.50	20 150 380					Weak to moderately weak thinly interlaminated to thinly interbedded light grey and grey fine SANDSTONE and SILTSTONE. Fractures are subhorizontal to 30° extremely closely to medium spaced planar smooth.	25.05	35.95	
75C	27.00 - 28.50	27.00	100 60 47					26.10 - 26.30m: 70° planar smooth fracture. 26.20 - 26.70m: Disintegrated to fine sand. 26.55 - 26.80m: 70° planar smooth fracture.			
76CS	28.26 - 28.50		NI								
77C 78CS	28.50 - 30.00 28.60 - 29.08	28.50	NI 200 380								
79C	30.00 - 31.50	30.00	100 93 82					27.40 - 28.15m: Stained brown and greyish brown. 27.45 - 28.05m: Fractures are 60-70° closely spaced planar smooth.			
80CS	30.81 - 31.03		55 250 410								
81C	31.50 - 33.00	31.50	NI 90 130					29.55 - 32.40m: Rare becoming frequent 60° planar smooth rarely incipient fractures frequently stained orangish brown.			
			100 61 59								
			NI 40 160					31.10 - 32.40m: Fractures are very closely spaced and intersecting.			
			100 40 29								

Continued Next Page

HOLE CONSTRUCTION				WATER STRIKE			
TOP (m)	BASE (m)	TYPE	PLANT USED	DEPTH (m)	CASING (m)	ROSE TO (m)	AFTER (min) REMARKS

CASING DEPTH		BARREL DIAMETER		BACKFILL		INSTRUMENTATION	
DIAM (mm)	BASE (m)	DIAM (mm)	BASE (m)	TOP (m)	BASE (m) MATERIAL	DEPTH (m)	TYPE

HOLE PROGRESS				REMARKS			
DATE	TIME	DEPTH (m)	CASING (m)	WATER (m)			

CONTRACT	CHECKED
37349	CT

BOREHOLE LOG



BH22/07

CLIENT CITY FOOTBALL GROUP LIMITED

SITE ETIHAD GROUND INVESTIGATION

Sheet 5 of 6

Start Date 15 November 2022 Easting 386804

Scale 1:50

End Date 19 December 2022 Northing 398696 Ground Level 61.00mOD Depth 45.00 m

sample no & type	sample depth (m) from to	casing depth (m)	samp. /core range	lf	water record depth (m)	instru- ment	test type & value	description	depth (m)	reduced level (m)	legend
82CS	32.40 - 32.80							32.40 - 33.80m: Sandstone is fine to coarse.			
83C	33.00 - 34.50	33.00	100	NI				32.80 - 33.00m: 60° planar smooth fracture stained orangish brown.			
84CS	33.00 - 33.40		54	80				33.00 - 33.80m: Fractures are widely spaced.			
			54	800				33.25m: Medium strong.			
				NI				Extremely weak to very weak thickly laminated grey and dark grey MUDSTONE. Bedding fractures are subhorizontal to 20° locally 50-70° extremely closely and very closely spaced planar smooth.	33.80	27.20	
85C	34.50 - 36.00	34.50	100	NI							
			52	60							
			0	140				Extremely weak to weak dark grey MUDSTONE frequently disintegrated to angular and subangular fine to coarse gravel with very closely to widely spaced thinly interlaminated to very thinly interbedded brownish grey siltstone. Fractures are subhorizontal to 30° very closely and closely spaced planar smooth rarely 80° to subvertical planar smooth.	35.35	25.65	
86D	35.90 - 36.00	36.00	100	NI				36.50 - 36.65m: Carbonaceous.			
87C	36.00 - 37.50		67	100				Extremely weak to very weak grey becoming light grey MUDSTONE frequently disintegrated to angular fine to coarse gravel. Bedding fractures are subhorizontal to 30° extremely closely to closely spaced planar and undulating smooth.	36.70	24.30	
			27	100							
88D	37.40 - 37.50	37.50	100	NI							
89C	37.50 - 39.00		41	110				Very weak dark grey carbonaceous MUDSTONE. Fractures are subhorizontal to 20° very closely and closely spaced planar smooth.	38.25	22.75	
			21	180				Very weak to weak grey locally fossiliferous MUDSTONE with extremely closely and very closely spaced thinly interlaminated grey siltstone. Fractures are 10-40° closely and medium spaced planar rough.	38.85	22.15	
90D	38.00 - 38.10			250				39.00 - 39.20m: Disintegrated to subangular fine to coarse gravel.			
				59				39.30 - 39.80m: 50° becoming subvertical undulating rough fracture intersecting with subvertical planar smooth fracture.			
91CS	38.70 - 38.81							Continued Next Page			
92C	39.00 - 40.50	39.00	100								

HOLE CONSTRUCTION				WATER STRIKE Groundwater not encountered prior to use of flush			
TOP (m)	BASE (m)	TYPE	PLANT USED	DEPTH (m)	CASING (m)	ROSE TO (m)	AFTER (min) REMARKS

CASING DEPTH		BARREL DIAMETER		BACKFILL		INSTRUMENTATION	
DIAM (mm)	BASE (m)	DIAM (mm)	BASE (m)	TOP (m)	BASE (m) MATERIAL	DEPTH (m)	TYPE

HOLE PROGRESS				REMARKS			
DATE	TIME	DEPTH (m)	CASING (m)	WATER (m)			
							AGS
							CONTRACT
							CHECKED
							37349
							CT



BH22/07

SITE ETIHAD GROUND INVESTIGATION

End Date	19 December 2022	Northing	398696	Ground Level	61.00mOD	Depth	45.00 m
----------	------------------	----------	--------	--------------	----------	-------	---------

HOLE PROGRESS				REMARKS
DATE TIME	DEPTH (m)	CASING (m)	WATER (m)	
				 CONTRACT 37349 CHECKED CT

Appendix C Greenfield Runoff Calculations

[Print](#)[Close Report](#)

Greenfield runoff rate estimation for sites

www.ukstds.com | Greenfield runoff tool

Calculated by:

Site name:

Site location:

Site Details

Latitude:

Longitude:

Reference:

Date:

This is an estimation of the greenfield runoff rates that are used to meet normal best practice criteria in line with Environment Agency guidance "Rainfall runoff management for developments", SC030219 (2013), the SuDS Manual C753 (Ciria, 2015) and the non-statutory standards for SuDS (Defra, 2015). This information on greenfield runoff rates may be the basis for setting consents for the drainage of surface water runoff from sites.

Runoff estimation approach

Site characteristics

Total site area (ha):

Methodology

Q_{BAR} estimation method:

SPR estimation method:

Soil characteristics

Default

Edited

SOIL type:

HOST class:

SPR/SPRHOST:

Hydrological characteristics

Default

Edited

SAAR (mm):

Hydrological region:

Growth curve factor 1 year:

Growth curve factor 30 years:

Growth curve factor 100 years:

Growth curve factor 200 years:

Notes

(1) Is Q_{BAR} < 2.0 l/s/ha?

When Q_{BAR} is < 2.0 l/s/ha then limiting discharge rates are set at 2.0 l/s/ha.

(2) Are flow rates < 5.0 l/s?

Where flow rates are less than 5.0 l/s consent for discharge is usually set at 5.0 l/s if blockage from vegetation and other materials is possible. Lower consent flow rates may be set where the blockage risk is addressed by using appropriate drainage elements.

(3) Is SPR/SPRHOST ≤ 0.3?

Where groundwater levels are low enough the use of soakaways to avoid discharge offsite would normally be preferred for disposal of surface water runoff.

Greenfield runoff rates

Default

Edited

Q_{BAR} (l/s):


1 in 1 year (l/s):

1 in 30 years (l/s):

1 in 100 year (l/s):

1 in 200 years (l/s):

Appendix D Surface Water Drainage Strategy



Appendix E Hydraulic Calculations

BuroHappold Ltd										Page 2	
Camden Mill Lower Bristol Road Bath					Project North Stand Manchester Surface Water Drainage Strategy						
Date 17/04/2023 File 230413 Etihad North Stan...					Designed by CRM Checked by NH						
Innovyze					Network 2020.1.3						
<u>Network Design Table for Surface Water Permanent</u>											
PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	68.557	0.415	165.0	0.152	15.00	0.0	0.600	o	225	Pipe/Conduit	
S1.001	23.171	0.140	165.0	0.059	0.00	0.0	0.600	o	225	Pipe/Conduit	
S2.000	17.217	0.455	37.8	0.013	15.00	0.0	0.600	o	225	Pipe/Conduit	
S3.000	24.049	0.146	164.7	0.022	15.00	0.0	0.600	o	225	Pipe/Conduit	
S3.001	23.013	0.139	165.0	0.072	0.00	0.0	0.600	o	225	Pipe/Conduit	
S3.002	10.847	0.045	240.0	0.027	0.00	0.0	0.600	o	300	Pipe/Conduit	
S3.003	11.661	0.049	240.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
S2.001	11.072	0.067	165.2	0.045	0.00	0.0	0.600	o	300	Pipe/Conduit	
S2.002	18.611	0.113	165.0	0.093	0.00	0.0	0.600	o	300	Pipe/Conduit	
S1.002	26.242	0.109	240.7	0.042	0.00	0.0	0.600	o	300	Pipe/Conduit	
S4.000	22.979	0.139	165.3	0.050	15.00	0.0	0.600	o	225	Pipe/Conduit	
S4.001	9.692	0.059	165.0	0.038	0.00	0.0	0.600	o	225	Pipe/Conduit	
S4.002	7.586	0.546	13.9	0.029	0.00	0.0	0.600	o	225	Pipe/Conduit	
S1.003	27.625	0.086	321.2	0.037	0.00	0.0	0.600	o	375	Pipe/Conduit	
<u>Network Results Table</u>											
PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	
S1.000	50.00	16.13	60.121	0.152	0.0	0.0	0.0	1.02	40.4	20.6	
S1.001	50.00	16.51	59.706	0.211	0.0	0.0	0.0	1.02	40.4	28.6	
S2.000	50.00	15.13	60.200	0.013	0.0	0.0	0.0	2.13	84.8	1.7	
S3.000	50.00	15.39	59.075	0.022	0.0	0.0	0.0	1.02	40.4	3.0	
S3.001	50.00	15.77	58.929	0.094	0.0	0.0	0.0	1.02	40.4	12.7	
S3.002	50.00	15.95	58.715	0.121	0.0	0.0	0.0	1.01	71.4	16.4	
S3.003	50.00	16.14	58.669	0.121	0.0	0.0	0.0	1.01	71.4	16.4	
S2.001	50.00	16.29	58.621	0.179	0.0	0.0	0.0	1.22	86.3	24.3	
S2.002	50.00	16.55	58.554	0.272	0.0	0.0	0.0	1.22	86.3	36.8	
S1.002	50.00	16.98	58.441	0.525	0.0	0.0	0.0	1.01	71.3	71.1	
S4.000	50.00	15.38	60.200	0.050	0.0	0.0	0.0	1.01	40.3	6.8	
S4.001	50.00	15.54	60.061	0.088	0.0	0.0	0.0	1.02	40.4	11.9	
S4.002	50.00	15.57	60.002	0.117	0.0	0.0	0.0	3.53	140.3	15.8	
S1.003	50.00	17.44	58.257	0.679	0.0	0.0	0.0	1.01	111.0	91.9	
©1982-2020 Innovyze											

BuroHappold Ltd		Page 4
Camden Mill Lower Bristol Road Bath	Project North Stand Manchester Surface Water Drainage Strategy	
Date 17/04/2023	Designed by CRM	
File 230413 Etihad North Stan...	Checked by NH	
Innovyze	Network 2020.1.3	

Network Design Table for Surface Water Permanent

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S8.000	23.127	0.140	165.2	0.027	15.00	0.0	0.600	o	225	Pipe/Conduit	
S8.001	30.370	0.184	165.1	0.043	0.00	0.0	0.600	o	225	Pipe/Conduit	
S8.002	22.252	0.093	240.0	0.022	0.00	0.0	0.600	o	300	Pipe/Conduit	
S8.003	26.866	0.112	240.0	0.037	0.00	0.0	0.600	o	300	Pipe/Conduit	
S8.004	22.928	0.096	240.0	0.065	0.00	0.0	0.600	o	300	Pipe/Conduit	
S8.005	10.250	0.032	320.3	0.046	0.00	0.0	0.600	o	375	Pipe/Conduit	
S8.006	12.199	0.038	321.0	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
S9.000	7.993	0.048	166.5	0.051	15.00	0.0	0.600	o	225	Pipe/Conduit	
S9.001	3.330	0.020	165.0	0.015	0.00	0.0	0.600	o	225	Pipe/Conduit	
S9.002	13.019	0.259	50.3	0.048	0.00	0.0	0.600	o	225	Pipe/Conduit	
S9.003	4.705	0.314	15.0	0.032	0.00	0.0	0.600	o	225	Pipe/Conduit	
S9.004	10.360	0.691	15.0	0.034	0.00	0.0	0.600	o	225	Pipe/Conduit	
S8.007	12.718	0.016	794.9	0.000	0.00	0.0	0.600	o	375	Pipe/Conduit	
S10.000	4.286	0.013	329.7	0.324	15.00	0.0	0.600	oo	400	Double Pipe	
S10.001	33.100	0.083	400.0	0.000	0.00	0.0	0.600	o	450	Pipe/Conduit	
S11.000	4.135	0.013	318.1	0.323	15.00	0.0	0.600	oo	400	Double Pipe	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	E I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S8.000	50.00	15.38	59.047	0.027	0.0	0.0	0.0	1.01	40.3	3.6
S8.001	50.00	15.88	58.907	0.069	0.0	0.0	0.0	1.01	40.4	9.4
S8.002	50.00	16.25	58.648	0.092	0.0	0.0	0.0	1.01	71.4	12.4
S8.003	50.00	16.69	58.555	0.128	0.0	0.0	0.0	1.01	71.4	17.4
S8.004	50.00	17.07	58.443	0.193	0.0	0.0	0.0	1.01	71.4	26.2
S8.005	50.00	17.24	58.273	0.239	0.0	0.0	0.0	1.01	111.2	32.4
S8.006	50.00	17.44	58.241	0.239	0.0	0.0	0.0	1.01	111.1	32.4
S9.000	50.00	15.13	60.250	0.051	0.0	0.0	0.0	1.01	40.2	6.8
S9.001	50.00	15.19	60.202	0.066	0.0	0.0	0.0	1.02	40.4	8.9
S9.002	50.00	15.30	60.182	0.113	0.0	0.0	0.0	1.85	73.5	15.4
S9.003	50.00	15.33	59.923	0.146	0.0	0.0	0.0	3.40	135.0	19.8
S9.004	50.00	15.38	59.609	0.180	0.0	0.0	0.0	3.40	135.0	24.3
S8.007	50.00	17.77	58.203	0.419	0.0	0.0	0.0	0.63	70.1	56.7
S10.000	50.00	15.07	59.110	0.324	0.0	0.0	0.0	1.03	259.8	43.8
S10.001	50.00	15.62	59.047	0.324	0.0	0.0	0.0	1.01	160.7	43.8
S11.000	50.00	15.07	59.110	0.323	0.0	0.0	0.0	1.05	264.6	43.7

BuroHappold Ltd										Page 6	
Camden Mill Lower Bristol Road Bath					Project North Stand Manchester Surface Water Drainage Strategy						
Date 17/04/2023 File 230413 Etihad North Stan...					Designed by CRM Checked by NH						
Innovyze Network 2020.1.3											
Manhole Schedules for Surface Water Permanent											
MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam.,L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)
S1	61.546	1.425	Open Manhole	1200	S1.000	60.121	225				
S2	61.477	1.771	Open Manhole	1200	S1.001	59.706	225	S1.000	59.706	225	
S3	61.050	0.850	Open Manhole	1200 x 900	S2.000	60.200	225				
S4	60.640	1.565	Open Manhole	1200	S3.000	59.075	225				
S5	60.734	1.805	Open Manhole	1200	S3.001	58.929	225	S3.000	58.929	225	
S6	60.638	1.923	Open Manhole	1200	S3.002	58.715	300	S3.001	58.790	225	
S7	60.959	2.290	Open Manhole	1200	S3.003	58.669	300	S3.002	58.669	300	
S8	60.990	2.369	Open Manhole	1200	S2.001	58.621	300	S2.000	59.745	225	1049
								S3.003	58.621	300	
S9	60.991	2.437	Open Manhole	1200	S2.002	58.554	300	S2.001	58.554	300	
S10	61.009	2.568	Open Manhole	1200	S1.002	58.441	300	S1.001	59.565	225	1049
								S2.002	58.441	300	
S11	61.050	0.850	Open Manhole	1200 x 900	S4.000	60.200	225				
S12	61.050	0.989	Open Manhole	1200 x 900	S4.001	60.061	225	S4.000	60.061	225	
S13	61.050	1.048	Open Manhole	1200 x 900	S4.002	60.002	225	S4.001	60.002	225	
S14	61.026	2.769	Open Manhole	1500	S1.003	58.257	375	S1.002	58.332	300	
								S4.002	59.456	225	1049
S15	61.022	2.926	Open Manhole	1500	S1.004	58.096	450	S1.003	58.171	375	
S16	61.136	1.478	Open Manhole	1200	S5.000	59.658	225				
S17	60.874	1.500	Open Manhole	1200	S5.001	59.374	300	S5.000	59.449	225	
S18	60.900	1.607	Open Manhole	1200	S5.002	59.293	300	S5.001	59.293	300	
S19	61.017	3.071	Open Manhole	1500	S1.005	57.946	525	S1.004	58.021	450	
								S5.002	59.219	300	1048
S20	61.014	3.082	Open Manhole	1500	S1.006	57.932	525	S1.005	57.932	525	
S21	61.017	3.125	Open Manhole	1500	S1.007	57.892	525	S1.006	57.892	525	
S22	61.050	3.255	Open Manhole	1500	S1.008	57.795	600	S1.007	57.870	525	
S23	61.050	0.850	Open Manhole	1200 x 900	S6.000	60.200	225				
S24	61.050	0.926	Open Manhole	1200 x 900	S6.001	60.124	225	S6.000	60.124	225	
S25	61.050	0.968	Open Manhole	1200 x 900	S6.002	60.082	225	S6.001	60.082	225	
S26	61.050	0.850	Open Manhole	1200 x 900	S7.000	60.200	225				
S27	61.050	1.214	Open Manhole	1200 x 900	S6.003	59.836	225	S6.002	59.843	225	7
								S7.000	59.836	225	
S28	61.050	1.425	Open Manhole	1200	S6.004	59.625	225	S6.003	59.625	225	
S29	60.600	1.553	Open Manhole	1200	S8.000	59.047	225				
©1982-2020 Innovyze											

BuroHappold Ltd									Page 7		
Camden Mill Lower Bristol Road Bath					Project North Stand Manchester Surface Water Drainage Strategy						
Date 17/04/2023 File 230413 Etihad North Stan...					Designed by CRM Checked by NH						
Innovyze					Network 2020.1.3						
<u>Manhole Schedules for Surface Water Permanent</u>											
MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)
S30	60.640	1.733	Open Manhole	1200	S8.001	58.907	225	S8.000	58.907	225	
S31	60.850	2.202	Open Manhole	1200	S8.002	58.648	300	S8.001	58.723	225	
S32	60.851	2.295	Open Manhole	1200	S8.003	58.555	300	S8.002	58.555	300	
S33	60.963	2.520	Open Manhole	1200	S8.004	58.443	300	S8.003	58.443	300	
S34	60.983	2.710	Open Manhole	1500	S8.005	58.273	375	S8.004	58.348	300	
S35	61.050	2.809	Open Manhole	1500	S8.006	58.241	375	S8.005	58.241	375	
S36	61.050	0.800	Open Manhole	1200 x 900	S9.000	60.250	225				
S37	61.050	0.848	Open Manhole	1200 x 900	S9.001	60.202	225	S9.000	60.202	225	
S38	61.050	0.868	Open Manhole	1200 x 900	S9.002	60.182	225	S9.001	60.182	225	
S39	61.050	1.127	Open Manhole	1200 x 900	S9.003	59.923	225	S9.002	59.923	225	
S40	61.050	1.441	Open Manhole	1200 x 900	S9.004	59.609	225	S9.003	59.609	225	
S41	61.050	2.847	Open Manhole	1500	S8.007	58.203	375	S8.006	58.203	375	
								S9.004	58.918	225	566
S42	60.800	1.690	Open Manhole	1800	S10.000	59.110	400				
S43	60.800	1.753	Open Manhole	1800	S10.001	59.047	450	S10.000	59.097	400	
S44	60.800	1.690	Open Manhole	1800	S11.000	59.110	400				
S45	60.800	1.753	Open Manhole	1800	S11.001	59.047	450	S11.000	59.097	400	
S46	60.702	1.828	Open Manhole	1500	S10.002	58.874	525	S10.001	58.964	450	16
								S11.001	58.949	450	
S47	61.050	2.297	Open Manhole	1500	S10.003	58.753	600	S10.002	58.828	525	
S48	61.050	4.350	Open Manhole	1500	S1.009	56.700	675	S1.008	57.785	600	1010
								S6.004	59.595	225	2445
								S8.007	58.187	375	1187
								S10.003	58.743	600	1968
S49	61.050	4.371	Open Manhole	1500	S1.010	56.679	675	S1.009	56.679	675	
S	61.050	4.394	Open Manhole	0		OUTFALL		S1.010	56.656	675	
MH Name Manhole Easting (m) Manhole Northing (m) Intersection Easting (m) Intersection Northing (m) Manhole Access Layout (North) S1 386964.618 398684.425 386964.618 398684.425 Required											
©1982-2020 Innovyze											

Project North Stand Manchester
Surface Water
Drainage Strategy



Designed by CRM

Checked by NH

Network 2020.1.3

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
S44	386743.125	398627.770	386743.125	398627.770	Required	
S45	386741.926	398631.728	386741.926	398631.728	Required	
S46	386779.690	398642.767	386779.690	398642.767	Required	
S47	386773.612	398664.239	386773.612	398664.239	Required	
S48	386770.549	398686.586	386770.549	398686.586	Required	
S49	386774.973	398699.725	386774.973	398699.725	Required	
S	386778.417	398704.120			No Entry	

BuroHappold Ltd		Page 14
Camden Mill Lower Bristol Road Bath	Project North Stand Manchester Surface Water Drainage Strategy	
Date 17/04/2023 File 230413 Etihad North Stan...	Designed by CRM Checked by NH	
Innovyze	Network 2020.1.3	

PIPELINE SCHEDULES for Surface Water Permanent

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S6.003	o	225	S27	61.050	59.836	0.989	Open Manhole	1200 x 900
S6.004	o	225	S28	61.050	59.625	1.200	Open Manhole	1200
S8.000	o	225	S29	60.600	59.047	1.328	Open Manhole	1200
S8.001	o	225	S30	60.640	58.907	1.508	Open Manhole	1200
S8.002	o	300	S31	60.850	58.648	1.902	Open Manhole	1200
S8.003	o	300	S32	60.851	58.555	1.995	Open Manhole	1200
S8.004	o	300	S33	60.963	58.443	2.220	Open Manhole	1200
S8.005	o	375	S34	60.983	58.273	2.335	Open Manhole	1500
S8.006	o	375	S35	61.050	58.241	2.434	Open Manhole	1500
S9.000	o	225	S36	61.050	60.250	0.575	Open Manhole	1200 x 900
S9.001	o	225	S37	61.050	60.202	0.623	Open Manhole	1200 x 900
S9.002	o	225	S38	61.050	60.182	0.643	Open Manhole	1200 x 900
S9.003	o	225	S39	61.050	59.923	0.902	Open Manhole	1200 x 900
S9.004	o	225	S40	61.050	59.609	1.216	Open Manhole	1200 x 900

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S6.003	6.043	28.6	S28	61.050	59.625	1.200	Open Manhole	1200
S6.004	13.202	435.7	S48	61.050	59.595	1.230	Open Manhole	1500
S8.000	23.127	165.2	S30	60.640	58.907	1.508	Open Manhole	1200
S8.001	30.370	165.1	S31	60.850	58.723	1.902	Open Manhole	1200
S8.002	22.252	240.0	S32	60.851	58.555	1.995	Open Manhole	1200
S8.003	26.866	240.0	S33	60.963	58.443	2.220	Open Manhole	1200
S8.004	22.928	240.0	S34	60.983	58.348	2.335	Open Manhole	1500
S8.005	10.250	320.3	S35	61.050	58.241	2.434	Open Manhole	1500
S8.006	12.199	321.0	S41	61.050	58.203	2.472	Open Manhole	1500
S9.000	7.993	166.5	S37	61.050	60.202	0.623	Open Manhole	1200 x 900
S9.001	3.330	165.0	S38	61.050	60.182	0.643	Open Manhole	1200 x 900
S9.002	13.019	50.3	S39	61.050	59.923	0.902	Open Manhole	1200 x 900
S9.003	4.705	15.0	S40	61.050	59.609	1.216	Open Manhole	1200 x 900
S9.004	10.360	15.0	S41	61.050	58.918	1.907	Open Manhole	1500

BuroHappold Ltd		Page 15
Camden Mill Lower Bristol Road Bath	Project North Stand Manchester Surface Water Drainage Strategy	
Date 17/04/2023	Designed by CRM	
File 230413 Etihad North Stan...	Checked by NH	
Innovyze	Network 2020.1.3	

PIPELINE SCHEDULES for Surface Water Permanent

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S8.007	o	375	S41	61.050	58.203	2.472	Open Manhole	1500
S10.000	oo	400	S42	60.800	59.110	1.290	Open Manhole	1800
S10.001	o	450	S43	60.800	59.047	1.303	Open Manhole	1800
S11.000	oo	400	S44	60.800	59.110	1.290	Open Manhole	1800
S11.001	o	450	S45	60.800	59.047	1.303	Open Manhole	1800
S10.002	o	525	S46	60.702	58.874	1.303	Open Manhole	1500
S10.003	o	600	S47	61.050	58.753	1.697	Open Manhole	1500
S1.009	o	675	S48	61.050	56.700	3.675	Open Manhole	1500
S1.010	o	675	S49	61.050	56.679	3.696	Open Manhole	1500

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S8.007	12.718	794.9	S48	61.050	58.187	2.488	Open Manhole	1500
S10.000	4.286	329.7	S43	60.800	59.097	1.303	Open Manhole	1800
S10.001	33.100	400.0	S46	60.702	58.964	1.288	Open Manhole	1500
S11.000	4.135	318.1	S45	60.800	59.097	1.303	Open Manhole	1800
S11.001	39.344	400.0	S46	60.702	58.949	1.303	Open Manhole	1500
S10.002	22.316	490.0	S47	61.050	58.828	1.697	Open Manhole	1500
S10.003	22.556	2210.5	S48	61.050	58.743	1.707	Open Manhole	1500
S1.009	13.864	660.2	S49	61.050	56.679	3.696	Open Manhole	1500
S1.010	5.584	240.0	S	61.050	56.656	3.719	Open Manhole	0

BuroHappold Ltd		Page 18
Camden Mill Lower Bristol Road Bath	Project North Stand Manchester Surface Water Drainage Strategy	
Date 17/04/2023 File 230413 Etihad North Stan...	Designed by CRM Checked by NH	
Innovyze	Network 2020.1.3	
Synthetic Rainfall Details Winter Storms No Cv (Summer) 0.750 Cv (Winter) 0.840 Storm Duration (mins) 30		
©1982-2020 Innovyze		

BuroHappold Ltd		Page 19					
Camden Mill	Project North Stand Manchester						
Lower Bristol Road	Surface Water						
Bath	Drainage Strategy						
Date 17/04/2023	Designed by CRM						
File 230413 Etihad North Stan...	Checked by NH						
Innovyze	Network 2020.1.3						
<u>Online Controls for Surface Water Permanent</u>							
<u>Hydro-Brake® Optimum Manhole: S48, DS/PN: S1.009, Volume (m³): 19.4</u>							
Unit Reference	MD-SHE-0232-3820-3100-3820						
Design Head (m)	3.100						
Design Flow (l/s)	38.2						
Flush-Flo™	Calculated						
Objective	Minimise upstream storage						
Application	Surface						
Sump Available	Yes						
Diameter (mm)	232						
Invert Level (m)	56.700						
Minimum Outlet Pipe Diameter (mm)	300						
Suggested Manhole Diameter (mm)	Site Specific Design (Contact Hydro International)						
Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)		
Design Point (Calculated)	3.100	38.1	Kick-Flo®	1.849	29.7		
Flush-Flo™	0.889	37.8	Mean Flow over Head Range	-	33.2		
The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated							
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	7.7	1.200	37.2	3.000	37.5	7.000	56.4
0.200	23.3	1.400	36.1	3.500	40.4	7.500	58.4
0.300	31.4	1.600	34.2	4.000	43.1	8.000	60.2
0.400	34.0	1.800	30.9	4.500	45.6	8.500	62.0
0.500	35.7	2.000	30.9	5.000	48.0	9.000	63.8
0.600	36.8	2.200	32.3	5.500	50.2	9.500	65.5
0.800	37.8	2.400	33.7	6.000	52.4		
1.000	37.8	2.600	35.0	6.500	54.4		
©1982-2020 Innovyze							

BuroHappold Ltd		Page 20																																																																														
Camden Mill Lower Bristol Road Bath	Project North Stand Manchester Surface Water Drainage Strategy																																																																															
Date 17/04/2023 File 230413 Etihad North Stan...	Designed by CRM Checked by NH																																																																															
Innovyze	Network 2020.1.3																																																																															
Storage Structures for Surface Water Permanent Porous Car Park Manhole: S4, DS/PN: S3.000 <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>20.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>20.0</td></tr><tr><td>Max Percolation (l/s)</td><td>111.1</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>60.200</td><td>Cap Volume Depth (m)</td><td>0.300</td></tr></table> Porous Car Park Manhole: S29, DS/PN: S8.000 <table><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Width (m)</td><td>20.0</td></tr><tr><td>Membrane Percolation (mm/hr)</td><td>1000</td><td>Length (m)</td><td>20.0</td></tr><tr><td>Max Percolation (l/s)</td><td>111.1</td><td>Slope (1:X)</td><td>0.0</td></tr><tr><td>Safety Factor</td><td>2.0</td><td>Depression Storage (mm)</td><td>5</td></tr><tr><td>Porosity</td><td>0.30</td><td>Evaporation (mm/day)</td><td>3</td></tr><tr><td>Invert Level (m)</td><td>60.200</td><td>Cap Volume Depth (m)</td><td>0.300</td></tr></table> Cellular Storage Manhole: S48, DS/PN: S1.009 <table><tr><td>Invert Level (m)</td><td>56.700</td><td>Safety Factor</td><td>2.0</td></tr><tr><td>Infiltration Coefficient Base (m/hr)</td><td>0.00000</td><td>Porosity</td><td>0.95</td></tr><tr><td>Infiltration Coefficient Side (m/hr)</td><td>0.00000</td><td></td><td></td></tr></table> <table><tr><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th><th>Depth (m)</th><th>Area (m²)</th><th>Inf. Area (m²)</th></tr><tr><td>0.000</td><td>650.0</td><td>0.0</td><td>2.301</td><td>0.0</td><td>0.0</td></tr><tr><td>2.300</td><td>650.0</td><td>0.0</td><td></td><td></td><td></td></tr></table>			Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	20.0	Membrane Percolation (mm/hr)	1000	Length (m)	20.0	Max Percolation (l/s)	111.1	Slope (1:X)	0.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	60.200	Cap Volume Depth (m)	0.300	Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	20.0	Membrane Percolation (mm/hr)	1000	Length (m)	20.0	Max Percolation (l/s)	111.1	Slope (1:X)	0.0	Safety Factor	2.0	Depression Storage (mm)	5	Porosity	0.30	Evaporation (mm/day)	3	Invert Level (m)	60.200	Cap Volume Depth (m)	0.300	Invert Level (m)	56.700	Safety Factor	2.0	Infiltration Coefficient Base (m/hr)	0.00000	Porosity	0.95	Infiltration Coefficient Side (m/hr)	0.00000			Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	0.000	650.0	0.0	2.301	0.0	0.0	2.300	650.0	0.0			
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	20.0																																																																													
Membrane Percolation (mm/hr)	1000	Length (m)	20.0																																																																													
Max Percolation (l/s)	111.1	Slope (1:X)	0.0																																																																													
Safety Factor	2.0	Depression Storage (mm)	5																																																																													
Porosity	0.30	Evaporation (mm/day)	3																																																																													
Invert Level (m)	60.200	Cap Volume Depth (m)	0.300																																																																													
Infiltration Coefficient Base (m/hr)	0.00000	Width (m)	20.0																																																																													
Membrane Percolation (mm/hr)	1000	Length (m)	20.0																																																																													
Max Percolation (l/s)	111.1	Slope (1:X)	0.0																																																																													
Safety Factor	2.0	Depression Storage (mm)	5																																																																													
Porosity	0.30	Evaporation (mm/day)	3																																																																													
Invert Level (m)	60.200	Cap Volume Depth (m)	0.300																																																																													
Invert Level (m)	56.700	Safety Factor	2.0																																																																													
Infiltration Coefficient Base (m/hr)	0.00000	Porosity	0.95																																																																													
Infiltration Coefficient Side (m/hr)	0.00000																																																																															
Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)																																																																											
0.000	650.0	0.0	2.301	0.0	0.0																																																																											
2.300	650.0	0.0																																																																														
©1982-2020 Innovyze																																																																																

BuroHappold Ltd		Page 21	
Camden Mill Lower Bristol Road Bath		Project North Stand Manchester Surface Water Drainage Strategy	
Date 17/04/2023		Designed by CRM	
File 230413 Etihad North Stan...		Checked by NH	
Innovyze		Network 2020.1.3	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for
Surface Water Permanent

Simulation Criteria

Areal Reduction Factor 1.000	Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0	MADD Factor * 10m ³ /ha Storage 2.000
Hot Start Level (mm) 0	Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500	Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000	

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
Number of Online Controls 1 Number of Storage Structures 3 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 386840 398863 SJ 86840 98863
Data Type	Point
Cv (Summer)	0.750
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm) 300.0

Analysis Timestep 2.5 Second Increment (Extended)

DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440

Return Period(s) (years) 2, 30, 100

Climate Change (%) 0, 0, 45

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.000	S1	30 Winter	2	+0%	100/15 Summer				60.208
S1.001	S2	30 Winter	2	+0%	100/15 Summer				59.813
S2.000	S3	30 Winter	2	+0%	100/15 Summer				60.214
S3.000	S4	120 Winter	2	+0%	30/15 Summer				59.100
S3.001	S5	15 Winter	2	+0%	30/15 Summer				59.005
S3.002	S6	15 Winter	2	+0%	30/15 Summer	100/15 Summer			58.811
S3.003	S7	15 Winter	2	+0%	30/15 Summer				58.767
S2.001	S8	15 Winter	2	+0%	30/15 Summer				58.733
S2.002	S9	15 Winter	2	+0%	30/15 Summer				58.697
S1.002	S10	15 Winter	2	+0%	30/15 Summer				58.647
S4.000	S11	30 Winter	2	+0%					60.250

©1982-2020 Innovyze

BuroHappold Ltd							Page 24		
Camden Mill Lower Bristol Road Bath				Project North Stand Manchester Surface Water Drainage Strategy					
Date 17/04/2023 File 230413 Etihad North Stan...				Designed by CRM Checked by NH					
Innovyze				Network 2020.1.3					
<u>2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Water Permanent</u>									
			</						

BuroHappold Ltd		Page 25	
Camden Mill Lower Bristol Road Bath		Project North Stand Manchester Surface Water Drainage Strategy	
Date 17/04/2023		Designed by CRM	
File 230413 Etihad North Stan...		Checked by NH	
Innovyze		Network 2020.1.3	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)

for Surface Water Permanent

Simulation Criteria

Areal Reduction Factor 1.000	Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0	MADD Factor * 10m³/ha Storage 2.000
Hot Start Level (mm) 0	Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500	Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000	

Number of Input Hydrographs 0	Number of Offline Controls 0	Number of Time/Area Diagrams 0
Number of Online Controls 1	Number of Storage Structures 3	Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location GB 386840 398863 SJ 86840 98863	
Data Type	Point
Cv (Summer)	0.750
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep 2.5 Second Increment (Extended)	
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440	
Return Period(s) (years) 2, 30, 100	
Climate Change (%) 0, 0, 45	

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.000	S1 30 Winter		30	+0%	100/15 Summer				60.264
S1.001	S2 15 Winter		30	+0%	100/15 Summer				59.921
S2.000	S3 30 Winter		30	+0%	100/15 Summer				60.226
S3.000	S4 15 Winter		30	+0%	30/15 Summer				59.430
S3.001	S5 15 Winter		30	+0%	30/15 Summer				59.431
S3.002	S6 15 Winter		30	+0%	30/15 Summer	100/15 Summer			59.396
S3.003	S7 15 Winter		30	+0%	30/15 Summer				59.374
S2.001	S8 15 Winter		30	+0%	30/15 Summer				59.351
S2.002	S9 15 Winter		30	+0%	30/15 Summer				59.261
S1.002	S10 15 Winter		30	+0%	30/15 Summer				59.163
S4.000	S11 30 Winter		30	+0%					60.277

©1982-2020 Innovyze

BuroHappold Ltd					Page 26			
Camden Mill Lower Bristol Road Bath				Project North Stand Manchester Surface Water Drainage Strategy				
Date 17/04/2023 File 230413 Etihad North Stan...				Designed by CRM Checked by NH				
Innovyze				Network 2020.1.3				
<u>30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Surface Water Permanent</u>								

BuroHappold Ltd			Page 29																																																																																											
Camden Mill Lower Bristol Road Bath		Project North Stand Manchester Surface Water Drainage Strategy																																																																																												
Date 17/04/2023 File 230413 Etihad North Stan...		Designed by CRM Checked by NH																																																																																												
Innovyze		Network 2020.1.3																																																																																												
<u>100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Surface Water Permanent</u>																																																																																														
<u>Simulation Criteria</u>																																																																																														
Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000																																																																																														
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000																																																																																														
Hot Start Level (mm) 0 Inlet Coefficient 0.800																																																																																														
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000																																																																																														
Foul Sewage per hectare (l/s) 0.000																																																																																														
Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0																																																																																														
Number of Online Controls 1 Number of Storage Structures 3 Number of Real Time Controls 0																																																																																														
<u>Synthetic Rainfall Details</u>																																																																																														
Rainfall Model FEH																																																																																														
FEH Rainfall Version 2013																																																																																														
Site Location GB 386840 398863 SJ 86840 98863																																																																																														
Data Type Point																																																																																														
Cv (Summer) 0.750																																																																																														
Cv (Winter) 0.840																																																																																														
Margin for Flood Risk Warning (mm) 300.0																																																																																														
Analysis Timestep 2.5 Second Increment (Extended)																																																																																														
DTS Status OFF																																																																																														
DVD Status ON																																																																																														
Inertia Status ON																																																																																														
Profile(s) Summer and Winter																																																																																														
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440																																																																																														
Return Period(s) (years) 2, 30, 100																																																																																														
Climate Change (%) 0, 0, 45																																																																																														
WARNING: Half Drain Time has not been calculated as the structure is too full.																																																																																														
<table><tr><th>PN</th><th>US/MH Name</th><th>Storm</th><th>Return Period</th><th>Climate Change</th><th>First (X) Surcharge</th><th>First (Y) Flood</th><th>First (Z) Overflow</th><th>Overflow Act.</th><th>Water Level (m)</th></tr><tr><td>S1.000</td><td>S1 30</td><td>Winter</td><td>100</td><td>+45%</td><td>100/15</td><td>Summer</td><td></td><td></td><td>61.532</td></tr><tr><td>S1.001</td><td>S2 15</td><td>Winter</td><td>100</td><td>+45%</td><td>100/15</td><td>Summer</td><td></td><td></td><td>60.957</td></tr><tr><td>S2.000</td><td>S3 15</td><td>Winter</td><td>100</td><td>+45%</td><td>100/15</td><td>Summer</td><td></td><td></td><td>60.753</td></tr><tr><td>S3.000</td><td>S4 30</td><td>Winter</td><td>100</td><td>+45%</td><td>30/15</td><td>Summer</td><td></td><td></td><td>60.335</td></tr><tr><td>S3.001</td><td>S5 15</td><td>Winter</td><td>100</td><td>+45%</td><td>30/15</td><td>Summer</td><td></td><td></td><td>60.624</td></tr><tr><td>S3.002</td><td>S6 15</td><td>Winter</td><td>100</td><td>+45%</td><td>30/15</td><td>Summer</td><td>100/15 Summer</td><td></td><td>60.640</td></tr><tr><td>S3.003</td><td>S7 15</td><td>Winter</td><td>100</td><td>+45%</td><td>30/15</td><td>Summer</td><td></td><td></td><td>60.689</td></tr><tr><td>S2.001</td><td>S8 15</td><td>Winter</td><td>100</td><td>+45%</td><td>30/15</td><td>Summer</td><td></td><td></td><td>60.742</td></tr></table>					PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)	S1.000	S1 30	Winter	100	+45%	100/15	Summer			61.532	S1.001	S2 15	Winter	100	+45%	100/15	Summer			60.957	S2.000	S3 15	Winter	100	+45%	100/15	Summer			60.753	S3.000	S4 30	Winter	100	+45%	30/15	Summer			60.335	S3.001	S5 15	Winter	100	+45%	30/15	Summer			60.624	S3.002	S6 15	Winter	100	+45%	30/15	Summer	100/15 Summer		60.640	S3.003	S7 15	Winter	100	+45%	30/15	Summer			60.689	S2.001	S8 15	Winter	100	+45%	30/15	Summer			60.742
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)																																																																																					
S1.000	S1 30	Winter	100	+45%	100/15	Summer			61.532																																																																																					
S1.001	S2 15	Winter	100	+45%	100/15	Summer			60.957																																																																																					
S2.000	S3 15	Winter	100	+45%	100/15	Summer			60.753																																																																																					
S3.000	S4 30	Winter	100	+45%	30/15	Summer			60.335																																																																																					
S3.001	S5 15	Winter	100	+45%	30/15	Summer			60.624																																																																																					
S3.002	S6 15	Winter	100	+45%	30/15	Summer	100/15 Summer		60.640																																																																																					
S3.003	S7 15	Winter	100	+45%	30/15	Summer			60.689																																																																																					
S2.001	S8 15	Winter	100	+45%	30/15	Summer			60.742																																																																																					
©1982-2020 Innovyze																																																																																														

BuroHappold Ltd										Page 1																																																																																																																																																																																																																									
Camden Mill Lower Bristol Road Bath					Project North Stand Manchester Foul Water Drainage Strategy																																																																																																																																																																																																																														
Date 17/04/2023					Designed by CRM																																																																																																																																																																																																																														
File 230413 Etihad North Stan...					Checked by NH																																																																																																																																																																																																																														
Innovyze					Network 2020.1.3																																																																																																																																																																																																																														
<u>FOUL SEWERAGE DESIGN</u> <u>Design Criteria for Foul Water Network</u> Pipe Sizes STANDARD Manhole Sizes STANDARD <table><tr><td>Industrial Flow (l/s/ha)</td><td>0.00</td><td>Add Flow / Climate Change (%)</td><td>0</td></tr><tr><td>Industrial Peak Flow Factor</td><td>0.00</td><td>Minimum Backdrop Height (m)</td><td>0.000</td></tr><tr><td>Calculation Method</td><td>EN 752</td><td>Maximum Backdrop Height (m)</td><td>0.000</td></tr><tr><td>Frequency Factor</td><td>1.00</td><td>Min Design Depth for Optimisation (m)</td><td>1.000</td></tr><tr><td>Domestic (l/s/ha)</td><td>0.00</td><td>Min Vel for Auto Design only (m/s)</td><td>0.75</td></tr><tr><td>Domestic Peak Flow Factor</td><td>6.00</td><td>Min Slope for Optimisation (1:X)</td><td>500</td></tr></table> Designed with Level Soffits												Industrial Flow (l/s/ha)	0.00	Add Flow / Climate Change (%)	0	Industrial Peak Flow Factor	0.00	Minimum Backdrop Height (m)	0.000	Calculation Method	EN 752	Maximum Backdrop Height (m)	0.000	Frequency Factor	1.00	Min Design Depth for Optimisation (m)	1.000	Domestic (l/s/ha)	0.00	Min Vel for Auto Design only (m/s)	0.75	Domestic Peak Flow Factor	6.00	Min Slope for Optimisation (1:X)	500																																																																																																																																																																																																
Industrial Flow (l/s/ha)	0.00	Add Flow / Climate Change (%)	0																																																																																																																																																																																																																																
Industrial Peak Flow Factor	0.00	Minimum Backdrop Height (m)	0.000																																																																																																																																																																																																																																
Calculation Method	EN 752	Maximum Backdrop Height (m)	0.000																																																																																																																																																																																																																																
Frequency Factor	1.00	Min Design Depth for Optimisation (m)	1.000																																																																																																																																																																																																																																
Domestic (l/s/ha)	0.00	Min Vel for Auto Design only (m/s)	0.75																																																																																																																																																																																																																																
Domestic Peak Flow Factor	6.00	Min Slope for Optimisation (1:X)	500																																																																																																																																																																																																																																
<u>Network Design Table for Foul Water Network</u> <table><tr><th>PN</th><th>Length (m)</th><th>Fall (m)</th><th>Slope (1:X)</th><th>Area (ha)</th><th>Freq Factor</th><th>Units</th><th>Base Flow (l/s)</th><th>k (mm)</th><th>HYD SECT</th><th>DIA (mm)</th><th>Section Type</th><th>Auto Design</th></tr><tr><td>F1.000</td><td>12.488</td><td>0.083</td><td>150.5</td><td>0.000</td><td>1.00</td><td>136.5</td><td>0.0</td><td>1.500</td><td>o</td><td>150</td><td>Pipe/Conduit</td><td></td></tr><tr><td>F2.000</td><td>6.826</td><td>0.171</td><td>40.0</td><td>0.000</td><td>1.00</td><td>0.0</td><td>0.0</td><td>1.500</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>F2.001</td><td>5.684</td><td>0.142</td><td>40.0</td><td>0.000</td><td>1.00</td><td>0.0</td><td>0.0</td><td>1.500</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>F2.002</td><td>4.327</td><td>0.054</td><td>80.0</td><td>0.000</td><td>1.00</td><td>28.5</td><td>0.0</td><td>1.500</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>F2.003</td><td>1.892</td><td>0.024</td><td>80.0</td><td>0.000</td><td>1.00</td><td>28.5</td><td>0.0</td><td>1.500</td><td>o</td><td>150</td><td>Pipe/Conduit</td><td></td></tr><tr><td>F3.000</td><td>8.801</td><td>0.390</td><td>22.6</td><td>0.000</td><td>1.00</td><td>0.0</td><td>0.0</td><td>1.500</td><td>o</td><td>100</td><td>Pipe/Conduit</td><td></td></tr><tr><td>F2.004</td><td>3.748</td><td>0.047</td><td>79.8</td><td>0.000</td><td>1.00</td><td>0.0</td><td>0.0</td><td>1.500</td><td>o</td><td>150</td><td>Pipe/Conduit</td><td></td></tr><tr><td>F2.005</td><td>6.610</td><td>0.083</td><td>79.6</td><td>0.000</td><td>1.00</td><td>0.0</td><td>0.0</td><td>1.500</td><td>o</td><td>150</td><td>Pipe/Conduit</td><td></td></tr></table> <u>Network Results Table</u> <table><tr><th>PN</th><th>US/IL (m)</th><th>Σ Area (ha)</th><th>Σ Base Flow (l/s)</th><th>Σ Units</th><th>Add Flow (l/s)</th><th>P.Dep (mm)</th><th>P.Vel (m/s)</th><th>Vel (m/s)</th><th>Cap (l/s)</th><th>Flow (l/s)</th></tr><tr><td>F1.000</td><td>58.728</td><td>0.000</td><td>0.0</td><td>136.5</td><td>0.0</td><td>114</td><td>0.81</td><td>0.71</td><td>12.6</td><td>11.7</td></tr><tr><td>F2.000</td><td>59.400</td><td>0.000</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0</td><td>0.00</td><td>1.05</td><td>8.3</td><td>0.0</td></tr><tr><td>F2.001</td><td>59.229</td><td>0.000</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0</td><td>0.00</td><td>1.05</td><td>8.3</td><td>0.0</td></tr><tr><td>F2.002</td><td>59.087</td><td>0.000</td><td>0.0</td><td>28.5</td><td>0.0</td><td>75</td><td>0.85</td><td>0.74</td><td>5.8</td><td>5.3</td></tr><tr><td>F2.003</td><td>58.983</td><td>0.000</td><td>0.0</td><td>57.0</td><td>0.0</td><td>69</td><td>0.95</td><td>0.98</td><td>17.3</td><td>7.5</td></tr><tr><td>F3.000</td><td>59.400</td><td>0.000</td><td>0.0</td><td>0.0</td><td>0.0</td><td>0</td><td>0.00</td><td>1.41</td><td>11.0</td><td>0.0</td></tr><tr><td>F2.004</td><td>58.960</td><td>0.000</td><td>0.0</td><td>57.0</td><td>0.0</td><td>69</td><td>0.95</td><td>0.98</td><td>17.3</td><td>7.5</td></tr><tr><td>F2.005</td><td>58.913</td><td>0.000</td><td>0.0</td><td>57.0</td><td>0.0</td><td>69</td><td>0.95</td><td>0.98</td><td>17.4</td><td>7.5</td></tr></table>												PN	Length (m)	Fall (m)	Slope (1:X)	Area (ha)	Freq Factor	Units	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design	F1.000	12.488	0.083	150.5	0.000	1.00	136.5	0.0	1.500	o	150	Pipe/Conduit		F2.000	6.826	0.171	40.0	0.000	1.00	0.0	0.0	1.500	o	100	Pipe/Conduit		F2.001	5.684	0.142	40.0	0.000	1.00	0.0	0.0	1.500	o	100	Pipe/Conduit		F2.002	4.327	0.054	80.0	0.000	1.00	28.5	0.0	1.500	o	100	Pipe/Conduit		F2.003	1.892	0.024	80.0	0.000	1.00	28.5	0.0	1.500	o	150	Pipe/Conduit		F3.000	8.801	0.390	22.6	0.000	1.00	0.0	0.0	1.500	o	100	Pipe/Conduit		F2.004	3.748	0.047	79.8	0.000	1.00	0.0	0.0	1.500	o	150	Pipe/Conduit		F2.005	6.610	0.083	79.6	0.000	1.00	0.0	0.0	1.500	o	150	Pipe/Conduit		PN	US/IL (m)	Σ Area (ha)	Σ Base Flow (l/s)	Σ Units	Add Flow (l/s)	P.Dep (mm)	P.Vel (m/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)	F1.000	58.728	0.000	0.0	136.5	0.0	114	0.81	0.71	12.6	11.7	F2.000	59.400	0.000	0.0	0.0	0.0	0	0.00	1.05	8.3	0.0	F2.001	59.229	0.000	0.0	0.0	0.0	0	0.00	1.05	8.3	0.0	F2.002	59.087	0.000	0.0	28.5	0.0	75	0.85	0.74	5.8	5.3	F2.003	58.983	0.000	0.0	57.0	0.0	69	0.95	0.98	17.3	7.5	F3.000	59.400	0.000	0.0	0.0	0.0	0	0.00	1.41	11.0	0.0	F2.004	58.960	0.000	0.0	57.0	0.0	69	0.95	0.98	17.3	7.5	F2.005	58.913	0.000	0.0	57.0	0.0	69	0.95	0.98	17.4	7.5
PN	Length (m)	Fall (m)	Slope (1:X)	Area (ha)	Freq Factor	Units	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design																																																																																																																																																																																																																							
F1.000	12.488	0.083	150.5	0.000	1.00	136.5	0.0	1.500	o	150	Pipe/Conduit																																																																																																																																																																																																																								
F2.000	6.826	0.171	40.0	0.000	1.00	0.0	0.0	1.500	o	100	Pipe/Conduit																																																																																																																																																																																																																								
F2.001	5.684	0.142	40.0	0.000	1.00	0.0	0.0	1.500	o	100	Pipe/Conduit																																																																																																																																																																																																																								
F2.002	4.327	0.054	80.0	0.000	1.00	28.5	0.0	1.500	o	100	Pipe/Conduit																																																																																																																																																																																																																								
F2.003	1.892	0.024	80.0	0.000	1.00	28.5	0.0	1.500	o	150	Pipe/Conduit																																																																																																																																																																																																																								
F3.000	8.801	0.390	22.6	0.000	1.00	0.0	0.0	1.500	o	100	Pipe/Conduit																																																																																																																																																																																																																								
F2.004	3.748	0.047	79.8	0.000	1.00	0.0	0.0	1.500	o	150	Pipe/Conduit																																																																																																																																																																																																																								
F2.005	6.610	0.083	79.6	0.000	1.00	0.0	0.0	1.500	o	150	Pipe/Conduit																																																																																																																																																																																																																								
PN	US/IL (m)	Σ Area (ha)	Σ Base Flow (l/s)	Σ Units	Add Flow (l/s)	P.Dep (mm)	P.Vel (m/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)																																																																																																																																																																																																																									
F1.000	58.728	0.000	0.0	136.5	0.0	114	0.81	0.71	12.6	11.7																																																																																																																																																																																																																									
F2.000	59.400	0.000	0.0	0.0	0.0	0	0.00	1.05	8.3	0.0																																																																																																																																																																																																																									
F2.001	59.229	0.000	0.0	0.0	0.0	0	0.00	1.05	8.3	0.0																																																																																																																																																																																																																									
F2.002	59.087	0.000	0.0	28.5	0.0	75	0.85	0.74	5.8	5.3																																																																																																																																																																																																																									
F2.003	58.983	0.000	0.0	57.0	0.0	69	0.95	0.98	17.3	7.5																																																																																																																																																																																																																									
F3.000	59.400	0.000	0.0	0.0	0.0	0	0.00	1.41	11.0	0.0																																																																																																																																																																																																																									
F2.004	58.960	0.000	0.0	57.0	0.0	69	0.95	0.98	17.3	7.5																																																																																																																																																																																																																									
F2.005	58.913	0.000	0.0	57.0	0.0	69	0.95	0.98	17.4	7.5																																																																																																																																																																																																																									
©1982-2020 Innovyze																																																																																																																																																																																																																																			

BuroHappold Ltd												Page 4	
Camden Mill Lower Bristol Road Bath						Project North Stand Manchester Foul Water Drainage Strategy							
Date 17/04/2023						Designed by CRM							
File 230413 Etihad North Stan...						Checked by NH							
Innovyze						Network 2020.1.3							
Network Design Table for Foul Water Network													
PN	Length (m)	Fall (m)	Slope (1:X)	Area (ha)	Freq Factor	Units	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section	Type	Auto Design
F12.000	2.399	0.060	40.0	0.000	0.70	85.0	0.0	1.500	o	100	Pipe/Conduit		
F12.001	14.437	0.361	40.0	0.000	0.70	85.0	0.0	1.500	o	150	Pipe/Conduit		
F12.002	12.724	0.318	40.0	0.000	0.70	85.0	0.0	1.500	o	150	Pipe/Conduit		
F12.003	9.687	0.242	40.0	0.000	0.70	80.0	0.0	1.500	o	150	Pipe/Conduit		
F12.004	11.016	0.275	40.0	0.000	0.70	80.0	0.0	1.500	o	150	Pipe/Conduit		
F12.005	18.013	0.450	40.0	0.000	0.70	80.0	0.0	1.500	o	150	Pipe/Conduit		
F12.006	8.418	0.210	40.0	0.000	0.70	80.0	0.0	1.500	o	150	Pipe/Conduit		
F1.005	14.229	0.119	120.0	0.000	1.00	0.0	0.0	1.500	o	225	Pipe/Conduit		
F1.006	15.927	0.133	120.0	0.000	1.00	0.0	0.0	1.500	o	225	Pipe/Conduit		
F13.000	5.286	0.132	40.0	0.000	0.70	85.0	0.0	1.500	o	100	Pipe/Conduit		
F13.001	10.487	0.262	40.0	0.000	0.70	80.0	0.0	1.500	o	150	Pipe/Conduit		
F13.002	6.012	0.150	40.0	0.000	0.70	85.0	0.0	1.500	o	150	Pipe/Conduit		
F13.003	6.530	0.163	40.0	0.000	0.70	80.0	0.0	1.500	o	150	Pipe/Conduit		
F13.004	7.220	0.181	40.0	0.000	0.70	85.0	0.0	1.500	o	150	Pipe/Conduit		
F13.005	6.476	0.162	40.0	0.000	0.70	81.0	0.0	1.500	o	150	Pipe/Conduit		
F1.007	25.774	0.368	70.0	0.000	1.00	0.0	0.0	1.500	o	225	Pipe/Conduit		
Network Results Table													
PN	US/IL (m)	Σ Area (ha)	Σ Base Flow (l/s)	Σ Units	Add Flow (l/s)	P.Dep (mm)	P.Vel (m/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)			
F12.000	60.288	0.000	0.0	85.0	0.0	66	1.17	1.05	8.3	6.5			
F12.001	60.178	0.000	0.0	170.0	0.0	63	1.28	1.39	24.5	9.1			
F12.002	59.817	0.000	0.0	255.0	0.0	71	1.35	1.39	24.5	11.2			
F12.003	59.499	0.000	0.0	335.0	0.0	77	1.40	1.39	24.5	12.8			
F12.004	59.257	0.000	0.0	415.0	0.0	82	1.44	1.39	24.5	14.3			
F12.005	58.981	0.000	0.0	495.0	0.0	87	1.47	1.39	24.5	15.6			
F12.006	58.531	0.000	0.0	575.0	0.0	91	1.50	1.39	24.5	16.8			
F1.005	57.837	0.000	0.0	862.0	0.0	122	1.08	1.05	41.6	23.8			
F1.006	57.719	0.000	0.0	862.0	0.0	122	1.08	1.05	41.6	23.8			
F13.000	59.793	0.000	0.0	85.0	0.0	66	1.17	1.05	8.3	6.5			
F13.001	59.611	0.000	0.0	165.0	0.0	63	1.28	1.39	24.5	9.0			
F13.002	59.349	0.000	0.0	250.0	0.0	71	1.35	1.39	24.5	11.1			
F13.003	59.198	0.000	0.0	330.0	0.0	77	1.40	1.39	24.5	12.7			
F13.004	59.035	0.000	0.0	415.0	0.0	82	1.44	1.39	24.5	14.3			
F13.005	58.855	0.000	0.0	496.0	0.0	87	1.47	1.39	24.5	15.6			
F1.007	57.586	0.000	0.0	1358.0	0.0	115	1.39	1.37	54.6	28.5			
©1982-2020 Innovyze													

BuroHappold Ltd										Page 6	
Camden Mill Lower Bristol Road Bath					Project North Stand Manchester Foul Water Drainage Strategy						
Date 17/04/2023					Designed by CRM						
File 230413 Etihad North Stan...					Checked by NH						
Innovyze					Network 2020.1.3						
<u>Manhole Schedules for Foul Water Network</u>											
MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam.,L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	
F1	60.650	1.922	Open Manhole	1200	F1.000	58.728	150				
F2	60.650	1.250	Open Manhole	1200	F2.000	59.400	100				
F3	60.650	1.421	Open Manhole	1200	F2.001	59.229	100	F2.000	59.229	100	
F4	60.650	1.563	Open Manhole	1200	F2.002	59.087	100	F2.001	59.087	100	
F5	60.650	1.667	Open Manhole	1200	F2.003	58.983	150	F2.002	59.033	100	
F6	60.650	1.250	Open Manhole	1200	F3.000	59.400	100				
F7	60.650	1.690	Open Manhole	1200	F2.004	58.960	150	F2.003	58.960	100	
								F3.000	59.010	100	
F8	60.650	1.737	Open Manhole	1200	F2.005	58.913	150	F2.004	58.913	100	
F9	60.650	1.820	Open Manhole	1200	F2.006	58.830	150	F2.005	58.830	100	
F10	60.650	1.550	Open Manhole	1200 x 900	F4.000	59.100	100				
F11	60.650	1.909	Open Manhole	1200	F2.007	58.741	150	F2.006	58.742	100	
								F4.000	58.791	100	
F12	60.650	2.080	Open Manhole	1200	F1.001	58.570	225	F1.000	58.645	100	
								F2.007	58.645	100	
F13	60.650	1.250	Open Manhole	1200	F5.000	59.400	100				
F14	60.650	1.571	Open Manhole	1200	F5.001	59.079	100	F5.000	59.079	100	
F15	60.650	1.650	Open Manhole	1200	F6.000	59.000	100				
F16	60.800	1.400	Open Manhole	1200	F7.000	59.400	100				
F17	60.650	1.512	Open Manhole	1200	F7.001	59.138	100	F7.000	59.138	100	
F18	60.650	1.836	Open Manhole	1200	F5.002	58.814	150	F5.001	58.864	100	
								F6.000	58.864	100	
								F7.001	58.864	100	
F19	60.650	1.890	Open Manhole	1200	F5.003	58.760	150	F5.002	58.760	100	
F20	60.650	1.953	Open Manhole	1200	F5.004	58.697	150	F5.003	58.697	100	
F21	60.650	1.450	Open Manhole	1200	F8.000	59.200	100				
F22	60.650	1.685	Open Manhole	1200	F8.001	58.965	100	F8.000	58.965	100	
F23	60.650	2.052	Open Manhole	1200	F5.005	58.598	150	F5.004	58.598	100	
								F8.001	58.648	100	
F24	60.650	1.550	Open Manhole	1200	F9.000	59.100	100				
F25	60.650	2.225	Open Manhole	1200	F1.002	58.425	225	F1.001	58.425	225	
								F5.005	58.500	100	
								F9.000	58.550	100	
F26	60.650	1.650	Open Manhole	1200	F10.000	59.000	100				
©1982-2020 Innovyze											

BuroHappold Ltd								Page 7			
Camden Mill Lower Bristol Road Bath				Project North Stand Manchester Foul Water Drainage Strategy							
Date 17/04/2023 File 230413 Etihad North Stan...				Designed by CRM Checked by NH							
Innovyze				Network 2020.1.3							
<u>Manhole Schedules for Foul Water Network</u>											
MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)	Backdrop (mm)
F27	60.656	1.976	Open Manhole	1200	F10.001	58.680	100	F10.000	58.680	100	463
F28	60.712	2.462	Open Manhole	1200	F1.003	58.250	225	F1.002	58.250	225	
								F10.001	58.375	100	
F29	60.800	1.400	Open Manhole	1200	F11.000	59.400	100				
F30	60.800	1.512	Open Manhole	1200	F11.001	59.288	100	F11.000	59.288	100	408
F31	60.682	1.665	Open Manhole	1200	F11.002	59.017	100	F11.001	59.017	100	
F32	60.653	1.773	Open Manhole	1200	F11.003	58.880	100	F11.002	58.880	100	
F33	60.796	2.777	Open Manhole	1200	F1.004	58.020	225	F1.003	58.020	225	
								F11.003	58.608	100	
F34	61.050	0.762	Open Manhole	1200	F12.000	60.288	100				1032
F35	61.050	0.872	Open Manhole	1200	F12.001	60.178	150	F12.000	60.228	100	
F36	61.050	1.233	Open Manhole	1200	F12.002	59.817	150	F12.001	59.817	150	
F37	61.050	1.551	Open Manhole	1200	F12.003	59.499	150	F12.002	59.499	150	
F38	61.050	1.793	Open Manhole	1200	F12.004	59.257	150	F12.003	59.257	150	37
F39	61.050	2.069	Open Manhole	1200	F12.005	58.981	150	F12.004	58.981	150	
F40	61.050	2.519	Open Manhole	1200	F12.006	58.531	150	F12.005	58.531	150	
F41	61.050	3.213	Open Manhole	1200	F1.005	57.837	225	F1.004	57.837	225	
								F12.006	58.321	150	
F42	61.050	3.331	Open Manhole	1200	F1.006	57.719	225	F1.005	57.719	225	
F43	61.050	1.257	Open Manhole	1200	F13.000	59.793	100				
F44	61.050	1.439	Open Manhole	1200	F13.001	59.611	150	F13.000	59.661	100	
F45	61.050	1.701	Open Manhole	1200	F13.002	59.349	150	F13.001	59.349	150	
F46	61.050	1.852	Open Manhole	1200	F13.003	59.198	150	F13.002	59.198	150	
F47	61.050	2.015	Open Manhole	1200	F13.004	59.035	150	F13.003	59.035	150	
F48	61.050	2.195	Open Manhole	1200	F13.005	58.855	150	F13.004	58.855	150	
F49	61.050	3.464	Open Manhole	1200	F1.007	57.586	225	F1.006	57.586	225	
								F13.005	58.693	150	
F50	61.050	1.600	Open Manhole	1200	F14.000	59.450	100				
F51	61.050	1.785	Open Manhole	1200	F15.000	59.265	100				
F52	61.050	1.916	Open Manhole	1200	F14.001	59.134	100	F14.000	59.134	100	
								F15.000	59.134	100	
F53	61.050	1.886	Open Manhole	1200	F16.000	59.164	100				
F54	61.050	2.202	Open Manhole	1200	F14.002	58.848	100	F14.001	58.885	100	
								F16.000	58.848	100	
©1982-2020 Innovyze											

BuroHappold Ltd		Page 8
Camden Mill Lower Bristol Road Bath	Project North Stand Manchester Foul Water Drainage Strategy	
Date 17/04/2023	Designed by CRM	
File 230413 Etihad North Stan...	Checked by NH	
Innovyze	Network 2020.1.3	

Manhole Schedules for Foul Water Network


MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Pipe Out Diameter (mm)	PN	Pipes In Invert Level (m)	Pipes In Diameter (mm)	Backdrop (mm)
F55	61.050	2.554	Open Manhole	1200	F14.003	58.496	100	F14.002	58.496	100	
F56	61.050	2.839	Open Manhole	1200	F14.004	58.211	100	F14.003	58.211	100	
F57	61.050	3.125	Open Manhole	1200	F14.005	57.925	100	F14.004	57.925	100	
F58	61.050	3.832	Open Manhole	1200	F1.008	57.218	225	F1.007	57.218	225	
								F14.005	57.743	100	400
F59	60.954	3.872	Open Manhole	1200	F1.009	57.082	225	F1.008	57.082	225	
F	60.948	4.248	Open Manhole	0		OUTFALL		F1.009	56.700	225	

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
F1	386772.783	398607.464	386772.783	398607.464	Required	
F2	386807.323	398616.092	386807.323	398616.092	Required	
F3	386814.147	398616.250	386814.147	398616.250	Required	
F4	386814.016	398621.932	386814.016	398621.932	Required	
F5	386813.510	398626.229	386813.510	398626.229	Required	
F6	386812.482	398636.342	386812.482	398636.342	Required	
F7	386812.152	398627.547	386812.152	398627.547	Required	
F8	386808.536	398626.559	386808.536	398626.559	Required	
F9	386802.594	398623.665	386802.594	398623.665	Required	

BuroHappold Ltd		Page 18																																																																																																																																													
Camden Mill Lower Bristol Road Bath	Project North Stand Manchester Foul Water Drainage Strategy																																																																																																																																														
Date 17/04/2023 File 230413 Etihad North Stan...	Designed by CRM Checked by NH																																																																																																																																														
Innovyze	Network 2020.1.3																																																																																																																																														
Area Summary for Foul Water Network <table><thead><tr><th>Pipe Number</th><th>Gross Area (ha)</th><th>Pipe Total (ha)</th></tr></thead><tbody><tr><td>1.000</td><td>0.000</td><td>0.000</td></tr><tr><td>2.000</td><td>0.000</td><td>0.000</td></tr><tr><td>2.001</td><td>0.000</td><td>0.000</td></tr><tr><td>2.002</td><td>0.000</td><td>0.000</td></tr><tr><td>2.003</td><td>0.000</td><td>0.000</td></tr><tr><td>3.000</td><td>0.000</td><td>0.000</td></tr><tr><td>2.004</td><td>0.000</td><td>0.000</td></tr><tr><td>2.005</td><td>0.000</td><td>0.000</td></tr><tr><td>2.006</td><td>0.000</td><td>0.000</td></tr><tr><td>4.000</td><td>0.000</td><td>0.000</td></tr><tr><td>2.007</td><td>0.000</td><td>0.000</td></tr><tr><td>1.001</td><td>0.000</td><td>0.000</td></tr><tr><td>5.000</td><td>0.000</td><td>0.000</td></tr><tr><td>5.001</td><td>0.000</td><td>0.000</td></tr><tr><td>6.000</td><td>0.000</td><td>0.000</td></tr><tr><td>7.000</td><td>0.000</td><td>0.000</td></tr><tr><td>7.001</td><td>0.000</td><td>0.000</td></tr><tr><td>5.002</td><td>0.000</td><td>0.000</td></tr><tr><td>5.003</td><td>0.000</td><td>0.000</td></tr><tr><td>5.004</td><td>0.000</td><td>0.000</td></tr><tr><td>8.000</td><td>0.000</td><td>0.000</td></tr><tr><td>8.001</td><td>0.000</td><td>0.000</td></tr><tr><td>5.005</td><td>0.000</td><td>0.000</td></tr><tr><td>9.000</td><td>0.000</td><td>0.000</td></tr><tr><td>1.002</td><td>0.000</td><td>0.000</td></tr><tr><td>10.000</td><td>0.000</td><td>0.000</td></tr><tr><td>10.001</td><td>0.000</td><td>0.000</td></tr><tr><td>1.003</td><td>0.000</td><td>0.000</td></tr><tr><td>11.000</td><td>0.000</td><td>0.000</td></tr><tr><td>11.001</td><td>0.000</td><td>0.000</td></tr><tr><td>11.002</td><td>0.000</td><td>0.000</td></tr><tr><td>11.003</td><td>0.000</td><td>0.000</td></tr><tr><td>1.004</td><td>0.000</td><td>0.000</td></tr><tr><td>12.000</td><td>0.000</td><td>0.000</td></tr><tr><td>12.001</td><td>0.000</td><td>0.000</td></tr><tr><td>12.002</td><td>0.000</td><td>0.000</td></tr><tr><td>12.003</td><td>0.000</td><td>0.000</td></tr><tr><td>12.004</td><td>0.000</td><td>0.000</td></tr><tr><td>12.005</td><td>0.000</td><td>0.000</td></tr><tr><td>12.006</td><td>0.000</td><td>0.000</td></tr><tr><td>1.005</td><td>0.000</td><td>0.000</td></tr><tr><td>1.006</td><td>0.000</td><td>0.000</td></tr><tr><td>13.000</td><td>0.000</td><td>0.000</td></tr><tr><td>13.001</td><td>0.000</td><td>0.000</td></tr><tr><td>13.002</td><td>0.000</td><td>0.000</td></tr><tr><td>13.003</td><td>0.000</td><td>0.000</td></tr></tbody></table>			Pipe Number	Gross Area (ha)	Pipe Total (ha)	1.000	0.000	0.000	2.000	0.000	0.000	2.001	0.000	0.000	2.002	0.000	0.000	2.003	0.000	0.000	3.000	0.000	0.000	2.004	0.000	0.000	2.005	0.000	0.000	2.006	0.000	0.000	4.000	0.000	0.000	2.007	0.000	0.000	1.001	0.000	0.000	5.000	0.000	0.000	5.001	0.000	0.000	6.000	0.000	0.000	7.000	0.000	0.000	7.001	0.000	0.000	5.002	0.000	0.000	5.003	0.000	0.000	5.004	0.000	0.000	8.000	0.000	0.000	8.001	0.000	0.000	5.005	0.000	0.000	9.000	0.000	0.000	1.002	0.000	0.000	10.000	0.000	0.000	10.001	0.000	0.000	1.003	0.000	0.000	11.000	0.000	0.000	11.001	0.000	0.000	11.002	0.000	0.000	11.003	0.000	0.000	1.004	0.000	0.000	12.000	0.000	0.000	12.001	0.000	0.000	12.002	0.000	0.000	12.003	0.000	0.000	12.004	0.000	0.000	12.005	0.000	0.000	12.006	0.000	0.000	1.005	0.000	0.000	1.006	0.000	0.000	13.000	0.000	0.000	13.001	0.000	0.000	13.002	0.000	0.000	13.003	0.000	0.000
Pipe Number	Gross Area (ha)	Pipe Total (ha)																																																																																																																																													
1.000	0.000	0.000																																																																																																																																													
2.000	0.000	0.000																																																																																																																																													
2.001	0.000	0.000																																																																																																																																													
2.002	0.000	0.000																																																																																																																																													
2.003	0.000	0.000																																																																																																																																													
3.000	0.000	0.000																																																																																																																																													
2.004	0.000	0.000																																																																																																																																													
2.005	0.000	0.000																																																																																																																																													
2.006	0.000	0.000																																																																																																																																													
4.000	0.000	0.000																																																																																																																																													
2.007	0.000	0.000																																																																																																																																													
1.001	0.000	0.000																																																																																																																																													
5.000	0.000	0.000																																																																																																																																													
5.001	0.000	0.000																																																																																																																																													
6.000	0.000	0.000																																																																																																																																													
7.000	0.000	0.000																																																																																																																																													
7.001	0.000	0.000																																																																																																																																													
5.002	0.000	0.000																																																																																																																																													
5.003	0.000	0.000																																																																																																																																													
5.004	0.000	0.000																																																																																																																																													
8.000	0.000	0.000																																																																																																																																													
8.001	0.000	0.000																																																																																																																																													
5.005	0.000	0.000																																																																																																																																													
9.000	0.000	0.000																																																																																																																																													
1.002	0.000	0.000																																																																																																																																													
10.000	0.000	0.000																																																																																																																																													
10.001	0.000	0.000																																																																																																																																													
1.003	0.000	0.000																																																																																																																																													
11.000	0.000	0.000																																																																																																																																													
11.001	0.000	0.000																																																																																																																																													
11.002	0.000	0.000																																																																																																																																													
11.003	0.000	0.000																																																																																																																																													
1.004	0.000	0.000																																																																																																																																													
12.000	0.000	0.000																																																																																																																																													
12.001	0.000	0.000																																																																																																																																													
12.002	0.000	0.000																																																																																																																																													
12.003	0.000	0.000																																																																																																																																													
12.004	0.000	0.000																																																																																																																																													
12.005	0.000	0.000																																																																																																																																													
12.006	0.000	0.000																																																																																																																																													
1.005	0.000	0.000																																																																																																																																													
1.006	0.000	0.000																																																																																																																																													
13.000	0.000	0.000																																																																																																																																													
13.001	0.000	0.000																																																																																																																																													
13.002	0.000	0.000																																																																																																																																													
13.003	0.000	0.000																																																																																																																																													
©1982-2020 Innovyze																																																																																																																																															

BuroHappold Ltd		Page 19																																																														
Camden Mill Lower Bristol Road Bath	Project North Stand Manchester Foul Water Drainage Strategy																																																															
Date 17/04/2023	Designed by CRM																																																															
File 230413 Etihad North Stan...	Checked by NH																																																															
Innovyze	Network 2020.1.3																																																															
Area Summary for Foul Water Network <table><thead><tr><th>Pipe Number</th><th>Gross Area (ha)</th><th>Pipe Total (ha)</th></tr></thead><tbody><tr><td>13.004</td><td>0.000</td><td>0.000</td></tr><tr><td>13.005</td><td>0.000</td><td>0.000</td></tr><tr><td>1.007</td><td>0.000</td><td>0.000</td></tr><tr><td>14.000</td><td>0.000</td><td>0.000</td></tr><tr><td>15.000</td><td>0.000</td><td>0.000</td></tr><tr><td>14.001</td><td>0.000</td><td>0.000</td></tr><tr><td>16.000</td><td>0.000</td><td>0.000</td></tr><tr><td>14.002</td><td>0.000</td><td>0.000</td></tr><tr><td>14.003</td><td>0.000</td><td>0.000</td></tr><tr><td>14.004</td><td>0.000</td><td>0.000</td></tr><tr><td>14.005</td><td>0.000</td><td>0.000</td></tr><tr><td>1.008</td><td>0.000</td><td>0.000</td></tr><tr><td>1.009</td><td>0.012</td><td>0.012</td></tr><tr><td></td><td>Total</td><td>Total</td></tr><tr><td></td><td>0.012</td><td>0.012</td></tr></tbody></table> Free Flowing Outfall Details for Foul Water Network <table><thead><tr><th>Outfall Pipe Number</th><th>Outfall Name</th><th>C. Level (m)</th><th>I. Level (m)</th><th>Min I. Level (m)</th><th>D, L (mm)</th><th>W (mm)</th></tr></thead><tbody><tr><td>F1.009</td><td>F</td><td>60.948</td><td>56.700</td><td>0.000</td><td>0</td><td>0</td></tr></tbody></table>			Pipe Number	Gross Area (ha)	Pipe Total (ha)	13.004	0.000	0.000	13.005	0.000	0.000	1.007	0.000	0.000	14.000	0.000	0.000	15.000	0.000	0.000	14.001	0.000	0.000	16.000	0.000	0.000	14.002	0.000	0.000	14.003	0.000	0.000	14.004	0.000	0.000	14.005	0.000	0.000	1.008	0.000	0.000	1.009	0.012	0.012		Total	Total		0.012	0.012	Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D, L (mm)	W (mm)	F1.009	F	60.948	56.700	0.000	0	0
Pipe Number	Gross Area (ha)	Pipe Total (ha)																																																														
13.004	0.000	0.000																																																														
13.005	0.000	0.000																																																														
1.007	0.000	0.000																																																														
14.000	0.000	0.000																																																														
15.000	0.000	0.000																																																														
14.001	0.000	0.000																																																														
16.000	0.000	0.000																																																														
14.002	0.000	0.000																																																														
14.003	0.000	0.000																																																														
14.004	0.000	0.000																																																														
14.005	0.000	0.000																																																														
1.008	0.000	0.000																																																														
1.009	0.012	0.012																																																														
	Total	Total																																																														
	0.012	0.012																																																														
Outfall Pipe Number	Outfall Name	C. Level (m)	I. Level (m)	Min I. Level (m)	D, L (mm)	W (mm)																																																										
F1.009	F	60.948	56.700	0.000	0	0																																																										
©1982-2020 Innovyze																																																																

Appendix F Foul Water Strategy



Appendix G United Utilities Correspondence

Christopher Moore

From: wastewaterdeveloperservices@uuplc.co.uk
Sent: 21 September 2022 14:21
To: Christopher Moore
Subject: RE: Project Manchester Pre-development Enquiry - UU Ref. 02777724

****External Email. This email originated from outside Buro Happold.****

Good afternoon Chris,

Pre Development Enquiry for: Project Manchester, Gibbon Street UU Reference Number : 02777724

We have carried out an assessment of your application which is based on the information provided. This pre-development advice on your drainage strategy will be valid for 12 months. Your drainage strategy will need to be reviewed by other competent authorities as part of the planning process, and we advise that you carry out the necessary site investigations to confirm the viability of your proposals.

If your investigations require access to our public sewer network, we ask that you contact our network engineers with a request for an access certificate via our main contact telephone number 0345 6723 723 or refer to the link below:

<https://www.unitedutilities.com/builders-developers/working-near-our-assets/>

Foul Water

Foul flow from this site will be allowed to drain into the public foul water/combined sewer system.

Our preferred point of discharge would be to the 520*710 mm public combined sewer located to the West of your proposed development (**UUMH6700**) at an unrestricted rate.

If you are able to identify an alternative, more suitable point of discharge, we request that you contact us at your earliest convenience so that we can assess suitability.

If the applicant wishes to keep **UUMH7701** at the proposed point of connection. The applicant needs to provide further investigation (CCTV survey) to clarify the outfall point from the manhole as the current records show the outfall sewer to the north was abandoned. Meanwhile, I will ask our network team to investigate this issue more.

Please ensure all proposed manhole chambers cover levels and finished floor levels are higher than the receiving public sewer.

In accordance with our infrastructure plans we may ask you to change your point of connection. Therefore please contact us when you are ready to formalise your drainage proposals, we would suggest before you submit for Full Planning.

Surface Water

All surface water flow from the proposed development should drain in-line with the drainage hierarchy, as outlined in

Paragraph 80, (Reference ID: 7-080-20150323), of the National Planning Practice Guidance. We also recommend you prioritise the use of multi-functional sustainable drainage systems for the management of surface water in accordance with national planning policy.

Generally, the aim should be to discharge surface run off as high up the following hierarchy of drainage options as reasonably practicable.

This is outlined as follows, in order of priority:

1. **into the ground (infiltration);**
2. **to a surface waterbody;**
3. **to a surface water sewer or highway drain;**
4. **to a combined sewer.**

For guidance, The [North West SuDS Pro-Forma](#) provides information on the appropriate evidence required at each stage of the hierarchy, to demonstrate how each level has been discounted.

The Lead Local Flood Authority has responsibility for all surface water drainage concerns and their input to your proposal is critical. You should also consider whether it is necessary to discuss your proposal with the Environment Agency, or Internal Drainage Board (if operating in your area).

The Local Planning Authority are the determining authority for any application for planning permission and the appropriate authority for determining cost viability of a proposed drainage scheme, such assessments are outside of the jurisdiction of United Utilities.

Infiltration

According to the provided document ref: A3174-13 dated 02/2014 prepared by ESG, we are satisfied that infiltration is not feasible, we accept the provided sufficient evidence to discount infiltration.

Waterbody

If an evidence based assessment has been carried out and confirms that infiltration is not feasible, we recommend that you contact the Lead Local Flood Authority and/or Environment Agency to discuss a point of discharge to the canal located 80m North of the proposed site.

We would encourage you to identify and engage with any third party landowner and riparian owner to agree access and discharge rights to the water body if this is not in your ownership.

Highway Drainage

If an evidence based assessment has been carried out and confirms that infiltration is not feasible, we recommend that you investigate the possibility of draining surface water to the highway drain where this ultimately discharges to a watercourse, by contacting the relevant Highway Authority.

Public Sewer

In accordance with the hierarchy of drainage options within the National Planning Practice Guidance, both discharge to ground via infiltration and discharge to a waterbody should be discounted prior to consideration of discharging surface water to the public sewer system. Evidence should be provided to demonstrate how these have been discounted, as

outlined in the North West SuDS pro-forma.

Once evidence is provided as outlined above, United Utilities will consider a connection to the 520*710 mm public combined sewer located West of the proposed site (**UUMH6700**) at a pass forward flow to be agreed by the Lead Local Flood Authority. United Utilities request that any agreed rate does not exceed 33.1l/s.

Similar to what was stated in the foul water section, if the investigation identifies the final outfall from UUMH 7701, then UU will consider this option.

As a Water Company, we have no obligation to accept highway drainage into our public sewer network. However, should your proposals include runoff from highways, we would request that consideration is given to SuDS components that deliver source control are incorporated within the design of the scheme to reduce the volume and frequency of discharges of these flows to the public sewer.

Levels

For low-lying sites, (where the ground level of the site or the level of a basement is below the ground level at the point where the drainage connects to the public sewer), care should be taken to ensure that the property is not at increased risk of flooding. If these circumstances exist, we recommend that you contact us to discuss further. It could affect the detailed design of your site and result in the need to incorporate appropriate mitigating measures in your drainage scheme.

Land drainage / Overland flows / track drainage


United Utilities have no obligation, and furthermore we do not accept land drainage, overland flows or track drainage into the public sewerage network under any circumstances

Existing Wastewater Assets Crossing the Site

Regarding the easement question for the below sewers:

-
- 850mm dia surface water sewer running east to west through the north of the site (upstream of MH6704). This is not a surface water sewer, it is an over flow sewer with a 6m legal easement.
- 900mm dia combined sewer running from south to north on the east side of the site (MH 8600 to MH 8700). sewer with a 6m easement.
- 375mm dia concrete sewer running from south to north on the west side of the site (MH7600 to MH7601 to junction with sewer running west to east). sewer with a 6m legal easement.
- 375mm dia VC sewer and 550mm x 950mm running along the northern boundary of the site (MH6700 to MH7701 to MH8702). sewer with a 6m legal easement.

There is another **10m** easement according to our records, it starts from UUMH7701 going to the west as highlighted in yellow below:



According to our public sewer records there are public sewers located within your site boundary. We will require unrestricted access to the sewer for maintenance purposes, we would ask that you maintain a minimum clearance of 6m which is measured 3m from the centre line of the pipe unless there happens to be a formal easement agreement in place, in which case the specified easement width would apply. If you cannot achieve this then you may wish to consider diverting and or abandoning the public sewer.

Please be aware that any proposed diversion may require modelling. This process may take up to 6 months in order to reach an acceptable design.

Please refer to the link below to obtain full details of the processes involved with sewer diversions:

<https://www.unitedutilities.com/builders-developers/larger-developments/wastewater/sewer-diversions/>

Please refer to the link below to obtain full details of the processes involved with sewer closure:

<https://www.unitedutilities.com/builders-developers/wastewater-services/close-a-sewer/sewer-closures/>

Existing Water Assets Crossing the Site

It is the developer responsibility to identify utilities on-site. Where clean water assets are shown on our records, we recommend that you contact our Water Pre-Development Team, via the following email address:

DeveloperServicesWater@uuplc.co.uk. Further information for this service can be found on our website via the link below:

<https://www.unitedutilities.com/builders-developers/larger-developments/pre-development/water-pre-dev/>

Connection Application

Although we may discuss and agree discharge points and rates in principle, please be aware that you will have to apply for a formal sewer connection. This is so that we can assess the method of construction, Health & Safety requirements and to ultimately inspect the connection when it is made. Details of the application process and the form itself can be obtained from our website by following the link below:

<https://www.unitedutilities.com/builders-developers/wastewater-services/sewer-connections/sewer-connection/>

We recommend that the detailed design should confirm the locations of all utilities in the area and ensure that any proposed drainage solution considers routing and clash checks where required.

Sewer Adoptions

You have indicated on your application form that you intend to put the sewers forward for adoption (including any SuDS components that can come within the meaning of a sewer).

United Utilities assess adoption applications based on the current Design & Construction Guidance and local practices which have now replaced 'Sewers For Adoption 6th Edition'.

We recommend that you submit a pre design assessment to the sewer adoption mailbox (SewerAdoptions@uuplc.co.uk) stating pre design assessment in the title

Please refer to links below to obtain further guidance:

<https://www.unitedutilities.com/builders-developers/larger-developments/wastewater/sewer-adoptions/>

Site drainage must be designed in accordance with Building Regulations, National Planning Policy, and local flood authority guidelines, we would recommend that you speak and make suitable agreements with the relevant statutory bodies.

If you intend to put forward your wastewater assets for adoption by United Utilities, the proposed detail design will be subject to a technical appraisal by an Adoption Engineer as we need to be sure that the proposals meets the

requirements set out in the Design & Construction Guidance. The proposed design should give consideration to long term operability and give United Utilities a safe and cost effective proposal for the lifetime of the assets. In these cases, we strongly recommend that no construction commences until the detailed drainage design, submitted as part of the Section 104 application, has been assessed and accepted in writing by United Utilities. Any work carried out prior to the technical assessment being approved is done entirely at the developer's own risk and could be subject to change.

SuDS

If your development proposal incorporates any SuDS component(s) which interact with a sewer network you plan on offering for adoption to United Utilities; contact should be made with our technical team at your earliest convenience, please complete the 'Section 104 pre-application form : ' and include as much relevant detail as you can. These discussions can help prevent delays later in the development process.

Section 104 Pre application form (1b)

As per the sewerage sector guidance, all SuDS should be designed in accordance with the standards within the Design & construction guidance & the CIRIA SuDS manual (C753)

Codes For Adoption

The new Codes for Adoption are outlined on the Water UK Website. The link below takes you to their webpage:

<https://www.water.org.uk/technical-guidance/developers-services/codes-for-adoption/>

A free copy of the new Design & Construction Guidance can be downloaded via the link below:

<https://www.water.org.uk/sewerage-sector-guidance-approved-documents/>

Many thanks and kind regards,



Mohammed Aljafarawi (He/Him)

Developer Engineer
Developer Services & Metering
Customer Services
M: 07950474499
unitedutilities.com

If you have received a great service today why not tell us?

Visit: unitedutilities.com/wow



The information contained in this e-mail is intended only for the individual to whom it is addressed. It may contain legally privileged or confidential information or otherwise be exempt from disclosure. If you have received this Message in error or there are any problems, please notify the sender immediately and delete the message from your computer. You

must not use, disclose, copy or alter this message for any unauthorised purpose. Neither United Utilities Group PLC nor any of its subsidiaries will be liable for any direct, special, indirect or consequential damages as a result of any virus being passed on, or arising from the alteration of the contents of this message by a third party.

United Utilities Group PLC, Haweswater House, Lingley Mere
Business Park, Lingley Green Avenue, Great Sankey,
Warrington, WA5 3LP
Registered in England and Wales. Registered No 6559020

www.unitedutilities.com
www.unitedutilities.com/subsidiaries

Alex Mulroy
Buro Happold Limited
Camden Mill
Lower Bristol Road
Bath
BA2 3DQ
UK

T: +44 (0)1225 320 600

F: +44 (0)870 787 4148

Email: alex.mulroy@burohappold.com

$$\text{North Stand } Q_{peak} = 1.0\sqrt{287} = 16.94\text{l/s}$$

Based on the above calculations the total site discharge for the site is:

$$\text{Total Site Discharge} = 5.22\text{l/s} + 22.91\text{l/s} + 16.94\text{l/s} = 45.07\text{l/s}$$

The above calculations are considered industry standard for calculating total site; however, for this development it can be reasonably assumed that the individual buildings will not be concurrently discharging at peak flow and therefore the calculated total site discharge is likely to be conservative.

UU have agreed to accept flows from the site at an unrestricted rate to their network – refer to **Appendix G** for correspondence.