© This drawing and the building works depicted are the copyright of the Engineers and may not be reproduced except by written permission.

NOLAN ASSOCIATES

CONSTRUCTION DRAWING

REV	DESCRIPTION	BY	CHKD	DATE
A	Construction	K.Hall	ARW	14.07.23
T1	Tender	K.Hall	ARW	24.02.23

Green Frog Connect
Ashton Old Road, Manchester

Site Layout

NOLAN ASSOCIATES
CONSULTING CIVIL & STRUCTURAL ENGINEERS
54 HAGLEY ROAD, EDGBASTON, BIRMINGHAM B16 8PE
TEL: 0121-454 3099 FAX: 0121-454 3059
E-MAIL: enquiries@nolanassociates.co.uk

Drawn by	Date	Plot Date	Scale
K.Hall	Feb 23	Feb 23	1: 100@A1
Checked by	**Project No**		**Dwg No**
ARW	2022-178		02 A

10000 Concrete Ramp, min 150mm thick reinforced with 1 layer A393 mesh

DNO substation, refer to drawing 03 for GA details

2300x1500x200 thick Standby Generator slab reinforced with 1 layer A252 mesh bottom

1500x1100x200 thick NER slab reinforced with 1 layer A252 mesh bottom

Power TX bund, refer to drawing 11 for details

Private switchroom, refer to drawing 08 for GA details

2000x1300x200 thick Aux TX slab reinforced with 1 layer A252 mesh bottom

4No 750x750x600 deep square concrete pedestals. TOC +76.000

Gas kiosk slab, refer to drawing 12 for details

2m high gabions (1No 1x1x1, 1No 1x1.5x1), top of gabion +77.300

Tree root barrier to 3m below GL (+72.900)

PALISADE HT2.2m

TARMAC FOOTPATH

GROUND DRAIN

GATE

EAVE

RIDGE

BUILDING