



Arboriculturalist to monitor the excavation of the trench for the drainage runs, to ensure no major roots are damaged.

Glen Maye

Proposed tree to mitigate for the removal of the Norway Maple tree. Tree to be Acer campestre, 14-16cm girth, Extra Heavy Standard, 4-5m high

South Manchester
Quaker
Meeting House

Norway Maple tree to be removed to accommodate the drainage alignments.

Additional proposed tree locations if further trees are to be removed to facilitate the surface and foul water drainage alignments

LEGEND

- Existing Trees to be Retained
- Existing Trees to be Removed
- Existing Root Zone
- Proposed Small Ornamental Trees
Proposed as part of wider landscape masterplan
- Proposed POS Trees
Proposed as part of wider landscape masterplan
- Proposed Mitigation Trees
Trees to be planted as 14-16cm, Extra Heavy Standard, 4-5m high. Trees to be secured with tree stakes.
- Proposed Ornamental Hedgerows
Proposed as part of wider landscape masterplan
- Proposed Shrub Planting
Proposed as part of wider landscape masterplan
- Proposed Native Shrub Mix
Proposed as part of wider landscape masterplan

- GENERAL NOTES**
- This drawing is the copyright of tpm landscape Ltd and cannot be reproduced in any form without the consent of the company.
 - This drawing is to be read in conjunction with detail landscape drawings, details and specification.
 - This drawing is to be read in conjunction with all relevant Architects', Engineer's, Specialists, Bills of Quantities and Specifications.
 - The insertion of any firm or proprietary brand on this drawing is an indication of the class or quality required and does not exclude the use of alternative materials that are equal in performance, quality and appearance, provided that they have been approved in writing by the Landscape Architect.
 - The Contractor is responsible for accurately ascertaining the position of underground services and responding to all relevant service easement requirements.
 - All dimensions are in millimetres unless stated otherwise, for the purposes of construction this drawing must not be scaled and only written dimensions used. Written and scaled dimensions to be checked on site, any discrepancies reported prior to work commencing. IF IN DOUBT PLEASE ASK.
 - All work and materials are to be in accordance with the relevant British Standards and Code of Practice.
 - All Proprietary products are to be used strictly in accordance with the manufacturer's instructions and details.

REVISION NOTES

Rev	By	Description	Date

Client
Miller Homes North West

Project
Moss Hey Drive, Northenden

Description
Tree Mitigation Plan

Status
For Approval

Scale @ A1	Drawn	Checked	Date
1:200	TS	DC	05.01.23
Job number	Drawing number	Revision	
3882	105	-	