

Date: 16/01/2023

RE: NEW VICTORIA PLANNING CONDITION 06

HE Simm are designing and installing the external lighting system for the New Victoria residential development in compliance with the Arup Building Services Employees Requirements (Rev P07).

External Lighting Site Wide:

HE Simm have designed, supplied, installed, tested and commissioned the external lighting scheme

The design intent and performance requirements for the external lighting is shown on the drawings. Its HE Simm's responsibility to develop and complete the lighting design based on the given performance criteria.

HE Simm shall ensure compliance with all Secure by Design lighting requirements.

External lighting shall be contactor controlled by means of a photocell and time clock with manual override on the switch for maintenance.

Illumination for safety and security shall be included at all entrance and egress points from the building, external areas and circulation routes which are to form part of an co-ordinated external lighting scheme for the proposed external and undercroft at grade car park and the pedestrian bridge.

Scheme is compliant with the following guides and standards relating to the external lighting:

- BS 5489-1: Code of Practice for the design of Road Lighting. Lighting of roads and amenity areas.
- BS 12464-2: Light and Lighting - Lighting of work places. Part 2 – Outdoor work places.
- ILP GN01: Guidance Note for the Reduction of Obtrusive Light

LIVERPOOL OFFICE

Suites 5&6 Spinnaker House
141 Sefton Street
Liverpool L8 5SN

 0151 707 3222

@ info@hesimm.co.uk

hesimm.co.uk