



- Undertake photographic survey of working areas prior to undertaking works.
- Ensure sufficient protection is in place to in-situ atrium glazing and glass ballustrade.
- Lift existing flags to atrium entrance and exit landings to be lifted in 3 no. sections in sequence shown on drawing.
- Number each flag and carefully set aside for reinstatement.
- Undertake photographic record of substrate once exposed and report any defects uncovered to architect.
- Allow access for architect to inspect and agree any changes to scope of works.
- Inspect and restrain for any obstructions and remove any blockages from channel and gullies.
- Carriage return stones to existing positions and re-bed in mortar to match existing.
- Existing finished floor level must be retained following relaying of flags.
- Ensure all paving joints are fully pointed and drainage covers returned to original positions.
- Remove protection on completion of the works.
- Clean down and leave site tidy to be returned to operational use.

A 16/12/22 Preliminary issue

Rev	Date/Intls	Details
-----	------------	---------

© The moral rights of the author are hereby asserted.
This drawing and design is the sole property of Buttress Ltd and must not be reproduced without permission.
Buttress Ltd is Registered in England and Wales: 5363573



41 Bengal St
Manchester
M4 6AF

T 0161 236 3303
E contact@buttress.net
W www.buttress.net

Project Title	Manchester Art Gallery
Client	Manchester City Council
Location	Mosley Street, Manchester

Drawing Title Ground Floor
Atrium Entrance / Exit Waterproofing Details

Date	16/12/22	Scale	1:25
Checked	NC	Orig Paper Size	A1

Status Preliminary

Project: Origin: Zone: Level: Type: Disc: Number: Rev:

9518-BA - B2 - B2 - DR - A - (11)003 - P1