

White Moss Road, Manchester

Flood Risk Assessment & Drainage Strategy

The Guinness Partnership

January 2023

Notice

This document and its contents have been prepared and are intended solely as information for Guinness Partnership and use in relation to a full planning application for a residential development site on land off White Moss Road in Manchester.

Atkins Limited assumes no responsibility to any other party in respect of or arising out of or in connection with this document and/or its contents.

Document history

Revision	Purpose description	Originated	Checked	Reviewed	Authorised	Date
1.0	For Client Review	RW	FL	CB	GC	20/01/23

Client signoff

Client	The Guinness Partnership
Project	White Moss Road, Manchester
Job number	5218589
Client signature / date	

Contents

Chapter	Page
1. Introduction	5
2. Background Information	6
2.1. Environment Agency (EA)	6
2.2. United Utilities (UU)	6
2.3. Manchester City Council (MCC)	6
3. Site Description	7
3.1. Location	7
3.2. Topography	7
3.3. Land Use	7
3.4. Ground Conditions	8
3.5. Water Environment	8
4. Proposed Development	10
4.1. Description	10
4.2. Sequential Test	10
5. Flood Risk Assessment	11
5.1. Flooding History	11
5.2. Identification of Flooding Sources	11
5.3. Flood Risk Management	13
5.4. Residual Risks	13
6. Surface Water Drainage Strategy	14
6.1. Existing Drainage Regime	14
6.2. Proposed Outfall	14
6.3. Maximum Permitted Discharge Rate	14
6.4. SuDS Selection	15
6.5. Proposed Strategy	17
6.6. Adoption & Maintenance	17
7. Foul Water Drainage Strategy	18
7.1. Foul Water Flow Rates	18
7.2. Proposed Outfall	18
7.3. Strategy	18
7.4. Adoption & Maintenance	18
8. Conclusions & Recommendations	19
8.1. Conclusions	19
8.2. Recommendations	19
Appendices	20
Appendix A. Correspondence	21
Appendix B. Drawings	22
Appendix C. SuDS Selection	23
Appendix D. Surface Water Calculations	25

Tables

Table 6-1 - Existing surface water run-off rates	14
--	----

Table 6-2 - Catchments discharge rates	14
Table 6-3 - Development pollution hazard indices	15
Table 6-4 - % of total run-off treated by each SuDS component	16
Table 6-5 - Pollution mitigation indices for permeable paving	16
Table 6-6 - Potential SuDS configurations	16
Table 6-7 - Storage requirements	17

Figures

Figure 3-1 Site location plan (not to scale)	7
Figure 4-1 Environment Agency Flood Map	10
Figure 5-1 Environment Agency Surface Water Flood Map	12
Figure 5-2 Environment Agency Reservoir Flood Map	12

1. Introduction

Atkins has been commissioned by The Guinness Partnership to prepare a Flood Risk Assessment and Drainage Strategy to inform a full design package for a proposed residential development (the “Proposed Development”), on the land off White Moss Road, Manchester (the “Site”).

This Flood Risk Assessment and Drainage Strategy has been prepared in accordance with the National Planning Policy Framework (NPPF)¹ and associated Planning Practice Guidance². The scope of this Assessment has been established through consultation with and using documentation provided by United Utilities (UU), Environment Agency (EA) and the Manchester City Council (Lead Local Flood Authority (LLFA)).

¹ National Planning Policy Framework, February 2019, Department for Communities and Local Government

² Planning Practice Guidance, March 2014, Department for Communities and Local Government

2. Background Information

2.1. Environment Agency (EA)

An enquiry was submitted to the Environment Agency (EA). The response received is summarised below and included in full in **Appendix A**:

- The site is in Flood Zone 1, very low risk. Their nearest model is in Blackley, which has no impact on this site location.
- The EA do not have any records of flooding affecting the Site.
- The EA have no flood defences in the vicinity of this Site.

2.2. United Utilities (UU)

A Developer Enquiry was submitted to UU. A copy of the response and sewer records are included in **Appendix A** and the key points summarised below:

- UU have no current record of sewer flooding within the vicinity of the Proposed Development.
- UU allow foul flows from the Proposed Development to be discharged into their public combined sewer at an unrestricted rate. Their preferred point of connection is the 225mm diameter public combined sewer to the west of the site.
- In relation to surface water, UU will consider a connection to their 225mm diameter public combined sewer located to the west of the site at discharge rate not exceeding 6l/s, only once evidence is provided that surface water cannot be discharged via methods that are higher in the drainage hierarchy within the National Planning Practice Guidance².
- There are public sewers within the Site boundary. UU will require unrestricted access to the sewer for maintenance purposes, a minimum clearance of 3m either side from the centre line of the pipe is required. If this cannot be achieved, then considerations should be given to diverting and or abandoning the public sewer.
- UU assess adoption applications based on the current Design & Construction Guidance and local practices.
- Site drainage must be designed in accordance with Building Regulations, National Planning Policy, and local flood authority guidelines.
- All SuDS should be designed in accordance with the standards within the Design & construction guidance & the CIRIA SuDS manual (C753).
- Sewer Records show that there are combined sewers crossing and surrounding the Site. There is a sewer running along White Moss Road; a sewer crossing the northern area of the Site, eventually connecting into the sewer under White Moss Road. There is a sewer along Lilstock Walk to the west of the site, turning in Woodmere Drive, and a sewer running along the site's south-western boundary, which eventually turns in Dam Head Drive.

2.3. Manchester City Council (MCC)

MCC, as the LLFA, have been consulted regarding requirements specific to the site and the preliminary development proposals. A copy of the full response received is included in **Appendix A** and summarised below:

- The Site is located in the Conurbation Core Critical Drainage Area.
- The nearest flood/drainage incident on record is approximately 30m south of the central part of the Site, dated 16/06/2020, described as "blocked gully or drain".
- The asset register highlights an indicative risk that the Lionfield Brook culverted ordinary watercourse crosses the Site or is in close proximity to the Site. An indicative culvert route is shown crossing Wanley Walk in the central Site; while 3rd party historic OS mapping indicates a 'river' was proximal to the eastern Site boundary. This culvert is an indicative asset and has not been verified with survey.
- The 1984 drainage survey of major assets highlights an indicative culvert asset proximal to the eastern Site boundary.
- A planning application on this site would benefit from site investigation of the indicative culvert risk, which should be presented to support the planning application. Should a culverted ordinary watercourse be identified during site investigations, any planning application's masterplan should take account of the culverted watercourse and any required permissions should be obtained.

3. Site Description

3.1. Location

The Site is located in a residential area approximately 600m south of junction 20 of the M60 (Manchester Outer Ring Road). The Site is bounded to the north by White Moss Road and Wanley Walk, to the west by Lilstock Walk and Woodmere Drive and to the south by Dam Head Drive and a public open space. The site comprises of two parts: a quadrilateral shape to the north-west and an L-shaped part to the south-east. The approximate centre of the Site has easting and northing coordinates of 386432, 403448.



Figure 3-1 Site location plan (not to scale)

3.2. Topography

The Site has an approximate area of 1.11ha. The topographical survey of the Site is shown in **Appendix B**.

Ground levels within the Site slope in a southerly direction from approximately 99.6m AOD at the northern corner of the Site to approximately 89.7m AOD at the southern end of the Site. There is a retaining wall up to 1.3m high along the Lilstock Walk, which is located at a lower level compared to the Site. Ground levels within the Site are relatively steep, approximately 1 in 10, and there is a steep slope of approximately 1 in 4 at the south-eastern end of the Site, falling in a south-easterly direction.

The Site's surrounding area generally falls in a southerly direction.

3.3. Land Use

3.3.1. Historic

An examination of old Ordnance Survey maps dating 1848, shows that the site was occupied by Dam Head Farm and had a pond. More recent mapping, 1980, shows no evidence of the Farm and pond. From 1950s the area surrounding the Site, becomes progressively more developed and by 1975 residential developments, including apartment blocks, had been built within 100m in all directions of the site. Maps from 2000 shows two residential houses located in the southern corner of the Site. These are not shown on maps from 2009.

3.3.2. Current

The Site is currently used as a public landscape area and is entirely covered with grass, with the exception of footpaths, a concrete paved area and an abandoned section of road along the southern boundary. There are sporadic mature trees and smaller vegetation across the Site.

The surrounding area comprises of residential developments, including terraced houses and blocks of flats.

3.4. Ground Conditions

The content of this section has been informed by Geo-Environmental and Geotechnical Reports prepared by Curtins (reference: 077873-CUR-00-XX-RP-GE-041-P01 and 077873-CUR-00-XX-RP-GE-042-P01, date: November 2022) together with information from a number of on-line, public domain data sources.

3.4.1. Soils

According to Soilscales, the soils on the site are described as *slowly permeable and seasonally wet acid loamy and clayey soils*. No information is currently available regarding the depth of this stratum.

3.4.2. Made Ground

Made ground was encountered up to a depth of 2.6m.

Made Ground soils comprises either soft to firm blackish grey sand clay, grey gravelly slightly sandy cobbles, dark brown slightly silty gravelly clay with occasional cobbles, blackish brown gravelly sand, soft to firm brown gravelly very sandy clay, or grey sandy gravel of fine to coarse subangular of brick, concrete and sandstone.

3.4.3. Geology

3.4.3.1. Superficial Deposits

The Geotechnical Reports have identified that the Site is underlain by Glacial Till, comprising predominantly cohesive deposits, interbedded with granular layers at various depth horizons in the northern area of the site, and described typically as a firm to stiff sandy clay and brown gravelly sand in the southern part of the site.

3.4.3.2. Bedrock

Maps from the British Geological Survey identify the bedrock beneath the site to be Manchester Marls Formation bedrock (majority of site) and Chester Formation bedrock (northwest and southwest corner).

3.4.3.3. Contamination

The Geo-Environmental and Geotechnical Reports have identified the presence of Polycyclic Aromatic Hydrocarbons (PAH), asbestos as loose fibres and board and elevated concentrations of Total Petroleum Hydrocarbon (TPH) (which may be associated with pond infill). Supplementary investigation is recommended. Gas protection measures will be required for the proposed residential development.

3.5. Water Environment

3.5.1. Drainage

3.5.1.1. Land Drainage

There is no evidence indicating that there are any land drainage systems within the site. If any land drainage is encountered during construction, it must be reconnected and/or diverted to ensure ongoing drainage post-development.

3.5.1.2. Private Drainage

There are no records of any private drainage within the Site. However, due to the Site being surrounded by residential developments, it is possible that private drainage is present within the Site.

3.5.1.3. Public Sewerage

UU sewer records for the site and surrounding area have been obtained are provided in **Appendix A**.

There is a 525mm diameter combined sewer of unknown depth running along White Moss Road, which flows in a westerly direction. A combined sewer (525mm diameter, approximately 3.5m deep) runs through the northern area of the Site and connects into the sewer under White Moss Road.

There is a 225mm diameter combined sewer, approximately 3m deep, along Lilstock Walk to the west of the site, flowing in an easterly direction, before turning in Woodmere Drive. A 225mm diameter combined sewer, approximately 3m deep, runs along the site's south-westerly boundary, before turning into Dam Head Drive. This sewer flows in a south-easterly direction.

A site constraints plan (drawing reference 5218589-ATK-WT-XX-DR-D-0501) showing the public sewers location is provided in **Appendix B**.

3.5.2. Watercourses

MCC development enquiry response (section 2.3) highlights the possibility of the presence a section of the Lionfield Brook culverted watercourse crossing the site or is in close proximity to the Site.

The Lionfield Brook, ordinary watercourse, is located approximately 100m to the south of the site, within Bailey's Wood. The Boggart Hole Brook is located approximately 1km to the south of the site.

3.5.3. Waterbodies

There are no waterbodies located within the site. A Boating Lake is located approximately 1km to the south of the site.

3.5.4. Groundwater

According to Environment Agency mapping and the Geo-Environmental and Geotechnical Reports, the Site is not located within any groundwater source protection zones. The superficial deposits are designated as a Secondary Undifferentiated Aquifer. The bedrock underlying the Site is classified as a Secondary B aquifer.

Groundwater was encountered at a minimum depth of 0.9m AOD in a borehole at the southern corner of the Site.

4. Proposed Development

4.1. Description


The proposal involves the development of residential housing, comprising of 38 units, a mix of 2 and 3 bedroom properties and a new access road. The new access road will come off White Moss Road and provide access to 25 of the new houses, with the other 13 houses being accessed from Dam Head Drive.

The proposed development layout is included in **Appendix B**.

4.2. Sequential Test

According to the Environment Agency Flood Map, shown in Figure 4-1, the Site is located wholly within Flood Zone 1 (low risk; <0.1% annual exceedance probability (AEP)).

According to the Planning Practice Guidance², Table 2, the Proposed Development is classified as *More Vulnerable* as it is a residential development. Planning Practice Guidance, Table 3 shows that *More Vulnerable* development is compatible with Flood Zone 1 hence the Proposed Development is deemed to pass the Sequential Test.



Source: Environment Agency

Figure 4-1 Environment Agency Flood Map

5. Flood Risk Assessment

5.1. Flooding History

Consultation with the EA and UU has established that there are no records of flooding at or in the vicinity of the Site. MCC have a flood/drainage incident on record, approximately 30m south of the central part of the Site, dated 2020, associated with blocked gully or drain.

5.2. Identification of Flooding Sources

The Planning Practice Guidance² requires the risk of flooding from the following sources be considered:

- **Fluvial (river)** – The Environment Agency Flood Map, included in Figure 4-1, shows that the site is entirely located within Flood Zone 1 (low risk, <0.1% AEP), therefore the risk of fluvial flooding is considered low and does not require further consideration.
- **Coastal, tidal and estuarine** – The Site is remote from coastal, tidal and estuarine waters hence the risk associated with this source is negligible.
- **Surface water** – The Environment Agency Surface Water Flood Map, included in Figure 5-1, shows that the Site is not affected by surface water flooding. Minor area in roads surrounding the Site (White Moss Road, Dam Head Drive, Cullen Grove and Earby Road) are affected by low and medium risk of surface water flooding, however their associated flow paths do not encroach the Site area. MCC recorded a blocked gully or drain incident to the south of the Site, where levels are lower than Site levels. Therefore, the risk associated with surface water flooding is negligible.
- **Groundwater** – As described in section 3.5.4, groundwater was encountered in boreholes at a minimum depth of 0.9m AOD. MCC groundwater flooding mapping shows that the site is not located in an area subject to groundwater flooding. Also, as the Site is relatively steep and the area to the south of the Site sits at lower ground levels than the Site; if groundwater was to emerge, it would flow towards the south into the Lionfield Brook. Therefore, the risk of groundwater flooding is considered to be low and does not require further consideration.
- **Sewers** – Consultation with UU has established that are no records of sewer flooding incidents at or in the vicinity of the Site and did not mention any capacity issues. Therefore, the risk of sewer flooding is considered low and does not require further consideration.
- **Artificial sources** – The EA Reservoir Flood Map, included in Figure 5-2, shows that the Site is not located in a flow path of impounded water bodies at an elevation higher than the site, hence the risk from this source is negligible and does not require further assessment.




Figure 5-1 Environment Agency Surface Water Flood Map




Figure 5-2 Environment Agency Reservoir Flood Map

5.3. Flood Risk Management

The Proposed Development will incorporate the following flood risk management measures to mitigate flooding risk:

- The finished floor level of all accommodation buildings within each plot will be at least 0.15m above adjacent external ground levels in order to reduce the risk of overland flows entering the property. Where flush thresholds are required, these must be ramped up to the finished floor level to maintain the required level difference.
- Wherever possible, the external ground profile around buildings will ensure that surface water is directed away from the building.
- The Proposed Development will incorporate a positive surface water drainage system, described further in section 6, that will intercept run-off from roofs and paved areas rather than allowing them to flow unchecked through the Proposed Development.

5.4. Residual Risks

Residual risks are those risks that remain once the flood risk management measures described above have been implemented. These are typically associated with extreme events (greater than the 1% AEP plus climate change event) that overwhelm drainage systems and exceed the parameters used to design any mitigation measures.

The principal residual risk that will affect this Site is an extreme rainfall event which exceeds the capacity of the proposed surface water drainage system to both intercept and convey flows. During such an event, water that is unable to enter the formal drainage system, will flow over the ground surface through the Proposed Development, and be directed towards the highway drainage for the northern area of the Site and towards the south into the Lionfield Brook for the southern area of the Site.

6. Surface Water Drainage Strategy

6.1. Existing Drainage Regime

The Site in its current condition drains either via infiltration into the ground or by overland flow into the highway drainage surrounding the Site.

In order to assess the existing run-off flow rates that could be generated by the Site, the current greenfield runoff rates have been calculated using IH124 Flood Estimation for Small Catchments with the ICP SUDS modifications as the Site has an area of less than 50ha. MicroDrainage Source Control was used to undertake the calculations using the following parameters:

- Area 1.11ha
- SAAR (Standard Annual Average Rainfall) 995mm
- SOIL 0.45
- Urban 0.000
- Region 10

The calculation results are shown in Table 6-1.

AEP	Run-off flow (l/s)
100%	6.1
42.9% (QBAR)	7.0
3.3%	11.9
1%	14.6

Table 6-1 - Existing surface water run-off rates

6.2. Proposed Outfall

Surface water run-off from the Proposed Development will be discharged into a local public combined water sewer located to the west of the site at two separate point of connections (UU manhole ref. 4415 and 4305).

As described in section 3.4.3.3, the ground beneath the Site is likely to be contaminated; therefore, infiltration as a means of surface water disposal is not considered viable due to the risk of mobilising contaminants.

6.3. Maximum Permitted Discharge Rate

The maximum total discharge rate from the Proposed Development into the public combined water sewer will be limited to 6l/s. This flow rate has been provided by UU (refer to section 0) and it is lower than the Qbar greenfield runoff rate of 7.0l/s.

As the Site is proposed to discharge surface water into two different point of connections, the maximum total discharge rate has been pro-rated based on catchment areas. The calculation results are shown in Table 6-2.

Catchment	Area (ha)	Discharge Rate (l/s)
Western	0.72	3.9
Eastern	0.39	1.1

Table 6-2 - Catchments discharge rates

6.4. SuDS Selection

The LLFA requires SuDS to be considered for inclusion within the drainage strategy for the Proposed Development. The SuDS techniques suitable for this development have been identified using the selection process defined in CIRIA C697 *The SuDS Manual*³ and information provided in CIRIA C753 *The SuDS Manual*⁴.

The Proposed Development is residential; therefore, according to CIRIA C697³, Table 5.2 (reproduced in **Appendix C**), all SuDS techniques other than perimeter sand filter are considered acceptable.

As described in Section 6.2, surface water from the Proposed Development will be discharged into UU's combined sewer. Surface water disposal via infiltration is not considered to be viable as the primary method of surface water discharge, due to the risk of mobilising contaminants.

According to CIRIA C753⁴, Table 4.3, the Proposed Development, including the access roads, has a *low* pollution hazard level. For *low* pollution hazard levels, this necessitates the *Simple Index Approach* to assess the water quality management requirements for the proposed development.

According to CIRIA C753⁴, Table 26.2, the *low* pollution hazard levels for the Proposed Development translate to the pollution hazard indices set out in Table 6-5.

Land use	Pollution hazard level	Total suspended solids (TSS)	Metals	Hydrocarbons
Residential roofs	Very low	0.2	0.2	0.05
Individual property driveways, residential car parks, low traffic roads (<300 movements/day)	Low	0.5	0.4	0.4

Table 6-3 - Development pollution hazard indices

The parameters for the initial selection of SuDS components for this site using CIRIA C697³ Table 5.4, reproduced in **Appendix C** are as follows:

- Soils: Impermeable
- Area draining to a single SuDS component: 0 – 2ha
- Minimum depth to water table: 0-1m
- Site slope: > 5%
- Available head: 1 – 2m
- Available space: Low

Based on this initial selection process, the following SuDS techniques are identified as being potentially suitable for this site:

- Subsurface storage
- Green roofs
- Rainwater harvesting

Subsurface storage is anticipated to provide the primary surface water storage within the Proposed Development. This will take the form of storage tanks located underneath the private section of the roads for the western catchment and oversized pipes for both the western and eastern catchments.

The Proposed Development does not include green roofs. This is due to uncertainties regarding the ongoing future maintenance that the householder will need to undertake to ensure that they remain operational and effective into the future.

Rainwater harvesting systems for the residential properties on this site are not proposed for this development. This is due to uncertainty regarding the maintenance of such systems when installed in private properties. However, all properties may be fitted with rainwater butts on appropriate downpipes.

³ C697 The SUDS Manual, CIRIA, 2007

⁴ C753 The SUDS Manual, CIRIA, 2016

Although CIRIA C697³, Table 5.2, rules out permeable paving due to high water table and site slope; hence able provide only limited storage; it is proposed to use permeable paving in the parking areas and private roads to provide water treatment for flows passing through it. The private parking areas are considered to present a higher risk of surface run-off pollution due to substances dripping from parked vehicles and tyre and brake material deposited as vehicles manoeuvre. Permeable paving will need to be lined and constructed above the water table.

Trapped gullies will be used on the public road to separate contaminants and silt from the surface water run-off before it reaches the outfall.

Pocket filter drains are proposed for each residential housing downpipe to provide both interception and water quality benefits for residential roof runoff. Details of pocket filter drains will be established later in the design process.

The percentage of the total Site's run-off treated by each SuDS component is shown in Table 6-4.

SuDS component	Run-off treated by the SuDS component (% of total runoff)
Permeable paving	30
Pocket filter drain	55
Trapped Gully	15

Table 6-4 - % of total run-off treated by each SuDS component

The pollution mitigation indices for pocket filter drain and permeable paving are set out in Table 6-5 as follows (CIRIA C753, Table 26.3).

SuDS component	Total suspended solids (TSS)	Metals	Hydrocarbons
Pocket filter drain	0.4	0.4	0.4
Permeable paving	0.7	0.6	0.7

Source: CIRIA C753, Table 26.3 and 26.4 (extract)

Table 6-5 - Pollution mitigation indices for permeable paving

Table 6-6 demonstrates that the SuDS techniques identified above will achieve the required degree of pollution mitigation for each of the different land uses.

Land use	Pollution hazard indices			SuDS feature	Pollution mitigation indices		
	TSS	Metals	Hydrocarbons		TSS	Metals	Hydrocarbons
Residential roofs	0.2	0.2	0.05	Green roof	0.4	0.4	0.4
Individual property driveways, carparks, low traffic roads (<300 movements/day)	0.5	0.5	0.4	Permeable paving	0.7	0.6	0.7

Table 6-6 - Potential SuDS configurations

6.5. Proposed Strategy

The drainage strategy is illustrated on drawing number 5218589-ATK-WT-XX-DR-D-0502 *Proposed Drainage Strategy*, included in **Appendix B**.

The Proposed Development is divided into two catchments areas (Western and Eastern), each of which is proposed to drain independently to its own outfall. Based on proposed development layout plans, the development has been calculated 60% impermeable. The total impermeable area that the surface water drainage system must achieve is 0.67ha.

It is proposed that the surface water drainage system will comprise a conventional pipe network, alongside SuDS components, draining to cellular storage tanks for the western catchment and oversized pipes for both the western and eastern catchments. Due to high groundwater, floatation checks need to be undertaken on the cellular storage and measures to prevent groundwater ingress into the tank implemented.

Hydro-Brake® flow controls are proposed to be used prior to each outfall into the sewer, limiting the flow to the maximum permitted flow rate for the Site, as detailed in Table 6-2.

The storage has been designed to provide the necessary flow attenuation for all rainfall events up to and including the 1% AEP +45% climate change event.

The required storage volumes have been determined using MicroDrainage Source Control; results are illustrated in Table 6-7. Calculation results in full are provided in **Appendix D**.

Catchment	Total Area (ha)	Imp. Area (ha)	Discharge Rate (l/s)	Required Storage (m³)
West	0.72	0.43	3.9	280
East	0.39	0.24	1.1	140

Table 6-7 - Storage requirements

6.6. Adoption & Maintenance

It is anticipated that the underground pipework and attenuation storage within the proposed surface water drainage system will be offered to UU for adoption.

7. Foul Water Drainage Strategy

7.1. Foul Water Flow Rates

As described in section 4.1, the Proposed Development comprises 38 accommodation buildings. Based on the Design and Construction Guidance, clause B3.1.1.(b), each dwelling generates 4,000 l/dwelling/day; therefore, the peak foul water flow rate generated by the proposed development will be 1.8l/s (based on 6 dry weather flow (DWF)).

7.2. Proposed Outfall

Correspondence with UU confirmed that there is a suitable point of connection into a 225mm diameter public combined sewer located to the west of the Proposed Development at an unrestricted rate.

Foul water flows from the Proposed Development will be discharged into this public combined sewer at two separate points of connection (UU manhole ref. 4415 and 4305).

7.3. Strategy

It is proposed that foul water flows within the Proposed Development will be conveyed via a gravity pipe network. The pipe network will consist of pipes laid at gradients that enable self-cleansing flow velocities to be achieved in accordance with the Design and Construction Guidance.

7.4. Adoption & Maintenance

It is anticipated that the proposed foul water drainage system will be offered to UU for adoption.

8. Conclusions & Recommendations

8.1. Conclusions

The Site is located within Flood Zone 1 (<0.1% AEP, low risk) for fluvial flooding. Therefore, the risk associated with fluvial flooding is considered low.

Minor areas in roads surrounding the Site are affected by low and medium risk of surface water flooding, but their associated flow paths do not encroach the Site area and therefore are considered negligible.

Risks of flooding from; groundwater, sewers, reservoirs, coastal, tidal, and estuarine are considered to be low or negligible.

The following flood risk management measures will be incorporated into the Proposed Development:

- Finished floor levels shall be at least 0.15m above adjacent external ground levels.
- External ground profiles shall, where possible, fall away from buildings.
- A positive surface water drainage system shall be implemented.

The primary residual risk affecting the Proposed Development relates to an extreme rainfall event exceeding the capacity of the proposed surface water drainage system to intercept and convey flows. This will result in additional overland flows through the Site and potential surface water flooding

Surface water run-off from the Proposed Development will be discharged into a local public combined water sewer located to the west of the site at two separate points of connection (UU manhole ref. 4415 and 4305) at a maximum total discharge rate of 6l/s, prorated based on catchment areas. The ground beneath the Site is likely to be contaminated; therefore, infiltration as a means of surface water disposal is not considered viable.

The proposed surface water drainage system will incorporate SuDS. Subsurface storage is anticipated to provide the primary surface water storage within the Proposed Development, in the form of storage tanks and oversized pipes. The Proposed Development does not include green roofs and rainwater harvesting systems, due to uncertainties regarding the ongoing future maintenance that the householder will need to undertake to ensure that they remain operational and effective. However, all properties may be fitted with rainwater butts on appropriate downpipes.

Permeable pavings are proposed in the parking areas and private roads to provide water treatment for flows passing through it. These will need to be lined and constructed above the water table. Pocket filter drains are proposed for each residential housing downpipe to provide both interception and water quality benefits for residential roof runoff.

The Proposed Development is divided into two catchments areas (Western and Eastern), each of which is proposed to drain independently to its own outfall. It is proposed that the surface water drainage system will primarily comprise a conventional pipe network draining to cellular storage tanks for the western catchment and oversized pipes for both the western and eastern catchments. Due to high groundwater, floating checks need to be undertaken on the cellular storage and measures to prevent groundwater ingress into the tank implemented.

Hydro-Brake® flow controls are proposed to be used prior to each outfall into the sewer, limiting the flow to the maximum permitted flow rate for the Site.

The storage has been designed to provide the necessary flow attenuation for all rainfall events up to and including the 1% AEP +45% climate change event.

The peak foul water flow rate generated by the proposed development will be 1.8l/s. These are proposed to be discharged into the public combined sewer to the west of the site at two separate points of connection (UU manhole ref. 4415 and 4305). The suitability of the connections has been confirmed by UU.

Both the proposed surface and foul water drainage systems will be offered to UU for adoption.

8.2. Recommendations

This Flood Risk Assessment is suitable for submission in support of a full planning application for the Proposed Development.

The design of the Proposed Development and its drainage systems must comply with the principles and parameters defined in this document or a suitable alternative as agreed with the relevant approving authorities.

Appendices



Appendix A. Correspondence

Wilkinson, Ruth

From: GMMC Info Requests <InfoRequests.GMMC@environment-agency.gov.uk>
Sent: 19 October 2022 09:23
To: Wilkinson, Ruth
Subject: GMMC281028SW Response attached from the Environment Agency

Dear Ruth,

Thank you for your enquiry which was received on 23/09/22.

We respond to requests under the Freedom of Information Act 2000 and Environmental Information Regulations 2004.

The site proposal is located in Flood Zone 1, very low risk. Our nearest model is in Blackley, which has no impact to this site location.

We have no flood defences in the vicinity of this site.

We have no records of flooding affecting the site. However, this does not mean flooding has not occurred in the past or that it will not flood in future. We recommend that you also contact United Utilities and the lead local flood authority who may hold additional information (the former especially in relation to sewer flooding).

For further information on your property's flood risk, visit:

Long term flood risk website: <https://flood-warning-information.service.gov.uk/long-term-flood-risk/>

Flood Map for Planning: <https://flood-map-for-planning.service.gov.uk/>

For surface water information please use link: <https://check-long-term-flood-risk.service.gov.uk/map?easting=362125.07&northing=388310.97&map=SurfaceWater>

Please refer to the [Open Government Licence](#) which explains the permitted use of this information.

Please get in touch if you have any further queries or contact us within two months if you'd like us to review the information we have sent.

Kind regards,

Sarah

Sarah Walters | Customer and Engagement Officer
Greater Manchester, Merseyside and Cheshire

Direct email: InfoRequests.GMMC@environment-agency.gov.uk

Office address: Richard Fairclough House, Knutsford Road, Latchford, Warrington, WA4 1HT



From: Wilkinson, Ruth <Ruth.Wilkinson@atkinsglobal.com>
Sent: 23 September 2022 10:50

To: Enquiries, Unit <enquiries@environment-agency.gov.uk>

Subject: 220929/GA09-Ref: Development enquiry - Former White Moss Day Care Centre, Benmore Road, M9 6DN

You don't often get email from ruth.wilkinson@atkinsglobal.com. [Learn why this is important](#)

Good morning,

I am contacting you in regards to a proposed residential development at former White Moss Day Care Centre near Benmore Road, Manchester. Please find the site location details below and the site location plan attached.

Site location: Adjacent to Benmore Road, M9 6DN

NGR coordinates: 386650, 403521

I am preparing a Drainage Strategy to support a planning application and would be grateful if you could advise on the following:

- Confirm that the site lies within Flood Zone 1
- Whether there are any records of flooding from any source in the vicinity of the site
- Are you aware of any specific flood risk and/or drainage issues that need to be considering within the Drainage Strategy for this site?


Please contact me if you require any clarifications about this enquiry.

Kind Regards,

Ruth Wilkinson *MEng*
Graduate Civil Engineer, Infrastructure
UK & Europe
Engineering, Civil Engineering & Advanced Technology

 + (44) 1214835888

Two Chamberlain Square, Birmingham, West Midlands, B3 3AX



Company



At Atkins - member of the SNC-Lavalin Group, we work flexible hours around the world. Although I have sent this email at a time convenient for me, I don't expect you to respond until it works for you.

NOTICE – This email message and any attachments may contain information or material that is confidential, privileged, and/or subject to copyright or other rights. Any unauthorized viewing, disclosure, retransmission, dissemination, or other use of or reliance on this message or anything contained therein is strictly prohibited and may be unlawful. If you believe you may have received this message in error, kindly inform the sender by return email and delete this message from your system. Thank you.

Information in this message may be confidential and may be legally privileged. If you have received this message by mistake, please notify the sender immediately, delete it and do not copy it to anyone else. We have checked this email and its attachments for viruses. But you should still check any attachment before opening it. We may have to

make this message and any reply to it public if asked to under the Freedom of Information Act, Data Protection Act or for litigation. Email messages and attachments sent to or from any Environment Agency address may also be accessed by someone other than the sender or recipient, for business purposes.

Wilkinson, Ruth

From: Walters, Sarah <Sarah.Walters2@environment-agency.gov.uk>
Sent: 17 January 2023 13:42
To: Wilkinson, Ruth
Subject: GMMC281028SW Response attached from the Environment Agency
Attachments: Ref: 220929/GA10-Development enquiry - White Moss Road, M9 6DA;
GMMC281028SW Response attached from the Environment Agency

Dear Ruth,

Thank you for your enquiry.

We respond to requests under the Freedom of Information Act 2000 and Environmental Information Regulations 2004.

I have attached the response that was sent on the 19th October 2022. Occasionally we get multiple requests for the same sites and to reduce workload with our limited resources, we close these as duplicate emails sent in error. Our team believed both emails submitted were regarding the same site as their postcodes were the same, so the information provided was referring to both enquiries, I apologise for any inconvenience caused.

If you require any further information, please let me know.

Please refer to the [Open Government Licence](#) which explains the permitted use of this information.

Please get in touch if you have any further queries or contact us within two months if you'd like us to review the information we have sent.

Kind regards,

Sarah

Sarah Walters | Customer and Engagement Officer
Greater Manchester, Merseyside and Cheshire

Direct email: InfoRequests.GMMC@environment-agency.gov.uk

Office address: Richard Fairclough House, Knutsford Road, Latchford, Warrington, WA4 1HT

Please consider this a “thanks” in advance.

Every email has a carbon footprint. So if you don't hear back from me,
it's not because of you, it's because of the planet.

#WhatWeCanDo

From: Enquiries, Unit <enquiries@environment-agency.gov.uk>
Sent: 17 January 2023 12:08
To: 'Wilkinson, Ruth' <Ruth.Wilkinson@atkinsglobal.com>
Cc: GMMC Info Requests <InfoRequests.GMMC@environment-agency.gov.uk>
Subject: RE: 220929/GA10-Development enquiry - White Moss Road, M9 6DA

Good Afternoon,

For your information, I have passed your email onto the local Customer and Engagement team who will be able to look into request 220929/GA10.

Kind Regards,

Ian Collier
National Customer Contact Centre
Environment Agency

☎ Tel: 03708 506 506

💻 Web Site: www.gov.uk/environment-agency

From: Wilkinson, Ruth <Ruth.Wilkinson@atkinsglobal.com>
Sent: 09 January 2023 11:00
To: Enquiries, Unit <enquiries@environment-agency.gov.uk>
Subject: RE: 220929/GA10-Development enquiry - White Moss Road, M9 6DA

Good Morning,

I requested some information for a flood risk assessment on a potential site in Manchester. The reference is 220929/GA10. I do not believe that I ever received an email with the following information that was asked for back on the 29th September 2022.

- Confirm that the site lies within Flood Zone 1
- Whether there are any records of flooding from any source in the vicinity of the site
- Are you aware of any specific flood risk and/or drainage issues that need to be considering within the Flood Risk Assessment and Drainage Strategy for this site?

At the time I put in another request, with reference 220929/GA09, and received an email in response with the relevant information on the 19th October 2022.

Please could you help clarify if this email was every sent out with the information on and if not please could I have that information at the earliest convenience.

Many thanks,

Ruth Wilkinson *MEng*
Graduate Civil Engineer, Infrastructure
UK & Europe
Engineering, Civil Engineering & Advanced Technology

☎ +(44)1214835888

Two Chamberlain Square, Birmingham, West Midlands, B3 3AX



ATKINS
Member of the SNC-Lavalin Group

Company    

From: Enquiries, Unit <enquiries@environment-agency.gov.uk>
Sent: 29 September 2022 11:36
To: Wilkinson, Ruth <Ruth.Wilkinson@atkinsglobal.com>
Subject: Ref: 220929/GA10-Development enquiry - White Moss Road, M9 6DA

Good morning Ruth,

I have passed your e-mail to the local customer team who will deal with your request.

The Freedom of Information Act and Environmental Information Regulations state that a public authority must respond to requests for information within 20 working days.

You can find more information about our service commitment by clicking on the link below:

<https://www.gov.uk/government/publications/environment-agency-customer-service-commitment>

You can contact our customer team directly on the contact details below, or call the National Customer Contact Centre on 03708 506506 who will transfer you to the area team.

Please quote your enquiry reference 220929/GA10 in any correspondence with us regarding this matter.

Customers and Engagement
Environment Agency
Greater Manchester, Merseyside and Cheshire Area
Richard Fairclough House
Knutsford Road
Latchford
Warrington
WA4 1HT

Kind regards,

Gabriella Alföldy
Customer Service Advisor
Environment Agency
Tel: 03708 506 506
Web Site: <https://www.gov.uk/environment-agency>
Click an icon to keep in touch with us:



From: Wilkinson, Ruth <Ruth.Wilkinson@atkinsglobal.com>
Sent: 23 September 2022 10:44
To: Enquiries, Unit <enquiries@environment-agency.gov.uk>
Subject: Ref: 220929/GA10-Development enquiry - White Moss Road, M9 6DA

You don't often get email from ruth.wilkinson@atkinsglobal.com. [Learn why this is important](#)

Good morning,

I am contacting you in regards to a proposed residential development at White Moss Road, Manchester. Please find the site location details below and the site location plan attached.

Site location: Adjacent to White Moss Road, M9 6DA. Between Lilstock Walk and Wanley Walk.

NGR coordinates: 386427, 403450

I am preparing a Flood Risk Assessment and Drainage Strategy to support a planning application and would be grateful if you could advise on the following:

- Confirm that the site lies within Flood Zone 1
- Whether there are any records of flooding from any source in the vicinity of the site
- Are you aware of any specific flood risk and/or drainage issues that need to be considering within the Flood Risk Assessment and Drainage Strategy for this site?

Please contact me if you require any clarifications about this enquiry.

Kind Regards,

Ruth Wilkinson *MEng*

Graduate Civil Engineer, Infrastructure

UK & Europe

Engineering, Civil Engineering & Advanced Technology

+ (44) 121 483 5888

Two Chamberlain Square, Birmingham, West Midlands, B3 3AX



ATKINS

Member of the SNC-Lavalin Group

Company



At Atkins - member of the SNC-Lavalin Group, we work flexible hours around the world. Although I have sent this email at a time convenient for me, I don't expect you to respond until it works for you.

NOTICE – This email message and any attachments may contain information or material that is confidential, privileged, and/or subject to copyright or other rights. Any unauthorized viewing, disclosure, retransmission, dissemination, or other use of or reliance on this message or anything contained therein is strictly prohibited and may be unlawful. If you believe you may have received this message in error, kindly inform the sender by return email and delete this message from your system. Thank you.

Information in this message may be confidential and may be legally privileged. If you have received this message by mistake, please notify the sender immediately, delete it and do not copy it to anyone else. We have checked this email and its attachments for viruses. But you should still check any attachment before opening it. We may have to make this message and any reply to it public if asked to under the Freedom of Information Act, Data Protection Act or for litigation. Email messages and attachments sent to or from any Environment Agency address may also be accessed by someone other than the sender or recipient, for business purposes.

Information in this message may be confidential and may be legally privileged. If you have received this message by mistake, please notify the sender immediately, delete it and do not copy it to anyone else. We have checked this email and its attachments for viruses. But you should still check any attachment before opening it. We may have to make this message and any reply to it public if asked to under the Freedom of Information Act, Data Protection Act or for litigation. Email messages and attachments sent to or from any Environment Agency address may also be accessed by someone other than the sender or recipient, for business purposes.

Wilkinson, Ruth

From: wastewaterdeveloperservices@uuplc.co.uk
Sent: 06 October 2022 16:17
To: Wilkinson, Ruth
Subject: RE: Our reference - 02844365 White Moss Road, Manchester, M9 6DA

Good afternoon Ruth,

Pre Development Enquiry for: Charlestown, Manchester UU Reference Number : 02844365

We have carried out an assessment of your application which is based on the information provided. This pre-development advice on your drainage strategy will be valid for 12 months. Your drainage strategy will need to be reviewed by other competent authorities as part of the planning process, and we advise that you carry out the necessary site investigations to confirm the viability of your proposals.

If your investigations require access to our public sewer network, we ask that you contact our network engineers with a request for an access certificate via our main contact telephone number 0345 6723 723 or refer to the link below:

<https://www.unitedutilities.com/builders-developers/working-near-our-assets/>

Foul Water

Foul flow from this site will be allowed to drain into the public foul water/combined sewer system.

Our preferred point of discharge would be to the 225mm diameter public 4combined sewer located to the West of your proposed development at an unrestricted rate.

If you are able to identify an alternative, more suitable point of discharge, we request that you contact us at your earliest convenience so that we can assess suitability.

Please ensure all proposed manhole chambers cover levels and finished floor levels are higher than the receiving public sewer.

Surface Water

All surface water flow from the proposed development should drain in-line with the drainage hierarchy, as outlined in Paragraph 80, (Reference ID: 7-080-20150323), of the National Planning Practice Guidance. We also recommend you prioritise the use of multi-functional sustainable drainage systems for the management of surface water in accordance with national planning policy.

Generally, the aim should be to discharge surface run off as high up the following hierarchy of drainage options as reasonably practicable.

This is outlined as follows, in order of priority:

1. **into the ground (infiltration);**
2. **to a surface waterbody;**
3. **to a surface water sewer or highway drain;**
4. **to a combined sewer.**

For guidance, The [North West SuDS Pro-Forma](#) provides information on the appropriate evidence required at each stage of the hierarchy, to demonstrate how each level has been discounted.

The Lead Local Flood Authority has responsibility for all surface water drainage concerns and their input to your proposal is critical. You should also consider whether it is necessary to discuss your proposal with the Environment Agency, or Internal Drainage Board (if operating in your area).

The Local Planning Authority are the determining authority for any application for planning permission and the appropriate authority for determining cost viability of a proposed drainage scheme, such assessments are outside of the jurisdiction of United Utilities.

Infiltration

Surface water runoff generated from this development should discharge to the ground via infiltration system where feasible.

A detailed evidence based feasibility assessment must be carried out in line with Chapter 25 of the CIRIA SuDS Manual 2015 to determine whether infiltration is a suitable method of surface water disposal.

Particular attention must be paid to Ground Water Source Protection Zones to ensure that the risk of pollution to these valuable resources is not compromised. Details can be obtained from the government website:

<https://www.gov.uk/guidance/groundwater-source-protection-zones-spzs#find-groundwater-spzs>

If your site is in a Groundwater Source Protection Zone, you should have regard to the Environment Agency's approach to Groundwater Protection. Information on this is available via the link below:

<https://www.gov.uk/government/publications/groundwater-protection-position-statements>

Please note that such a location could have implications for the principle of your development and the need for additional mitigating measures to protect the groundwater environment and public water supply in the detailed design of your site.

Waterbody

If an evidence based assessment has been carried out and confirms that infiltration is not feasible, we recommend that you contact the Lead Local Flood Authority and/or Environment Agency to discuss a point of discharge to the culverted/open ordinary watercourse located 40m Southeast of the proposed site.

We would encourage you to identify and engage with any third party landowner and riparian owner to agree access and discharge rights to the water body if this is not in your ownership.

Highway Drainage

If an evidence based assessment has been carried out and confirms that infiltration is not feasible, we recommend that you investigate the possibility of draining surface water to the highway drain where this ultimately discharges to a watercourse, by contacting the relevant Highway Authority.

Public Sewer

In accordance with the hierarchy of drainage options within the National Planning Practice Guidance, both discharge to ground via infiltration and discharge to a waterbody should be discounted prior to consideration of discharging surface water to the public sewer system. Evidence should be provided to demonstrate how these have been discounted, as outlined in the North West SuDS pro-forma.

Once evidence is provided as outlined above, United Utilities will consider a connection to the 225mm diameter public combined sewer located West of the proposed site at a pass forward flow to be agreed by the Lead Local Flood Authority. United Utilities request that any agreed rate does not exceed 6l/s.

As a Water Company, we have no obligation to accept highway drainage into our public sewer network. However, should your proposals include runoff from highways, we would request that consideration is given to SuDS components that deliver source control are incorporated within the design of the scheme to reduce the volume and frequency of discharges of these flows to the public sewer.

Levels

For low-lying sites, (where the ground level of the site or the level of a basement is below the ground level at the point where the drainage connects to the public sewer), care should be taken to ensure that the property is not at increased risk of flooding. If these circumstances exist, we recommend that you contact us to discuss further. It could affect the detailed design of your site and result in the need to incorporate appropriate mitigating measures in your drainage scheme.

Land drainage / Overland flows / track drainage

United Utilities have no obligation, and furthermore we do not accept land drainage, overland flows or track drainage into the public sewerage network under any circumstances

Existing Wastewater Assets Crossing the Site

According to our public sewer records there are public sewers located within your site boundary. We will require unrestricted access to the sewer for maintenance purposes, we would ask that you maintain a minimum clearance of 6m which is measured 3m from the centre line of the pipe unless there happens to be a formal easement agreement in place, in which case the specified easement width would apply. If you cannot achieve this then you may wish to consider diverting and or abandoning the public sewer.

Please be aware that any proposed diversion may require modelling. This process may take up to 6 months in order to reach an acceptable design.

Please refer to the link below to obtain full details of the processes involved with sewer diversions:

<https://www.unitedutilities.com/builders-developers/larger-developments/wastewater/sewer-diversions/>

Please refer to the link below to obtain full details of the processes involved with sewer closure:

<https://www.unitedutilities.com/builders-developers/wastewater-services/close-a-sewer/sewer-closures/>

Existing Water Assets Crossing the Site

It is the developer responsibility to identify utilities on-site. Where clean water assets are shown on our records, we recommend that you contact our Water Pre-Development Team, via the following email address:

DeveloperServicesWater@uuplc.co.uk. Further information for this service can be found on our website via the link below:

<https://www.unitedutilities.com/builders-developers/larger-developments/pre-development/water-pre-dev/>

Connection Application

Although we may discuss and agree discharge points and rates in principle, please be aware that you will have to apply for a formal sewer connection. This is so that we can assess the method of construction, Health & Safety requirements and to ultimately inspect the connection when it is made. Details of the application process and the form itself can be obtained from our website by following the link below:

<https://www.unitedutilities.com/builders-developers/wastewater-services/sewer-connections/sewer-connection/>

We recommend that the detailed design should confirm the locations of all utilities in the area and ensure that any proposed drainage solution considers routing and clash checks where required.

Sewer Adoptions

You have indicated on your application form that you intend to put the sewers forward for adoption (including any SuDS components that can come within the meaning of a sewer).

United Utilities assess adoption applications based on the current Design & Construction Guidance and local practices which have now replaced 'Sewers For Adoption 6th Edition'.

We recommend that you submit a pre design assessment to the sewer adoption mailbox (SewerAdoptions@uuplc.co.uk) stating pre design assessment in the title

Please refer to links below to obtain further guidance:

<https://www.unitedutilities.com/builders-developers/larger-developments/wastewater/sewer-adoptions/>

Site drainage must be designed in accordance with Building Regulations, National Planning Policy, and local flood authority guidelines, we would recommend that you speak and make suitable agreements with the relevant statutory bodies.

If you intend to put forward your wastewater assets for adoption by United Utilities, the proposed detail design will be subject to a technical appraisal by an Adoption Engineer as we need to be sure that the proposals meets the requirements set out in the Design & Construction Guidance. The proposed design should give consideration to long term operability and give United Utilities a safe and cost effective proposal for the lifetime of the assets. In these cases, we strongly recommend that no construction commences until the detailed drainage design, submitted as part of the Section 104 application, has been assessed and accepted in writing by United Utilities. Any work carried out prior to the technical assessment being approved is done entirely at the developer's own risk and could be subject to change.

SuDS

If your development proposal incorporates any SuDS component(s) which interact with a sewer network you plan on offering for adoption to United Utilities; contact should be made with our technical team at your earliest convenience, please complete the 'Section 104 pre-application form : ' and include as much relevant detail as you can. These discussions can help prevent delays later in the development process.

Section 104 Pre application form (1b)

As per the sewerage sector guidance, all SuDS should be designed in accordance with the standards within the Design & construction guidance & the CIRIA SuDS manual (C753)

Codes For Adoption

The new Codes for Adoption are outlined on the Water UK Website. The link below takes you to their webpage:

<https://www.water.org.uk/technical-guidance/developers-services/codes-for-adoption/>

A free copy of the new Design & Construction Guidance can be downloaded via the link below:

<https://www.water.org.uk/sewerage-sector-guidance-approved-documents/>

Many thanks and kind regards,



Mohammed Aljafarawi (He/Him)

Developer Engineer
Developer Services & Metering
Customer Services
M: 07950474499
unitedutilities.com

If you have received a great service today why not tell us?

Visit: unitedutilities.com/wow



The information contained in this e-mail is intended only for the individual to whom it is addressed. It may contain legally privileged or confidential information or otherwise be exempt from disclosure. If you have received this Message in error or there are any problems, please notify the sender immediately and delete the message from your computer. You must not use, disclose, copy or alter this message for any unauthorised purpose. Neither United Utilities Group PLC nor any of its subsidiaries will be liable for any direct, special, indirect or consequential damages as a result of any virus being passed on, or arising from the alteration of the contents of this message by a third party.

United Utilities Group PLC, Haweswater House, Lingley Mere
Business Park, Lingley Green Avenue, Great Sankey,
Warrington, WA5 3LP
Registered in England and Wales. Registered No 6559020

www.unitedutilities.com

www.unitedutilities.com/subsidiaries

Atkins - Utility Solutions

The Hub
500 Park Avenue,, Aztec West, Almondsbury
Bristol,
BS32 4RZ

FAO:

How to contact us:

United Utilities Water Limited
Property Searches
Haweswater House
Lingley Mere Business Park
Great Sankey
Warrington
WA5 3LP

Telephone: 0370 7510101

E-mail: propertysearches@uuplc.co.uk

Your Ref: 115545
Our Ref: UUPS-ORD-452036
Date: 08/12/2022

Dear Sirs

Location: 1 LINDSIDE WALK, MANCHESTER, M9 6DH

I acknowledge with thanks your request dated 07/12/2022 for information on the location of our services.

Please find enclosed plans showing the approximate position of United Utilities' apparatus known to be in the vicinity of this site.

The enclosed plans are being provided to you subject to the United Utilities terms and conditions for both the wastewater and water distribution plans which are shown attached.

If you are planning works anywhere in the North West, please read United Utilities' access statement before you start work to check how it will affect our network. <http://www.unitedutilities.com/work-near-asset.aspx>.

I trust the above meets with your requirements and look forward to hearing from you should you need anything further.

If you have any queries regarding this matter please [contact us](#).

Yours Faithfully,




Karen McCormack
Property Searches Manager

TERMS AND CONDITIONS - WASTEWATER AND WATER DISTRIBUTION PLANS

These provisions apply to the public sewerage, water distribution and telemetry systems (including sewers which are the subject of an agreement under Section 104 of the Water Industry Act 1991 and mains installed in accordance with the agreement for the self construction of water mains) (UUWL apparatus) of United Utilities Water Limited "(UUWL)".


TERMS AND CONDITIONS:

- This Map and any information supplied with it is issued subject to the provisions contained below, to the exclusion of all others and no party relies upon any representation, warranty, collateral contract or other assurance of any person (whether party to this agreement or not) that is not set out in this agreement or the documents referred to in it.
- This Map and any information supplied with it is provided for general guidance only and no representation, undertaking or warranty as to its accuracy, completeness or being up to date is given or implied.
- In particular, the position and depth of any UUWL apparatus shown on the Map are approximate only. UUWL strongly recommends that a comprehensive survey is undertaken in addition to reviewing this Map to determine and ensure the precise location of any UUWL apparatus. The exact location, positions and depths should be obtained by excavation trial holes.
- The location and position of private drains, private sewers and service pipes to properties are not normally shown on this Map but their presence must be anticipated and accounted for and you are strongly advised to carry out your own further enquiries and investigations in order to locate the same.
- The position and depth of UUWL apparatus is subject to change and therefore this Map is issued subject to any removal or change in location of the same. The onus is entirely upon you to confirm whether any changes to the Map have been made subsequent to issue and prior to any works being carried out.
- This Map and any information shown on it or provided with it must not be relied upon in the event of any development, construction or other works (including but not limited to any excavations) in the vicinity of UUWL apparatus or for the purpose of determining the suitability of a point of connection to the sewerage or other distribution systems.
- No person or legal entity, including any company shall be relieved from any liability howsoever and whensoever arising for any damage caused to UUWL apparatus by reason of the actual position and/or depths of UUWL apparatus being different from those shown on the Map and any information supplied with it.
- If any provision contained herein is or becomes legally invalid or unenforceable, it will be taken to be severed from the remaining provisions which shall be unaffected and continue in full force and affect.
- This agreement shall be governed by English law and all parties submit to the exclusive jurisdiction of the English courts, save that nothing will prevent UUWL from bringing proceedings in any other competent jurisdiction, whether concurrently or otherwise.





Refno	Cover	Func	Invert	Size x	Size y	Shape	Matl	Length	Grad	Refno	Cover	Func	Invert	Size x	Size y	Shape	Matl	Length	Grad
6403	100.52		94.51	525			VC	100.2088	1 in 1432	2207	94.63	CO	92.55	225			VC	5.52704	
6403	100.52		94.51	525			VC	100.2088	1 in 1432	2207	94.63	CO	92.55	225			VC	5.52704	
5601	101.27		90.75	225			VC	32.04955	1 in 201	2424	94.63	CO	92.55	225			VC	38.58756	1 in 16
4701	102.29		90.49	225			VC	86.30705	1 in 93	2424	94.63	CO	92.55	225			VC	38.58756	1 in 16
4701	102.29		90.49	225			VC	86.30705	1 in 93	2424	94.63	CO	92.55	225			VC	38.58756	1 in 16
5705			94.49	150			VC	9.284122		1708	94.63	CO	94.37	225			VC	4.472136	
3430	96.46		94.49	225			VC	17	1 in 26	4804	96.59	CO	94.37	225			VC	4.472136	
3430	96.46		94.49	225			VC	17	1 in 26	4804	96.59	CO	94.37	225			VC	4.472136	
4405	96.04		95.49	225			VC	45.185	1 in 21	4804	96.59	CO	94.37	225			VC	4.472136	
4404	97.49		95.85	150			VC	30.01666	1 in 25	4822		CO		150			VC	15.19679	1 in 95
5402	98.4		94.43	525			CO	97.02444	1 in 25	4822		CO		150			VC	15.19679	1 in 95
5402	98.4		94.43	525			CO	97.02444	1 in 25	4822		CO		150			VC	15.19679	1 in 95
5402	98.4		94.43	525			CO	97.02444	1 in 25	4822		CO		150			VC	15.19679	1 in 95
5402	98.4		94.43	525			CO	97.02444	1 in 25	4822		CO		150			VC	15.19679	1 in 95
4610	98.4		94.43	525			VC	8.598775		3013	95.75	CO	91.53	300			VC	5.40033	1 in 37
4501	100.14		98.21	225			VC	50.21952	1 in 173	2827		CO		150			VC	5.00031	
4501	100.14		98.21	225			VC	50.21952	1 in 173	2827		CO		150			VC	5.00031	
4507			95.24	117			VC	9.524117		2829		CO		150			VC	7.296511	1 in 85
4507			95.24	117			VC	9.524117		2829		CO		150			VC	7.296511	1 in 85
4508			95.24	117			VC	9.524117		2829		CO		150			VC	7.296511	1 in 85
4508			95.24	117			VC	9.524117		2829		CO		150			VC	7.296511	1 in 85
4508			95.24	117			VC	9.524117		2829		CO		150			VC	7.296511	1 in 85
3503	100.49		98.99	225			VC	44.10215	1 in 48	2805	95.72	CO	96.32	100			VC	69.34499	1 in 17
4794	103.62		101.58	225			VC	33.22611	1 in 129	1841		CO		0	300		VC	2.717144	
2434	95.94		93.13	225			VC	13.85283		1804		CO		0	300		VC	2.717144	
2434	95.94		93.13	225			VC	13.85283		1804		CO		0	300		VC	2.717144	
3412	96.24		94.54	225			VC	36.78754	1 in 33	1808		CO		0	300		VC	2.717144	
3412	96.24		94.54	225			VC	36.78754	1 in 33	1808		CO		0	300		VC	2.717144	
3410	95.5		93.22	300			VC	48.08326	1 in 22	1828		CO		0	300		VC	2.717144	
3410	95.5		93.22	300			VC	48.08326	1 in 22	1828		CO		0	300		VC	2.717144	
3504	97.49		96.37	225			VC	47.50789	1 in 41	1902	100.2	CO	97.33	300			VC	29.52965	1 in 95
3517	98.08		96.96	150			VC	22.84732	1 in 15	2003	96.79	CO	93.84	300			VC	21.18602	1 in 94
3518	98.08		96.96	150			VC	22.84732	1 in 15	2003	96.79	CO	93.84	300			VC	21.18602	1 in 94
3518	98.08		96.96	150			VC	22.84732	1 in 15	2003	96.79	CO	93.84	300			VC	21.18602	1 in 94
3519			96.96	150			VC	22.84732	1 in 15	2003	96.79	CO	93.84	300			VC	21.18602	1 in 94
3519			96.96	150			VC	22.84732	1 in 15	2003	96.79	CO	93.84	300			VC	21.18602	1 in 94
3519			96.96	150			VC	22.84732	1 in 15	2003	96.79	CO	93.84	300			VC	21.18602	1 in 94
3508	98.32		97.02	225			VC	33.28663	1 in 53	1921		CO		150			VC	12.07601	
3508	98.32		97.02	225			VC	33.28663	1 in 53	1921		CO		150			VC	12.07601	
3513			97.02	225			VC	33.28663	1 in 53	1921		CO		150			VC	12.07601	
3513			97.02	225			VC	33.28663	1 in 53	1921		CO		150			VC	12.07601	
1419	93.14		90.84	225			VC	33.01515	1 in 12	1903	96.79	CO	93.84	300			VC	12.07601	
1419	93.14		90.84	225			VC	33.01515	1 in 12	1903	96.79	CO	93.84	300			VC	12.07601	
2411	92.55		87.51	525			VC	30.4795	1 in 8	1904	96.79	CO	93.84	300			VC	12.07601	
2411	92.55		87.51	525			VC	30.4795	1 in 8	1904	96.79	CO	93.84	300			VC	12.07601	
1407	94.9		92.88	225			VC	24.16609	1 in 81	1905	96.79	CO	93.84	300			VC	12.07601	
1407	94.9		92.88	225			VC	24.16609	1 in 81	1905	96.79	CO	93.84	300			VC	12.07601	
1506	96.56		92.42	450			VC	32.44996	1 in 74	1904	96.79	CO	93.84	300			VC	12.07601	
1506	96.56		92.42	450			VC	32.44996	1 in 74	1904	96.79	CO	93.84	300			VC	12.07601	
2518			90.04	225			VC	11.7129		1912		CO		150			VC	16.24288	
2518			90.04	225			VC	11.7129		1912		CO		150			VC	16.24288	
2518			90.04	225			VC	11.7129		1912		CO		150			VC	16.24288	
2413	92.54		90.04	225			VC	16.12452	1 in 7	1901	99.94	CO	96.57	300			VC	106.9439	1 in 95
2413	92.54		90.04	225			VC	16.12452	1 in 7	1901	99.94	CO	96.57	300			VC	106.9439	1 in 95
1418	89.99		87.65	225			VC	18.35756	1 in 13	3514	98.33	CO	96.43	225			VC	27.52978	1 in 97
1418	89.99		87.65	225			VC	18.35756	1 in 13	3514	98.33	CO	96.43	225			VC	27.52978	1 in 97
1722			90.04	225			VC	17.4431		3514	98.33	CO	96.43	225			VC	27.52978	1 in 97
1722			90.04	225			VC	17.4431		3514	98.33	CO	96.43	225			VC	27.52978	1 in 97
1722			90.04	225			VC	17.4431		3514	98.33	CO	96.43	225			VC	27.52978	1 in 97
5805	96.32		95.93	225			VC	200.3397		4608	103.59	CO	101.49				VC	12.25978	1 in 249
5805	96.32		95.93	225			VC	200.3397		4608	103.59	CO	101.49				VC	12.25978	1 in 249
5801	96.32		95.93	225			VC	200.3397		4608	103.59	CO	101.49				VC	12.25978	1 in 249
5801	96.32		95.93	225			VC	200.3397		4608	103.59	CO	101.49				VC	12.25978	1 in 249
4811			95.93	225			VC	31.62278	1 in 31	4709		CO		150			VC	8.167535	
4811			95.93	225			VC	31.62278	1 in 31	4709		CO		150			VC	8.167535	
4839			95.93	225			VC	31.62278	1 in 31	4709		CO		150			VC	8.167535	
4839			95.93	225			VC	31.62278	1 in 31	4709		CO		150			VC	8.167535	
4839			95.93	225			VC	31.62278	1 in 31	4709		CO		150			VC	8.167535	
4839			95.93	225			VC	31.62278	1 in 31	4709		CO		150			VC	8.167535	
5815	96.99		97.67	150			VC	31.30495	1 in 14	4709		CO		150			VC	8.167535	
3804	102.72		100.24	225			VC	56.03389	1 in 32	4403	98.86	CO	0	525			VC	170.5814	1 in 96
4905	96.59		93.29	300			VC	66.78382	1 in 39	4423	97.01	CO	94.02	225			VC	36.05551	1 in 96
4905	96.59		93.29	300			VC	66.78382	1 in 39	4423	97.01	CO	94.02	225			VC	36.05551	1 in 96
3907	94.4		90.04	225			VC	51.24999		3601	100.55	CO	95.8	450			VC	55.75841	1 in 101
3907	94.4		90.04	225			VC	51.24999		3601	100.55	CO	95.8	450			VC	55.75841	1 in 101
3907	94.4		90.04	225			VC	51.24999		3601	100.55	CO	95.8	450			VC	55.75841	1 in 101
2905	96.59		94.41	450			VC	99.48109	1 in 991	3516		CO		150			VC	6.238036	
2905	96.59		94.41	450			VC	99.48109	1 in 991	3516		CO		150			VC	6.238036	
2905	96.59		94.41	450			VC	99.48109	1 in 991	3516		CO		150			VC	6.238036	
2911			93.34	150			VC	31.59476	1 in 151	1905	96.82	CO	92.68	225			VC	9.89495	
2911			93.34	150															



--	-------	--

**SEWER
RECORDS**

 **United
Utilities**

Lazzarin, Filippo

From: wastewaterdeveloperservices@uuplc.co.uk
Sent: 17 January 2023 11:01
To: Wilkinson, Ruth
Cc: Lazzarin, Filippo
Subject: DG5 Register for Manchester area

Good Morning Ruth,

Thank you for your email and the additional information.

The following information applies to all five addresses:

I can confirm that we have no current record of sewer flooding within the vicinity of the proposed development.

Please note that United Utilities Water Limited (U UW) can only record and check flooding events which are reported to us and we have to comply with our Regulators instructions on the qualification of flooding events to place on the register.

Our response does not include:

- any sewer flooding events caused by blockages or collapses which are the result of third party actions, natural events or other actions over which U UW has no control and not a facet of sewer capacity; or
- any historical sewer flooding events that have been removed from the register as a result of investment in our infrastructure.

As with all development sites, we recommend you liaise with our water and wastewater engineers by contacting our Developer Services team so the details of your development proposal can be considered further. Details can be found at the following link.

<https://www.unitedutilities.com/services/builders-developers/>

Should you require any further information please do not hesitate to contact me.

Kind regards



Louise Dack
Customer Advisor Advanced
Developer Services & Metering
Customer Services
T: 01925 233063 (33063 internal)
[unitedutilities.com](https://www.unitedutilities.com)

Did you know we now have a live chat facility available to you Mon to Friday 8 -5pm. You just click on the orange live chat box on our webpage and one of our advisors will be ready to chat to you and help you with your enquiry <https://www.unitedutilities.com/builders-developers/> or you can email us at WastewaterDeveloperServices@uuplc.co.uk

----- Original Message -----

From: Wilkinson, Ruth [ruth.wilkinson@atkinsglobal.com]

Sent: 16/01/2023 10:16

To: wastewaterdeveloperservices@uuplc.co.uk

Cc: filippo.lazzarin@atkinsglobal.com

Subject: FW: DG5 Register for Manchester area

EXTERNAL EMAIL This email originated outside of the organisation. Do not click links or open attachments unless you recognise the sender and know the content is safe.

Good Morning Louise,

The addresses and postcode for the 5 sites are as follows:

1. Benmore Road, M9 6DN
2. White Moss Road, M9 6DA
3. Canberra Street, M11 4NL
4. Queens Road, M40 8TQ
5. Palgrave Avenue, M40 8JW

If you could perform a search on our system, that would be greatly appreciated. If you need any more information please just let me know.

Kind Regards,

Ruth Wilkinson *MEng*


Graduate Civil Engineer, Infrastructure

UK & Europe

Engineering, Civil Engineering & Advanced Technology

 + (44) 121 483 5888

Two Chamberlain Square, Birmingham, West Midlands, B3 3AX



Company



From: wastewaterdeveloperservices@uuplc.co.uk <wastewaterdeveloperservices@uuplc.co.uk>

Sent: 16 January 2023 10:07

To: Lazzarin, Filippo <Filippo.Lazzarin@atkinsglobal.com>

Subject: DG5 Register for Manchester area

Good Morning Filippo,

Thank you for contacting United Utilities.

Unfortunately, we cannot provide a copy of the DG5 register and we cannot provide information regarding specific properties.

We can provide an overview of the area if you can supply the five property addresses.

Our response does not include:

1. any sewer flooding events caused by blockages or collapses which are the result of third party actions, natural events or other actions over which U UW has no control and not a facet of sewer capacity; or
2. any historical sewer flooding events that have been removed from the register as a result of investment in our infrastructure.

If you can provide the full addresses and post codes, we can perform a search on our system.

Kind Regards,



Louise Dack

Customer Advisor Advanced
Developer Services & Metering
Customer Services
T: 01925 233063 (33063 internal)
[unitedutilities.com](https://www.unitedutilities.com)

Did you know we now have a live chat facility available to you Mon to Friday 8 -5pm. You just click on the orange live chat box on our webpage and one of our advisors will be ready to chat to you and help you with your enquiry <https://www.unitedutilities.com/builders-developers/> or you can email us at WastewaterDeveloperServices@uuplc.co.uk

From: Lazzarin, Filippo <Filippo.Lazzarin@atkinsglobal.com>
Sent: 12 January 2023 11:06
To: propertysearches@uuplc.co.uk
Subject: DG5 Register for Manchester area

EXTERNAL EMAIL This email originated outside of the organisation. Do not click links or open attachments unless you recognise the sender and know the content is safe.

Good Morning,

I am working on Flood Risk Assessments for 5 no. sites in the Manchester area.

In order to assess the risk of flooding from sewers, could you please provide me with a copy of the DG5 register for the Manchester area?


Kind Regards,

Filippo Lazzarin *MEng*
Civil Engineer, Infrastructure
CE&AT MIDLANDS, SW & WALES
Engineering, Design & Project Management

☐ +441214835583



Two Chamberlain Square, Birmingham, B3 3AX



Company



At Atkins - member of the SNC-Lavalin Group, we work flexible hours around the world. Although I have sent this email at a time convenient for me, I don't expect you to respond until it works for you.

NOTICE – This email message and any attachments may contain information or material that is confidential, privileged, and/or subject to copyright or other rights. Any unauthorized viewing, disclosure, retransmission, dissemination, or other use of or reliance on this message or anything contained


therein is strictly prohibited and may be unlawful. If you believe you may have received this message in error, kindly inform the sender by return email and delete this message from your system. Thank you.

The information contained in this e-mail is intended only for the individual to whom it is addressed. It may contain legally privileged or confidential information or otherwise be exempt from disclosure. If you have received this Message in error or there are any problems, please notify the sender immediately and delete the message from your computer. You must not use, disclose, copy or alter this message for any unauthorised purpose. Neither United Utilities Group PLC nor any of its subsidiaries will be liable for any direct, special, indirect or consequential damages as a result of any virus being passed on, or arising from the alteration of the contents of this message by a third party.

United Utilities Group PLC, Haweswater House, Lingley Mere
Business Park, Lingley Green Avenue, Great Sankey,
Warrington, WA5 3LP
Registered in England and Wales. Registered No 6559020

www.unitedutilities.com

www.unitedutilities.com/subsidiaries



Lead Local Flood Authority

Highways Service
Growth and Neighbourhoods Directorate
Manchester City Council
PO Box 532
Town Hall
Manchester
M60 2LA

Email: floodriskmanagement@manchester.gov.uk

DATE 04/01/2022

Dear Sir or Madam,

RE: Our Ref: MCC004A/01/2023

We acknowledge with thanks your payment received on 15/12/2022 for our LLFA data screen service.

Please find enclosed plan showing the results of the data screen. The position of features shown on this plan is approximate only and is given in accordance with the best information currently available.

The enclosed plan cannot be used to substitute a competent site investigation.

The enclosed plan is being provided to you subject to Manchester City Council's terms and conditions which are shown attached.

I trust the above meets your requirements and look forward to hearing from you should you need anything further.

If you have any queries regarding this matter, please do not hesitate to contact us.

Yours Faithfully,



Neil Bayliss-Rowe, Highways Development Control & Flood Risk Manager, Lead Local Flood Authority

TERMS AND CONDITIONS – LLFA DATA SCREEN

These provisions apply to LLFA data supplied by Manchester City Council (“MCC”).

TERMS AND CONDITIONS:

- This data Map and any information supplied with it is issued subject to the provisions contained below, to the exclusion of all others and no party relies upon any representation, warranty, collateral contract or other assurance of any person (whether party to this agreement or not) that is not set out in this agreement or the documents referred to in it.
- MCC has taken all reasonable care to compile this data Map. This data Map and any information supplied with it is provided for general guidance only and MCC makes no representation, undertaking or warranty of any kind as to its accuracy, completeness or being up to date is given or implied.
- In particular, the position of any culverted assets shown on the data Map are approximate only. MCC strongly recommends that a comprehensive site investigation is undertaken in addition to reviewing this data Map to determine and ensure the precise location of any assets. The exact location, positions and depths should be obtained by an appropriate survey which may include but shall not be limited to GPR and CCTV.
- The data screened may be modified over time without notice and therefore this data Map is issued subject to any removal or change in location of the same. The onus is entirely upon you to confirm whether any changes to the data Map have been made subsequent to issue and prior to any works being carried out.
- This data Map and any information shown on it or provided with it must not be relied upon in the event of any development, construction or other works (including but not limited to any excavations) or for the purpose of determining the suitability of a point of connection to discharge.
- No person or legal entity, including any company shall be relieved from any liability howsoever and whensoever arising from damages of any kind caused to assets by reason of the actual position and/or existence of assets being different from those shown on the data Map and any information supplied with it.
- If any provision contained herein is or becomes legally invalid or unenforceable, it will be taken to be severed from the remaining provisions which shall be unaffected and continue in full force and affect.
- This agreement shall be governed by English law and all parties submit to the exclusive jurisdiction of the English courts, save that nothing will prevent MCC from bringing proceedings in any other competent jurisdiction, whether concurrently or otherwise.

DATA SCREEN SYMBOLOGY

Bridge

-  Good
-  Fair
-  Poor
-  Very Poor
-  Unknown

Trash Screen

-  Good
-  Fair
-  Poor
-  Very Poor
-  Unknown

Culvert Orifice

-  Very Good
-  Good
-  Fair
-  Poor
-  Very Poor
-  Unknown

Culvert Conduit

-  CCTV surveyed
-  Not CCTV surveyed
-  Ordinary Watercourse Conduit
-  MCC SuDS
-  MCC Flood Incident Points
-  MCC Section 19 Report
-  MCC Flood Incident Polygons
-  MCC Local Authority Boundary

Supplementary Information where available:


Critical Drainage Area – The Site is in the Conurbation Core CDA

Flood Incidents – The nearest flood/drainage incident on record is approximately 30m south of the central part of the Site, dated 16/06/2020, described as “blocked gully or drain”.

Culvert Conduits – The asset register highlights an indicative risk that the Lionfield Brook culverted ordinary watercourse crosses the Site or is in close proximity to the Site. An indicative culvert route is shown crossing Wanley Walk in the central Site; while 3rd party historic OS mapping indicates a ‘river’ was proximal to the eastern Site boundary. This culvert is an indicative asset and has not been verified with survey.

Survey and Design Archive – The 1984 drainage survey of major assets (enclosed) highlights an indicative culvert asset proximal to the eastern Site boundary (dash-dot-dot line).

Any other information identified by LLFA officer during screening – A planning application on this site would benefit from site investigation of the indicative culvert risk, which should be presented to support the planning application. Inadequate site investigations to prove or disprove the asset’s presence could result in an objection to the application from the LLFA. Should a culverted ordinary watercourse be identified during site investigations, any planning application’s masterplan should take account of the culverted watercourse and any required permissions should be obtained.



**MANCHESTER
CITY COUNCIL**

LLFA DATA SCREEN

Address/Site Ref:
White Moss Road, M9 6DA

Our Ref: **MCC004A/01/2023**


Author: Manchester City Council LLFA
Date: 04/01/2023
Scale: 1:1,778

The position of features shown on this plan is approximate only and is given in accordance with the best information currently available. Manchester City Council will not accept liability for any loss or damage caused by the actual position being different from those shown.

0 12.5 25 50
Meters



Contains OS data © Crown Copyright
and database right 2022.



**MANCHESTER
CITY COUNCIL**

LLFA DATA SCREEN

Address/Site Ref:
White Moss Road, M9 6DA

Our Ref: **MCC004A/01/2023**

Author: Manchester City Council LLFA
Date: 04/01/2023
Scale: 1:1,778

The position of features shown on this plan is approximate only and is given in accordance with the best information currently available. Manchester City Council will not accept liability for any loss or damage caused by the actual position being different from those shown.


0 12.5 25 50
Meters



Contains OS data © Crown Copyright and database right 2022.

Contains OS data © Crown Copyright and database right 2020

Appendix B. Drawings



© Survey & Engineering Projects Ltd. 2021
Reproduction in whole or in part by any means is prohibited
without the prior permission of Survey & Engineering Projects Ltd.
T: 0161 672 0000 F: 0161 672 0001 W: www.surveyandengineering.co.uk E: info@suep.co.uk




The format is 1:200 at A3 size

LEGEND	
AB	ABUTMENT
AD	ADDITIONAL ROAD
AK	AK
AL	AL
AM	AM
AN	AN
AO	AO
AP	AP
AR	AR
AS	AS
AT	AT
AV	AV
AW	AW
AX	AX
AY	AY
AZ	AZ
BA	BA
BB	BB
BC	BC
BD	BD
BE	BE
BF	BF
BG	BG
BH	BH
BI	BI
BJ	BJ
BK	BK
BL	BL
BM	BM
BN	BN
BO	BO
BP	BP
BQ	BQ
BR	BR
BS	BS
BT	BT
BU	BU
BV	BV
BW	BW
BX	BX
BY	BY
BZ	BZ
CA	CA
CB	CB
CC	CC
CD	CD
CE	CE
CF	CF
CG	CG
CH	CH
CI	CI
CJ	CJ
CK	CK
CL	CL
CM	CM
CN	CN
CO	CO
CP	CP
CQ	CQ
CR	CR
CS	CS
CT	CT
CU	CU
CV	CV
CW	CW
CX	CX
CY	CY
CZ	CZ
DA	DA
DB	DB
DC	DC
DD	DD
DE	DE
DF	DF
DG	DG
DH	DH
DI	DI
DJ	DJ
DK	DK
DL	DL
DM	DM
DN	DN
DO	DO
DP	DP
DQ	DQ
DR	DR
DS	DS
DT	DT
DU	DU
DV	DV
DW	DW
DX	DX
DY	DY
DZ	DZ
EA	EA
EB	EB
EC	EC
ED	ED
EE	EE
EF	EF
EG	EG
EH	EH
EI	EI
EJ	EJ
EK	EK
EL	EL
EM	EM
EN	EN
EO	EO
EP	EP
EQ	EQ
ER	ER
ES	ES
ET	ET
EU	EU
EV	EV
EW	EW
EX	EX
EY	EY
EZ	EZ
FA	FA
FB	FB
FC	FC
FD	FD
FE	FE
FF	FF
FG	FG
FH	FH
FI	FI
FJ	FJ
FK	FK
FL	FL
FM	FM
FN	FN
FO	FO
FP	FP
FQ	FQ
FR	FR
FS	FS
FT	FT
FU	FU
FV	FV
FW	FW
FX	FX
FY	FY
FZ	FZ
GA	GA
GB	GB
GC	GC
GD	GD
GE	GE
GF	GF
GG	GG
GH	GH
GI	GI
GJ	GJ
GK	GK
GL	GL
GM	GM
GN	GN
GO	GO
GP	GP
GQ	GQ
GR	GR
GS	GS
GT	GT
GU	GU
GV	GV
GW	GW
GX	GX
GY	GY
GZ	GZ
HA	HA
HB	HB
HC	HC
HD	HD
HE	HE
HF	HF
HG	HG
HH	HH
HI	HI
HJ	HJ
HK	HK
HL	HL
HM	HM
HN	HN
HO	HO
HP	HP
HQ	HQ
HR	HR
HS	HS
HT	HT
HU	HU
HV	HV
HW	HW
HX	HX
HY	HY
HZ	HZ
IA	IA
IB	IB
IC	IC
ID	ID
IE	IE
IF	IF
IG	IG
IH	IH
II	II
IJ	IJ
IK	IK
IL	IL
IM	IM
IN	IN
IO	IO
IP	IP
IQ	IQ
IR	IR
IS	IS
IT	IT
IU	IU
IV	IV
IW	IW
IX	IX
IY	IY
IZ	IZ
JA	JA
JB	JB
JC	JC
JD	JD
JE	JE
JF	JF
JG	JG
JH	JH
JI	JI
JJ	JJ
JK	JK
JL	JL
JM	JM
JN	JN
JO	JO
JP	JP
JQ	JQ
JR	JR
JS	JS
JT	JT
JU	JU
JV	JV
JW	JW
JX	JX
JY	JY
JZ	JZ
KA	KA
KB	KB
KC	KC
KD	KD
KE	KE
KF	KF
KG	KG
KH	KH
KI	KI
KJ	KJ
KK	KK
KL	KL
KM	KM
KN	KN
KO	KO
KP	KP
KQ	KQ
KR	KR
KS	KS
KT	KT
KU	KU
KV	KV
KW	KW
KX	KX
KY	KY
KZ	KZ
LA	LA
LB	LB
LC	LC
LD	LD
LE	LE
LF	LF
LG	LG
LH	LH
LI	LI
LJ	LJ
LK	LK
LL	LL
LM	LM
LN	LN
LO	LO
LP	LP
LQ	LQ
LR	LR
LS	LS
LT	LT
LU	LU
LV	LV
LW	LW
LX	LX
LY	LY
LZ	LZ
MA	MA
MB	MB
MC	MC
MD	MD
ME	ME
MF	MF
MG	MG
MH	MH
MI	MI
MJ	MJ
MK	MK
ML	ML
MM	MM
MN	MN
MO	MO
MP	MP
MQ	MQ
MR	MR
MS	MS
MT	MT
MU	MU
MV	MV
MW	MW
MX	MX
MY	MY
MZ	MZ
NA	NA
NB	NB
NC	NC
ND	ND
NE	NE
NF	NF
NG	NG
NH	NH
NI	NI
NJ	NJ
NK	NK
NL	NL
NM	NM
NO	NO
NP	NP
NQ	NQ
NR	NR
NS	NS
NT	NT
NU	NU
NV	NV
NW	NW
NX	NX
NY	NY
NZ	NZ
OA	OA
OB	OB
OC	OC
OD	OD
OE	OE
OF	OF
OG	OG
OH	OH
OI	OI
OJ	OJ
OK	OK
OL	OL
OM	OM
ON	ON
OO	OO
OP	OP
OQ	OQ
OR	OR
OS	OS
OT	OT
OU	OU
OV	OV
OW	OW
OX	OX
OY	OY
OZ	OZ
PA	PA
PB	PB
PC	PC
PD	PD
PE	PE
PF	PF
PG	PG
PH	PH
PI	PI
PJ	PJ
PK	PK
PL	PL
PM	PM
PN	PN
PO	PO
PP	PP
PQ	PQ
PR	PR
PS	PS
PT	PT
PU	PU
PV	PV
PW	PW
PX	PX
PY	PY
PZ	PZ
QA	QA
QB	QB
QC	QC
QD	QD
QE	QE
QF	QF
QG	QG
QH	QH
QI	QI
QJ	QJ
QK	QK
QL	QL
QM	QM
QN	QN
QO	QO
QP	QP
QQ	QQ
QR	QR
QS	QS
QT	QT
QU	QU
QV	QV
QW	QW
QX	QX
QY	QY
QZ	QZ
RA	RA
RB	RB
RC	RC
RD	RD
RE	RE
RF	RF
RG	RG
RH	RH
RI	RI
RJ	RJ
RK	RK
RL	RL
RM	RM
RO	RO
RP	RP
RQ	RQ
RR	RR
RS	RS
RT	RT
RU	RU
RV	RV
RW	RW
RX	RX
RY	RY
RZ	RZ
SA	SA
SB	SB
SC	SC
SD	SD
SE	SE
SF	SF
SG	SG
SH	SH
SI	SI
SJ	SJ
SK	SK
SL	SL
SM	SM
SN	SN
SO	SO
SP	SP
SQ	SQ
SR	SR
SS	SS
ST	ST
SU	SU
SV	SV
SW	SW
SX	SX
SY	SY
SZ	SZ
TA	TA
TB	TB
TC	TC
TD	TD
TE	TE
TF	TF
TG	TG
TH	TH
TI	TI
TJ	TJ
TK	TK
TL	TL
TM	TM
TO	TO
TP	TP
TQ	TQ
TR	TR
TS	TS
TT	TT
TU	TU
TV	TV
TW	TW
TX	TX
TY	TY
TZ	TZ
UA	UA
UB	UB
UC	UC
UD	UD
UE	UE
UF	UF
UG	UG
UH	UH
UI	UI
UJ	UJ
UK	UK
UL	UL
UM	UM
UN	UN
UO	UO
UP	UP
UQ	UQ
UR	UR
US	US
UT	UT
UU	UU
UV	UV
UW	UW
UX	UX
UY	UY
UZ	UZ
VA	VA
VB	VB
VC	VC
VD	VD
VE	VE
VF	VF
VG	VG
VH	VH
VI	VI
VJ	VJ
VK	VK
VL	VL
VM	VM
VO	VO
VP	VP
VQ	VQ
VR	VR
VS	VS
VT	VT
VU	VU
VV	VV
VW	VW
VX	VX
VY	VY
VZ	VZ
WA	WA
WB	WB
WC	WC
WD	WD
WE	WE
WF	WF
WG	WG
WH	WH
WI	WI
WJ	WJ
WK	WK
WL	WL
WM	WM
WO	WO
WP	WP
WQ	WQ
WR	WR
WS	WS
WT	WT
WU	WU
WV	WV
WW	WW
WX	WX
WY	WY
WZ	WZ
XA	XA
XB	XB
XC	XC
XD	XD
XE	XE
XF	XF
XG	XG
XH	XH
XI	XI
XJ	XJ
XK	XK
XL	XL
XM	XM
XN	XN
XO	XO
XP	XP
XQ	XQ
XR	XR
XS	XS
XT	XT
XU	XU
XV	XV
XW	XW
XX	XX
XY	XY
XZ	XZ
YA	YA
YB	YB
YC	YC
YD	YD
YE	YE
YF	YF
YG	YG
YH	YH
YI	YI
YJ	YJ
YK	YK
YL	YL
YM	YM
YN	YN
YO	YO
YP	YP
YQ	YQ
YR	YR
YS	YS
YT	YT
YU	YU
YV	YV
YW	YW
YX	YX
YY	YY
YZ	YZ
ZA	ZA
ZB	ZB
ZC	ZC
ZD	ZD
ZE	ZE
ZF	ZF
ZG	ZG
ZH	ZH
ZI	ZI
ZJ	ZJ
ZK	ZK
ZL	ZL
ZM	ZM
ZN	ZN
ZO	ZO
ZP	ZP
ZQ	ZQ
ZR	ZR
ZS	ZS
ZT	ZT
ZU	ZU
ZV	ZV
ZW	ZW
ZX	ZX
ZY	ZY
ZZ	ZZ

NOTES:
All levels are to G.D. (British Datum). Distances are to nearest 0.1m.
Survey carried out on a plane local grid, oriented to National Grid.
Detail shown within bold dashed line surveyed May 2021 and
indicated by an existing property line.

SURVEY DATA			
Name	Eastings	Northings	Height
ST1	388430.000	403330.000	82.121
ST2	388430.000	403330.000	82.121
ST3	388430.000	403330.000	82.121
ST4	388430.000	403330.000	82.121



0 2m 4m 8m 12m 16m
SCALE BAR


REV	DATE	DESCRIPTION



Client:
Curtis Consulting Limited
Rose Wharf
78-80 East Street
Leeds
LS1 6EE

Project title:
Topographical Survey of Land at:
Dam Head Drive
Manchester
M16 6LX

Surveyed	Drawn	Checked
A. Fellowes	M. Charlton	R. Critchley
Scale	Date	Drawing Ref.
1:200	May 21	S22526-T
No.	Size	Rev
02	A0	--



DO NOT SCALE

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following:

CONSTRUCTION

- PROXIMITY TO LIVE TRAFFIC
- BURIED SERVICES

MAINTENANCE/CLEANING

- PROXIMITY TO LIVE TRAFFIC
- BURIED SERVICES

DECOMMISSIONING/DEMOLITION

- PROXIMITY TO LIVE TRAFFIC
- BURIED SERVICES

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement

NOTES:

1. ALL DIMENSIONS ARE IN METRES (m) UNLESS OTHERWISE STATED.
2. SITE UTILITIES ALIGNMENT TRACED OVER PDF VERSION OF UTILITY REPORT (REF. 077873.006, White Moss Road - Utilities Search, PROVIDED BY CORNERSTONE PROJECT LTD. RECEIVED 22/11/2021).
3. SEWER RECORDS TRACED OVER PDF VERSION OF UNITED UTILITIES REPORT (REF. Single Utility Report - 115545 - Whiternoss Road & Benmore, RECEIVED 12/12/2022).
4. CULVERTED WATERCOURSE TRACED OVER PDF VERSION OF MANCHESTER CITY COUNCIL LLFA DATA SCREEN (REF. DataScreen_WhiteMossRoad, RECEIVED 05/01/2023).
5. SITE LAYOUT PROVIDED BY JOHN MCCALL ARCHITECTS (REF. PL 003A, RECEIVED IN NOVEMBER 22).

KEY:

-
-  SITE BOUNDARY
 ELECTRICITY SERVICES
 UU COMBINED SEWER
 CLEAN WATER DISTRIBUTION MAIN
 BT CABLE
 VIRGIN MEDIA CABLE
 GAS MAIN
 LIVE BT BOX
 UU EASEMENT - 6m WIDE STRIP
 CULVERTED WATERCOURSE

P01	20/01/23	FIRST ISSUE	RW	FL	CE
Rev.	Date	Description	By	Chk'd	App

Drawing Status

FOR INFORMATION

Suitability

S2

**SNC • LAVALIN****ATKINS**

Member of the SNC-Lavalin Group

Two Chamberlain Square
Birmingham
West Midlands
B3 3AX

Tel: +44 (0)121 483 5757

www.atkinsglobal.com

© SNC-Lavalin (2022)



Project Title

PROJECT 500 MANCHESTER

Drawing Title

CONSTRAINTS PLAN

Scale SCALE	Designed RW	Drawn RW	Checked FL	Authorised CB
Original Size A1	Date 05/12/22	Date 05/12/22	Date 17/01/23	Date 17/01/23

Drawing Number

5218589-ATK-WT-XX-DR-D-0501

vision

901

PROPOSED PLAN




- N
- SITE BOUNDARY
- SITE AREA : 11,091m²
- EXISTING TREES
 - EXISTING TREES TO BE REMOVED
 - PROPOSED SOFT LANDSCAPING (Subject to a detailed landscaping strategy)
 - PROPOSED TREES (Subject to a detailed landscaping strategy)
 - PROPOSED STREET TREES (Subject to a detailed landscaping strategy)
 - EV 7kW Charge Point
 - DUAL ASPECT UNITS TO ADDRESS EACH CORNER
 - POTENTIAL PARTY WALL DISCUSSIONS NEEDED

	House Type	Total
	2B4P House Type 1 @ 79m ²	12
	2B4P House Type 2 @ 79m ²	14
	3B5P House Type 1 @ 93m ²	12
		38

Air source heat pump and 15m buffer zone

PROPOSED MASSING



USER: PANG8291 Date: 20/1/23 10:57:09
Filename: \\watkins.com\project\GBEM\WCSE\Projects\Cities\218589 Guinness Partnership Sites, Manchester, P5007\WIP\DCAD\DR\5218589-ATK-WT-XX-DR-0-0502 Drainage Layout.dwg

In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following:

- ## MAINTENANCE/CLEANING
- PROXIMITY TO LIVE TRAFFIC
 - BURIED SERVICES

- PROXIMITY TO LIVE TRAFFIC
- BURIED SERVICES

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement

1. ALL DIMENSIONS ARE IN METRES (m) UNLESS OTHERWISE STATED.
2. ALL LEVELS ARE SHOWN IN METRES ABOVE ORDNANCE DATUM (mAOD) UNLESS OTHERWISE STATED.
3. ACCESS FOR MAINTENANCE OF CELLULAR STORAGE IS REQUIRED.
4. TOPOGRAPHICAL SURVEY DATA TAKEN FROM DRAWING REFERENCE "5218589-ATK-WT-XX-M2-D-5501-TOPOGRAPHICAL SURVEY".
5. SEWER RECORDS TRACED OVER PDF VERSION OF UNITED UTILITIES REPORT (REF. Single Utility Report - 115545 - Whittemoss Road & Benmore, RECEIVED 12/12/2022).
6. CULVERTED WATERCOURSE TRACED OVER PDF VERSION OF MANCHESTER CITY COUNCIL LLFA DATA SCREEN (REF. DataScreen_WhittemossRoad, RECEIVED 05/01/2023).
7. SITE LAYOUT PROVIDED BY JOHN MCCALL ARCHITECTS (REF. PL.003A, RECEIVED IN NOVEMBER 2022).

 SITE BOUNDARY
 PROPOSED SURFACE WATER DRAINAGE
 PROPOSED FOUL WATER DRAINAGE
 PROPOSED COMBINED SEWER
 EXISTING UU COMBINED SEWER
 PROPOSED CELLULAR STORAGE TANK
 CULVERTED WATERCOURSE
 EAST CATCHMENT AREA
 WEST CATCHMENT AREA

[illegible]

PO1	20/01/23	FIRST ISSUE	RW	FL	CE
Rev.	Date	Description	By	Chk'd	App

FOR INFORMATION



Project Title

PROJECT 500 MANCHESTER

Drawing Title

DRAINAGE LAYOUT

Scale SCALE	Designed RW	Drawn RW	Checked FL	Authorised CB
Original Size A1	Date 18/01/23	Date 18/01/23	Date 20/01/23	Date 20/01/23

Drawing Number	Revision
5218589-ATK-WT-XX-DR-D-0502	P01

Internal Project Number: XXXXXXXX

CLASSIFICATION - Baseline (Low Risk)

Appendix C. SuDS Selection

The following tables are taken from CIRIA C697 The SuDS Manual (2007).

CIRIA C697, Table 5.2 Land Use Selection Matrix

SuDS group	Technique	Low density	Residential	Local roads	Commercial	Hotspots	Construction site	Brownfield	Contaminated land
Retention	Retention pond	Y	Y	Y ₁	Y ₂	Y ₂	Y ₃	Y	Y ₂
	Subsurface storage	Y	Y	Y	Y	Y	Y ₃	Y	Y
Wetland	Shallow wetland	Y	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Extended detention wetland	Y	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Pond/wetland	Y	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Pocket wetland	Y	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Submerged gravel wetland	Y	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Wetland channel	Y	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
Infiltration	Infiltration trench	Y	Y	Y ₁	Y ₂	N	N	Y	Y ₄
	Infiltration basin	Y	Y	Y ₁	Y ₂	N	N	Y	Y ₄
	Soakaway	Y	Y	Y ₁	Y ₂	N	N	Y	Y ₄
Filtration	Surface sand filter	N	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Sub-surface sand filter	N	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Perimeter sand filter	N	N	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Bioretention/filter strip	Y	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
	Filter trench	Y	Y	Y ₁	Y ₂	Y ₂	N	Y	Y ₂
Detention	Detention basin	Y	Y	Y ₁	Y ₂	Y _{1,2}	Y ₃	Y	Y ₂
Open channels	Conveyance swale	Y	Y	Y ₁	Y ₂	Y ₂	Y ₃	Y	Y ₂
	Enhanced dry swale	Y	Y	Y ₁	Y ₂	Y ₂	Y ₃	Y	Y ₂
	Enhanced wet swale	Y	Y	Y ₁	Y ₂	Y ₁	Y ₃	Y	Y ₂
Source control	Green roof	Y	Y	N	Y ₂	Y	N	Y	Y
	Rainwater harvesting	Y	Y	N	Y ₂	N	N	Y	Y
	Permeable paving	Y	Y	N	Y ₂	Y ₁	N	Y	Y ₂

Y: Yes N: No

¹ May require two treatment train stages, depending on type and intensity of road use and receiving water sensitivity.

² May require three treatment train stages, depending on receiving watercourse sensitivity.

³ Will require draw-down and rehabilitation following construction activities, prior to use as a permanent drainage system.

⁴ Providing designs prevent mobilisation of contamination.

CIRIA C697, Table 5.4 Site Characteristics Selection Matrix

SuDS group	Technique	Soils		Area draining to a single SuDS component		Minimum depth to water table		Site slope		Available head		Available space	
		Impermeable	Permeable	0 - 2ha	>2ha	0 - 1m	>1m	0 - 5%	>5%	0 - 1m	1 - 2m	Low	High
Retention	Retention pond	Y	Y ₁	Y	Y ₅	Y	Y	Y	Y	Y	Y	N	Y
	Subsurface storage	Y	Y	Y	Y ₅	Y	Y	Y	Y	Y	Y	Y	Y
Wetland	Shallow wetland	Y ₂	Y ₄	Y ₄	Y ₆	Y ₂	Y ₂	Y	N	Y	Y	N	Y
	Extended detention wetland	Y ₂	Y ₄	Y ₄	Y ₆	Y ₂	Y ₂	Y	N	Y	Y	N	Y
	Pond/wetland	Y ₂	Y ₄	Y ₄	Y ₆	Y ₂	Y ₂	Y	N	Y	Y	N	Y
	Pocket wetland	Y ₂	Y ₄	Y ₄	N	Y ₂	Y ₂	Y	N	Y	Y	Y	Y
	Submerged gravel wetland	Y ₂	Y ₄	Y ₄	Y ₆	Y ₂	Y ₂	Y	N	Y	Y	N	Y
	Wetland channel	Y ₂	Y ₄	Y ₄	Y ₆	Y ₂	Y ₂	Y	N	Y	Y	N	Y
Infiltration	Infiltration trench	N	Y	Y	N	N	Y	Y	Y	Y	N	Y	Y
	Infiltration basin	N	Y	Y	Y ₅	N	Y	Y	Y	Y	N	N	Y
	Soakaway	N	Y	Y	N	N	Y	Y	Y	Y	N	Y	Y
Filtration	Surface sand filter	Y	Y	Y	Y ₅	N	Y	Y	N	N	Y	N	Y
	Sub-surface sand filter	Y	Y	Y	N	N	Y	Y	N	N	Y	Y	Y
	Perimeter sand filter	Y	Y	Y	N	N	Y	Y	N	Y	Y	Y	Y
	Bio-retention/filter strip	Y	Y	Y	N	N	Y	Y	N	Y	Y	N	Y
	Filter trench	Y	Y ₁	Y	N	N	Y	Y	N	Y	Y	Y	Y
Detention	Detention basin	Y	Y ₁	Y	Y ₅	N	Y	Y	Y	N	Y	N	Y
Open channels	Conveyance swale	Y	Y	Y	N	N	Y	Y	N ₃	Y	N	N	Y
	Enhanced dry swale	Y	Y	Y	N	N	Y	Y	N ₃	Y	N	N	Y
	Enhanced wet swale	Y ₂	Y ₄	Y	N	Y	Y	Y	N ₃	Y	N	N	Y
Source control	Green roof	Y	Y	Y	N	Y	Y	Y	Y	Y	Y	Y	Y
	Rainwater harvesting	Y	Y	Y	N	Y	Y	Y	Y	Y			
	Permeable paving	Y	Y	Y	Y	N	Y	Y	N	Y	Y	Y	Y

Y: Yes N: No

¹ With liner

² With surface baseflow

³ Unless follows contours

⁴ With liner and constant surface baseflow, or high ground water table

⁵ Possible, but not recommended (implies appropriate management train not in place)

⁶ Where high flows are diverted around SuDS component.

Appendix D. Surface Water Calculations

Atkins (Epsom)		Page 1
Woodcoste Grove Ashley Road, Epsom Surrey, KT18 5BW		
Date 19/01/2023 13:18 File WT_NETWORKS.MDX	Designed by LAZZ4777 Checked by	
Innovyze Network 2020.1.3		

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm north

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	1	PIMP (%)	100
M5-60 (mm)	18.500	Add Flow / Climate Change (%)	0
Ratio R	0.331	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

©1982-2020 Innovyze

Atkins (Epsom)

Woodcote Grove
Ashley Road, Epsom
Surrey, KT18 5BW

Date 19/01/2023 13:18
File WT_NETWORKS.MDX

Innovyze

Designed by LAZZ4777
Checked by

Network 2020.1.3

Page 2



100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm north

Simulation Criteria

Areal Reduction Factor 1.000

Hot Start (mins) 0

Hot Start Level (mm) 0

Manhole Headloss Coeff (Global) 0.500

Foul Sewage per hectare (l/s) 0.000

Additional Flow - % of Total Flow 0.000

MADD Factor * 10m³/ha Storage 2.000

Inlet Coefficient 0.800

Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0

Number of Online Controls 1

Number of Offline Controls 0

Number of Storage Structures 2

Number of Time/Area Diagrams 0

Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FSR

Region England and Wales Cv (Summer) 0.750

M5-60 (mm) 18.500 Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0

Analysis Timestep 2.5 Second Increment (Extended)

DTS Status OFF

DVD Status ON

Inertia Status ON

Profile(s) Summer and Winter

Duration(s) (mins) 15, 30, 60, 120, 240, 360, 480, 960, 1440, 2160, 2880

Return Period(s) (years) 100

Climate Change (%) 45

	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Water
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	Level
									(m)
S1.000	S1 480	Winter	100	+45%	100/240	Winter			94.473
S2.000	S2 480	Winter	100	+45%	100/360	Winter			94.472
S2.001	S3 480	Winter	100	+45%	100/240	Winter			94.472
S1.001	S1 480	Winter	100	+45%	100/240	Winter			94.473
S3.000	S5 480	Winter	100	+45%	100/240	Winter			94.460
S1.002	S2 480	Winter	100	+45%	100/240	Winter			94.479
S1.003	S7 480	Winter	100	+45%	100/120	Winter			94.509
S4.000	S8 480	Winter	100	+45%	100/15	Summer			94.511
S1.004	S4 480	Winter	100	+45%	100/15	Summer			94.511

	US/MH	Depth	Volume	Flow / Overflow	Half Drain	Pipe		Level
PN	Name	(m)	(m³)	Cap. (l/s)	Time (mins)	Flow (l/s)	Status	Exceeded
S1.000	S1	0.128	0.000	0.01		3.7	SURCHARGED	
S2.000	S2	0.085	0.000	0.01		4.2	SURCHARGED	
S2.001	S3	0.125	0.000	0.03		14.2	SURCHARGED	

©1982-2020 Innovyze

Atkins (Epsom)		Page 3
Woodcoste Grove		
Ashley Road, Epsom		
Surrey, KT18 5BW		
Date 19/01/2023 13:18	Designed by LAZZ4777	
File WT_NETWORKS.MDX	Checked by	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm north

Atkins (Epsom)		Page 2
Woodcoste Grove Ashley Road, Epsom Surrey, KT18 5BW		
Date 19/01/2023 13:15 File WT_NETWORKS.MDX	Designed by LAZZ4777 Checked by	
Innovyze	Network 2020.1.3	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm north

PN	US/MH Name	Surcharged		Flooded		Half Drain		Pipe	Status	Level Exceeded
		Depth (m)	Volume (m ³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)			
S1.000	S1	0.602	0.000	0.01			5.5		SURCHARGED	
S2.000	S2	0.560	0.000	0.02			6.2		SURCHARGED	
S2.001	S3	0.600	0.000	0.03			15.0		SURCHARGED	
S1.001	S1	0.678	0.000	0.04			16.4		SURCHARGED	
S3.000	S5	0.738	0.000	0.16		643	34.9		SURCHARGED	
S1.002	S2	0.762	0.000	0.07			30.2		SURCHARGED	
S1.003	S7	0.828	0.000	0.08			17.6		FLOOD RISK	
S4.000	S8	1.255	0.000	0.17			7.7		FLOOD RISK	
S1.004	S4	1.447	0.000	0.36		1164	3.9		FLOOD RISK	

Atkins (Epsom)		Page 1
Woodcoste Grove Ashley Road, Epsom Surrey, KT18 5BW		
Date 19/01/2023 12:54 File WT_NETWORKS.MDX	Designed by LAZZ4777 Checked by	
Innovyze	Network 2020.1.3	

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm south

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	1	PIMP (%)	100
M5-60 (mm)	18.500	Add Flow / Climate Change (%)	0
Ratio R	0.331	Minimum Backdrop Height (m)	0.200
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	1.500
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Atkins (Epsom)

Woodcote Grove
Ashley Road, Epsom
Surrey, KT18 5BW

Date 19/01/2023 12:50
File WT_NETWORKS.MDX

Innovyze

Designed by LAZZ4777
Checked by

Network 2020.1.3

Page 1



100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm south

Simulation Criteria			
Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		
Number of Input Hydrographs	0	Number of Storage Structures	0
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details			
Rainfall Model		FEH	
FEH Rainfall Version		2013	
Site Location	GB 386560 403466 SD 86560	03466	
Data Type		Point	
Cv (Summer)		0.750	
Cv (Winter)		0.840	
Margin for Flood Risk Warning (mm)		300.0	
Analysis Timestep	2.5 Second Increment (Extended)		
DTS Status		OFF	
DVD Status		ON	
Inertia Status		ON	
Profile(s)		Summer and Winter	
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440, 2160, 2880		
Return Period(s) (years)		100	
Climate Change (%)		45	

									Water
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Level (m)
S2.000	S4 480	Winter	100	+45%	100/240	Winter			92.172
S2.001	S4 480	Winter	100	+45%	100/240	Winter			92.172
S2.002	S3 480	Winter	100	+45%	100/240	Winter			92.172
S2.003	S3 480	Winter	100	+45%	100/15	Summer			92.172

Surcharged Flooded					Half Drain	Pipe			
PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Status	Level Exceeded
S2.000	S4	0.672	0.000	0.00			6.1	SURCHARGED	
S2.001	S4	0.746	0.000	0.00			8.8	SURCHARGED	
S2.002	S3	0.853	0.000	0.00			1.7	SURCHARGED	
S2.003	S3	2.211	0.000	0.15			2.0	SURCHARGED	

©1982-2020 Innovyze

Filippo Lazzarin
Atkins Limited
Two Chamberlain Square
Birmingham
B3 3AX

Tel: +44 (0)121 483 5583