

Estimate

Date: Friday, October 07, 2022

Pages: 2

To: Mudasir Nawaz

Company: Mudasir Nawaz

Email: nm-architecture@outlook.com

From: Alan Evans

Project: 171 Princess Road

Quotation Ref: Q2209098AE

We have pleasure in submitting our quotation with reference to the above project. We draw your particular attention to the second page of this quotation where any materials or services not included are listed. It may be possible to include these items if required. If you would like us to re-quote, please do not hesitate to contact us.

Brief Description of Works:

The following estimate is a budget proposal for a bespoke mechanically assisted flue system, suitable for serving your proposed 1 no gas fired pizza oven unit at the aforementioned project.

Our stainless-steel grade 316/304 twin wall insulated flue system will navigate from the appliance, out through the rear building wall before terminating horizontally under mechanical assistance.

Our proposal includes for the provision of all required general fixings and support components. We have also included for the supply only of a suitable control panel, carbon dioxide monitor and gas shut off switch for the installation, wiring and commissioning by others.

TOTAL SUPPLY & INSTALLATION COST £8336.00 net + VAT

THE ABOVE OFFER PRICE IS HELD FOR A MAXIMUM PERIOD OF 30 DAYS
FROM THE DATE OF OUR QUOTATION

Please Note:

- Our proposal is based on limited information supplied by yourself and is therefore meant only as a rough price guide at this stage. Our proposal is subject on the undertaking of a detailed site survey. This will allow us to confirm all safety and logistical requirements along with a firm quotation.
- We have allowed for one day's labour to carry out the above estimated works. Any unforeseen circumstances on site, (out of our control) preventing us from completing our installation may require additional labour. This will be charged at **£1700.00 net (Per Day)**.
- This estimation excludes all other services unless stated otherwise above, including builders works / making good / roofers works / painting / ventilation / appliance ancillaries / filtration units / Smokie unit / scaffolding / access equipment / pressure testing / sweeping / handling of asbestos / drain run offs / mechanical assistance / attenuators / draught stabilisers / Lightning tag connections / out of hours labour / VAT / wiring & commissioning.
- We must confirm that any orders containing non-stock or specially manufactured items are liable to be subject to a cancellation charge, in the event that we have commenced procurement of materials after receipt of your purchase order or instruction. Any items already committed to our stock or in the manufacture process that we are unable to return will be charged and delivered to a location of your choice
- All flue discharge heights must be approved by the relevant local authority public health department as required under the current clean air act memorandum. Chimflue Ltd is not responsible for obtaining this approval and therefore assumes that approval has already been sort by others prior to commencement of our proposed works.

Payment: Our terms of trading are 30 days nett monthly for customers with an approved trading account and sufficient credit facilities. An invoice will be forwarded for the full amount on completion of works, or monthly interim invoices where the installation continues over a single month.

For Proforma account customers, we will require a deposit payment of 60% of the quotation value plus VAT on placement of order. Progression of orders, including design drawings cannot commence until cleared funds are received. Interim and final invoices will be raised for progressed works and payment will be due by return.

Delivery Delay: The current delay is 10-20 working days.

We trust that your requirements have been fully met in this offer. However, if there are any points you are not sure of, or require further information, please do not hesitate to contact us.

Alan Evans

Sales Engineer

E. and O.E.