

Photos

Project Reference: 7135

Project Description: UoM Museum Kitchen Photos

Client: University of Manchester
Manchester Museum, Oxford Road, Manchester, M13 9GP

Date: 28 November 2022

Revision 01 (12 Dec 2022, additional specification added)



Existing function kitchen has non historic wall tiling and kitchen fittings. The proposals are to remove the existing kitchen fittings, the limited amount of wall tiling and vinyl flooring, then replace with new pvc wall cladding and new vinyl flooring. The existing white painted walls and ceiling will be repainted Dulux trade mouldshield eggshell white. The existing paintwork is non historic non original. The flooring will be Forbo safestep R11, colour: granite. These do not affect the fabric of the historic elements of the building.



Proposed opening through to corridor includes a non-historic water tank. Door to right is also not historic. The clothes hooks are for removal, these are not original or historic. Walls will then be filled and decorated in Dulux trade mouldshield eggshell to match the existing non historic white paint.



Corridor into which the new door will open may well be original, but is not presented as a historic building element, unlikely to have been plastered with historic materials, and includes many modern finishes such as the vinyl floor, metal ceiling and white painted walls. The wall requires an opening for a new door. This opening will require 2 no. fire rated concrete lintels. The walls will then be replastered in modern gypsum plaster and decorated in Dulux pyroshield eggshell white to match the existing non-historic white paint.



Café kitchen has non historic fittings, vinyl floor, metal ceiling tiles, whiteroc and stainless steel wall cladding. The proposals include removing the dirty metal ceiling tiles, pvc wall cladding and rubber flooring and replacing with new metal clip in ceiling tiles, pvc wall cladding and vinyl flooring.

The new ceiling system is a white SAS internation clip in ceiling. The pvc wall cladding will be white coloured whiteroc. The flooring will be Forbo safestep R11, colour: granite.

These do not affect the fabric of the historic elements of the building.



Servery area includes a non historic serving counter. The proposals include removing a section of this counter to allow kitchen staff better circulation into the kitchen. Once removed, the green painted wall and skirting will need to be filled flush and redecorated in the green coloured little Greene paint used in the recent refurbishment (under a separate application by others). These do not affect the fabric of the historic elements of the building.