

CAREFULLY DISMANTLE TERRACOTTA COPING TO CORNICE. INSPECT & ALLOW TO REBUILD, ALLOW PC SUM FOR RENEWAL AND REPAIRS AS STATED. AS C41/ 114.

CAREFULLY DISMANTLE/ REMOVE EXISTING TERRACOTTA. (WHERE APPLICABLE) PROVIDE NEW TO MATCH EXISTING. (OR AS STATED) AS C41/ 115

CAREFULLY DISMANTLE, ALLOW TO REBUILD BRICKWORK/ ALLOW FOR RENEWAL AS STATED C41/ 112.

TERRACOTTA MISSING- PREPARE AND PROVIDE NEW SECTION AS C41/ 121 (WILL REQUIRE PATTERN)

ITEM 5.04
ALLOW TO DOFF CLEAN 100% OF BRICK & TERRACOTTA &
REINSPECT WITH CA SUBSEQUENTLY. ALL AS C40/235

