

SILVERWOOD HOUSE, 129 BARLOW MOOR ROAD,
DIDSBURY, MANCHESTER, M20 2PW.

Clearscript Limited

Waste Management Statement

Waste Management Strategy

PA Number:

Development description: Proposed Residential Scheme

Development location: M20 2PW

Strategy prepared by: Nigel Baxter

Date Prepared: 11/02/2016



Notes


The following strategy should be prepared using the guidance document available from:

<http://www.manchester.gov.uk/opservices/rubbish/developers.htm>

1. Number of bins proposed?	- Please provide details of the number of bins proposed and how this was calculated. 4 No. 240 litre wheelie bins per house – calculated on information provided by Enterprise (Manchester) Tel: 0161 957 8308. They suggested that due to the size of the properties the larger domestic bins would be required. The apartments will have 2No, 1100 litre trade waste containers.
2. Bin storage area	- Please include a plan of the proposed bin storage area, showing the bins that are proposed and the proposed collection point. - Please describe how occupants will transfer waste to the bin store and the distance travelled in doing so. All the bins will be provided as shown on the plan below. All within 10m of the exit to each unit. The occupants of each unit will then take waste to the designated bins. The apartments have a communal bin area within the car park.
3. Bin collection arrangements	- Please describe the bin collection area, including how and where bins will be moved to in order to reach the collection vehicle. - Please include plans showing how the collection vehicle will travel around the site. The bins will be in a specific bin storage area located in the curtilage of each dwelling as shown on the plan below. On the designated dates each property will bring the required bin to the pavement/drive and the collection vehicle is able to access these points as shown on the plan below. The communal bin area is accessible by the refuse vehicle.



Survey Path Analysis Profile for
D832 Refuse Vehicle



- Overall Vehicle
 - Overall Width
 - Overall Height
 - Min Body Ground Clearance
 - Track Width
 - Wheels to Rear Turning Radius
- | |
|--------|
| 7.500m |
| 2.400m |
| 3.300m |
| 0.350m |
| 2.400m |
| 9.625m |