



This Plan is for Planning and Building Regulations Purposes Only
This Plan is not a Working Construction Drawing.


NOTES Ref 133120/FH/2022
SITE PREPARATION



Proposed Front Elevation 1:50
Proposed Rear Elevation 1:50
Proposed Cross Section X-X 1:50



Proposed Ground Floor Plan [as existing] 1:50
Proposed Loft Level Plan 1:50



Proposed side elevation on A-A 1:100
Proposed side elevation on B-B 1:100

Don't scale from this Plan. All dimensions to be checked on Site before any work starts.

Notes (continued)

- STAIRCASE
- THE STAIRCASE MUST FORM PART OF AN ENCLOSED FIRE ROOF PASSAGEWAY LEADING FROM THE 1ST FLOOR TO AN EXIT TO THE GROUND LEVEL WITHOUT PASSING THROUGH ANY UNPROTECTED ROOM.
- THE STAIRCASE MUST ALSO COMPLY WITH ALL THE FOLLOWING POINTS:-
- 1) ALL TREADS TO BE SOLID, LEVEL AND OF EQUAL WIDTH.
 - 2) ALL RISERS TO BE SOLID AND OF EQUAL HEIGHT.
 - 3) MINIMUM RISE OF STAIRS TO BE 42°.
 - 4) THE SUM OF THE RISE OF A STAIR PLUS TWO TIMES ITS RUN TO BE MORE THAN 500mm AND LESS THAN 700mm.
 - 5) MINIMUM TREAD DEPTH TO BE 220mm.
 - 6) MINIMUM RISE HEIGHT TO BE 220mm.
 - 7) ALL TREADS TO BE NON-SLIP.
 - 8) MINIMUM HEADROOM OVER THE LINE OF STAIRS TO BE 2000mm.
 - 9) STAIRS AND HANDRAILS TO BE CONTINUOUS AND UNINTERRUPTED ON ONE SIDE ONLY AS DESCRIBED IN 1.10 OF APPROVED DOCUMENT K1 OF THE BUILDING REGS.
 - 10) A FIXED CONTINUOUS HANDRAIL TO ONE SIDE OF THE STAIRS TO BE A MINIMUM HEIGHT OF 900mm ABOVE THE LINE OF STAIRS.
 - 11) STAIRS TO BE SECURED TO THE STRUCTURE.
 - 12) STAIRS TO COMPLY WITH K1 OF THE BUILDING REGULATIONS.
 - 13) MEANS OF ESCAPE IN CASE OF FIRE.
 - 14) THE LEFT FLOOR LEVEL SHOULD BE SERVED BY A PROTECTED 1/2 HOUR FIRE RATED STAIRWAY WHICH MUST LEAD TO AN EXTERNAL DOOR EXIT AND HAVE ALL THE DOORS LEADING TO IT TO BE 1/2 HOUR FIRE PROTECTED INCLUDING FIRE RAMP FRAMES WITH INTUMESCENT SMOKE STRIP.
 - 15) THE ONLY DOOR TO BE EXCEPTED FROM THIS IS A BATHROOM DOOR.
 - 16) ALL HABITABLE ROOMS AT 1st FLOOR LEVEL TO HAVE AN ESCAPE WINDOW WHICH COMPLETES THE FOLLOWING CONDITIONS:
 - 17) THE WINDOW MUST BE UNOBTURDED.
 - 18) THE WINDOW MUST BE AT LEAST 0.33 x 2.00m.
 - 19) THE WINDOW MUST BE AT LEAST 450mm WIDE AND MINIMUM 450mm HIGH.
 - 20) THE BOTTOM OF THE OPENING AREA SHOULD NOT BE MORE THAN 1100mm ABOVE FLOOR LEVEL.
 - 21) THE ESCAPE WINDOW SHOULD ENABLE THE PERSON ESCAPING TO REACH A PLACE FREE FROM ANY OBSTACLES AS DESCRIBED IN 1.10 OF APPROVED DOCUMENT K1 OF THE BUILDING REGS.
 - 22) THE ESCAPE WINDOW SHOULD BE AT LEAST 200mm ABOVE FLOOR LEVEL.
 - 23) THE ESCAPE WINDOW SHOULD BE AT LEAST 200mm ABOVE FLOOR LEVEL.
 - 24) WINDOWS SHOULD BE DESIGNED SUCH THAT THEY WILL REMAIN IN THE OPEN POSITION MAKING THEIR ESCAPE.
 - 25) LOCKS (WITH OR WITHOUT REMOVABLE KEYS) AND STRAYS MAY BE FITTED TO STAIRS BEING WENT WITH A RELEASE CATCH WHICH MAY BE CHILD RESISTANT.
 - 26) THE PROVISIONS OF APPROVED DOCUMENT K OF THE BUILDING REGULATIONS (PROTECTION FROM FALLING; COLLISION AND IMPACT) SHOULD APPLY.
 - 27) THE TOP (LOFT) STOREY MUST BE SEPARATED FROM THE LOWER STOREYS BY AT LEAST 1/2 HOUR FIRE RESISTANT MATERIAL AND CONSTRUCTION.
 - 28) ALL THE RELEVANT PARTS OF APPROVED DOCUMENT B OF THE BUILDING REGS. MUST APPLY TO THE WHOLE BUILDING.

Proposed Loft Conversion forming two bedrooms and a bathroom at 631 Burnage Lane Burnage Manchester M19 1WB			
Client	HABIB EJAZ		
L.H.ARDON Building Design			
1 ASHLANDS DRIVE AUDENSHAW MANCHESTER M34 5EL			
Tele 01613207563 M 07950829709			
SCALE	1:50		
DATE	10-12-21		
Amendments Ref 133120/FH/2022			
DATE	CHANGED	BY	REASON
10-12-21	10-12-21	1	NAME CHANGED
10-12-21	10-12-21	2	NAME CHANGED
10-12-21	10-12-21	3	NAME CHANGED
FURTHER NOTES ADDED TO THE PLAN. SEE THE PLAN FOR DETAILS.			