Copyright of this drawing is vested in Jon Matthews Architects and it must not be copied or reproduced without written consent. Figured dimensions only are to be taken from this drawing. Do not scale from this drawing.

All Contractors must visit the site and are responsible for taking and checking all dimensions relative to their work, Jon Matthews Architects are to be advised of any variation between drawings and site conditions.

Electronic data/ drawings issued as 'read only' and should not be interrogated for measurement. All dimensions and levels should be read only from those values stated/ noted on the drawings

⚠ CONSTRUCTION - It is considered that the proposed works are within the scope of a competent Contractor and as such no unusual hazards have been identified, refer to relevant Key/ Schedule/ Designers Risk Assessment

Key Plan:

- Back Painted Glass

POV - Parrel Opening Vent

MATERIAL KEY

- M3 Solid, bronze coloured metallic PPC aluminium fence and gate. Height tba with GMP.
- M4 Flush fixed, capless, floor to floor, clear, fixed, glazed windows with PPC aluminium frame in a unitised system and metal panel behind the glazing to mask floor construction.
- M5 Flush fixed, solid, bronze coloured metallic PPC aluminium insulated cladding panel in a unitised system.
- M6 Flush fixed, perforated or louvred (to achieve a 40% clear area), bronze coloured metallic PPC aluminium cladding panel with an openable vent behind in a unitised system.
- M7 Mid-dark grey, mechanically brick slip system with shadow gap detail.
- M8 Flush fixed, capless, openable windows PPC aluminium frame in a unitised system.
- M9 Flush fixed, silicon sealed, clear glazed curtain walling and entrance doors with PPC aluminium frame and manifestation, Metal panel behind the glazing to mask floor construction.
- M10 Insitu concrete columns.
- M11 Flush fixed, solid, bronze coloured metallic PPC aluminium insulated cladding panel system.
- M15 Bronze coloured metallic PPC metal box section.
- M16 Back painted, flush fixed, capless, floor to floor, fixed, glazed windows with PPC aluminium frame in a unitised system.
- M17 Flush fixed, perforated or louvred (to achieve a 40% clear area), bronze coloured metallic PPC aluminium cladding panel in a unitised system.
- M19 Glass Balustrade
- M20 PPC louvred metal doors, colour to match item M7.
- M21 PPC metal doors, colour to match item M11
- M22 Flush fixed, capless, openable windows in PPC aluminium frame.
- M24 Bronze coloured metallic PPC plant louvres.
- M25 Flush fixed, perforated or louvred (to achieve a 40% clear area), silver grey coloured metallic PPC aluminium cladding panel with an openable vent behind in a unitised system.
- M26 PPC metal doors, to match item M24.

Revisions.

In Abeyance.

Rev.	Date:	Details:
U	22.08.22	LV Switch Room Door Removed & Removal of 3m high glass balustrades
T	11.08.22	Issued for planning
S	08.07.22	Issued for planning
R	17.06.22	Issued for planning
Q	22.04.22	Updated level & parapet height
P	22.02.22	Issued For Information
N	07.02.22	Addition of Comms Room External Door

09
B1-10-4209

Jon Matthews Architects
Union, 2-10 Albert Square, Manchester, M2 6LW

Project:
10-12
Whitworth Street West

Title:
South Elevation

Scale:	Origin Date:	Drawn:	Checked:
1:200@A3	19.12.14	MH	JM

Status:
Information

Project:	Drawing No:	Rev:
05247	_B1_04_2202	U