

GENERAL NOTES:

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND ENGINEERS DRAWINGS AND SPECIFICATIONS.
2. DESIGN BASED ON TOPOGRAPHICAL SURVEY AND CCTV SURVEY INFORMATION AVAILABLE AT THE TIME OF DESIGN. ALL EXISTING SEWERS, CONNECTIONS, PIPE SIZES AND INVERT LEVELS TO BE CONFIRMED BY CONTRACTOR PRIOR TO COMMENCEMENT OF WORKS TO ENSURE CONNECTIVITY. ANY VARIANCE FROM THE INFORMATION SHOWN SHOULD BE REPORTED TO THE ENGINEER FOR REVIEW.
3. DO NOT SCALE THIS DRAWING. ALL DETAILS AND DIMENSIONS ARE TO BE CHECKED BY THE CONTRACTOR. ANY DISCREPANCIES TO BE REPORTED TO THE ENGINEER.
4. ALL DIMENSIONS ARE IN METRES AND LEVELS IN METRES ABOVE ORDNANCE DATUM UNLESS OTHERWISE NOTED.
5. COVER LEVELS, GULLY POSITIONS, AND BUILDINGS LOCATION ARE APPROXIMATE AND SHALL BE CONFIRMED BY ARCHITECT/ LANDSCAPE ARCHITECT.

Manhole schedule- Surface Water Drainage														
MH REF	EASTING	NORTHING	CL (mAOD)	IL (mAOD)	DEPTH TO SOFFIT (m)	DS PIPE DIA (mm)	MH DIA (mm)	MH TYPE	COVER SIZE (mm)	COVER CLASS	COVER TYPE	RECESSED	RESTRICTED ACCESS	COMMENTS
LD01 - CP	383727.581	393240.572	31.480	30.330	1.000	150	600	PPIC	600X600	D400	SINGLE SEALED	Y	N	CATCHPIT TYPE (500mm SUMP) POSITION SUBJECT TO CONFIRMATION OF EXISTING
LD02 - CP	383712.906	393248.128	31.440	30.330	0.960	150	600	PPIC	600 X 600	D400	SINGLE SEALED	Y	N	CATCHPIT TYPE (500mm SUMP) POSITION SUBJECT TO CONFIRMATION OF EXISTING
LD03 - CP	383723.045	393268.757	31.460	30.330	0.980	150	600	PPIC	600 X 600	D400	SINGLE SEALED	Y	N	CATCHPIT TYPE (500mm SUMP) POSITION SUBJECT TO CONFIRMATION OF EXISTING
S1 - CP	383655.720	393198.297	31.130	30.303	0.677	150	600	PPIC	600 X 600	D400	SINGLE SEALED	N	N	
S2 - CP	383683.028	393243.155	31.190	29.778	1.262	150	600	PPIC	600 X 600	D400	SINGLE SEALED	N	Y	350 REDUCER REQUIRED CATCHPIT TYPE (500mm SUMP)
S3 - CP	383697.772	393232.302	31.000	29.533	1.242	225	1050	TYPE 2	750 x 750	D400	SINGLE SEALED	N	N	CATCHPIT TYPE (500mm SUMP)
S3A - CP	383685.103	393211.803	30.810	29.675	0.910	225	1050	TYPE 2	750 X 750	D400	SINGLE SEALED	N	N	CATCHPIT TYPE (500mm SUMP)
S3B - CP	383678.453	393203.186	31.190	29.859	1.181	150	600	PPIC	600 X 600	D400	SINGLE SEALED	N	N	CATCHPIT TYPE (500mm SUMP)
S3C - CP	383670.135	393189.522	31.020	30.036	0.834	150	600	PPIC	600 X 600	D400	SINGLE SEALED	N	N	CATCHPIT TYPE (500mm SUMP)
S4 - CP	383685.805	393241.475	31.220	29.370	1.550	300	1500	TYPE 2	1200 X 675	D400	SINGLE SEALED	Y	N	CATCHPIT TYPE (500mm SUMP)
S5	383693.401	393254.291	31.070	29.308	1.462	300	1500	TYPE 2	1200 X 675	D400	SINGLE SEALED	Y	N	
S6A	383756.303	393262.744	31.500	30.500	0.850	150	600	PPIC	600 X 600	D400	SINGLE SEALED	Y	N	
S6	383749.015	393248.776	31.420	30.000	1.120	300	1500	TYPE 2	1200 X 675	D400	SINGLE SEALED	Y	N	
S7A	383743.471	393238.287	31.310	29.860	1.150	300	1500	TYPE 2	1200 X 675	D400	SINGLE SEALED	Y	N	
S7	383740.626	393232.888	31.240	29.800	1.140	300	1500	TYPE 2	1200 X 675	D400	SINGLE SEALED	Y	N	
S8	383708.995	393249.271	31.360	29.450	1.460	450	1500	TYPE2	1200 X 675	D400	SINGLE SEALED	Y	N	
S9	383729.000	393277.715	31.510	29.630	1.580	300	1200	TYPE2	600 X 600	D400	SINGLE SEALED	Y	N	
S10	383717.189	393254.922	31.470	29.450	1.720	300	1200	TYPE 2	600 X 600	D400	SINGLE SEALED	Y	N	
S11	383695.039	393264.998	31.400	29.258	1.842	300	1500	TYPE 2	600 X 600	D400	SINGLE SEALED	Y	N	
S12	383694.439	393349.408	30.950	29.216	1.434	300	1200	TYPE 2	600 X 600	D400	SINGLE SEALED	N	N	CATCHPIT TYPE (500mm SUMP)
S13 - FCC	383708.954	3933380.081	31.000	29.199	1.651	150	1500	TYPE 2	600 X 600	D400	SINGLE SEALED	N	N	FLOW CONTROL CHAMBER
S13A	383710.759	393383.897	31.000	29.157	1.693	150	1200	TYPE 2	600 X 600	D400	SINGLE SEALED	N	N	CATCHPIT TYPE (500mm SUMP)
S14	383726.486	393417.042	31.000	29.059	1.791	150	1200	TYPE 2	600 X 600	D400	SINGLE SEALED	N	N	
S15	383735.043	393416.473	31.000	28.849	2.001	150	1200	TYPE 2	600 X 600	D400	SINGLE SEALED	N	N	
S16	383706.145	393381.956	31.000	29.210	1.640	150	1200	TYPE 2	600 X 600	D400	SINGLE SEALED	N	N	
OUTFALL	383736.495	393422.439	30.500	28.788	1.712		HEADWALL	TBC	N/A	N/A	N/A	N	N	HEADWALL OUTFALL - SUBJECT TO AGREEMENT WITH LLFA

Manhole schedule- Foul Water Drainage														
MH REF	EASTING	NORTHING	CL (mAOD)	IL (mAOD)	DEPTH TO SOFFIT (m)	DS PIPE DIA (mm)	MH DIA (mm)	MH TYPE	COVER SIZE (mm)	COVER CLASS	COVER TYPE	RECESSED	RESTRICTED ACCESS	COMMENTS
F1	383735.393	393277.693	31.550	30.330	1.070	150	450	PPIC	450 X 450	B125	DOUBLE SEALED	Y	N	INTERNAL MANHOLE
F2	383749.742	393270.265	31.550	30.120	1.280	150	450	PPIC	450 X 450	B125	DOUBLE SEALED	Y	Y	INTERNAL MANHOLE. 350 REDUCER REQUIRED
F3	383719.536	393256.182	31.520	30.715	0.655	150	450	PPIC	450 X 450	D400	SINGLE SEALED	Y	N	
F4	383744.839	393243.117	31.360	30.156	1.054	150	450	PPIC	450 X 450	D400	SINGLE SEALED	Y	N	
F5	383747.643	393248.563	31.430	30.070	1.210	150	450	PPIC	450 X 450	D400	SINGLE SEALED	Y	Y	
F6	383750.233	393253.589	31.500	30.000	1.350	150	450	PPIC	450 X 450	D400	SINGLE SEALED	Y	Y	BDIL:30.755
F6A	383724.967	393266.775	31.525	30.715	0.660	150	450	PPIC	450 X 450	D400	SINGLE SEALED	Y	N	
F7	383754.157	393261.201	31.520	29.937	1.433	150	450	PPIC	450 X 450	D400	SINGLE SEALED	Y	N	
F8	383722.342	393261.617	31.520	30.715	0.655	150	450	PPIC	450 X 450	D400	SINGLE SEALED	Y	N	
F9	383728.786	383728.786	31.530	30.715	0.665	150	450	PPIC	450 X 450	D400	SINGLE SEALED	Y	N	
F10	383780.650	393249.136	31.550	29.645	1.755	150	1200	TYPE 2	600 X 600	D400	SINGLE SEALED	Y	N	
EX MH15	383760.179	393263.460	31.520	30.100	1.270	150	1500	TYPE 2	1200 X 675	D400	SINGLE SEALED	Y	N	MH15 IS EXISTING THEREFORE INVERT LEVELS NEEDS TO BE CONFIRMED

ALL COVER LEVELS ARE APPROXIMATE - SUBJECT TO CONFIRMATION OF FINISHED LEVELS

C01	ISSUED FOR CONSTRUCTION	05/08/22	CS	CG
P07	STAGE 4 UPDATE	29/06/22	CS	CG
P06	STAGE 4 UPDATE	11/02/22	CS	CG
P05	STAGE 4 UPDATE	19/11/21	CD	CG
P04	DRAFT STAGE 4 UPDATE	05/11/21	CD	CG
P03	UPDATED TO INCORPORATE TEAMS COMMENTS	30/06/21	CS	CD
P02	STAGE 4	14.06.21	CD	CG
P01	STAGE 3 ISSUE	16/04/21	CD	CG
Rev:	Description:	Date:	By:	Chkd:



Merchant Exchange, 17-19 Whitworth Street West, Manchester, M1 5WG

0161 236 2384

manchester@curtins.com

www.curtins.com

Civils & Structures • Transport Planning • Environmental • Infrastructure • Geotechnical • Conservation & Heritage • Principal Designer

Birmingham • Bristol • Cambridge • Cardiff • Douglas • Dublin • Edinburgh • Glasgow • Kentish • Leeds • Liverpool • London • Manchester • Nottingham

Status:

STAGE 5

Project:

HOUGH END SPORTS VILLAGE

Orig Title:

MANHOLE SCHEDULE

Size:	Date:	Drawn By:	Designed By:	Checked By:			
A1	16.04.21	CD	CG	CG			
Scale:	NTS						
Project No:	Originator:	Zone:	Level:	Type:	Discipline:	Category / Number:	Rev:
HEV	- CUR	- XX	- XX	- DR	- C	- 92510	-C01

\\msb02\Projects\070801 - 07000\070170 - Hough End Sports Village\QA-Production\4-Notes\Drawings\CC\0520