

SCHEDULE NO. 12 – ROOF MOUTED VENTILATION UNITS

Manufacturer:	To be confirmed by Integral (Monodraught Units used for Co-ordination)
Location:	Sports Hall Roof
Quantity:	4No as indicated on Architect Roof Plan
Model Ref:	X-Air 200

Notes:

1. Each unit is to be supplied complete with a fully automatic intelligent control system with seasonal control, external and internal temperature, SD card Data logger and a wall mounted controller, which includes inbuilt CO₂ sensors for indoor air quality monitoring, user override buttons and traffic light indicator for guidance on window operation. Units to be linked to the BMS via modbus.
2. Internal grille to be provided as part of unit.