



BOUNDARIES (as drg p/03)

- Proposed levels
- Proposed paving falls
- House FFL indicated on plan.
- Retention

HOUSING AREA-

New highway works to footpaths and roads.

- Roads
- Footpaths
- DRIVEWAYS Macadam finishes with half battered precast kerbs and drop kerbs to housing frontages and new highway works to roads and footpaths to Manchester City Council adoptable standards.
- Precast paving to side and rear paths 450x450x50mm.

Macadam to front driveways, pink kerb edging to planted area and driveways. Highways construction as per Engineer's details.

BOUNDARIES (as drg p/03)

- Proposed levels
- Proposed paving falls

All footpaths to be no steeper than 1:21

Highways levels and drainage to be verified by Carley Daines

CONSTRUCTION ISSUE

REVISIONS
A alleyway levels revised 12/10/2022
B Plot 2 a/b/ floor levels and surrounding levels revised.
Site survey base indicated 19/10/2022

Stephen Martlew Landscape Architecture

Unit 2 8a Loom Street Manchester M4 6AN
TELEPHONE 0161 907 3226

DRAWING	TITLE	HOUSING HARD SURFACES AND LEVELS PLAN
DRAWING No	1907/C/06	
PROJECT	DOWNLEY DRIVE	
CLIENT	Great Places /Buttress/Rowlinson	
SCALE	1:125 @ A 1	REVISION B
DATE	March 2022	REVISED
DRAWN	PG	CHECKED SM