



T C TREE SERVICES LTD

Commercial Tree Surgery Specialists

FAO: Manchester City Council

Ref: 22.042

Works Schedule; 32 Barlow Moor Road, Didsbury,
Manchester, M20 2GJ.

3rd November 2022

tc-treeandsite.co.uk

Quotation for the undertaking of tree works as specified;***Directions based on the front of the property facing Barlow Moor Road.**

Item No:	Location:	Description Of Works:
1.0	Driveway Access To The Side Elevation	
1.1		Tree identified as T1 on the attached plan. Multi stemmed small Hazel tree noted to have a number of stems growing over the access driveway. Allow to cut all branches growing over the access driveway back to ensure clear vehicular access is provided to the rear car parking area.
1.2		Tree identified as T2 on the attached plan. Multi stemmed small Hazel tree noted to have a number of stems growing over the access driveway. Allow to cut all branches growing over the access driveway back to ensure clear vehicular access is provided to the rear car parking area.
1.3		Tree identified as T3 on the attached plan. Single stem medium sized mature Cherry tree. Tree noted to be in good condition with a number of branches visibly overhanging the access driveway, also noted to be in contact with the building at high level. Allow to undertake a crown reduction of 2m to bring the tree into a neat and tidy condition. Works will also include to crown lift by 3m from ground level.
1.4		Tree identified as T4 on the attached plan. Single stem medium sized mature Silver Birch. Tree noted to be in good condition with a number of branches visibly overhanging the access driveway and in contact with the building at high level. Allow to undertake a reduction of 3m to the Silver Birch tree to bring the tree into a neat and manageable shape. All extended branches over the property will be cut back to ensure a minimum 2m clearance is provided. Works will include a 3m crown lift to ensure vehicular access is clear.

		Tree will require climbing to ensure branches are cut and lowered carefully to prevent damage.
1.5		Tree identified as T5 on the attached plan. Multi stem medium sized mature Beech tree. The tree appears to be in good condition with a number of branches visibly overhanging the access driveway and noted to be in contact with the building at high level. Allow to undertake a crown reduction of 3m to the Beech tree to reduce the height and canopy of the tree into a neat and presentable condition. Works will include a crown lift by 3m to ensure vehicle access is clear. Branches will be cut back to ensure a minimum clearance of 2m will be provided between the tree and the property. Tree will require climbing to ensure branches are cut and lowered carefully to prevent damage.

Thank you for reading this works schedule which forms part of the planning application for tree works at 32 Barlow Moor Rd, Didsbury. T C Tree Services Ltd strive to provide our clients with the best professional services possible. Nothing is too much trouble, if you wish to discuss the works or would like to meet on site to run over the proposals please feel free to ask.

Kind Regards,

TC Smith

Thomas Smith BSc (HONS) MRICS

Director

T C Tree Services Ltd

E: tom@tc-treeandsite.co.uk

Office: 0161 541 2912

Mobile: 07737 411378

