



Angela Leckie
Manchester City Council
Town Hall
Manchester
M2 5DB

27th October 2022

Dear Madam,

As discussed, the proposed scaffold(s) to Rylands Building will be designed and erected in accordance with the previously agreed Conservation Strategy. All works will be undertaken in accordance the following listed areas of the report: -

3.1.2 Protection
3.1.4 Access scaffolding
3.2.3 Mortar (including cement)
3.2.4 Stone masonry

We would confirm that the ends of ALL scaffold tubes are to be protected with plastic caps which are to be fitted prior to delivery to site. Where it is necessary to cut scaffold tubes during erection the end is to be re-capped. We would ensure any architectural features or areas prone to damage are suitably protected.

All decorative masonry, corner pieces and stone entrance areas of the host building will be boxed in with plywood to prevent damage from the scaffold during the scaffold's erection and removal.

All vulnerable historic surfaces at are to be suitably protected to prevent the scaffold damaging existing external and internal finishes.

The clock upon Market Street will be boxed in with plywood to prevent damage from the proposed scaffold.

Yours faithfully

Infinity Outdoor Ltd