



**1119 Ashton Old Road,
Manchester**

Ground Investigation Report



Report for:


Eco NRG Solutions Ltd

Date: 1st September 2017

T&P Ref: 2017Sep_ASH1867_GI Report_Issue2

T & P Regeneration Ltd
Unit 4, Brunel Lock Development
Smeaton Road
Bristol
BS1 6SE
Tel: 0117 927 7756

Document Issuance

Client	Eco NRG Solutions Ltd	
Project	1119 Ashton Old Road, Manchester	
Issue	1 (One) – First issue	
Date:	30 th June 2017	
PREPARED BY	CHECKED BY	APPROVED BY
		
Raife Crookes	Helen Matheson /James Dodd	Mike Nicholas

Document Revision Record

Issue Number	Date	Revision Details	Revised by	Checked by	Approved by
2	01/09/2017	Addition of equipment serial numbers to Gas Monitoring sheets and associated equipment certificates.	RC	PJ	PJ

The information and advice contained within this report is provided by T&P Regeneration Ltd for sole use and reliance by its Client in performance of T&P Regeneration Ltd's duties under its contract with the Client. Any advice, opinions or recommendations within this report should be read and relied upon only in the context of the report as a whole. The advice within the reports is based upon the information made available to T&P Regeneration Ltd within the financial and timeframe constraints imposed. The report is based on UK standards, codes and common practice current at time of writing. When considering this report regard should be given to the terms and conditions of T&P Regeneration Ltd's contract with the Client under which the report was prepared. The copyright of this report is held by T&P Regeneration Ltd. Should the Client wish to release this report to a Third Party for that party's reliance, T&P Regeneration Ltd may agree to such release provided that: (i) T&P Regeneration Ltd's written agreement to such release is obtained (ii) By release of the report, T&P Regeneration Ltd assumes no duties, liabilities or obligations to the Third Party and that the Third Party does not acquire any rights whatsoever against T&P Regeneration Ltd (iii) T&P Regeneration Ltd accepts no responsibility for any loss incurred by the Client through the Client's release of the report to the Third Party. Following final issue of this report, T&P Regeneration Ltd has no further obligation to advise the Client on any matters such as changes in legislation or codes of practice that may affect the advice contained within the report.

CONTENTS PAGE

1	INTRODUCTION.....	1
1.1	CONTRACT DETAILS	1
1.2	PROPOSED DEVELOPMENT	1
1.3	PURPOSE OF THE ASSESSMENT	1
1.4	PREVIOUS REPORTS	1
1.5	SCOPE OF WORKS	1
1.6	REPORT LIMITATIONS	2
2	CURRENT SITE DESCRIPTION AND LOCATION	3
2.1	SITE LOCATION	3
2.2	SITE DESCRIPTION	3
2.3	SITE CONTEXT	3
3	CONCEPTUAL SITE MODEL	6
3.1	POTENTIAL CONTAMINATIVE SOURCES	6
3.2	POTENTIAL RECEPTORS	7
3.3	EXPOSURE AND PATHWAY MECHANISMS	7
3.4	SUMMARY OF SOURCE – PATHWAY – RECEPTOR RELATIONSHIPS	8
3.5	GEOTECHNICAL HAZARD IDENTIFICATION SUMMARY	12
4	SCOPE OF GROUND INVESTIGATION WORKS.....	13
4.1	GENERAL SCOPE OF FIELDWORK	13
4.2	EXPLORATORY HOLE POSITIONING AND ACCESS RESTRICTIONS	13
4.3	DYNAMIC SOIL SAMPLING BOREHOLES	13
4.4	ENVIRONMENTAL MONITORING	13
5	SUMMARY OF GROUND CONDITIONS AND LABORATORY TESTING.....	14
5.1	RECORDED GROUND CONDITIONS	14
5.2	GROUNDWATER	15
5.3	LABORATORY TESTING	15
6	HUMAN HEALTH RISK ASSESSMENT.....	17
6.1	INTRODUCTION	17
6.2	ASSESSMENT OF AVERAGING AREAS/ZONES FOLLOWING GROUND INVESTIGATION WORKS	17
6.3	PRESENTATION OF RISK ASSESSMENT	17
6.4	SUMMARY FINDINGS OF HUMAN HEALTH RISK ASSESSMENT AND RECOMMENDATIONS	23
7	CONTROLLED WATERS RISK ASSESSMENT	24
7.1	CONCEPTUAL MODEL	24
7.2	RISK EVALUATION	24
8	GAS PROTECTION REQUIREMENTS.....	26
8.1	OVERVIEW	26
8.2	GROUND GAS MONITORING RESULTS	26
8.3	GAS SCREENING VALUES	27
8.4	DISCUSSION	27
9	PLANT GROWTH AND POTABLE SUPPLY PIPEWORK RISK ASSESSMENT	28
9.1	PHYTOTOXIC RISK ESTIMATION	28
9.2	POTABLE WATER SUPPLY PIPEWORK RISK ESTIMATION	29
10	REFINED CONCEPTUAL SITE MODEL	31

10.1 SOURCES	31
10.2 PATHWAYS	31
10.3 RISK EVALUATION	32
11 WASTE CLASSIFICATION	36
11.1 LANDFILL ACCEPTANCE CRITERIA	36
11.2 LIST OF WASTE (LOW) CODE	36
11.3 HAZARDOUS WASTE CODES AND SOIL WASTE CLASSIFICATION	36
11.4 WASTE ACCEPTANCE CRITERIA (WAC) TESTING	37
11.5 LANDFILL TAX	37
11.6 WASTE ASSESSMENT DISCUSSION	37
12 COMMENTS ON ENGINEERING DESIGN.....	38
12.1 GENERAL	38
12.2 SUMMARY OF GEOTECHNICAL PARAMETERS	38
12.3 CONSTRUCTION CONSIDERATIONS	40
12.4 PRELIMINARY FOUNDATION RECOMMENDATIONS	41
13 CONSIDERATIONS AND RECOMMENDATIONS	43
13.1 CONSIDERATIONS	43
13.2 RECOMMENDATIONS: HUMAN HEALTH AND CONTROLLED WATERS	43
13.3 RECOMMENDATIONS: PLANT GROWTH AND POTABLE WATER SUPPLY PIPEWORK	43
13.4 RECOMMENDATIONS: ENGINEERING	43
13.5 RECOMMENDATIONS: GENERAL	44

APPENDICES

A	DRAWINGS
B	PHOTOGRAPHS
C	EXPLORATORY HOLE RECORDS
D	GEOTECHNICAL ANALYSIS RESULTS
E	CHEMICAL ANALYSIS RESULTS
F	MONITORING RESULTS
G	HAZWASTE PRINTOUT
H	STATISTICAL ASSESSMENT

EXECUTIVE SUMMARY

Project information and site setting	Project details	This ground investigation report has been prepared by T&P Regeneration Ltd (T&P) on behalf of Eco NRG Solutions Ltd for the site located north of Old Ashton Road, Manchester – postcode M11 1AA / NGR: 388635, 397445. This report presents a review of third party Phase 1 desk study information and the findings of a Phase 2 intrusive ground investigation.
	Current land use	At the time of the ground investigation works, the site was found to be a rectangular parcel of land approximately 35m by 46m orientated northeast to southwest, currently used as a storage area by the neighbouring car body/ auto repair shop. Access was gained via a wide double gate in the north east of the site. At the time of the walkover it was noted that a wire basket containing a number of sealed and unsealed containers was present in the north of the site. Signs of burning and staining of the surrounding ground area was identified.
	Development	The potential future development will comprise the construction of a STOR gas generator plant. Current proposed plans show the commercial development to consist of approximately 85% hardstanding and 15% gravel cover, a warehouse style building, substation and oil and gas storage tanks.
Phase 1 desk study assessment and conceptual model	Environmental setting	Published geological records indicate that the site is underlain by Superficial Devensian Till (Secondary – Undifferentiated aquifer). Underlying the Till the Chester Pebble Bed Formation, a principal aquifer is recorded. Historical boreholes less than 50m from the site, record the superficial deposits to extend to at least 24 metres below ground level (mbgl). There are no surface water features within a 500m radius of the site. There are no licensed groundwater, potable water or surface water abstractions within 500m of the site.
	Radon	The site is situated inside a 1km² Ordnance Survey (OS) grid area where between <1% of properties are within a Radon Affected area, therefore radon protection measures will not be required.
	Site history	In summary, the site has been previously associated with a number of industrial land uses including a Cotton Mill and Works (Iron Foundry, Dye and Print Works). These different uses have seen the site be incorporated with buildings to the south and north, with satellite imagery suggesting current levels were reached in 2009. Neighbouring industrial land uses included oil, steel, engineering and chemical works. Infilling of a canal (registered landfill) to the immediate west and a sand pit 100m to the north of the site. Historical Openshaw Bridge Works 50m east are identified as manufacturing/handling insulation material.
	Areas of potential concern	Areas of potential concern in relation to ground contamination have been identified as follows: • Unsealed and discarded chemical containers in the north central area of site, including thinners and other unlabelled chemicals; • Gas and contaminant migration from the infilled canal/ landfill to the immediate west; • Contaminant migration from industrial practices in the surrounding area; • Made ground from historical industrial activities and miscellaneous development on site; • Former refuse pit located approximately 98m north-east of site which may have been infilled with made ground of unknown composition.

Phase 2 Ground investigation	T&P ground investigation	An intrusive ground investigation was undertaken by T&P at the site on Friday 28th April and in summary comprised the following: Drilling of 7No dynamic soil sampling boreholes; Installation of 3No boreholes as environmental monitoring wells; Ground gas monitoring on 6No occasions; Logging of ground conditions and soil sampling by a suitably qualified engineer. Selected samples collected during the ground investigation were submitted to the laboratory for geotechnical and environmental testing.
	Ground conditions	Made ground was found within all exploratory hole locations to depths of 0.70m to 1.2mbgl. This was found to comprise dark gravelly sand and sandy gravelly clay. The gravel was angular fine to coarse of red brick, concrete, ceramics, plastic, glass and wood. Underneath the made ground to maximum depths of 1.8 – 2.2mbgl stiff to very stiff orangish brown mottled grey occasionally sandy clay was encountered. Underling this to an unconfirmed maximum depth of 5mbgl a dense to very dense occasionally slightly clayey sand was encountered. The clay and sand is considered to be representative of the Superficial Till Deposits recorded in the area by BGS mapping.
	Groundwater	Groundwater was encountered within WS01, WS04, WS06 and WS07 at 3m bgl during the ground investigation.
Principal findings and conclusions	Human health	Chemical analysis has shown that potential contaminants within the both the made ground (except within WS04) and natural ground are beneath the adopted screening levels for a commercial development. A singular raised elevation of Lead – 4030mg/kg was detected within the made ground sample WS04 (0.5 – 0.8m bgl). This has been identified as a hotspot, however based upon the proposed design this will be encapsulated underneath areas of hardstanding and will not pose a risk to the critical receptor.
	Controlled waters	Based on the available information, we consider that the risk posed to the controlled waters by potential sources of contamination on site is low. This is based upon the proposed development limiting percolation/leaching and subsequent vertical migration of determinants, evidence of monitoring of the sand band within the underlying Till is not a significant water bearing unit and chemical testing demonstrating a significant reduction in contaminant concentrations with depth.
	Gas protection	A six-week gas monitoring regime has been completed at the site and has demonstrated the site to be categorised as a Characteristic Situation 1 (CS1). As such gas protection measures will not be required within the design. The site is also shown to be in an area where <1% of homes are affected by radon gas, so radon protection measures will not be required on the site.
	Plant growth and buried potable supply pipework	The site wide made ground on site is not typically considered suitable for existing flora. However, current flora on site does not show signs of wilting. Upgraded pipework will be required where placed within the existing made ground.

	Waste	The topsoil and natural ground and the majority of the made ground is classified as non-hazardous waste. The chemical data indicates the soil will likely be treated as inert or stable non-reactive waste, avoiding the higher rate of landfill tax. In locations where hazardous waste has been identified, (made ground in the areas of WS02, 03, 04 and SS01) the material will need to be dealt with separately to the majority of the material being removed from site. It is recommended that the hazardous material is segregated and removed as hazardous waste. Receiving landfills will require WAC testing to be carried out on the hazardous waste in order to determine whether or not it can be classified as inactive material which would mean that it could avoid the higher landfill tax rate.
	Engineering design	The cohesive soils have shown to be of moderate shrinkage potential. CBR values have not been provided for the site, although made ground is not typically classed as suitable for use beneath adoptable road, due to the private nature of the hardstanding on site, it may be applicable to utilise the made ground as a formation surface, in such situation coarse material should be removed as to prevent differential settlement. It is considered that pad foundations (1m by 1m) placed at depths of 1.2mbgl within the cohesive clay could be designed for an allowable bearing pressure of 125kPa. Should a larger bearing pressure be required, a 1.5m by 1.5m pad at 2.0mbgl within the sand could be designed for an allowable bearing capacity of 250kPa for acceptable settlement. Sulphate testing of selected soil samples indicates that a suitable design mix for concrete for buried structures is likely to be DS1-AC1s. Any inflows into excavations above this depth would be expected to be low and should be adequately dealt with via sump pumping. Where excavations will surpass 3m below current ground levels the use of specialist dewatering techniques will likely be required and the advice of specialist dewatering contractors should be sought.
	Considerations	The conceptual site model has been based on the current proposed development which involves the majority of site becoming hard standing and gravelled area. Any updates to this design should be assessed against the recommendations within this report.

Considerations and further works	Recommendations	<u>Human health/Controlled Waters</u> - Based upon laboratory testing a Lead hotspot has been identified within the eastern corner of the site (WS04). Based upon the current proposed development plan this area will be capped and the pathway to critical receptors removed. - Where gross soil contamination has been identified i.e. non-aqueous phase (NAPL), such as in the vicinity of SS01, which is anticipated to be the result of surface spillage of oils/solvents observed to be stored on-site, it is recommended that this is removed during construction, under a watching brief to further reduce the risks to Controlled Waters in accordance with best practice. This will further lower the residual vapour risk to future site users. - Although through the redevelopment of the site the risks to receptors is low, advice and controls should be put in place for those visiting and using the site currently. <u>Plant growth and potable water supply pipework</u> - The made ground soils on-site are not considered suitable for plant growth. However the proposed layout doesn't identify any areas of planting and as such this is not considered to require any specific action. - Upgraded potable pipework will be required in all areas of made ground on site. <u>Engineering</u> - The cohesive Till deposits have been characterized as having medium volume change potential, as such foundations should be a minimum of 0.9mbgl. These soils will also be moderately effected by on site trees and hedgerows, as such it is recommended that an arboricultural survey of the site should be consulted during foundation design. 1m by 1m pad foundations at a depth of 1.2mbgl could be designed for an allowable bearing capacity of 125kPa for allowable settlement within the cohesive Till Deposits. In the event that greater pad sized are required and or a larger bearing capacity, pads within the granular sand deposits could be designed for a allowable bearing capacity of 250kPa. - Based upon the Hazwaste results it is expected that where disposal is required the made ground in the east of the site will be classed as hazardous and be at the higher tax rate, while areas in the west will be classed as non-Hazardous and be at the standard rate. <u>General</u> - The statutory water provider should be consulted regarding suitable water supply pipework requirements. - Discussions should be held with local landfill facilities to determine their classification for any soils to be disposed off-site arising from its development. - A site-specific health and safety plan should be prepared to inform on risks posed from the previous site use and mitigations for ground workers developing the site e.g. requirements for appropriate PPE, hygiene practices, environmental monitoring and requirements for mitigation measures during construction works. - Construction workers should remain vigilant for visible and olfactory signs of gross contamination which has not been identified and assessed within this ground investigation. In the event that gross contamination is found an environmental engineer should be consulted.
---	-------------------------------	---

		• On-site boreholes should be decommissioned in accordance with Environment Agency guidance prior to development. • The relevant regulatory authorities should be forwarded a copy of the ground investigation report, to confirm that they are in agreement with the conclusions and recommendations herein.
--	--	---

1 INTRODUCTION

1.1 Contract details

Following instruction from Eco NRG Solutions Ltd – ‘the client’, this report presents the results of a geo-environmental ground investigation undertaken to support planning application 113808/FO/2016 for a commercial Energy Reserve Facility at 1119 Ashton Old Road, Manchester - ‘the site’.

1.2 Proposed development

Information presented to T&P Regeneration Ltd (T&P) indicates that planned development is to comprise the erection of a single story building to form a small-scale gas fired Energy Reserve Facility involving flues to roof, associated outbuildings, plant, hardstanding and boundary treatment.

A proposed layout is included as Appendix A.

1.3 Purpose of the assessment

The purpose of the assessment has been to establish the environmental and geotechnical conditions of the site to support discharge of conditions relating to planning consent ref 113808/FO/2016. This report also considers the likely foundation options appropriate to the site, along with requirements for any related ground improvement works and/or remediation considered necessary to mitigate against any unacceptable human health or environmental risks resulting from existing or former land uses.

1.4 Previous reports

A desk study and preliminary risk assessment was previously completed for the site by a third party¹. Pertinent information from the report and existing Groundsure report (issued August 2016) is summarised and used within this assessment.

1.5 Scope of works

The scope of works to fulfil the purpose of the assessment has included the following:

- Review of the third party report.
- Drilling of 7N° dynamic soil sampling boreholes.
- 3N° environmental monitoring installations.
- Preparation of engineering exploratory hole logs to record the observed ground conditions.
- Chemical and geotechnical testing of the soils.
- 6N° return groundwater and ground gas monitoring visits.

¹ Desk Study and Preliminary Risk Assessment – RPS Group (September 2016)

- Preparation of an interpretative report presenting the findings of the investigations.

1.6 Report limitations

The recommendations, interpretations and conclusions of this report are based on the historical and current site conditions reported by the previous third party report and observed during the intrusive investigations undertaken. No responsibility can be accepted for the accuracy of third party information including reference data contained within site specific database reports. Due to the inherent variability of the ground conditions between exploratory hole positions these conditions can only be interpreted and not defined and are accurate only for the date of the investigation works.

2 CURRENT SITE DESCRIPTION AND LOCATION

2.1 Site location

The site occupies an area of approximately 0.2 hectares (ha) and is located around National Grid Reference (NGR): 388635, 397445 in the east of Manchester. The nearest postcode for the site is M11 1AA.

2.2 Site description

At the time of the ground investigation works, the site was found to be a rectangular shaped parcel of land measuring approximately 35m north to south and 46m east to west. The site was found to be predominantly level with a slight fall from E to W and a raised berm running adjacent to the south boundary, elevated approximately 1m above the rest of the site. The northern and western boundaries of the site are demarked by palisade fencing. The eastern and southern boundaries are demarked by a 1m wide concrete path adjacent to the adjacent commercial businesses. Service plans and evidence gathered during the site walkover indicates surface water drainage may run underneath this path exiting the site via the north-east boundary.

Access was gained to the site via a wide double gate in the north-east of the site. The yard is currently associated with a nearby car body/auto repair shop and is indicated to be used currently for storage. Items recorded on site during the investigation include a horsebox, disused barbeque, kennel, numerous car parts in the north of the site (plastic bumpers) and a wire mesh container containing numerous open and sealed containers. The area surrounding this wire container showed dark staining of the soils, along with additional plastic containers surrounding with one labelled as 'Standard Thinners' and evidence of ash in the bottom of the wire container.

The immediate surrounding area was found to comprise industrial buildings and a public footpath (Old Canal) to the west. The surrounding industries include a recycling centre to the north, car body/repair shop and a motorbike accessories store to the south.

The wider area comprises terraced residential housing to the east, a primary School and Old Ashton Road (A635) to the south-east, a wholesale market and recycling centre to the south-west and commercial buildings to the west/north.

Mature trees were noted on the western boundary of the site. It is understood these will remain as part of the future redevelopment.

An annotated site features plan is provided within Appendix A and a selection of photographs within Appendix B.

2.3 Site context

2.3.1 Geological setting

The published solid and drift geological mapping (1:50,000 sheet 85) indicates the site to be entirely underlain by Devensian Superficial Till Deposits comprising clay to sandy clay, unsorted with common pebbles, cobbles and some boulders. The Chester Pebble Beds Formation (Lower Triassic) is recorded to underlie the Till deposits and consists of a reddish brown and pinkish red medium grained sandstone with common quartzite pebbles towards the base.

3N⁰ historical borehole records are available within 150m of the site. These were completed in 1970 and record varying deposits of clay and sand to depths of approximately 24mbgl. These logs are considered to demonstrate the local thickness of superficial till deposits below the site to greater than 24m bgl.

2.3.2 Hydrogeology and groundwater sensitivity

The underlying Superficial Till Deposits are recorded as a Secondary – Undifferentiated Aquifer with the underlying Chester Pebble Beds Formation being recorded as a Principal Aquifer by the Environment Agency.

Evidence from historical borehole reference SJ89NE1127 located <50m south-east from the assessment site identifies the superficial till deposits predominantly as a sandy clay with, bands of sand, lenses of silt and some gravel, terminating within them at 24m bgl. This overlying thickness of till deposits will significantly limit the potential for vertical connectivity with the underlying Chester Pebble Beds Formation to be active. As such the principal aquifer will not be assessed as a potential receptor further within this report.

2.3.3 Hydrology and surface water quality

No surface water features are recorded to be present within 500m of the site.

2.3.4 Groundwater and surface water abstractions and discharges

Based on previous reports and data available on the Environment Agency website no surface water or groundwater abstractions are recorded within a 500m radius of the site. The site is not located within a Source Protection Zone (SPZ).

2.3.5 Radon

The third party desk study report indicates that the site is within an area where <1% of properties are within a Radon Affected Area. Therefore, no radon protective measures are required within future redevelopment.

2.3.6 Historical site usage

The available historical maps were reviewed as part of the third party desk study report. A summary of the pertinent points is included below.

The site has been previously associated with a number of industrial land uses including a cotton mill, delivery forecourt and works (iron foundry, dye and print works). A tank is identified in the west of the site circa 1922.

By 1974, historical mapping indicates previous buildings and associated structures have largely been demolished. Aerial imagery from 2009 shows the site to be stripped with only the perimeter pathway recorded.

The third party report indicates that surrounding land uses have comprised a variety of industrial activities, including former oil, steel, engineering, carriage/wagon and chemical works. The Manchester and Stockport canal was located to the west of the site between 1797 and 1970. Furthermore, a refuse pit was located 98m to the north-east of the site between 1890 and 1915.

Both features may have been historically infilled and could represent an off-site source of ground gas.

2.3.7 Landfill sites and waste management facilities

The third party desk study report indicates that there are no current landfills located within 500m of the site boundary; however, 3N° historical landfills were identified. The closest historical landfill is associated with the infilling of the historical Stockport Branch Canal, which was registered as having accepted inert waste and liquid sludge.

2.3.8 Sensitive environmental designations

There are no recorded sensitive environmental designations in the area of the site.

3 CONCEPTUAL SITE MODEL

3.1 Potential contaminative sources

Potential on- and off-site sources of contamination as highlighted within the previous report are summarised in Table 3.1. Where applicable these have been expanded / updated by T&P as deemed necessary based on review of the previous reports.

Table 3.1 – Potentially contaminating sources summary			
	Areas of potential concern (APC)	Source origin/description	Source hazard contaminants
Existing sources (On-site)	1	Unsealed and discarded chemical containers in the north central area of site, including thinners and other unlabelled chemicals.	Asbestos, heavy metals, TPH, PAH, CO ₂ , CH ₄ , VOCs, sVOCs.
Existing sources (Off-site)	2	Gas and contaminant migration from the infilled canal/ landfill to the immediate west.	
	3	Contaminant migration from industrial practices in the surrounding area including a recycling centre 10m to the north and an auto repair shop/ spray shop 5m to the east.	
Historical sources (On-site)	4	Made ground from historical industrial activities and miscellaneous development on site.	
Historical sources (Off-site)	5	Former refuse pit located approximately 98m north-east of site which may have been infilled with made ground of unknown composition.	
Notes: PAH – polycyclic aromatic hydrocarbons. CH ₄ – methane. CO ₂ – carbon dioxide. TPH – total petroleum hydrocarbons. VOCs – volatile organic compounds. sVOCs – semi volatile organic compounds.			

3.2 Potential receptors

The future land use of the site has been considered as 'commercial' based upon the proposed end use and the land use scenarios described in SP1010².

With regard to the current and future proposed setting and form of the site, potential receptors to possible source hazards identified above are summarised below.

3.2.1 Humans

- Future on-site operatives – **critical receptor**.
- Future maintenance workers
- Construction workers.

3.2.2 Controlled waters

- Groundwater – The site is not recorded to lie within a SPZ and no potable water or groundwater abstraction points are recorded within a 500m radius. The underlying Superficial Till is classified as a Secondary Aquifer – Undifferentiated. With reference to national guidance³, the sensitivity of groundwater as a potential receptor to contaminant impact beneath the site is considered to be Low (L1).
- No surface water features are present within 500m of the site. As such surface water is not considered to require further consideration as a receptor within this report.

3.2.3 Other environmental receptors

- Potable water supply pipework and buried concrete associated with future development. Underground services associated with the proposed development may be affected by the chemical characteristics of the soil through direct chemical attack.

3.3 Exposure and pathway mechanisms

For potential sources of contamination to pose a risk to environmental and human receptors, there must be at least one active or potentially active pathway. Pathways can be considered in terms of direct exposure or in terms of migration routes and transport mechanisms.

For example, direct exposure can occur through: inhalation of toxic gases, dusts or vapours, and ingestion or dermal uptake of contaminated dusts, soils or vegetables. Contaminants can also migrate to receptors via physical transport processes including soil leaching, surface water and groundwater flow.

The proposed development identifies site use to be approximately 85% buildings and hardstanding and 15% with a gravel finish. Due to the extensive areas of hardstanding across the

² SP1010 – Development of Category 4 Screening Levels for Assessment of Land Affected by Contamination (2013 – as amended) – CL:AIRE

³ Annex 2 - Guidance for the Safe Development of Housing on land Affected by Contamination R&D66: 2008

site providing a physical barrier and proposed end use, pathways such as direct contact/ingestion, plant/vegetable uptake and dust inhalation are effectively severed. This hardstanding will also intercept rainwater, greatly reducing percolation through the made ground and potential leaching of contaminants.

Assumptions have been made that construction workers and current site visitors/ users would be working under appropriate health and safety controls such that their risks of exposure would be mitigated.

3.4 Summary of source – pathway – receptor relationships

Table 3.2 highlights the source-pathway-receptor relationships (SPRs) that are considered viable post development. Those SPRs assessed as low or very low risk do not require further consideration.

Table 3.2 - Potential source–pathway–receptor relationships						
Area of potential concern N°	Source	Pathway (s)	Receptor	Classification of consequence	Classification of probability	Classification of risk*
1	On-site Unsealed and discarded chemical containers in the north central area of site, including thinners and other unlabelled chemicals.	Oral ingestion	Future on-site operatives, construction workers	Medium	Unlikely	Low Risk
		Dermal contact	Future on-site operatives, construction workers	Medium	Unlikely	Low Risk
		Dust inhalation	Future on-site operatives, construction workers	Medium	Unlikely	Low Risk
		Leaching/dissolution with vertical migration	Groundwater	Medium	Unlikely	Low Risk
		Direct contact	Buildings and underground services	Medium	Low likelihood	Moderate/Low Risk
		Gas / vapour inhalation	Future on-site operatives, construction workers	Medium	Low likelihood	Moderate/Low Risk

Table 3.2 - Potential source–pathway–receptor relationships						
Area of potential concern N°	Source	Pathway (s)	Receptor	Classification of consequence	Classification of probability	Classification of risk*
2	<u>Off-site</u> Gas migration from infilled canal/ landfill to the immediate west.	Lateral gas migration and subsequent gas inhalation/explosion	Future on-site operatives, construction workers	Medium	Low likelihood	Moderate/Low Risk
3	<u>Off-site</u> Contaminant migration from industrial practices in the surrounding area including a recycling centre 10m to the north and an auto repair shop/ spray shop 5m to the east.	Lateral migration in groundwater and gas / vapour generation.	Future on-site operatives, construction workers	Medium	Low likelihood	Moderate/Low Risk
4	<u>On-site</u>	Downward migration	Groundwater	Medium	Unlikely	Low Risk

Table 3.2 - Potential source–pathway–receptor relationships						
Area of potential concern N°	Source	Pathway (s)	Receptor	Classification of consequence	Classification of probability	Classification of risk*
	Made ground from historical industrial activities and miscellaneous development on site.	Direct contact	Buildings and underground services	Medium	Likely	Moderate Risk
		Gas / vapour inhalation	Future on-site operatives, construction workers	Medium	Low Likelihood	Moderate/Low Risk
5	<u>Off-site</u> Former refuse pit located approximately 98m north-east of site which may have been infilled with made ground of unknown composition.	Lateral gas migration and subsequent gas inhalation/explosion	Future on-site operatives, construction workers	Medium	Unlikely	Low Risk

*Where multiple receptors exist the risk classification is based on most sensitive receptor for conservatism.

3.5 Geotechnical hazard identification summary

Based on information presented within Sections 2.0 and 3.0 above and the expected geology underlying the site, the following geotechnical hazards are worthy of consideration and are discussed further in later sections of this report:

- Attack of buried concrete by aggressive ground conditions.
- Volume change potential of superficial clays and influence of existing/ remaining trees.

4 SCOPE OF GROUND INVESTIGATION WORKS

4.1 General scope of fieldwork

An intrusive ground investigation was undertaken by T&P at the site on Friday 28th April and in summary comprised the following:

- Drilling of 7N° dynamic soil sampling boreholes;
- Installation of 3N° boreholes as environmental monitoring wells;
- Ground gas monitoring on 6N° occasions;
- Logging of ground conditions and soil sampling by a suitably qualified engineer.

Selected samples collected during the ground investigation were submitted to the laboratory for geotechnical and environmental testing.

An exploratory hole location plan is presented within Appendix A and the exploratory hole logs are presented as Appendix C.

4.2 Exploratory hole positioning and access restrictions

Table 4.1 presents the exploratory hole targeting rationale.

Table 4.1 - Rationale/targeting of T&P exploratory hole locations	
Exploratory hole(s)	Target
WS01-04 and WS06-07	General coverage
WS05	Raised bank bordering the south boundary.

4.3 Dynamic soil sampling boreholes

T&P supervised the drilling of 7N° windowless sample boreholes (WS01 – WS07) which were terminated at depths between 1.00 and 5.00m below ground level (bgl) due to driving refusal. *In situ* standard penetration testing (SPT) was undertaken at 1.00m intervals and at the base of the boreholes. Environmental monitoring wells were installed within WS01,03 and WS07.

4.4 Environmental monitoring

Measurement of ground gases and water levels have been undertaken on 6N° separate return monitoring visits at bi-weekly intervals.

All monitoring wells were installed to detect ground gases from the potential on- and off-site sources.

5 SUMMARY OF GROUND CONDITIONS AND LABORATORY TESTING

5.1 Recorded ground conditions

The ground conditions recorded across the site broadly correlated with the anticipated published geology detailed in Section 2.3 which recorded a substantial Superficial Till deposit across the majority of the site, with the Chester Pebble Bed Formation bedrock beneath.

The strata encountered across the site area are summarised in Table 5.1 and are described further in the following sub-sections.

Table 5.1 - Summary of strata encountered					
Depth (m bgl)		Exploratory holes identified	Area of site	Soil type	General description/comments
Top depth range	Base depth range				
Ground level	0.7 – 1.2	All Holes	General	Made Ground STRATUM M1	Gravelly SAND and sandy gravelly CLAY. (Made Ground)
0.7 – 1.2	1.8 – 2.2	WS01 – 04 and WS06-07	General	Natural Ground STRATUM N1	Stiff to very stiff dark orangish brown mottled grey CLAY. (Superficial Till)
1.8 - 2.2	4.0 – 5.0	WS01 – 04 and WS06-07	General	Natural Ground STRATUM N2	Medium dense to dense and dense orangish brown and reddish orangish brown occasionally clayey SAND. (Superficial Till)

5.1.1 Made Ground

Made ground was encountered across all areas of the site to a typical maximum depth of 1.2mbgl. The raised berm in the south of the site thought to be indicative of the original site level was found to comprise made ground to a depth of 1.0m bgl at which depth the borehole was met with refusal on hard strata (equivalent to average site level). The made ground consisted of slightly sandy gravelly clay. The gravel was angular fine to coarse of red brick, concrete, ceramics, plastic, glass and wood. An exception to this was found within WS07, where made ground consisted of red brick and concrete to 0.5m bgl underlain by a black sand to 0.7mbgl.

A slight hydrocarbon odour was detected within WS02 between 1.0 – 1.2mbgl and WS07 between 0.5 – 0.7mbgl.

5.1.2 Natural soils – Superficial Till Deposits

Beneath the made ground and covering the entire site area, to maximum depths of 1.8 – 2.2m bgl, a stiff to very stiff orangish brown mottled grey clay was encountered. Underlying the clay, a medium dense to dense occasionally clayey sand was encountered to 5.0mbgl which was the maximum depth achieved by the boreholes.

This is considered to represent clay and sand of the Devensian Glacial Till.

5.1.3 Evidence of contamination

With the exception of the areas of made ground noted above, no further significant visible or olfactory evidence of any contamination was noted during the ground investigation.

5.2 Groundwater

Groundwater was encountered within WS01, WS04, WS06 and WS07 at 3mbgl during the intrusive investigation. Groundwater levels recorded during the 6 week gas monitoring period is presented in Table 5.2 below.

Table 5.2 – Groundwater levels recorded during environmental monitoring visits.						
Hole ID	Groundwater level (m bgl)					
	Visit 1	Visit 2	Visit 3	Visit 4	Visit 5	Visit 6
WS01	3.17	3.04	ND	ND	2.16*	ND
WS03	3.05	3.06	ND	ND	ND	ND
WS07	3.09	3.03	ND	ND	ND	ND

**Uncharacteristically high reading. Taken post heavy downpour with standing water recorded in the centre of the site.*

ND – Not detected, as such groundwater is at greater depth than installation base. WS01 – 3.18m bgl WS03 – 3.11m bgl WS07 – 3.10m bgl

5.3 Laboratory testing

5.3.1 Geotechnical testing

The soil testing deemed necessary to adequately characterise the site from a geotechnical perspective in the context of the proposed development is given in the table below. The full set of geotechnical analysis results are provided in Appendix D.

Table 5.2 – Geotechnical testing summary		
Test	Notes	Quantity
Moisture content	-	4 soils
Atterberg limits	-	4 soils
Particle Size Distribution	-	1 soil
Geochemical analysis BRE SD1 Suite	K9.1 – Suite A	4 soils

5.3.2 Chemical testing – soils

The soil testing deemed necessary to adequately characterise the site from a contamination perspective in the context of the conceptual site model and proposed development is given in the table below.

Samples from the investigation were forwarded to The Environmental Laboratory Ltd, a UKAS and MCERTS accredited laboratory. The full set of chemical analysis results are provided in Appendix E.

Table 5.3 - Schedule of chemical testing	
Test type	Quantity
Soils	
Arsenic, Cadmium, Chromium, Lead, Mercury, Nickel, Copper, Zinc, Selenium, Soil Organic Matter and Speciated Polyaromatic Hydrocarbons.	9 soils
TPH – Total (C6-C40) – GCFID	4 soils
TPH – CWG Banded – aro/ali split	4 soils
Asbestos soil screen and ID	6 soils
sVOC – GCMS	3 soils

6 HUMAN HEALTH RISK ASSESSMENT

6.1 Introduction

The human health risk assessment discussed in this section has been undertaken in accordance with extant UK regulation and guidance on contaminated land and risk assessment as outlined in key government documents⁴.

6.2 Assessment of averaging areas/zones following ground investigation works

For the purposes of investigation and assessment a site can be divided into zones based on the historical usages or proposed end use and these zones can be further divided into averaging areas. These averaging areas can be used to assess different soil types revealed or different potential exposure pathways etc. for the purposes of accurately modelling the site conditions. Each averaging area can be considered independently of each other for human health exposure assessment.

Based upon the proposed end use of the site and the findings of the ground investigation it is proposed that a single zone split into two averaging areas are appropriate for the site as follows:

- General site area – Made ground.
- General site area – Natural ground.

6.3 Presentation of risk assessment

For each averaging area the analytical results from the T&P investigations for each determinant have been evaluated directly against the adopted screening levels⁵ for a 'commercial' end use.

Table 6.1 below presents the results for the averaging area – 'General site area – made ground'.

Table 6.1 – Summary of general site area (made ground)						
Determinant	Laboratory detection limit or recorded concentrations (mg/kg)					
	Screening levels	Screening level source	Made Ground			
			Min	Max	N° of exceedances	Calculated 95 th UCL
Metals						
Arsenic (inorganic)	640	C4SL	7.0	66.0	0 of 7	-
Boron	240,000	S4UL	0.5	1.3	0 of 7	-
Cadmium	410	C4SL	<0.5	21.8	0 of 7	-
Chromium III	8,600	S4UL	21.4	811	0 of 7	-

⁴ Environmental Protection Act 1990.

Contaminated Land Statutory Guidance (April 2012).

SP1010 – Development of Category 4 Screening Levels for Assessment of Land Affected by Contamination (2013 – as amended) – CL:AIRE.

CLR11 – Model procedures for the management of land contamination (2004) – DEFRA/Environment Agency.

⁵ C4SLs or S4ULs.

Table 6.1 – Summary of general site area (made ground)						
Determinant	Laboratory detection limit or recorded concentrations (mg/kg)					
	Screening levels	Screening level source	Made Ground			
			Min	Max	N° of exceedances	Calculated 95th UCL
Chromium VI	49	C4SL	<0.8	<0.8	0 of 7	-
Copper	68,000	S4UL	26.2	499	0 of 7	-
Lead²	2,300	C4SL	142	4030	1 of 7	Outlier
Mercury (inorganic)	1,100	S4UL	<0.5	0.5	0 of 7	-
Nickel	980	S4UL	12.8	100	0 of 7	-
Selenium	12,000	S4UL	<1.0	3.2	0 of 7	-
Zinc	730,000	S4UL	68.3	2460	0 of 7	-
Organics						
Total Organic Carbon (%)	n/a	-	1.7	20	-	-
Soil Organic Matter (%)	n/a	-	2.9	34.5	-	-
Total Monohydric Phenols	760 ⁽⁶⁾	S4UL	<5	<5	0 of 7	-
Naphthalene	190 (76.4) ⁽⁵⁾	S4UL	< 0.1	1.2	0 of 7	-
Acenaphthylene	83000 (86.1) ⁽⁵⁾	S4UL	< 0.1	0.2	0 of 7	-
Acenaphthene	84000 (57) ⁽⁵⁾	S4UL	< 0.1	0.7	0 of 7	-
Fluorene	63000 (30.9) ⁽⁵⁾	S4UL	< 0.1	0.5	0 of 7	-
Phenanthrene	22000	S4UL	< 0.1	6.6	0 of 7	-
Anthracene	52000	S4UL	< 0.1	1.9	0 of 7	-
Fluoranthene	23000	S4UL	0.3	10.5	0 of 7	-
Pyrene	54000	S4UL	0.3	9.3	0 of 7	-
Benz(a)anthracene	170	S4UL	< 0.1	5.0	0 of 7	-
Chrysene	350	S4UL	< 0.1	6.1	0 of 7	-
Benzo(b)fluoranthene	44	S4UL	< 0.1	5.1	0 of 7	-
Benzo(k)fluoranthene	1200	S4UL	< 0.1	5.1	0 of 7	-
Benzo(a)pyrene	77	C4SL	< 0.1	6.1	0 of 7	-
Indeno(123-cd) pyrene	500	S4UL	< 0.1	5.1	0 of 7	-
Dibenz(ah)anthracene	3.5	S4UL	< 0.1	2.4	0 of 7	-
Benzo(ghi)perylene	3900	S4UL	< 0.1	5.0	0 of 7	-
Petroleum hydrocarbons						
Benzene	98	C4SL	<0.1	<0.1	0 of 3	-

Table 6.1 – Summary of general site area (made ground)						
Determinant	Laboratory detection limit or recorded concentrations (mg/kg)					
	Screening levels	Screening level source	Made Ground			
			Min	Max	N° of exceedances	Calculated 95 th UCL
Toluene	56,000 (869) ⁽³⁾	S4UL	<0.1	<0.1	0 of 3	-
Ethylbenzene	5,700 (518) ⁽³⁾	S4UL	<1.0	<1.0	0 of 3	-
Xylenes ⁴	5,900 (576) ⁽³⁾	S4UL	<1.0	<1.0	0 of 3	-
Aliphatic C5-C6	3,200 (304) ⁽⁵⁾	S4UL	< 0.01	< 0.01	0 of 3	-
Aliphatic >C6-C8	7,800 (144) ⁽⁵⁾	S4UL	< 0.01	< 0.01	0 of 3	-
Aliphatic >C8-C10	2,000 (78) ⁽⁵⁾	S4UL	< 1.0	2.3	0 of 3	-
Aliphatic >C10-C12	9,700 (48) ⁽⁵⁾	S4UL	< 1.0	<1.0	0 of 3	-
Aliphatic >C12-C16	59,000 (24) ⁽⁵⁾	S4UL	1.2	23.7	0 of 3	-
Aliphatic >C16-C35	1,600,000	S4UL	619.2	17854	0 of 3	-
Aliphatic >C35-C40	1,600,000	S4UL	238	1610	0 of 3	-
Aromatic C5-C7	26,000 (1,220) ⁽⁵⁾	S4UL	<0.01	<0.01	0 of 3	-
Aromatic >C7-C8	56,000 (869) ⁽³⁾	S4UL	<0.01	<0.01	0 of 3	-
Aromatic >C8-C10	3,500 (613) ⁽³⁾	S4UL	<1.0	<1.0	0 of 3	-
Aromatic >C10-C12	16,000 (364) ⁽⁵⁾	S4UL	<1.0	<1.0	0 of 3	-
Aromatic >C12-C16	36,000 (169) ⁽⁵⁾	S4UL	<1.0	3.1	0 of 3	-
Aromatic >C16-C21	28,000	S4UL	22.8	256	0 of 3	-
Aromatic >C21-C35	28,000	S4UL	352	5220	0 of 3	-
Aromatic >C35-C40	28,000	S4UL	148	694	0 of 3	-
sVOCs						
Dimethyl phthalate	n/a	n/a	<0.01	0.46	0 of 3	-
Dibenzofuran	n/a	n/a	0.03	0.32	0 of 3	-
Carbazole	n/a	n/a	<0.01	0.20	0 of 3	-
Inorganics						
Water Soluble Sulphate (mg/l) * ³	n/a	n/a	0.04	1.45	0 of 7	-
pH * ⁴	n/a	n/a	7	9.2	-	-

Table 6.1 – Summary of general site area (made ground)						
Determinant	Laboratory detection limit or recorded concentrations (mg/kg)					
	Screening levels	Screening level source	Made Ground			
			Min	Max	Nº of exceedances	Calculated 95 th UCL
Asbestos screen	Presence	n/a	None Detected		0 of 6	n/a

Notes:

1. Category 4 Screening Level (C4SL) based on 6% Soil Organic Matter (SOM). SP1010 Development of Category 4 Screening Levels for Assessment of Land Affected by Contamination. Rev 2. CL:AIRE. 2014; Suitable 4 Use Level (S4UL) based on 1% SOM, where appropriate, as a conservative assessment. (The LQM/CIEH S4ULs for Human Health Risk Assessment (Land Quality Management, 2005).
2. C4SL for lead based on the LLTC of 3.5µg/dL-1 and C4SL exposure changes for child/adult receptors.
3. S4UL exceeds vapour saturation limit, which is presented in brackets.
4. Lowest S4UL selected for o-xylene, m-xylene or p-xylene. S4UL should be compared against total xylenes as the Health Criteria Value (HCV) is based on this, rather than individual isomers.
5. S4UL exceeds solubility saturation limit, which is presented in brackets.
6. S4UL based on threshold protective of direct skin contact.

As indicated by Table 6.1, a single soil concentration of lead within a sample of made ground from WS04 (0.4-0.8mbgl) was recorded in excess of the adopted screening levels. Statistical analysis has shown this value to be a statistical outlier and indicative of a hotspot. A copy of the statistical assessment is included within Appendix H. Although high concentrations of hydrocarbons have been shown to be present on the site associated with SS01 where evidence of surface spillage was noted, these results are associated with longer chain aliphatic/aromatic hydrocarbons which typically have a low volatility. Lighter hydrocarbon fractions are noted to be below detection limit. Recorded soil concentrations are all below adopted screening values for a commercial development. Furthermore, PID levels were recorded to be low during the 6 week period of monitoring. No other contaminants were noted to exceed relevant screening levels.

Table 6.2 presents the results for the averaging area – ‘General site area – natural ground’.

Table 6.2 – Summary of general site area (natural ground)						
Determinant	Laboratory detection limit or recorded concentrations (mg/kg)					
	Screening levels	Screening level source	Natural Ground			
			Min	Max	N° of exceedances	Calculated 95 th UCL
Metals						
Arsenic (inorganic)	640	C4SL	9.6	9.9	0 of 2	-
Boron	240,000	S4UL	0.6	1.0	0 of 2	-
Cadmium	410	C4SL	<0.5	0.5	0 of 2	-
Chromium III	8,600	S4UL	42.3	48.5	0 of 2	-
Chromium VI	49	C4SL	<0.8	<0.8	0 of 2	-
Copper	68,000	S4UL	35.2	36.4	0 of 2	-
Lead ²	2,300	C4SL	23.5	26.7	0 of 2	-
Mercury (inorganic)	1,100	S4UL	<0.5	<0.5	0 of 2	-
Nickel	980	S4UL	36.8	46.9	0 of 2	
Selenium	12,000	S4UL	<1.0	<1.0	0 of 2	-

Table 6.2 – Summary of general site area (natural ground)						
Determinant	Laboratory detection limit or recorded concentrations (mg/kg)					
	Screening levels	Screening level source	Natural Ground			
			Min	Max	N° of exceedances	Calculated 95th UCL
Zinc	730,000	S4UL	78.1	107	0 of 2	-
Organics						
Total Organic Carbon (%)	n/a	-	0.45	0.61	-	-
Soil Organic Matter (%)	n/a	-	0.26	0.35	-	-
Total Monohydric Phenols	760 ⁽⁶⁾	S4UL	<5	<0.5	0 of 2	-
Naphthalene	190 (76.4) ⁽⁵⁾	S4UL	< 0.1	< 0.1	0 of 2	-
Acenaphthylene	83000 (86.1) ⁽⁵⁾	S4UL	< 0.1	< 0.1	0 of 2	-
Acenaphthene	84000 (57) ⁽⁵⁾	S4UL	< 0.1	< 0.1	0 of 2	-
Fluorene	63000 (30.9) ⁽⁵⁾	S4UL	< 0.1	< 0.1	0 of 2	-
Phenanthrene	22000	S4UL	< 0.1	< 0.1	0 of 2	-
Anthracene	52000	S4UL	< 0.1	< 0.1	0 of 2	-
Fluoranthene	23000	S4UL	< 0.1	< 0.1	0 of 2	-
Pyrene	54000	S4UL	< 0.1	< 0.1	0 of 2	-
Benz(a)anthracene	170	S4UL	< 0.1	< 0.1	0 of 2	-
Chrysene	350	S4UL	< 0.1	< 0.1	0 of 2	-
Benzo(b)fluoranthene	44	S4UL	< 0.1	< 0.1	0 of 2	-
Benzo(k)fluoranthene	1200	S4UL	< 0.1	< 0.1	0 of 2	-
Benzo(a)pyrene	77	C4SL	< 0.1	< 0.1	0 of 2	-
Indeno(123-cd)pyrene	500	S4UL	< 0.1	0.2	0 of 2	-
Dibenz(ah)anthracene	3.5	S4UL	< 0.1	0.6	0 of 2	-
Benzo(ghi)perylene	3900	S4UL	< 0.1	0.3	0 of 2	-
Petroleum hydrocarbons						
Benzene	98	C4SL	<0.1	<0.1	0 of 1	-
Toluene	56,000 (869) ⁽³⁾	S4UL	<0.1	<0.1	0 of 1	-
Ethylbenzene	5,700 (518) ⁽³⁾	S4UL	<1.0	<0.1	0 of 1	-
Xylenes ⁴	5,900 (576) ⁽³⁾	S4UL	<1.0	<0.1	0 of 1	-

Table 6.2 – Summary of general site area (natural ground)						
Determinant	Laboratory detection limit or recorded concentrations (mg/kg)					
	Screening levels	Screening level source	Natural Ground			
			Min	Max	N° of exceedances	Calculated 95th UCL
Aliphatic C5-C6	3,200 (304) ⁽⁵⁾	S4UL	< 0.01	< 0.01	0 of 1	-
Aliphatic >C6-C8	7,800 (144) ⁽⁵⁾	S4UL	< 0.01	< 0.01	0 of 1	-
Aliphatic >C8-C10	2,000 (78) ⁽⁵⁾	S4UL	< 1.0	< 1.0	0 of 1	-
Aliphatic >C10-C12	9,700 (48) ⁽⁵⁾	S4UL	< 1.0	< 1.0	0 of 1	-
Aliphatic >C12-C16	59,000 (24) ⁽⁵⁾	S4UL	< 1.0	< 1.0	0 of 1	-
Aliphatic >C16-C35	1,600,000	S4UL	5.4	5.4	0 of 1	-
Aliphatic >C35-C40	1,600,000	S4UL	< 1.0	< 1.0	0 of 1	-
Aromatic C5-C7	26,000 (1,220) ⁽⁵⁾	S4UL	<0.01	<0.01	0 of 1	-
Aromatic >C7-C8	56,000 (869) ⁽³⁾	S4UL	<0.01	<0.01	0 of 1	-
Aromatic >C8-C10	3,500 (613) ⁽³⁾	S4UL	<1.0	<1.0	0 of 1	-
Aromatic >C10-C12	16,000 (364) ⁽⁵⁾	S4UL	<1.0	<1.0	0 of 1	-
Aromatic >C12-C16	36,000 (169) ⁽⁵⁾	S4UL	<1.0	<1.0	0 of 1	-
Aromatic >C16-C21	28,000	S4UL	<1.0	<1.0	0 of 1	-
Aromatic >C21-C35	28,000	S4UL	4.2	4.2	0 of 1	-
Aromatic >C35-C40	28,000	S4UL	<1.0	<1.0	0 of 1	-
Inorganics						
Water Soluble Sulphate (mg/l)	n/a	n/a	0.1	0.11	0 of 2	-
pH	n/a	n/a	7.6	7.6	-	-

Notes:

1. Category 4 Screening Level (C4SL) based on 6% Soil Organic Matter (SOM). SP1010 Development of Category 4 Screening Levels for Assessment of Land Affected by Contamination. Rev 2. CL:AIRE. 2014; Suitable 4 Use Level (S4UL) based on 1% SOM, where appropriate, as a conservative assessment. (The LQM/CIEH S4ULs for Human Health Risk Assessment (Land Quality Management, 2005).
2. C4SL for lead based on the LLTC of 3.5µg/dL-1 and C4SL exposure changes for child/adult receptors.
3. S4UL exceeds vapour saturation limit, which is presented in brackets.
4. Lowest S4UL selected for o-xylene, m-xylene or p-xylene. S4UL should be compared against total xylenes as the Health Criteria Value (HCV) is based on this, rather than individual isomers.
5. S4UL exceeds solubility saturation limit, which is presented in brackets.
6. S4UL based on threshold protective of direct skin contact.

As indicated by Table 6.2, no tested contaminants were shown to exceed the adopted screening levels.

6.4 Summary findings of human health risk assessment and recommendations

The chemical analysis has shown that determinants within the soil samples from both the made ground (except WS04 which is discussed further below) and natural ground are below the adopted screening levels for a commercial development.

Soil concentrations of semi-volatile compounds (SVOCs) dimethyl phthalate, dibenzofuran and carbazole were identified above the limit of detection. It is noted that there are currently no available human health screening levels for these determinants. These contaminants were detected within WS04 (0.50 – 0.80m) and WS06 (0.30 – 0.70m); however based upon the commercial end use and proposed design, interaction with material at these depths is unlikely/minimal deemed to be low risk to receptors.

A single elevated soil concentration of lead was encountered within WS04 (0.5-0.8mbgl) with a concentration of 4030mg/kg recorded (screening level = 2300mg/kg). Statistical analysis has identified this result to be a statistical outlier, indicative of a contamination hotspot. Based on the future development proposals, it is understood that the site will comprise approximately 90% hard standing, with WS04 located in the footprint of the proposed engine house, which will serve to sever direct contact/ingestion pathways with future site users.

As such, it is considered that on-site soils do not present an unacceptable risk to future site users within the proposed development. However, it is recommended that on-site controls are implemented to prevent unauthorised access to the site and that the use of personal protective equipment (PPE)/hygiene practices is implemented to minimise risks to current site users/visitors.

7 CONTROLLED WATERS RISK ASSESSMENT

7.1 Conceptual Model

No surface water has been identified within a 500m radius of the site.

The underlying Superficial Till deposits are categorised as a Secondary – Undifferentiated Aquifer.

Groundwater was encountered within WS01, WS04, WS06 and WS07 at 3m bgl within the superficial sand deposits, during the intrusive drilling works. Water levels throughout the 6 week period of the environmental monitoring found the shallow groundwater to reach a maximum level of 3.03m bgl (with the exception of WS01 visit 5), with no detects on 4 of 6 visits.

Furthermore, no active ground water abstractions or source protection zones are recorded within a 500m radius of the site. Situationally the surrounding area has historically been heavily industrialised and is still used for commercial practices to date. As such the future development of the shallow water as a potable water supply is limited, based upon the likelihood that background groundwater is of poor quality in the wider area.

Following the submission of the Phase 1 Desk Study and Risk Assessment a concern was raised by the local EHO regarding records of a laterally extensive water-bearing sand layer within the drift deposits in the area of the site. The concern related to the risk of the water bearing sand having the potential to act as a pathway for potentially contaminated shallow groundwater to migrate from the site.

7.2 Risk evaluation

The ground investigation identified low permeability clay to be present beneath made ground in all exploratory locations between 0.7 and 1.5m thick. Groundwater monitoring within WS01, WS03 and WS07, installed within the superficial Till identified water levels ranging between 3.03 and >3.18m bgl. WS02 and WS05 were recorded to be dry. Insufficient water was found to enable groundwater sampling to be conducted during the monitoring period. In consideration of the ground investigation findings, and subsequent monitoring, the evidence indicates that the sand band within the Till Deposits is not a significant water bearing unit.

Soil analysis of made ground and deeper natural soils has indicated that concentrations decrease with depth, indicating that the vertical leaching pathway is unlikely to be significantly active. An example of this is can be seen within the made ground sample and natural ground samples within WS04, where concentrations of metals, PAHs and hydrocarbons can be seen to significantly drop within the natural ground below.

In addition, it is also considered that the proposed development of the site will further mitigate potential risks to Controlled Waters. This is based upon two factors, firstly it is anticipated that made ground in areas of foundations and the southern bank will be removed to facilitate site redevelopment, which will reduce the residual contaminant mass. Secondly the finished site area will be approximately 85% hardstanding and 15% gravel, which will greatly reduce the infiltration of rainwater through the made ground, reducing the likelihood of contaminants leaching from made ground. In consideration of the site conceptual model and above assessment, the risks to Controlled Waters are considered to be low.

However, irrespective of the above assessment, where gross soil contamination has been identified i.e. non-aqueous phase (NAPL), such as in the vicinity of SS01, which is anticipated to be the result of surface spillage of oils/solvents observed to be stored on-site, it is recommended that this is removed during construction, under a watching brief to further reduce the risks to Controlled Waters in accordance with best practice. This will also reduce the residual risk associated with potential vapour generation in the area of the historical spill.

8 GAS PROTECTION REQUIREMENTS

8.1 Overview

Through the development of the preliminary conceptual model, potential on-site sources of gas and vapour generation were limited to made ground from previous site development. Off-site sources were identified to comprise the infilled former canal to the west and refuse pit to the north east.

The made ground was observed to comprise inert materials that are considered to have a low gas generating potential.

8.2 Ground gas monitoring results

Six ground gas monitoring visits have been undertaken over a six-week period throughout May and June 2017 utilising all three monitoring installations (WS01, WS03 and WS07).

The findings are summarised below with results attached in Appendix F:

- Atmospheric pressure conditions were found to vary from 985 and 1010mB over the monitoring period, with atmospheric pressure recorded as falling below 1000mB during Visit 1. Falling pressure was also recorded during Visit 1.
- Methane (Visit 1 peaked at 0.1%) and carbon monoxide levels were recorded at or below the instrument detection levels (<0.1% for methane and <0.1ppm for carbon monoxide).
- Peak carbon dioxide was recorded between <0.3% – 3.0% by volume across the monitoring period. Stable carbon dioxide levels were recorded between <0.3% - 2.5% by volume.
- Oxygen levels were recorded between 12.6% – 20.8% by volume across the period of monitoring. The lower volumes of oxygen did not correspond with high carbon dioxide levels.
- Ground gas flow rates were all recorded to be below instrument detection with the exception of WS01 on visit 1 which recorded a peak value of 0.6l/hr, equalising to a steady flow which was below instrument detection level after 5 seconds.
- Hydrogen sulphide was detected on one occasion (visit 1) within all wells, with concentrations of 1.0 – 1.1ppmv. This is likely to originate from bacterial reactions and is below the Occupational Exposure Limit (OEL) which is conservatively set at 5ppm for long term exposure.
- PID levels were recorded between <0.1(LOD) and 3.3 parts per million volume across the monitoring period. The highest reading of 3.3ppm was recorded within WS03 Visit 1, the following visits recorded this to be 0.7ppm or below.
- Ground water was identified within all wells on Visits 1 and 2 with no detects in the remaining 4. The highest recorded level was 3.03mbgl within WS07. An anomalous result within WS01 - Visit 5 of 2.16m bgl has been discounted as representative of ground water.

8.3 Gas screening values

Guideline gas screening values (GSV) (Q_{hg}) for maximum methane and carbon dioxide concentrations recorded at the site can be considered through calculation of the hazardous gas flow rate (Q_{hg}) in accordance with BS8485⁶ and CIRIA 665⁷ using the following equation:

$$Q_{hg} = (C_{hg}/100) \times q$$

Where ' C_{hg} ' is the gas concentration measured as a percentage and ' q ' is the flow rate.

This calculation is undertaken separately for both carbon dioxide and methane and the maximum Q_{hg} for each, including historical site data, has been calculated and listed below. For conservatism, where no gas flow was detected the gas detector limit of 0.1l/hr has been employed in the calculation:

$$Q_{hg} \text{ (GSV) – methane} = 0.0006 \text{ (based on peak flow of 0.6l/hr = worst case)}$$

$$Q_{hg} \text{ (GSV) – carbon dioxide} = 0.0066 \text{ (based on peak flow of 0.6l/hr = worst case)}$$

In accordance with the guidance documents above and the data set gathered, it is considered appropriate to adopt the calculated hazardous gas flow rates as the GSVs. As such, these adopted values suggest there to be no significant gas risk at the site from methane or carbon dioxide.

8.4 Discussion

The calculated GSVs indicate there to be no significant gas risk at the site suggesting it is suitable to characterise the site as Characteristic situation 1 based upon the CIRIA guidance, where no protection measures are required.

⁶ BS8485: *Code of Practice for the characterization and remediation from ground gas in affected development* – 2015.

⁷ *Assessing risks posed by hazardous ground gases for buildings* – CIRIA665 (2007.)

9 PLANT GROWTH AND POTABLE SUPPLY PIPEWORK RISK ASSESSMENT

9.1 Phytotoxic risk estimation

A summary of the chemical test results for phytotoxic contaminants is presented in Table 9.1 (made ground) to illustrate the distribution of potential phytotoxic risks revealed by the ground investigation works.

Table 9.1 – Summary of potentially phytotoxic contaminants				
Determinant	Laboratory detection limit or recorded concentrations(mg/kg)			
	Adopted screening level	Made Ground		
		Min	Max	N° of exceedances
Cadmium	8	<0.5	21.8	2 of 7
Chromium	154	21.4	811	1 of 7
Copper	130	26.2	499	3 of 7
Mercury	28	<0.5	0.5	0 of 7
Nickel	70	12.8	100	3 of 7
Selenium	10	<1.0	3.2	0 of 7
Zinc	300	68.3	2460	5 of 7
Boron	3	0.5	1.3	0 of 7

As indicated by the table above, concentrations of copper, nickel, zinc, cadmium and chromium within the made ground samples were found to be above the assessment criteria. Table 9.2 below summarised the distribution of the results across the site.

Table 9.2 – Distribution of phytotoxic exceedances			
Site area	Exploratory holes	Material Description	Determinant level
East	WS03	MADE GROUND: dark brown stained black clayey gravelly SAND.	Cadmium – 20mg/kg Chromium – 811mg/kg Copper – 301mg/kg Nickel – 71.1mg/kg Zinc – 2240mg/kg
	WS04		Cadmium – 20mg/kg Copper – 301mg/kg Nickel – 71.1mg/kg Zinc – 2240mg/kg
	SS01		Copper – 499mg/kg Nickel – 100mg/kg Zinc – 983mg/kg
North centre	WS02	MADE GROUND: dark brown slightly sandy gravelly CLAY.	Zinc – 309mg/kg

Table 9.2 – Distribution of phytotoxic exceedances			
Southern bank	WS05	MADE GROUND: dark brown sandy gravelly SILT	Zinc – 314mg/kg

Table 9.2 demonstrates that exceedances to phytotoxic levels are in the central to eastern portion of the site. Although there are no planned planted areas on the site, levels within the made ground to the west of the site are shown to be within acceptable levels for planting with current flora showing no signs of withering.

If the proposed development is updated to include limited areas of soft landscaping. It is recommended that provision of suitable thickness of topsoil (300mm-450mm) is imported to site for placement in areas of soft cover, in consultation with a landscaping specialist and the development landscaping plan.

9.2 Potable water supply pipework risk estimation

Extant water industry guidance⁸ states that only organic contaminants pose a potential risk to plastic pipe materials. The UKWIR report provides threshold values for polyethylene (PE) and polyvinyl chloride (PVC) pipes for the organic contaminants of concern. These are summarised below in context with the laboratory results gathered through this investigation.

Table 9.2 - Assessment of results against UKWIR criteria					
Determinant	Pipe material GAC (mg/kg)		Laboratory detection limit or recorded concentrations(mg/kg)		
	PE	PVC	Surface material results (7N°)		
			Min	Max	N° of exceedances
Extended VOC suite *2	0.5	0.125	<0.1	8.47	7 of 7
BTEX + MTBE	0.1	0.03	<0.01	<0.01	0 of 3
SVOCs TIC by purge and trap or head space and GC-MS with TIC (aliphatic and aromatic C ₅ -C ₁₀)	2	1.4	<0.01	2.3	1 of 3
Phenols *3	2	0.4	<5	<5	0 of 7
Cresols and chlorinated phenols *1	2	0.04	<1	<1	0 of 7
Mineral oil C ₁₁ -C ₂₀	10	Suitable	100.2	836.7	3 of 3
Mineral oil C ₂₁ – C ₄₀	500	Suitable	1284	24824	3 of 3
Corrosive (conductivity, redox and pH) *1	Suitable	Suitable	-	-	

(*1) Determinant not tested.

(*2) Based upon recorded BaP concentrations.

(*3) All singular phenols recorded below LOD of 1.0mg/kg.

⁸ Guidance for the selection of water supply pipes to be used in brownfield sites (UK Water Industry Research Limited (UKWIR) - Ref: 10/WM/03/21) - 2010

Site wide elevated concentrations of benzo(a)pyrene, mineral oils (C₁₁-C₂₀) and (C₂₁-C₄₀) were detected above the necessary values for PE and PVC pipework within the made ground across the site to 1.2mbgl. As such upgraded pipework will be required.

10 REFINED CONCEPTUAL SITE MODEL

10.1 Sources

The preliminary conceptual site model identified the following potential contamination sources:

1. Unsealed discarded chemical containers;
2. Gas and contamination migration from the infilled canal to the west;
3. Contaminant migration from adjacent industrial practices;
4. Made ground from historical industrial activities and miscellaneous development on site; and,
5. Gas generation and lateral migration from historical refuse pit.

Chemical testing has demonstrated that contaminant levels within the made and natural ground are below the adopted 'commercial' screening levels with the exception of a Lead hotspot in the east corner of the site (WS04). As such the hazard relating to sources 1 and 4 are significantly reduced.

Results of a six week gas monitoring programme has demonstrated minimal gas detection levels with worst case GSV's characterising the site as a CS1, therefore no gas protection will be required. As such gas hazards associated with sources 2, 3, 4 and 5 are significantly reduced.

No asbestos fibres were detected within 6N° samples of the made ground. As such the consequence of asbestos source within the made ground (Source 4) is significantly lower.

No further potential sources of impact were identified during the subsequent ground investigation works.

10.2 Pathways

When considering the proposed end use and the results of the investigation to date, the following exposure pathways have been discounted as plausible for the majority of the site and sensitive receptors identified:

- Leaching and migration to controlled water receptors.

Due to the proposed design the significant increase in hard standing across the site will act as a physical barrier significantly limiting the percolation of water through the made ground source. This will greatly reduce the leaching potential of the leaching and vertical migration of contaminants to shallow groundwater within the superficial sands below.

However, the pathways listed below are considered to be viable for areas of made ground identified across the site:

- Direct attack of buried services.
- Inhalation and explosion due to gases.

10.3 Risk evaluation

In order to demonstrate the risks associated with contaminant linkages identified above, a revised site specific risk evaluation updating the details presented in Section 5.0 with data gathered as part of this investigation has been carried out in accordance with national guidance. Table 10.1 summarises the evaluation of risk to identified receptors based upon investigation results to date and the proposed commercial end-use.

Table 10.1 – Revised source–pathway–receptor relationships							
Area of potential concern N°	Source	Comments	Pathway (s)	Receptor	Classification of consequence	Classification of probability	Classification of risk*
1	<u>On-site</u> Unsealed and discarded chemical containers in the north central area of site, including thinners and other unlabelled chemicals.	Chemical testing of surrounding soils shows contaminants to be within adopted screening levels. Furthermore, the proposed design also identifies the affected area to be encapsulated beneath tarmac hardstanding.	Direct contact	Buildings and Underground Services	Medium	Unlikely	Low Risk
			Gas / vapour inhalation	Future on-site operatives, construction workers	Medium	Unlikely	Low Risk
2	<u>Off-site</u> Gas migration from infilled canal/ landfill to the immediate west. Gas migration from infilled canal/ landfill to the immediate west.	Gas monitoring regime has proven acceptable GSV's and that no gas mitigation methods will be required.	Lateral migration and gas inhalation	Future on-site operatives, construction workers	Medium	Unlikely	Low Risk

Table 10.1 – Revised source–pathway–receptor relationships							
Area of potential concern N°	Source	Comments	Pathway (s)	Receptor	Classification of consequence	Classification of probability	Classification of risk*
3	<u>Off-site</u> Contaminant migration from industrial practices in the surrounding area including a recycling centre 10m to the north and an auto repair shop/ spray shop 5m to the east.	Gas monitoring regime has proven acceptable GSV's and that no gas mitigation methods will be required.	Lateral migration in groundwater and gas / vapour generation.	Future on-site operatives, construction workers	Medium	Unlikely	Low Risk
4	<u>On-site</u> Made ground from historical industrial activities and miscellaneous development on site.	Although a significant thickness of made ground has been identified across the site, chemical testing has identified contaminants to be below the adopted screening levels, except for a singular Lead hotspot in the east of site (WS04).	Downward migration	Groundwater	Medium	Unlikely	Low Risk
			Direct contact	Buildings and Underground Services	Medium	Unlikely	Low Risk
			Gas / vapour inhalation	Future on-site operatives, construction workers	Medium	Unlikely	Low Risk

Table 10.1 – Revised source–pathway–receptor relationships							
Area of potential concern N°	Source	Comments	Pathway (s)	Receptor	Classification of consequence	Classification of probability	Classification of risk*
5	<u>Off-site</u> Infilled sand pit 100m north – Gas generation.	Gas monitoring regime has proven acceptable GSV's and that no gas mitigation methods will be required.	Lateral migration and gas inhalation	Future on-site operatives, construction workers	Minor	Unlikely	Very Low Risk

*Where multiple receptors exist the risk classification is based on most sensitive receptor for conservatism.

11 WASTE CLASSIFICATION

11.1 Landfill acceptance criteria

When waste is intended for disposal at a suitably licensed landfill site it is necessary for the producer (i.e. the developer or consultant on their behalf) to identify, among other general information, the following:

- The List of Waste (LoW) code for the waste.
- The relevant hazardous property (HP1 to HP15).
- The landfill class where the waste may be accepted.
- Waste Acceptance Criteria (WAC) testing results.

Relevant information on the above can be found in WM3⁹.

11.2 List of Waste (LoW) code

Based on the chemical analysis results for the soils on the site, it is anticipated that the most suitable LoW codes for the site will be:

- **17 05 03** (soils and stones containing hazardous substances).
- **17 05 04** (soils and stones other than those mentioned in 17 05 03).

11.3 Hazardous waste codes and soil waste classification

For the determination of whether the soils revealed on the site are hazardous, the chemical analysis results obtained have been assessed using the Hazwaste online computer program.

A full copy of the computer printout is contained in Appendix G, the results of which are summarised in Table 11.1.

Table 11.1 - Summary of classification of potential soils for disposal from chemical analysis			
Exploration hole ref.	Depth (mbgl)	Soil type	Soil classification
WS02	1.0 - 1.2	Made ground	Hazardous
WS02	1.5 - 1.8	Natural ground	Non Hazardous
WS03	0.0-1.2	Made ground	Hazardous
WS04	0.5-0.8	Made ground	Hazardous
WS04	1.5-1.7	Natural ground	Non Hazardous
WS06	0.3-0.7	Made ground	Non Hazardous
WS06	0.5-0.7	Made ground	Non Hazardous

⁹ EA 'Guidance On the classification and assessment of waste (1st Edition 2015) - Technical Guidance WM3'

Table 11.1 - Summary of classification of potential soils for disposal from chemical analysis			
Exploration hole ref.	Depth (mbgl)	Soil type	Soil classification
WS07	0.7-1.0	Natural ground	Non Hazardous
SS01	0.0-0.3	Made ground	Hazardous
WS05	0.3-0.6	Made ground	Non Hazardous

11.4 Waste acceptance criteria (WAC) testing

Following the implementation of the Landfill Regulations 2002, the use of Waste Acceptance Criteria (WAC) testing for waste classification was introduced on 16th July 2005.

WAC testing is intended to supplement the waste identification and classification methods above, and is often required by landfills to assist in the determination of whether a waste can reliably be classified as 'inert' or 'stable non-reactive' as well as 'hazardous' or 'non-hazardous' and therefore whether the lower or higher rates of landfill tax apply.

11.5 Landfill tax

Following the termination of the landfill tax exemption scheme by the government in November 2008 any material leaving site that is classed as non-hazardous or hazardous waste will be liable to the landfill tax levy, which is currently set at £86.10/tonne (2017/2018)¹⁰ unless it can be proven to be inactive waste through WAC testing.

11.6 Waste assessment discussion

Based on the HazWaste assessment the natural ground and the majority of the made ground is classified as non-hazardous waste. The chemical data indicates the soil will likely be treated as inert or stable non-reactive waste, avoiding the higher rate of landfill tax. However, this is not guaranteed and will need to be confirmed through discussions with the receiving tip/waste soils treatment facility who may require WAC testing.

In locations where hazardous waste has been identified, made ground in the areas of WS02, 03, 04 and SS01, the material will need to be dealt with separately to the majority of the material being removed from site. It is recommended that the hazardous material is segregated and removed as hazardous waste. Receiving landfills will require WAC testing to be carried out on the hazardous waste in order to determine whether or not it can be classified as inactive material which would mean that it could avoid the higher landfill tax rate.

¹⁰ Details on landfill tax rates can be found at: <https://www.gov.uk/government/publications/landfill-tax-increase-in-rates/landfill-tax-increase-in-rates>

12 COMMENTS ON ENGINEERING DESIGN

12.1 General

Eurocode 7 (Section 2) advocates the use of geotechnical categorisation of the proposed structures to establish the design requirements. For the purposes of this investigation the proposed structures have been classified as follows:

- Geotechnical category 1: Small and relatively simple buildings with strip or piled foundations, roads, pavements, car parks, retaining walls below 2m, small excavations for drainage works, with the proposed development considered to be within this category.

Information presented to T&P indicates that a potential future development is to comprise the construction of 1N^o warehouse style structure containing 8N^o internal gas engines, along with on-site substation, transformer, gas skid and oil storage tank with associated tarmac parking and manoeuvring surface. It has been assumed that the buildings will be of steel and masonry construction with loads of between 150 - 250kN/m.

12.2 Summary of geotechnical parameters

Stratum thicknesses and geotechnical parameters for the soil and rock encountered in the investigation are summarised in the following sections. The level of confidence in the derived parameters is indicated as follows:

Table 12.1 – Level of confidence indicator references	
value	High level of confidence - based on information from investigation.
value	Medium level of confidence - based on published data.
value	Low level of confidence – more data required if parameter to be used in design.

12.2.1 Made Ground

The made ground encountered across the site was found to be locally variable, as such it is considered inappropriate to present geotechnical information.

12.2.2 Superficial Till Deposits - Cohesive

The design thicknesses and geotechnical parameters for use in the Superficial Till - Cohesive deposits are described in Table 12.2.

Table 12.2 – Summary of Geotechnical Parameters from the Superficial Till - Cohesive Deposits					
Parameter	Units	Min	Max	Design	Comments
Top Depth	mbgl	0.7	1.2	1.2	
Base Depth	mbgl	1.8	2.2	1.8	
Thickness	m	0.7	1.1	0.7	
Moisture Content	%	18	22	20	

Table 12.2 – Summary of Geotechnical Parameters from the Superficial Till - Cohesive Deposits					
Parameter	Units	Min	Max	Design	Comments
Liquid Limit	%	41	50	45	
Plastic Limit	%	19	22	20	
Plasticity Index	-	22	28	24	
% passing 425µm sieve	%	89	98	N/A	
Modified Plasticity Index	-	20.2	27.4	22	Based on the NHBC guidance, results are indicative of soils of a Medium volume change potential
Standard Penetration Resistance @ 1.0m	N Value	11	33	14	Values within head deposits are generally approximately 14 - 15 with the exception of one high result of 33 expected to be a sandstone cobble.
Undrained shear Strength	kPa	100	125	100	Values from WS01 only, attempted tests in other WS locations caused fracture of sample indicative of >125kPa.
Modulus of volume compressibility	m ² /MN	0.05	0.30	0.15	Based on published data for fluvio-glacial and overconsolidated clay and empirical relationship between PI values and SPT results.
Skempton Consolidation Factor μ	-	0.5	1.0	0.75	Based on published data - Normally consolidated to over-consolidated clay.
pH	-	7.5	7.7	7.6	
Water soluble sulphate (SO ₄ ²⁻)	mg/l	0.1	128	128	(Worst case scenario)

12.2.3 Superficial Till Deposits - Granular

The design thicknesses and geotechnical parameters for use in the Superficial Till – Granular are described in Table 12.3.

Table 12.3 – Summary of Geotechnical Parameters from the Superficial Till – Granular					
Parameter	Units	Min	Max	Design	Comments
Top Depth	mbgl	1.8	1.9	1.9	Based on depth to sand within the footprint of the main structure.
Base Depth	mbgl	4.0	5.0	4.5	
Thickness	M	>3.2	>1.1	1.00	
Gravel/cobbles	%	3	3	3	This is indicative of a slightly gravelly silty SAND - which is consistent with logging.
Sand	%	83	83	83	
Silt and clay	%	15	15	15	

Table 12.3 – Summary of Geotechnical Parameters from the Superficial Till – Granular					
Parameter	Units	Min	Max	Design	Comments
Standard Penetration Resistance @ 2.0m	N Value	21	43	28	
Standard Penetration Resistance @ 3.0m	N Value	16	44	30	
Standard Penetration Resistance @ 4.0m	N Value	38	50	45	Refusal within 5N° boreholes.
Standard Penetration Resistance @ 5.0m	N Value	50	50	50	Refusal within 1N° Borehole.
Angle of shearing resistance ϕ	°	36	41	36	Derived from empirical relationship with SPTs
Compressibility index		0.001	0.30	0.30	Most conservative assumption.

12.3 Construction considerations

12.3.1 Subsurface concrete

Based on the pH and water soluble sulphate values recorded by the chemical and geotechnical laboratory analysis, a DS1-AC1s design mix concrete should be suitable for buried structures when compared against the BRE¹¹ assessment levels.

12.3.2 Floor slabs

Due to the thickness of made ground across the site (0.7m > 1.2m) it is advised that proprietary suspended ground floor slabs are utilised on site. At this stage it is recommended that the clay is assumed to be of medium volume change potential and as a result any proprietary suspended ground floor slabs are designed with a minimum 250mm void based upon NHBC guidance as an example of best practice.

12.3.3 Building near trees

The cohesive soils found beneath the site are considered to have a medium shrinkage potential and will therefore be susceptible to the influence of trees/hedges like those adjacent to the western boundary. It is recommended that an arboricultural survey for the site is consulted during the design of foundations on the site.

Based upon the volume change potential the recommended minimum founding depth of traditional foundations should be 0.9m; however, due to the thickness of made ground foundations are expected to be placed at a greater depth than this. At this stage due to the volume change potential of the soils it is also recommended that provision be included for proprietary void formers as part of the foundation design where foundation depths exceed 1.5m and are in areas prone to the effect of trees.

¹¹ BRE Special Digest 1:2005 – Third edition – Concrete in aggressive ground.

12.3.4 Deep excavations

During the investigation, the underlying natural material in the boreholes were found to be generally stable apart from within the water logged sand where collapse was observed. Excavations within water bearing sand during the construction phase will likely need shoring. Man entry into any excavations should be avoided but if this is ultimately necessary then the sides should be adequately shored and supported or battered back to a safe angle in accordance with the site specific developed health and safety plan.

12.3.5 Groundwater

Groundwater was encountered within a number of the exploratory holes during the ground investigation with monitoring results showing water levels to rest at approximately 3m bgl. Any inflows into excavations above this depth would be expected to be low and should be adequately dealt with via sump pumping. Where excavations will surpass 3m below current ground levels the use of specialist dewatering techniques will likely be required and the advice of specialist dewatering contractors should be sought.

12.3.6 Buried utilities

Available utility service plans do not indicate any underlying services beneath the site. A medium pressure Gas main runs within the canal to the west.

12.3.7 Earthworks and material handling

Should organic rich material be encountered this should be removed from beneath all building and hard standing areas. It is understood that final development levels will be broadly similar to existing. As such, the cut/fill balance for the development is anticipated to require off-site disposal of surplus soils. No on-site re-use is considered likely to be required.

12.3.8 Road construction issues

Although no *in situ* or laboratory testing was required within the ground investigation, the proposed development identifies a large tarmacked area for vehicle movements.

Where made ground was revealed is not considered likely to be suitable as an effective formation for construction beneath adoptable roads. Where it is observed at formation soft spots and oversized material should be excavated and replaced with compacted granular fill.

12.4 Preliminary foundation recommendations

The future development is to comprise the construction of 1N° warehouse style structure containing 8N° internal gas engines, along with on-site substation, transformer, gas skid and oil storage tank with associated tarmac parking and manoeuvring surface. It has been assumed that the buildings will be of steel and masonry construction with loads of between 150 - 250kN/m.

The ground conditions across the site were generally found to comprise made ground to between 0.7 and 1.2m, underlain by stiff to very stiff cohesive superficial glacial till deposits to approximately 2.0m. This was underlain by medium dense to dense granular sand of the superficial glacial till deposits, the base of which is unproven.

Based on the ground conditions encountered and proposed development recommendations for the utilisation of square pad foundations targeted upon the cohesive deposits and the granular material below are presented within tables 12.4 and 12.5 below.

Table 12.4 – Superficial Glacial Till - Cohesive		
Design depth (mbgl)	Pad Dimensions	Allowable bearing capacity (kPa)
1.2	1.5m by 1.5m	100
1.2	1.0m by 1.0m	125

Note that the values for allowable bearing capacity given in the above table are for anticipated settlements of between 15 and 20mm.

Table 12.5 – Superficial Glacial Till - Granular		
Design depth (mbgl)	Pad Dimensions	Allowable bearing capacity (kPa)
2.0	1.5m by 1.5m	250

As demonstrated in the tables above the cohesive soils beneath the site provide comparatively lower allowable bearing capacity for acceptable settlement compared to founding within the granular material at 2.0m. Additionally, it is recommended that all pads are placed within the same founding stratum to minimise the possibility of differential settlement.

Considering the conceptual site model, the very low permeability clay is identified as a physical break to the pathway for contaminants within the overlying made ground to reach the water bearing sand deposits below (receptor). As such if deeper foundations are required, penetrating the granular material below, a preferential pathway will be formed. Removal of the hydrocarbon impacted soils present as part of the redevelopment works would mitigate this risk. However, as discussed previously in section 7.0 “Controlled waters” the proposed hardstanding areas of the site will greatly reduce the potential for leaching and vertical migration of determinants from the made ground to the low sensitivity shallow groundwater receptor.

13 CONSIDERATIONS AND RECOMMENDATIONS

13.1 Considerations

The following areas of uncertainty have been identified:

- The conceptual site model has been based on the current proposed development which involves the majority of site becoming hard standing and gravelled area. Any updates to this design should be assessed against the recommendations within this report.

13.2 Recommendations: Human health and controlled waters

The following recommendations for are made:

- Based upon laboratory testing a Lead hotspot has been identified within the eastern corner of the site (WS04). Based upon the current proposed development plan this area will be capped and the pathway to critical receptors removed.
- Where gross soil contamination has been identified i.e. non-aqueous phase (NAPL), such as in the vicinity of SS01, which is anticipated to be the result of surface spillage of oils/solvents observed to be stored on-site, it is recommended that this is chased out during construction, under a watching brief to further reduce the risks to Controlled Waters in accordance with best practice. Furthermore, this will lower the residual vapour risk.
- Although through the redevelopment of the site the risks to receptors is low, advice and controls should be put in place for those visiting and using the site currently.

13.3 Recommendations: Plant growth and potable water supply pipework

The following recommendations for further work are made with regard to plant growth and potable water supply pipework:

- The made ground soils on site are not considered suitable for plant growth. However the proposed layout doesn't identify any areas of planting and as such this will not be an issue.
- Upgraded potable pipework will be required in all areas of made ground on site.

13.4 Recommendations: Engineering

The following recommendations are made with regard to geotechnics:

- The cohesive Till deposits have been characterized as having medium volume change potential, as such foundations should be a minimum of 0.9mbgl. These soils will also be moderately effected by on site trees and hedgerows, as such it is recommended that an arboricultural survey of the site should be consulted during foundation design.
- 1m by 1m pad foundations at a depth of 1.2mbgl could be designed for an allowable bearing capacity of 125kPa for allowable settlement within the cohesive Till Deposits. In the event that greater pad sized are required and or a larger bearing capacity, pads within the granular sand deposits could be designed for an allowable bearing capacity of 250kPa.
- Based upon the Hazwaste results it is expected that where disposal is required the made ground will be classed as hazardous and be at the higher tax rate.


13.5 Recommendations: General

More general recommendations are provided as follows:


- The statutory water provider should be consulted regarding suitable water supply pipework requirements.
- Discussions should be held with local landfill facilities to determine their classification for any soils to be disposed off-site arising from its development.
- A site-specific health and safety plan should be prepared to inform on risks posed from the previous site use and mitigations for ground workers developing the site e.g. requirements for appropriate PPE, hygiene practices, environmental monitoring and requirements for mitigation measures during construction works.
- Contractors on site should remain vigilant for visible and olfactory signs of gross contamination which has not been identified and assessed within this ground investigation. In the event that gross contamination is found an environmental engineer should be consulted.
- On site boreholes should be decommissioned in accordance with environment agency guidance prior to development.
- The relevant regulatory authorities should be forwarded a copy of the ground investigation report, to confirm that they are in agreement with the conclusions and recommendations herein.

- A DRAWINGS
- B PHOTOGRAPHS
- C EXPLORATORY HOLE RECORDS
- D GEOTECHNICAL ANALYSIS RESULTS
- E CHEMICAL ANALYSIS RESULTS
- F MONITORING RESULTS
- G HAZWASTE PRINTOUT
- H STATISTICAL ASSESSMENT

Appendix A – Drawings



Rev.	Date	Amendment	Drawn	Ckd
Base map source: OS Maps				
T&P  Regen Unit 4 Brunel Lock Development, Smeaton Road, Bristol, BS1 6SE Tel: 0117 927 7756				
Project Name Ashton Old Road, Manchester				
Drawing Title Site Feature Plan				
Client Eco NRG Solutions Ltd				
Drawn by RC	Checked by HEM	Date 29/6/17	Scale 1:1000@A4	
Drawing No. ASH1867-01-003				Rev. A



Key:

-  T&P Window Sample Borehole Locations (WS01-07)

Note: Environmental monitoring wells installed within WS01, WS03 and WS07.

Rev.	Date	Amendment	Drawn	Ckd
Base map source: OS Maps				
 Unit 4 Brunel Lock Development, Smeaton Road, Bristol, BS1 6SE Tel: 0117 927 7756				
Project Name Ashton Old Road, Manchester				
Drawing Title Exploratory Hole Location Plan				
Client Eco NRG Solutions Ltd				
Drawn by RCJ	Checked by HEM	Date 5/5/17	Scale 1:1000@A4	
Drawing No. ASH1867-01-002				Rev. A



0m 5m 10m 20m 30m

Builders Yard

Garage

BUILDING

1119

Rev.	Date	Amendment	Drawn	Ckd
Base map source: RPS Group				
DWG No: 9722-0002-04				
Date: Sept 16				
				
Unit 4 Brunel Lock Development, Smeaton Road, Bristol, BS1 6SE Tel: 0117 927 7756				
Project Name				
Ashton Old Road, Manchester				
Drawing Title				
Proposed Development Plan				
Client				
Eco NRG Solutions Ltd				
Drawn by	RC	Checked by	HEM	Date
				30/6/17
Drawing No.				Rev.
ASH1867-01-004				A

Appendix B – Photographs

APPENDIX B – SITE RECONNAISSANCE PHOTOGRAPHS



Photo A – Mesh basket with sealed and open chemical containers, with car parts in the background. Visible staining of the ground.
Red Circle = location of SS01
(Facing north-east)



Photo B – Close up of the western side of the mesh basket showing signs of burnt material inside, white container at the base of image labelled “Thinners”



Photo C – View across the site to the south-east.



Photo D – View across the site to the south-west.




Photo E – Typical made ground spoil. WS01.



Photo F – Typical window sample core. Made ground to 0.7m clay to 1.9m and clayey sand to 4.0m. (WS07)

Appendix C – Exploratory Hole Records

 www.tandpregeneration.co.uk		Contract Name: Ashton Old Road		Client: EcoNRG			Borehole ID: WS01		
		Contract Number: ASH1867	Date Started: 28/04/2017	Logged By: RC	Checked By: JF	Status: FINAL	Sheet 1 of 1		
Windowless Sample Borehole Log		Easting:	Northing:	Ground Level:	Plant Used: Competitor Dart	Print Date: 29/06/2017	Scale: 1:25		
		Weather: Clear and sunny			Termination: Refusal		SPT Hammer: DART262 Energy Ratio: 72%		
Samples & In Situ Testing				Strata Details				Groundwater	
Depth	Sample ID	Windowless Sample Recovery	Test Result	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description	Water Strike	Backfill / Installation
0.00 - 0.50	ES1						MADE GROUND - Firm dark brown slightly sandy gravelly CLAY. Gravel is angular fine to coarse of red brick, concrete, ceramics and plastic.		
0.50 - 1.00	ES2				(1.20)			1	
1.30 - 1.50	ES3	1.20 - 2.00 = 100%	SPT(C) 1.20m, N=15 (3,4/3,5,3,4)		1.20		Very stiff orangish brown CLAY. (Devensian Till)		
1.60 - 1.80	D4				(0.80)				
2.30 - 2.50	D5	2.00 - 3.00 = 100%	SPT(C) 2.00m, N=26 (5,5/5,6,7,8)		2.00		Medium dense to dense orangish brown SAND. (Devensian Till)	2	
2.30 - 2.50	ES7								
3.00 - 4.00	B6	3.00 - 4.00 = 100%	SPT(C) 3.00m, N=34 (5,6/6,8,9,11)		(2.00)			3	
			SPT(C) 4.00m, N=50 (6,1/9,12,14,15)		4.00		End of Borehole at 4.00m	4	
								5	
Sample Key: B = Bulk Disturbed D = Small Disturbed U = Undisturbed Open-Drive W = Water G = Gas ES = Environmental Soil EW = Environmental Water									
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks: Hand dug pit to 1.2mbgl. Groundwater at 3.0mbgl post well installation.
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth	Dia (mm)	
28-04-2017	09:30	4.00		3.00	2.00	101			
					3.00	86			
					4.00	76			
Water Strikes					Installation				
Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks	Top (m)	Base (m)	Type	Dia (mm)
3.00			0	2.00		0.00	0.50	PLAIN	50
						0.50	4.00	SLOTTED	50
T&P Regeneration WS Template Issue Number: 1 Issue Date: June 2016									





 www.tandpregeneration.co.uk		Contract Name: Ashton Old Road		Client: EcoNRG			Borehole ID: WS02		
		Contract Number: ASH1867	Date Started: 28/04/2017	Logged By: RC	Checked By: JF	Status: FINAL	Sheet 1 of 1		
Windowless Sample Borehole Log		Easting:	Northing:	Ground Level:	Plant Used: Competitor Dart	Print Date: 29/06/2017	Scale: 1:25		
		Weather: Clear and sunny		Termination: Refusal		SPT Hammer: DART400 Energy Ratio: 66%			
Samples & In Situ Testing				Strata Details				Groundwater	
Depth	Sample ID	Windowless Sample Recovery	Test Result	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description	Water Strike	Backfill / Installation
1.00 - 1.20	ES1	0.50 - 1.00 = 100%	SPT(C) 1.00m, N=16 (2,2/3,4,4,5)		(1.20)		MADE GROUND - Firm dark brown slightly sandy gravelly CLAY. Gravel is angular fine to coarse of red brick, concrete, ceramics and plastic.	1	
		1.20			Between 1.0 - 1.2m - Slight hydrocarbon odour.				
1.50 - 1.80	ES2	1.00 - 2.00 = 100%	SPT(C) 2.00m, N=21 (5,5/5,5,5,6)		(0.70)		Stiff to very stiff dark reddish brown mottled grey CLAY. (Devensian Till)	2	
2.40 - 2.60	ES3	2.00 - 3.00 = 100%			1.90		Medium dense orangish brown and grey slightly clayey SAND. (Devensian Till)		
3.50 - 3.70	ES4	3.00 - 4.00 = 100%	SPT(C) 3.00m, N=16 (3,3/4,4,4,4)		(1.30)		Medium dense to dense dark orangish brown SAND. (Devensian Till)	3	
		3.20							
		SPT(C) 4.00m, 50 (11,12/50 for 255mm)			4.00		End of Borehole at 4.00m	4	
								5	
Sample Key: B = Bulk Disturbed D = Small Disturbed U = Undisturbed Open-Drive W = Water G = Gas ES = Environmental Soil EW = Environmental Water									
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks: Hand dug to 0.5mbgl. Groundwater not encountered.
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth	Dia (mm)	
28-04-2017	10:30	4.00			1.00	116			
					2.00	101			
					3.00	86			
					4.00	76			
Water Strikes					Installation				
Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks	Top (m)	Base (m)	Type	Dia (mm)
T&P Regeneration WS Template Issue Number: 1 Issue Date: June 2016									

 www.tandpregeneration.co.uk		Contract Name: Ashton Old Road		Client: EcoNRG			Borehole ID: WS03		
		Contract Number: ASH1867	Date Started: 28/04/2017	Logged By: RC	Checked By: JF	Status: FINAL	Sheet 1 of 1		
Windowless Sample Borehole Log		Easting:	Northing:	Ground Level:	Plant Used: Competitor Dart	Print Date: 29/06/2017	Scale: 1:25		
		Weather: Clear and sunny			Termination: Refusal		SPT Hammer: DART400 Energy Ratio: 66%		
Samples & In Situ Testing				Strata Details				Groundwater	
Depth	Sample ID	Windowless Sample Recovery	Test Result	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description	Water Strike	Backfill / Installation
0.00 - 1.20	ES1						MADE GROUND - Dark brown and black gravelly SAND. Gravel is angular fine to coarse of brick, ceramics, concrete and sandstone.		
0.80 - 1.10	D2				(1.20)				1
1.30 - 1.50	D3	1.20 - 2.00 = 100%	SPT(C) 1.20m, N=17 (2,3/4,4,4,5) HV 1.40m, 100/56kPa		1.20		Stiff to very stiff orangish brown mottled grey slightly sandy CLAY with occasional rounded fine to coarse gravel of sandstone. (Devensian Till)		
1.50 - 1.70	ES4		HV 1.70m, 125/60kPa		(1.00)				2
2.30 - 2.50	ES5	2.00 - 3.00 = 100%	SPT(C) 2.00m, N=29 (6,6/6,7,8,8)		2.20		Medium dense to dense orangish brown SAND. (Devensian Till)		
		3.00 - 4.00 = 100%	SPT(C) 3.00m, N=38 (6,7/8,8,11,11)		(2.80)				3
		4.00 - 5.00 = 100%	SPT(C) 4.00m, N=38 (8,9/9,10,9,10)		5.00			4	
			SPT(C) 5.00m, 50 (7,9/50 for 295mm)				End of Borehole at 5.00m	5	
Sample Key: B = Bulk Disturbed D = Small Disturbed U = Undisturbed Open-Drive W = Water G = Gas ES = Environmental Soil EW = Environmental Water									
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks: Hand dug pit to 1.2mbgl. Groundwater not encountered.
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth	Dia (mm)	
28-04-2017	09:00	5.00			1.00	116			
					2.00	101			
					3.00	86			
					4.00	76			
Water Strikes					Installation				
Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks	Top (m)	Base (m)	Type	Dia (mm)
						0.00	0.50	PLAIN	50
						0.50	4.00	SLOTTED	50
T&P Regeneration WS Template Issue Number: 1 Issue Date: June 2016									

 www.tandpregeneration.co.uk		Contract Name: Ashton Old Road		Client: EcoNRG			Borehole ID: WS04		
		Contract Number: ASH1867	Date Started: 28/04/2017	Logged By: RC	Checked By: JF	Status: FINAL	Sheet 1 of 1		
Windowless Sample Borehole Log		Easting:	Northing:	Ground Level:	Plant Used: Competitor Dart	Print Date: 29/06/2017	Scale: 1:25		
		Weather: Clear and sunny			Termination: Refusal		SPT Hammer: DART262 Energy Ratio: 72%		
Samples & In Situ Testing				Strata Details				Groundwater	
Depth	Sample ID	Windowless Sample Recovery	Test Result	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description	Water Strike	Backfill / Installation
0.50 - 0.80	ES1				(1.20)		MADE GROUND - Dark brown and black slightly clayey gravelly SAND with a slight hydrocarbon odour. Gravel is angular fine to coarse of brick, ceramics, concrete, wood and glass.	1	
1.50 - 1.70	ES2	1.00 - 2.00 = 100%	SPT(C) 1.00m, N=17 (2,5/5,5,3,4)		1.20		Stiff to very stiff dark brown CLAY with rare sandstone inclusions. (Devensian Till)		
		2.00 - 3.00 = 100%	SPT(C) 2.00m, N=33 (8,10/10,10,10,3)		1.90		Dense light orangish brown SAND. (Devensian Till)	2	
3.20 - 3.40	ES3	3.00 - 4.00 = 100%	SPT(C) 3.00m, N=43 (1,4/7,11,11,14)		(1.70)			3	
			SPT(C) 4.00m, N=50 (7,8/9,12,13,16)		3.60		Dense reddish orangish brown SAND. (Devensian Till)		
					4.00		End of Borehole at 4.00m	4	
								5	
Sample Key: B = Bulk Disturbed D = Small Disturbed U = Undisturbed Open-Drive W = Water G = Gas ES = Environmental Soil EW = Environmental Water									
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks: Hand dug pit to 0.8mbgl. Groundwater not encountered.
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth	Dia (mm)	
28-04-2017	12:00	4.00			1.00	116			
					2.00	101			
					3.00	86			
Water Strikes					Installation				
Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks	Top (m)	Base (m)	Type	Dia (mm)
T&P Regeneration WS Template Issue Number: 1 Issue Date: June 2016									

 www.tandpregeneration.co.uk		Contract Name: Ashton Old Road		Client: EcoNRG			Borehole ID: WS05			
		Contract Number: ASH1867	Date Started: 28/04/2017	Logged By: RC	Checked By: JF	Status: FINAL				
Windowless Sample Borehole Log		Easting:	Northing:	Ground Level:	Plant Used: Competitor Dart	Print Date: 29/06/2017	Sheet 1 of 1 Scale: 1:25			
		Weather: Clear and sunny		Termination: Refusal		SPT Hammer: DART262 Energy Ratio: 72%				
Samples & In Situ Testing				Strata Details				Groundwater		
Depth	Sample ID	Windowless Sample Recovery	Test Result	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description	Water Strike	Backfill / Installation	
0.30 - 0.60	ES1	0.00 - 1.00 = 100%	SPT(C) 1.00m, 50 (3,5/50 for 265mm)		(1.00)		MADE GROUND - Grass over dark brown gravelly sandy SILT. Gravel is angular fine to coarse of concrete and brick.			
				1.00			End of Borehole at 1.00m	1		
										2
										3
										4
							5			
Sample Key: B = Bulk Disturbed D = Small Disturbed U = Undisturbed Open-Drive W = Water G = Gas ES = Environmental Soil EW = Environmental Water										
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks: Groundwater not encountered.	
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth	Dia (mm)		
28-04-2017	13:00	1.00			1.00	116				
Water Strikes					Installation					
Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks	Top (m)	Base (m)	Type	Dia (mm)	
T&P Regeneration WS Template Issue Number: 1 Issue Date: June 2016										

 www.tandpregeneration.co.uk	Contract Name: Ashton Old Road			Client: EcoNRG			Borehole ID: WS06				
	Contract Number: ASH1867	Date Started: 28/04/2017	Logged By: RC	Checked By: JF	Status: FINAL	Sheet 1 of 1					
	Easting:	Northing:	Ground Level:	Plant Used: Competitor Dart	Print Date: 29/06/2017	Scale: 1:25					
Windowless Sample Borehole Log			Weather: Clear and sunny			Termination: Refusal			SPT Hammer: DART400 Energy Ratio: 66%		
Samples & In Situ Testing					Strata Details					Groundwater	
Depth	Sample ID	Windowless Sample Recovery	Test Result	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description	Water Strike	Backfill / Installation		
0.30 - 0.70	ES3	0.50 - 1.00 = 100%	SPT(C) 1.00m, N=11 (1,2/2,2,3,4)		(1.20)		MADE GROUND - Dark brown gravelly SAND. Gravel is angular fine to coarse of brick, concrete, sandstone and ceramics.	1			
1.60 - 1.70	ES1	1.00 - 2.00 = 100%			1.20		Stiff dark orangish brown mottled grey CLAY with occasional angular sandstone gravel inclusions. (Devensian Till)				
1.80 - 2.00	D2	2.00 - 3.00 = 100%	SPT(C) 2.00m, N=43 (10,10/11,10,11,11)		(0.80)		Dense to very dense orangish brown SAND. (Devensian Till)	2			
2.50 - 2.60	ES3				2.00						
		3.00 - 4.00 = 100%	SPT(C) 3.00m, N=44 (7,9/10,11,11,12)		(2.00)		End of Borehole at 4.00m	3			
		SPT(C) 4.00m, 50 (7,11/50 for 235mm)	4.00	4							
								5			
Sample Key: B = Bulk Disturbed D = Small Disturbed U = Undisturbed Open-Drive W = Water G = Gas ES = Environmental Soil EW = Environmental Water											
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks:		
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth	Dia (mm)	Hand dug to 0.5mbgl. Groundwater at 3.0mbgl post well installation.		
28-04-2017	13:30	4.00		3.00	1.00	116					
					2.00	101					
					3.00	86					
					4.00	76					
Water Strikes					Installation						
Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks	Top (m)	Base (m)	Type	Dia (mm)		
3.00			0	2.00							
T&P Regeneration WS Template Issue Number: 1 Issue Date: June 2016											

 www.tandpregeneration.co.uk	Contract Name: Ashton Old Road			Client: EcoNRG			Borehole ID: WS07				
	Contract Number: ASH1867	Date Started: 28/04/2017	Logged By: RC	Checked By: JF	Status: FINAL	Sheet 1 of 1					
	Easting:	Northing:	Ground Level:	Plant Used: Competitor Dart	Print Date: 29/06/2017	Scale: 1:25					
Windowless Sample Borehole Log			Weather: Clear and sunny			Termination: Refusal			SPT Hammer: DART400 Energy Ratio: 66%		
Samples & In Situ Testing					Strata Details					Groundwater	
Depth	Sample ID	Windowless Sample Recovery	Test Result	Level (mAOD)	Depth (m) (Thickness)	Legend	Strata Description	Water Strike	Backfill / Installation		
0.50 - 0.70	ES1	0.00 - 1.00 = 100%	SPT(C) 1.00m, N=14 (2,2/3,4,3,4)		(0.50)		MADE GROUND - Red brick and concrete.	1			
0.70 - 1.00	ES2				0.50		MADE GROUND - Black SAND.				
1.30 - 1.50	D3				0.70		Stiff to very stiff dark orangish brown mottled grey CLAY. (Devensian Till)				
1.50 - 1.70	ES4	1.00 - 2.00 = 100%	SPT(C) 2.00m, N=23 (4,6/6,6,5,6)		(1.10)			2			
2.50	ES5	2.00 - 3.00 = 100%			1.80						Medium dense orangish brown SAND. (Devensian Till)
2.80	ES6				2.20						Medium dense to dense dark orangish brown SAND. (Devensian Till)
		3.00 - 4.00 = 100%	SPT(C) 3.00m, N=24 (3,4/5,5,6,8)		(1.80)			3			
					4.00						End of Borehole at 4.00m
			SPT(C) 4.00m, 50 (7,10/50 for 250mm)					4			
								5			
Sample Key: B = Bulk Disturbed D = Small Disturbed U = Undisturbed Open-Drive W = Water G = Gas ES = Environmental Soil EW = Environmental Water											
Start & End of Shift Observations					Borehole Diameter		Casing Diameter		Remarks:		
Date	Time	Depth (m)	Casing (m)	Water (m)	Depth (m)	Dia (mm)	Depth	Dia (mm)	Groundwater at 3.0mbgl post well installation.		
28-04-2017	15:00	4.00		3.00	1.00	116					
					2.00	101					
					3.00	86					
					4.00	76					
Water Strikes					Installation						
Strike (m)	Casing (m)	Sealed (m)	Time (mins)	Rose to (m)	Remarks	Top (m)	Base (m)	Type	Dia (mm)		
3.00			0	2.00		0.00	0.50	PLAIN	50		
						0.50	4.00	SLOTTED	50		
T&P Regeneration WS Template Issue Number: 1 Issue Date: June 2016											

Appendix D – Geotechnical Analysis Results



Transmittal Note

South West Geotechnical Ltd
Unit 3 Brooklands,
Howden Road,
Tiverton,
Devon
EX16 5HW

Job No:	9106	Date Received:	09/05/17
Job Name:	Ashton Old Road	Date Sent:	23/05/17
Client Name:	T&P Regeneration	Transmittal Number:	T2095
Client Job No:	ASH1867	Senders Initials:	NWW
Client Address	Unit 4, Brunel Lock Development, Smeaton Road, Bristol BS1 6SE		

Test Detail	No. of Tests / Report No.
BS1377: Part 2: 1990: Clause 3 - Moisture Content	4
BS1377: Part 2: 1990: Clause 4 & 5 - Atterberg Limits	4
BS1377: Part 2: 1990: Clause 9.2 / 9.3 - Particle Size Distribution	1
Approved Signatories: Nick Worthington-Williams (Quality Manager), Dan Ayre (Deputy Quality Manager) Marc Davis (Laboratory Manager)	 8260 Accredited to ISO/IEC 17025:2005
This certificate shall not be reproduced except in full, without prior written approval of the laboratory.	



Summary of Classification Test Results

Unit 3 Brooklands,
Howden Road,
Tiverton,
Devon
EX16 5HW




Project No.		Project Name										 8260 Accredited to ISO/IEC 17025:2005
9106		Ashton Old Road										
Client Job No.		Client										
9106		T&P Regeneration										
Hole No.	Sample				Soil Description	mc	Passing 425µm	LL	PL	PI	Particle density	Remarks
	Type	Top	Base	Ref		CI.3.2			CI5.3	CI5.4		
						%	%	%	%	%	Mg/m3	
WS01	D	1.60	1.80	-	Dark brown slightly sandy slightly gravelly CLAY	19	96 - Sieved	41	19	22	-	
WS03	D	1.30	1.50	-	Dark brown slightly sandy slightly gravelly CLAY	21	89 - Sieved	46	22	24	-	
WS06	D	1.80	2.00	-	Dark brown slightly sandy slightly gravelly CLAY	18	92 - Sieved	41	19	22	-	
WS07	D	1.30	1.50	-	Dark brown slightly sandy slightly gravelly CLAY	22	98 - Sieved	50	22	28	-	
						-	-	-	-	-	-	
						-	-	-	-	-	-	
						-	-	-	-	-	-	
						-	-	-	-	-	-	
						-	-	-	-	-	-	
						-	-	-	-	-	-	
Preparation Clauses: Particle Density (BS1377:Part 1: 1990: CL7.4.4) Atterberg Limits (BS1377:Part 1: 1990: CL7.4.3) Moisture Content (BS1377: Part 1: 1990: CL7.3.3 & 7.4.2)												
Key Atterberg Limits BS1377-2:1990 4pt cone (CL.4.3) unless : 1pt - single point test (CL.4.4) 4.2.3 - Natural 4.2.4 - Sieved Moisture Content (mc) % Particle density BS1377-2:1990 sp - small pyknometer CL.8.3 gj - gas jar CL.8.2						Date		Approved By		Page No.	1	
						23/05/2017		Nick W-W - QM		KL001R Index Summary		

Graphical Summary of Atterberg Test Results

Unit 3 Brooklands,
Howden Road,
Tiverton,
Devon
EX16 5HW

Project No.	Project Name
9106	Ashton Old Road
Client Job No.	Client
ASH1867	T&P Regeneration

Casagrande Chart




● WS01 (D) @ 1.60 - 1.80m ● WS03 (D) @ 1.30 - 1.50m ● WS06 (D) @ 1.80 - 2.00m ● WS07 (D) @ 1.30 - 1.50m



8260
Accredited to
ISO/IEC 17025:2005

KL001a Index Graphical Summary	Approved By	Date	Page No.
	Nick W-Williams - Quality Manager	23/05/2017 15:40	1

	Particle Size Distribution BS1377:Part 2:1990, clause 9.2		Project No.	9106	
			Borehole/Pit No.	WS01	
Project Name	Ashton Old Road		Sample No.	-	
Soil Description	Greyish brown slightly gravelly silty SAND		Depth, m	3.00	- 4.00
Client Job No.	9106	Specimen Depth	3.00 m	Sample Type	B
Client	T&P Regeneration				



Sieving		Sedimentation	
Particle Size mm	% Passing	Particle Size mm	% Passing
125	-	-	-
75	-	-	-
63	-	-	-
50	-		
37.5	-		
20	100		
14	100		
10	100		
5	98		
2	98		
1.18	97		
0.6	96		
0.425	95		
0.3	92		
0.15	57		
0.063	15		

Sedimentation pre-treatment
N/A

Dry Mass of sample, g	804
-----------------------	-----

Sample Proportions	% dry mass
Very coarse	0
Gravel	3
Sand	83
Fines <0.063mm	15

Grading Analysis		
D100	mm	
D60	mm	0.16
D30	mm	0.0864
D10	mm	
Uniformity Coefficient		
Curvature Coefficient		

Remarks
Preparation and testing in accordance with BS1377: Part 1: 1990 CL7.3 & 7.4.5



Page No.	1	Date	Approved
Sheet ID: KL002R PSD	23/05/2017 16:35	Nick W-W - QM	

8260
Accredited to
ISO/IEC
17025:2015



Transmittal Note

South West Geotechnical Ltd
Unit 3 Brooklands,
Howden Road,
Tiverton,
Devon
EX16 5HW

Job No:	9106	Date Received:	09/05/17
Job Name:	Ashton Old Road	Date Sent:	18/05/17
Client Name:	T&P Regeneration	Transmittal Number:	T2095A
Client Job No:	ASH1867	Senders Initials:	SE
Client Address	Unit 4, Brunel Lock Development, Smeaton Road, Bristol BS1 6SE		

Test Detail	No. of Tests / Report No.
External Chemical Testing	17-58756.1
Approved Signatories: Nick Worthington-Williams (Quality Manager), Dan Ayre (Deputy Quality Manager) Marc Davis (Laboratory Manager)	 8260 Accredited to ISO/IEC 17025:2005
This certificate shall not be reproduced except in full, without prior written approval of the laboratory.	



Neil Forrow
South West Geotechnical Ltd
Unit 3 Brooklands
Howden Road
Tiverton
Devon
EX16 5HW



QTS Environmental Ltd
Unit 1
Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Kent
ME17 2JN
t: 01622 850410
russell.jarvis@qtsenvironmental.com

QTS Environmental Report No: 17-58756

Site Reference: Ashton Old Road

Project / Job Ref: 9106 / T2095A

Order No: None Supplied

Sample Receipt Date: 10/05/2017

Sample Scheduled Date: 10/05/2017

Report Issue Number: 1

Reporting Date: 16/05/2017

Authorised by:

Kevin Old
Associate Director of Laboratory

QTSE is the trading name of DETS Ltd, company registration number 03705645

Authorised by:

Russell Jarvis
Associate Director of Client Services



QTS Environmental Ltd
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate						
QTS Environmental Report No: 17-58756	Date Sampled	28/04/17	28/04/17	28/04/17	28/04/17	
South West Geotechnical Ltd	Time Sampled	None Supplied	None Supplied	None Supplied	None Supplied	
Site Reference: Ashton Old Road	TP / BH No	WS01	WS03	WS06	WS07	
Project / Job Ref: 9106 / T2095A	Additional Refs	None Supplied	None Supplied	None Supplied	None Supplied	
Order No: None Supplied	Depth (m)	1.60 - 1.80	1.30 - 1.50	1.80 - 2.00	1.30 - 1.50	
Reporting Date: 16/05/2017	QTSE Sample No	267924	267925	267926	267927	

Determinand	Unit	RL	Accreditation				
pH	pH Units	N/a	MCERTS	7.6	7.5	7.7	7.6
W/S Sulphate as SO ₄ (2:1)	mg/l	< 10	MCERTS	37	128	40	72
W/S Sulphate as SO ₄ (2:1)	g/l	< 0.01	MCERTS	0.04	0.13	0.04	0.07

Analytical results are expressed on a dry weight basis where samples are assisted-dried at less than 30°C

Analysis carried out on the dried sample is corrected for the stone content

Subcontracted analysis ⁽⁵⁾



QTS Environmental Ltd
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Sample Descriptions

QTS Environmental Report No: 17-58756

South West Geotechnical Ltd

Site Reference: Ashton Old Road

Project / Job Ref: 9106 / T2095A

Order No: None Supplied

Reporting Date: 16/05/2017

QTSE Sample No	TP / BH No	Additional Refs	Depth (m)	Moisture Content (%)	Sample Matrix Description
\$ 267924	WS01	None Supplied	1.60 - 1.80	13.5	Brown sandy clay with stones
\$ 267925	WS03	None Supplied	1.30 - 1.50	15.6	Brown sandy clay
\$ 267926	WS06	None Supplied	1.80 - 2.00	14.2	Brown sandy clay
\$ 267927	WS07	None Supplied	1.30 - 1.50	19.4	Brown clay

Moisture content is part of procedure E003 & is not an accredited test

Insufficient Sample ^{I/S}

Unsuitable Sample ^{U/S}

\$ samples exceeded recommended holding times



QTS Environmental Ltd
Unit 1, Rose Lane Industrial Estate
Rose Lane
Lenham Heath
Maidstone
Kent ME17 2JN
Tel : 01622 850410



Soil Analysis Certificate - Methodology & Miscellaneous Information

QTS Environmental Report No: 17-58756

South West Geotechnical Ltd

Site Reference: Ashton Old Road

Project / Job Ref: 9106 / T2095A

Order No: None Supplied

Reporting Date: 16/05/2017

Matrix	Analysed On	Determinand	Brief Method Description	Method No
Soil	D	Boron - Water Soluble	Determination of water soluble boron in soil by 2:1 hot water extract followed by ICP-OES	E012
Soil	AR	BTEX	Determination of BTEX by headspace GC-MS	E001
Soil	D	Cations	Determination of cations in soil by aqua-regia digestion followed by ICP-OES	E002
Soil	D	Chloride - Water Soluble (2:1)	Determination of chloride by extraction with water & analysed by ion chromatography	E009
Soil	AR	Chromium - Hexavalent	Determination of hexavalent chromium in soil by extraction in water then by acidification, addition of 1,5 diphenylcarbazine followed by colorimetry	E016
Soil	AR	Cyanide - Complex	Determination of complex cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Free	Determination of free cyanide by distillation followed by colorimetry	E015
Soil	AR	Cyanide - Total	Determination of total cyanide by distillation followed by colorimetry	E015
Soil	D	Cyclohexane Extractable Matter (CEM)	Gravimetrically determined through extraction with cyclohexane	E011
Soil	AR	Diesel Range Organics (C10 - C24)	Determination of hexane/acetone extractable hydrocarbons by GC-FID	E004
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of saturated calcium sulphate followed by electrometric measurement	E022
Soil	AR	Electrical Conductivity	Determination of electrical conductivity by addition of water followed by electrometric measurement	E023
Soil	D	Elemental Sulphur	Determination of elemental sulphur by solvent extraction followed by GC-MS	E020
Soil	AR	EPH (C10 - C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH Product ID	Determination of acetone/hexane extractable hydrocarbons by GC-FID	E004
Soil	AR	EPH TEXAS (C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C40)	Determination of acetone/hexane extractable hydrocarbons by GC-FID for C8 to C40. C6 to C8 by headspace GC-MS	E004
Soil	D	Fluoride - Water Soluble	Determination of Fluoride by extraction with water & analysed by ion chromatography	E009
Soil	D	FOC (Fraction Organic Carbon)	Determination of fraction of organic carbon by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	D	Loss on Ignition @ 450oC	Determination of loss on ignition in soil by gravimetrically with the sample being ignited in a muffle furnace	E019
Soil	D	Magnesium - Water Soluble	Determination of water soluble magnesium by extraction with water followed by ICP-OES	E025
Soil	D	Metals	Determination of metals by aqua-regia digestion followed by ICP-OES	E002
Soil	AR	Mineral Oil (C10 - C40)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge	E004
Soil	AR	Moisture Content	Moisture content; determined gravimetrically	E003
Soil	D	Nitrate - Water Soluble (2:1)	Determination of nitrate by extraction with water & analysed by ion chromatography	E009
Soil	D	Organic Matter	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	PAH - Speciated (EPA 16)	Determination of PAH compounds by extraction in acetone and hexane followed by GC-MS with the use of surrogate and internal standards	E005
Soil	AR	PCB - 7 Congeners	Determination of PCB by extraction with acetone and hexane followed by GC-MS	E008
Soil	D	Petroleum Ether Extract (PEE)	Gravimetrically determined through extraction with petroleum ether	E011
Soil	AR	pH	Determination of pH by addition of water followed by electrometric measurement	E007
Soil	AR	Phenols - Total (monohydric)	Determination of phenols by distillation followed by colorimetry	E021
Soil	D	Phosphate - Water Soluble (2:1)	Determination of phosphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Total	Determination of total sulphate by extraction with 10% HCl followed by ICP-OES	E013
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of sulphate by extraction with water & analysed by ion chromatography	E009
Soil	D	Sulphate (as SO4) - Water Soluble (2:1)	Determination of water soluble sulphate by extraction with water followed by ICP-OES	E014
Soil	AR	Sulphide	Determination of sulphide by distillation followed by colorimetry	E018
Soil	D	Sulphur - Total	Determination of total sulphur by extraction with aqua-regia followed by ICP-OES	E024
Soil	AR	SVOC	Determination of semi-volatile organic compounds by extraction in acetone and hexane followed by GC-MS	E006
Soil	AR	Thiocyanate (as SCN)	Determination of thiocyanate by extraction in caustic soda followed by acidification followed by addition of ferric nitrate followed by colorimetry	E017
Soil	D	Toluene Extractable Matter (TEM)	Gravimetrically determined through extraction with toluene	E011
Soil	D	Total Organic Carbon (TOC)	Determination of organic matter by oxidising with potassium dichromate followed by titration with iron (II) sulphate	E010
Soil	AR	TPH CWG (ali: C5- C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C34, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C35. C5 to C8 by headspace GC-MS	E004
Soil	AR	TPH LQM (ali: C5-C6, C6-C8, C8-C10, C10-C12, C12-C16, C16-C35, C35-C44, aro: C5-C7, C7-C8, C8-C10, C10-C12, C12-C16, C16-C21, C21-C35, C35-C44)	Determination of hexane/acetone extractable hydrocarbons by GC-FID fractionating with SPE cartridge for C8 to C44. C5 to C8 by headspace GC-MS	E004
Soil	AR	VOCS	Determination of volatile organic compounds by headspace GC-MS	E001
Soil	AR	VPH (C6-C8 & C8-C10)	Determination of hydrocarbons C6-C8 by headspace GC-MS & C8-C10 by GC-FID	E001

D Dried
AR As Received

Appendix E – Chemical Analysis Results



Unit A2
Windmill Road
Ponswood Industrial Estate
St Leonards on Sea
East Sussex
TN38 9BY
Telephone: (01424) 718618
Facsimile: (01424) 729911
info@elab-uk.co.uk

THE ENVIRONMENTAL LABORATORY LTD

Analytical Report Number: 17-11961

Issue: 2

Date of Issue: 18/05/2017

Contact: Raife Crookes

Customer Details: T & P Regeneration Ltd (Smeaton Road)
Unit 4
Brunel Lock Development
Bristol
BS1 6SF

Quotation No: Q15-00390

Order No: 2779-ASH1867

Customer Reference: ASH1867

Date Received: 03/05/2017

Date Approved: 18/05/2017

Details: ASH1867

Approved by:

John Wilson, Operations Manager

Any comments, opinions or interpretations expressed herein are outside the scope of UKAS accreditation (Accreditation Number 2683)

Sample Summary

Report No.: 17-11961

Elab No.	Client's Ref.	Date Sampled	Date Scheduled	Description	Deviations
98711	WS01 0.00 - 0.50	28/04/2017	05/05/2017		
98712	WS01 0.50 - 1.00	28/04/2017	05/05/2017		
98713	WS01 1.30 - 1.50	28/04/2017	05/05/2017		
98714	WS02 1.00 - 1.20	28/04/2017	15/05/2017	Sandy silty loam	g
98715	WS02 1.50 - 1.80	28/04/2017	05/05/2017	Clayey loam	
98716	WS02 2.40 - 2.60	28/04/2017	05/05/2017		
98717	WS02 3.50 - 3.70	28/04/2017	05/05/2017		
98718	WS03 0.00 - 1.20	28/04/2017	05/05/2017	Sandy silty loam	
98719	WS03 1.50 - 1.70	28/04/2017	05/05/2017		
98720	WS03 2.30 - 2.50	28/04/2017	05/05/2017		
98721	WS04 0.50 - 0.80	28/04/2017	15/05/2017	Sandy silty loam	g
98722	WS04 1.50 - 1.70	28/04/2017	15/05/2017	Silty clayey loam	g
98723	WS04 3.20 - 3.40	28/04/2017	05/05/2017		
98724	WS06 0.30 - 0.70	28/04/2017	05/05/2017	Sandy silty loam	
98725	WS06 1.60 - 1.70	28/04/2017	05/05/2017		
98726	WS06 2.50 - 2.60	28/04/2017	05/05/2017		
98727	WS07 0.50 - 0.70	28/04/2017	05/05/2017	Loamy sand	
98728	WS07 0.70 - 1.00	28/04/2017	05/05/2017	Silty clayey loam	
98729	WS07 1.50 - 1.70	28/04/2017	05/05/2017		
98730	WS07 2.50	28/04/2017	05/05/2017		
98731	WS07 2.80	28/04/2017	05/05/2017		
98732	SS01 0.00 - 0.30	28/04/2017	15/05/2017	Sandy silty loam	g
98733	WS01 2.30 - 2.50	28/04/2017	05/05/2017		
98734	WS05 0.30 - 0.60	28/04/2017	05/05/2017	Sandy silty loam	

Results Summary

Report No.: 17-11961

ELAB Reference	98714	98715	98718	98721	98722	98724
Customer Reference						
Sample ID						
Sample Type	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
Sample Location	WS02	WS02	WS03	WS04	WS04	WS06
Sample Depth (m)	1.00 - 1.20	1.50 - 1.80	0.00 - 1.20	0.50 - 0.80	1.50 - 1.70	0.30 - 0.70
Sampling Date	28/04/2017	28/04/2017	28/04/2017	28/04/2017	28/04/2017	28/04/2017

Determinand	Codes	Units	LOD						
Metals									
Arsenic	M	mg/kg	1	26.9	n/t	66.0	23.8	9.6	7.0
Cadmium	M	mg/kg	0.5	1.3	n/t	20.0	21.8	0.5	1.1
Chromium	M	mg/kg	5	56.5	n/t	811	84.7	48.5	22.1
Copper	M	mg/kg	5	119	n/t	301	355	35.2	67.3
Lead	M	mg/kg	5	345	n/t	721	4030	26.7	352
Mercury	M	mg/kg	0.5	< 0.5	n/t	0.5	< 0.5	< 0.5	< 0.5
Nickel	M	mg/kg	5	34.1	n/t	71.1	76.9	46.9	17.8
Selenium	M	mg/kg	1	1.3	n/t	3.2	1.9	< 1.0	< 1.0
Zinc	M	mg/kg	5	309	n/t	2240	2460	107	283
Anions									
Water Soluble Sulphate	M	g/l	0.02	0.68	n/t	1.45	0.14	0.11	0.08
Inorganics									
Hexavalent Chromium	N	mg/kg	0.8	< 0.8	n/t	< 0.8	< 0.8	< 0.8	< 0.8
Water Soluble Boron	N	mg/kg	0.5	1.3	n/t	1.1	1.1	0.6	0.5
Miscellaneous									
pH	M	pH units	0.1	7.0	n/t	7.2	7.2	7.6	9.0
Total Organic Carbon	N	%	0.01	2.0	n/t	20	3.7	0.61	1.7
Phenols									
Phenol	M	mg/kg	1	< 1	n/t	< 1	< 1	< 1	< 1
M,P-Cresol	N	mg/kg	1	< 1	n/t	< 1	< 1	< 1	< 1
O-Cresol	N	mg/kg	1	< 1	n/t	< 1	< 1	< 1	< 1
3,4-Dimethylphenol	N	mg/kg	1	< 1	n/t	< 1	< 1	< 1	< 1
2,3-Dimethylphenol	M	mg/kg	1	< 1	n/t	< 1	< 1	< 1	< 1
2,3,5-trimethylphenol	M	mg/kg	1	< 1	n/t	< 1	< 1	< 1	< 1
Total Monohydric Phenols	N	mg/kg	5	< 5	n/t	< 5	< 5	< 5	< 5
Polyaromatic hydrocarbons									
Naphthalene	M	mg/kg	0.1	< 0.1	n/t	1.2	0.5	< 0.1	0.2
Acenaphthylene	M	mg/kg	0.1	< 0.1	n/t	0.2	< 0.1	< 0.1	0.2
Acenaphthene	M	mg/kg	0.1	< 0.1	n/t	0.6	0.5	< 0.1	0.2
Fluorene	M	mg/kg	0.1	< 0.1	n/t	0.3	0.4	< 0.1	0.3
Phenanthrene	M	mg/kg	0.1	< 0.1	n/t	3.1	2.9	< 0.1	1.2
Anthracene	M	mg/kg	0.1	< 0.1	n/t	0.6	0.7	< 0.1	0.3
Fluoranthene	M	mg/kg	0.1	0.3	n/t	5.3	4.0	< 0.1	3.1
Pyrene	M	mg/kg	0.1	0.3	n/t	5.2	5.2	< 0.1	5.0
Benzo(a)anthracene	M	mg/kg	0.1	0.2	n/t	2.9	2.8	< 0.1	1.4
Chrysene	M	mg/kg	0.1	0.1	n/t	3.8	4.2	< 0.1	3.9
Benzo (b) fluoranthene	M	mg/kg	0.1	< 0.1	n/t	2.9	5.1	< 0.1	1.7
Benzo(k)fluoranthene	M	mg/kg	0.1	< 0.1	n/t	2.6	4.1	< 0.1	3.1
Benzo (a) pyrene	M	mg/kg	0.1	0.3	n/t	2.9	6.1	< 0.1	2.5
Indeno (1,2,3-cd) pyrene	M	mg/kg	0.1	< 0.1	n/t	2.2	5.1	< 0.1	3.2
Dibenzo(a,h)anthracene	M	mg/kg	0.1	< 0.1	n/t	0.5	2.4	< 0.1	1.7
Benzo[g,h,i]perylene	M	mg/kg	0.1	< 0.1	n/t	2.4	5.0	< 0.1	2.7
Total PAH(16)	M	mg/kg	0.4	1.4	n/t	36.6	49.0	< 0.4	30.6

Results Summary

Report No.: 17-11961

ELAB Reference	98714	98715	98718	98721	98722	98724
Customer Reference						
Sample ID						
Sample Type	SOIL	SOIL	SOIL	SOIL	SOIL	SOIL
Sample Location	WS02	WS02	WS03	WS04	WS04	WS06
Sample Depth (m)	1.00 - 1.20	1.50 - 1.80	0.00 - 1.20	0.50 - 0.80	1.50 - 1.70	0.30 - 0.70
Sampling Date	28/04/2017	28/04/2017	28/04/2017	28/04/2017	28/04/2017	28/04/2017

Determinand	Codes	Units	LOD						
BTEX									
Benzene	M	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
Benzene	M	ug/kg	10	g < 10.0	n/t	n/t	g < 10.0	g < 10.0	n/t
Toluene	M	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
Toluene	M	ug/kg	10	g < 10.0	n/t	n/t	g < 10.0	g < 10.0	n/t
Ethylbenzene	M	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
Ethylbenzene	M	ug/kg	10	g < 10.0	n/t	n/t	g < 10.0	g < 10.0	n/t
Xylenes	M	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
Xylenes	M	ug/kg	10	g < 10.0	n/t	n/t	g < 10.0	g < 10.0	n/t
MTBE	N	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
MTBE	N	ug/kg	10	g < 10.0	n/t	n/t	g < 10.0	g < 10.0	n/t
TPH CWG									
>C5-C6 Aliphatic	N	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
>C6-C8 Aliphatic	N	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
>C8-C10 Aliphatic	N	mg/kg	1	g < 1.0	n/t	n/t	g 2.3	g < 1.0	n/t
>C10-C12 Aliphatic	N	mg/kg	1	g < 1.0	n/t	n/t	g < 1.0	g < 1.0	n/t
>C12-C16 Aliphatic	N	mg/kg	1	g 1.2	n/t	n/t	g 6.2	g < 1.0	n/t
>C16-C21 Aliphatic	N	mg/kg	1	g 73.2	n/t	n/t	g 118	g < 1.0	n/t
>C21-C35 Aliphatic	N	mg/kg	1	g 546	n/t	n/t	g 2100	g 4.4	n/t
>C35-C40 Aliphatic	N	mg/kg	1	g 238	n/t	n/t	g 398	g < 1.0	n/t
>C5-C7 Aromatic	N	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
>C7-C8 Aromatic	N	mg/kg	0.01	g < 0.01	n/t	n/t	g < 0.01	g < 0.01	n/t
>C8-C10 Aromatic	N	mg/kg	1	g < 1.0	n/t	n/t	g < 1.0	g < 1.0	n/t
>C10-C12 Aromatic	N	mg/kg	1	g < 1.0	n/t	n/t	g < 1.0	g < 1.0	n/t
>C12-C16 Aromatic	N	mg/kg	1	g < 1.0	n/t	n/t	g 3.1	g < 1.0	n/t
>C16-C21 Aromatic	N	mg/kg	1	g 22.8	n/t	n/t	g 72.4	g < 1.0	n/t
>C21-C35 Aromatic	N	mg/kg	1	g 352	n/t	n/t	g 1100	g 4.2	n/t
>C35-C40 Aromatic	N	mg/kg	1	g 148	n/t	n/t	g 264	g < 1.0	n/t
Total (>C5-C40) Ali/Aro	N	mg/kg	1	g 1380	n/t	n/t	g 4070	g 8.6	n/t
Total Petroleum Hydrocarbons									
Total TPH (>C8-C40)	M	mg/kg	5	1610	< 5	n/t	2990	n/t	n/t

Results Summary

Report No.: 17-11961

ELAB Reference	98727	98728	98732	98734
Customer Reference				
Sample ID				
Sample Type	SOIL	SOIL	SOIL	SOIL
Sample Location	WS07	WS07	SS01	WS05
Sample Depth (m)	0.50 - 0.70	0.70 - 1.00	0.00 - 0.30	0.30 - 0.60
Sampling Date	28/04/2017	28/04/2017	28/04/2017	28/04/2017

Determinand	Codes	Units	LOD				
Metals							
Arsenic	M	mg/kg	1	8.7	9.9	49.2	22.6
Cadmium	M	mg/kg	0.5	< 0.5	< 0.5	1.9	1.0
Chromium	M	mg/kg	5	21.4	42.3	69.4	34.0
Copper	M	mg/kg	5	26.2	36.4	499	160
Lead	M	mg/kg	5	142	23.5	348	392
Mercury	M	mg/kg	0.5	< 0.5	< 0.5	< 0.5	< 0.5
Nickel	M	mg/kg	5	12.8	36.8	100	27.3
Selenium	M	mg/kg	1	< 1.0	< 1.0	< 1.0	1.1
Zinc	M	mg/kg	5	68.3	78.1	983	314
Anions							
Water Soluble Sulphate	M	g/l	0.02	0.05	0.10	0.04	0.09
Inorganics							
Hexavalent Chromium	N	mg/kg	0.8	< 0.8	< 0.8	< 0.8	< 0.8
Water Soluble Boron	N	mg/kg	0.5	1.2	1.0	0.7	1.1
Miscellaneous							
pH	M	pH units	0.1	8.3	7.6	7.5	9.2
Total Organic Carbon	N	%	0.01	3.8	0.45	1.9	3.6
Phenols							
Phenol	M	mg/kg	1	< 1	< 1	< 1	< 1
M,P-Cresol	N	mg/kg	1	< 1	< 1	< 1	< 1
O-Cresol	N	mg/kg	1	< 1	< 1	< 1	< 1
3,4-Dimethylphenol	N	mg/kg	1	< 1	< 1	< 1	< 1
2,3-Dimethylphenol	M	mg/kg	1	< 1	< 1	< 1	< 1
2,3,5-trimethylphenol	M	mg/kg	1	< 1	< 1	< 1	< 1
Total Monohydric Phenols	N	mg/kg	5	< 5	< 5	< 5	< 5
Polyaromatic hydrocarbons							
Naphthalene	M	mg/kg	0.1	< 0.1	< 0.1	< 0.1	0.5
Acenaphthylene	M	mg/kg	0.1	< 0.1	< 0.1	0.1	0.2
Acenaphthene	M	mg/kg	0.1	< 0.1	< 0.1	< 0.1	0.7
Fluorene	M	mg/kg	0.1	< 0.1	< 0.1	< 0.1	0.5
Phenanthrene	M	mg/kg	0.1	0.2	< 0.1	< 0.1	6.6
Anthracene	M	mg/kg	0.1	< 0.1	< 0.1	< 0.1	1.9
Fluoranthene	M	mg/kg	0.1	0.3	< 0.1	1.2	10.5
Pyrene	M	mg/kg	0.1	0.4	< 0.1	1.9	9.3
Benzo(a)anthracene	M	mg/kg	0.1	0.3	< 0.1	< 0.1	5.0
Chrysene	M	mg/kg	0.1	0.3	< 0.1	< 0.1	6.1
Benzo (b) fluoranthene	M	mg/kg	0.1	0.3	< 0.1	< 0.1	4.6
Benzo(k)fluoranthene	M	mg/kg	0.1	0.2	< 0.1	< 0.1	5.1
Benzo (a) pyrene	M	mg/kg	0.1	0.2	< 0.1	< 0.1	5.0
Indeno (1,2,3-cd) pyrene	M	mg/kg	0.1	0.5	0.2	< 0.1	3.5
Dibenzo(a,h)anthracene	M	mg/kg	0.1	0.2	0.6	< 0.1	1.0
Benzo[g,h,i]perylene	M	mg/kg	0.1	0.4	0.3	< 0.1	3.7
Total PAH(16)	M	mg/kg	0.4	3.2	1.1	3.5	64.2



Results Summary

2683

Report No.: 17-11961

ELAB Reference				98727	98728	98732	98734
Customer Reference							
Sample ID							
Sample Type				SOIL	SOIL	SOIL	SOIL
Sample Location				WS07	WS07	SS01	WS05
Sample Depth (m)				0.50 - 0.70	0.70 - 1.00	0.00 - 0.30	0.30 - 0.60
Sampling Date				28/04/2017	28/04/2017	28/04/2017	28/04/2017
Determinand	Codes	Units	LOD				
BTEX							
Benzene	M	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
Benzene	M	ug/kg	10	n/t	n/t	g < 10.0	n/t
Toluene	M	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
Toluene	M	ug/kg	10	n/t	n/t	g < 10.0	n/t
Ethylbenzene	M	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
Ethylbenzene	M	ug/kg	10	n/t	n/t	g < 10.0	n/t
Xylenes	M	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
Xylenes	M	ug/kg	10	n/t	n/t	g < 10.0	n/t
MTBE	N	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
MTBE	N	ug/kg	10	n/t	n/t	g < 10.0	n/t
TPH CWG							
>C5-C6 Aliphatic	N	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
>C6-C8 Aliphatic	N	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
>C8-C10 Aliphatic	N	mg/kg	1	n/t	n/t	g < 1.0	n/t
>C10-C12 Aliphatic	N	mg/kg	1	n/t	n/t	g < 1.0	n/t
>C12-C16 Aliphatic	N	mg/kg	1	n/t	n/t	g 23.7	n/t
>C16-C21 Aliphatic	N	mg/kg	1	n/t	n/t	g 554	n/t
>C21-C35 Aliphatic	N	mg/kg	1	n/t	n/t	g 17300	n/t
>C35-C40 Aliphatic	N	mg/kg	1	n/t	n/t	g 1610	n/t
>C5-C7 Aromatic	N	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
>C7-C8 Aromatic	N	mg/kg	0.01	n/t	n/t	g < 0.01	n/t
>C8-C10 Aromatic	N	mg/kg	1	n/t	n/t	g < 1.0	n/t
>C10-C12 Aromatic	N	mg/kg	1	n/t	n/t	g < 1.0	n/t
>C12-C16 Aromatic	N	mg/kg	1	n/t	n/t	g < 1.0	n/t
>C16-C21 Aromatic	N	mg/kg	1	n/t	n/t	g 256	n/t
>C21-C35 Aromatic	N	mg/kg	1	n/t	n/t	g 5220	n/t
>C35-C40 Aromatic	N	mg/kg	1	n/t	n/t	g 694	n/t
Total (>C5-C40) Ali/Aro	N	mg/kg	1	n/t	n/t	g 25600	n/t
Total Petroleum Hydrocarbons							
Total TPH (>C8-C40)	M	mg/kg	5	n/t	n/t	24400	n/t



Results Summary

Report No.: 17-11961

ELAB Reference	98721	98724	98732
Customer Reference			
Sample ID			
Sample Type	SOIL	SOIL	SOIL
Sample Location	WS04	WS06	SS01
Sample Depth (m)	0.50 - 0.80	0.30 - 0.70	0.00 - 0.30
Sampling Date	28/04/2017	28/04/2017	28/04/2017

Determinand	Codes	Units	LOD			
SVOC						
Phenol	N	mg/kg	0.01	0.05	0.02	0.13
Aniline	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Bis(2-chloroethyl)ether	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2-Chlorophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
1,3-Dichlorobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
1,4-Dichlorobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Benzyl Alcohol	N	mg/kg	0.01	< 0.01	< 0.01	0.75
1,2-Dichlorobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2-Methylphenol	N	mg/kg	0.01	0.02	0.02	< 0.01
Bis(2-chloroisopropyl)ether	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
3 and 4-methylphenol	N	mg/kg	0.01	0.08	0.04	0.03
N-Nitrosodi-n-propylamine	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Hexachloroethane	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Nitrobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Isophorone	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2-Nitrophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2,4-Dimethylphenol	N	mg/kg	0.01	0.04	0.05	0.04
Bis(2-chloroethoxy)methane	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2,4-Dichlorophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
1,3,5-Trichlorobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Naphthalene	N	mg/kg	0.01	0.77	0.09	0.17
3-Chloroaniline	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Hexachloro-1,3-butadiene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
4-Chloro-3-methylphenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2-Methylnaphthalene	N	mg/kg	0.01	0.43	0.10	0.11
1-Methylnaphthalene	N	mg/kg	0.01	0.33	0.07	0.06
Hexachlorocyclopentadiene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2,4,6-Trichlorophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2,4,5-Trichlorophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
1-Chloronaphthalene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2-Nitroaniline	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
1,4-Dinitrobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Dimethyl phthalate	N	mg/kg	0.01	0.46	< 0.01	< 0.01
1-3-dinitrobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2-6-dinitrotoluene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Acenaphthylene	N	mg/kg	0.01	0.05	0.08	0.12
1,2-Dinitrobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
3-Nitroaniline	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Acenaphthene	N	mg/kg	0.01	0.51	0.06	0.04
4-nitrophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Dibenzofuran	N	mg/kg	0.01	0.32	0.05	0.03
2,3,5,6-Tetrachlorophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
2,3,4,6-Tetrachlorophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Diethyl phthalate	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
1-chloro-4-phenoxybenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Fluorene	N	mg/kg	0.01	0.42	0.04	0.02
4-Nitroaniline	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Dinitro-o-cresol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Diphenylamine	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Azobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
1-bromo-4-phenoxybenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Hexachlorobenzene	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Pentachlorophenol	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01

Tests marked N are not UKAS accredited.
The Environmental Laboratory Ltd. Reg. No. 3882193



Results Summary

Report No.: 17-11961

ELAB Reference	98721	98724	98732
Customer Reference			
Sample ID			
Sample Type	SOIL	SOIL	SOIL
Sample Location	WS04	WS06	SS01
Sample Depth (m)	0.50 - 0.80	0.30 - 0.70	0.00 - 0.30
Sampling Date	28/04/2017	28/04/2017	28/04/2017

Determinand	Codes	Units	LOD			
SVOC						
Phenanthrene	N	mg/kg	0.01	3.16	0.59	0.37
Anthracene	N	mg/kg	0.01	0.49	0.23	0.15
Carbazole	N	mg/kg	0.01	0.20	0.05	< 0.01
Dibutyl phthalate	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Fluoranthene	N	mg/kg	0.01	5.85	1.43	0.58
Pyrene	N	mg/kg	0.01	5.57	1.31	2.08
Butyl benzyl phthalate	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Bis-2-ethylhexyladipate	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Butyl benzyl phthalate	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Benzo(a)anthracene	N	mg/kg	0.01	5.22	0.65	0.48
Chrysene	N	mg/kg	0.01	5.87	0.79	0.77
Bis(2-ethylhexyl)phthalate	N	mg/kg	0.01	< 0.01	< 0.01	< 0.01
Benzo(b)fluoranthene	N	mg/kg	0.01	5.53	1.02	1.27
Benzo(k)fluoranthene	N	mg/kg	0.01	7.08	0.64	0.94
Benzo(a)pyrene	N	mg/kg	0.01	8.47	0.96	1.20
Indeno(1,2,3-cd)pyrene	N	mg/kg	0.01	5.17	1.02	1.14
Dibenz(ah)anthracene	N	mg/kg	0.01	1.76	0.25	0.42
Benzo[g,h,i]perylene	N	mg/kg	0.01	6.63	2.39	1.72

Results Summary

Report No.: 17-11961

Asbestos Results

Analytical result only applies to the sample as submitted by the client. Any comments, opinions or interpretations (marked #) in this report are outside UKAS accreditation (Accreditation No2683). They are subjective comments only which must be verified by the client.

Elab No	Depth (m)	Clients Reference	Description of Sample Matrix #	Asbestos Identification	Gravimetric Analysis Total (%)	Gravimetric Analysis by ACM Type (%)	Free Fibre Analysis (%)	Total Asbestos (%)
98712	0.50 - 1.00	WS01	Brown soil with stones, brick, clinker, wood	No asbestos detected	n/t	n/t	n/t	n/t
98718	0.00 - 1.20	WS03	Brown soil with stones, brick, clinker	No asbestos detected	n/t	n/t	n/t	n/t
98721	0.50 - 0.80	WS04	Brown soil with stones, glass, clinker	No asbestos detected	n/t	n/t	n/t	n/t
98724	0.30 - 0.70	WS06	Brown soil with slate and concrete	No asbestos detected	n/t	n/t	n/t	n/t
98727	0.50 - 0.70	WS07	Black sandy soil with stones and glass	No asbestos detected	n/t	n/t	n/t	n/t
98734	0.30 - 0.60	WS05	Brown soil with stones, brick, clinker, wood	No asbestos detected	n/t	n/t	n/t	n/t

Method Summary

Report No.: 17-11961

Parameter	Codes	Analysis Undertaken On	Date Tested	Method Number	Technique
Soil					
Hexavalent chromium	N	As submitted sample	09/05/2017	110	Colorimetry
pH	M	Air dried sample	10/05/2017	113	Electromeric
Total Petroleum Hydrocarbons in solids	M	As submitted sample	09/05/2017	117	GC-FID
Aqua regia extractable metals	M	Air dried sample	10/05/2017	118	ICPMS
Phenols in solids	M	As submitted sample	09/05/2017	121	HPLC
PAH (GC-FID)	M	As submitted sample	09/05/2017	133	GC-FID
SVOC in solids	N	As submitted sample	09/05/2017	167	GC-MS
Water soluble anions	M	Air dried sample	10/05/2017	172	Ion Chromatography
BTEX in solids	M	As submitted sample	16/05/2017	181A	GC-MS
Water soluble boron	N	Air dried sample	09/05/2017	202	Colorimetry
Total organic carbon/Total sulphur	N	Air dried sample	11/05/2017	210	IR
Aliphatic hydrocarbons in soil	N	As submitted sample	16/05/2017	214	GC-FID
Aliphatic/Aromatic hydrocarbons in soil	N	As submitted sample	18/05/2017	214	GC-FID
Aromatic hydrocarbons in soil	N	As submitted sample	16/05/2017	214	GC-FID
Low range Aliphatic hydrocarbons soil	N	As submitted sample	16/05/2017	214	GC-MS
Low range Aromatic hydrocarbons soil	N	As submitted sample	16/05/2017	214	GC-MS
Asbestos identification	U	As submitted sample	09/05/2017	PMAN	Microscopy

Tests marked N are not UKAS accredited

Report Information

Report No.: 17-11961

Key

U	hold UKAS accreditation
M	hold MCERTS and UKAS accreditation
N	do not currently hold UKAS accreditation
^	MCERTS accreditation not applicable for sample matrix
*	UKAS accreditation not applicable for sample matrix
S	Subcontracted to approved laboratory UKAS Accredited for the test
SM	Subcontracted to approved laboratory MCERTS/UKAS Accredited for the test
I/S	Insufficient Sample
U/S	Unsuitable sample
n/t	Not tested
<	means "less than"
>	means "greater than"

Soil sample results are expressed on an air dried basis (dried at < 30°C)

Comments or interpretations are beyond the scope of UKAS accreditation

The results relate only to the items tested

PCB congener results may include any coeluting PCBs

Uncertainty of measurement for the determinands tested are available upon request

Deviation Codes

-
- | | |
|---|--|
| a | No date of sampling supplied |
| b | No time of sampling supplied (Waters Only) |
| c | Sample not received in appropriate containers |
| d | Sample not received in cooled condition |
| e | The container has been incorrectly filled |
| f | Sample age exceeds stability time (sampling to receipt) |
| g | Sample age exceeds stability time (sampling to analysis) |

Where a sample has a deviation code, the applicable test result may be invalid.

Sample Retention and Disposal

All soil samples will be retained for a period of one month

All water samples will be retained for 7 days following the date of the test report

Charges may apply to extended sample storage

Appendix F – Monitoring Results

Gas Monitoring Records



Job details:
Client: EcoNRG
Site: Ashton Old Road
Date: 11/05/2017

Job No: ASH1867
Visit No: 1 of 6
Operator: RC
Project Manager: RC

	Volatiles	Flow Data				Gas Concentrations												Well and Water Data							
Monitoring Point	PID Peak (ppm)	Flow rate (l/hr)		Differential borehole Pressure (Pa)	Time for flow to equalise (sec)	Methane (%v/v)		%LEL		Carbon dioxide (%v/v)		Carbon monoxide (ppmv)		Hydrogen sulphide (ppmv)		Oxygen (%v/v)		Run time (min)	Product thickness (mm)	Water level (mbgl)	Depth of well (m)	Reduced level (mAOD)	Water level (mAOD)	Response zone range (m)	Comments
		Peak	Steady			Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady								
WS01	<0.1	0.6	<0.1	1	5	0.1	<0.1	1	<0.1	1.1	1	<0.1	<0.1	1	<0.1	19.3	19.3	4	ND	3.17	3.18				30cm of pipe above ground level.
WS03	3.3	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	3	2.3	<0.1	<0.1	1.1	<0.1	12.6	16	5	ND	3.05	3.08				51cm od pipe above ground level
WS07	1.5	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	1	1	20.6	20.8	4	ND	3.09	3.10				30cm of pipe above ground level.
Max	3.3	0.6	0.0	1		0.1	0.0	1.0	0.0	3.0	2.3	0	0	1.1	1	20.6	20.8		0.0	3.17	3.18	0.00	0.00		
Min	1.5	0.6	0.0	0		0.1	0.0	1.0	0.0	1.1	1.0	0	0	1	1	12.6	16.0		0.0	3.05	3.08	0.00	0.00		

ND - Not detected
NR - Not recorded

METEOROLOGICAL AND SITE INFORMATION: (Put X in front of selected or enter data as applicable)

State of ground:	Dry	Moist	Wet	Snow	Frozen
Wind:	Calm	Light	Moderate	Strong	
Cloud cover:	None	Slight	Cloudy	Overcast	
Precipitation:	None	Slight	Moderate	Heavy	
Time monitoring performed:	Start	11:30	End	12:15	
Barometric pressure (mbar):	Start	990	End	985	
Pressure trend:	Falling	Steady	Rising		
Air temperature (degree C):	Before	17	After	18	

INSTRUMENTATION TECHNICAL SPECIFICATIONS:

Ground gas meter:	GAS DATA LMS xi	Serial No: 5071			
Gas range:	CH4: 0 - 100%	CO2: 0 - 100%	O2: 0 -25%		
Gas flow range:	+30/-10 l/hr				
Differential pressure:	+300/-30 Pa				
Date of last calibration:	09/02/2017				
Date of next calibration:	Jan-18				

PID:	MniRae Lite	Serial No: 595-001381
Calibrated range:	0-99 ppm	
Calibration gas:	Isobutylene	
Response time:	2 seconds	
Accuracy:	0.1 ppm	
Date of last calibration:	Jul-16	
Date of next calibration:	Jul-17	

Gas Monitoring Records



Job details:
Client: EcoNRG
Site: Ashton Old Road
Date: 19/05/2017

Job No: ASH1867
Visit No: 2 of 6
Operator: H.Rutter
Project Manager: RC

	Volatiles	Flow Data				Gas Concentrations												Well and Water Data							
Monitoring Point	PID Peak (ppm)	Flow rate (l/hr)		Differential borehole Pressure (Pa)	Time for flow to equalise (sec)	Methane (%v/v)		%LEL		Carbon dioxide (%v/v)		Carbon monoxide (ppmv)		Hydrogen sulphide (ppmv)		Oxygen (%v/v)		Run time (min)	Product thickness (mm)	Water level (mbgl)	Depth of well (m)	Reduced level (mAOD)	Water level (mAOD)	Response zone range (m)	Comments
		Peak	Steady			Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady								
WS01	0.3	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	1.6	1.6	<0.1	<0.1	<0.1	<0.1	14.3	14.3	4	ND	3.04	3.13				
WS03	0.2	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	2.5	2.5	<0.1	<0.1	<0.1	<0.1	16.4	16.4	4	ND	3.06	3.12				
WS07	0.1	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	20	20	4	ND	3.03	3.04				
Max	0.3	0.0	0.0	0		0.0	0.0	0.0	0.0	2.5	2.5	0	0	0	0	20.0	20.0		0.0	3.06	3.13	0.00	0.00		
Min	0.1	0.0	0.0	0		0.0	0.0	0.0	0.0	1.6	1.6	0	0	0	0	14.3	14.3		0.0	3.03	3.04	0.00	0.00		

ND - Not detected
NR - Not recorded

METEOROLOGICAL AND SITE INFORMATION: (Put X in front of selected or enter data as applicable)

State of ground:	Dry	Moist	Wet	Snow	Frozen
Wind:	Calm	Light	Moderate	Strong	
Cloud cover:	None	Slight	Cloudy	Overcast	
Precipitation:	None	Slight	Moderate	Heavy	
Time monitoring performed:	Start	14:42	End	12:58	
Barometric pressure (mbar):	Start	1004	End	1004	
Pressure trend:	Falling	Steady	Rising		
Air temperature (degree C):	Before	17	After	17	

INSTRUMENTATION TECHNICAL SPECIFICATIONS:

Ground gas meter:	Gasdata GFM 430	Serial No: 10356			
Gas range:	CH4: 0 - 100%	CO2: 0 - 100%	O2: 0 -25%		
Gas flow range:	+30/-10 l/hr				
Differential pressure:	+300/-30 Pa				
Date of last calibration:	26/04/2017				
Date of next calibration:	Apr-18				

PID:	PhoCheck Tiger	Serial No: 107622
Calibrated range:	0-99 ppm	
Calibration gas:	Isobutylene	
Response time:	2 seconds	
Accuracy:	0.1 ppm	
Date of last calibration:	10/11/2016	
Date of next calibration:	Nov-17	

Gas Monitoring Records



Job details:
Client: EcoNRG
Site: Ashton Old Road
Date: 26/05/2017

Job No: ASH1867
Visit No: 3 of 6
Operator: J. Dyer
Project Manager: RC

	Volatiles	Flow Data				Gas Concentrations												Well and Water Data							
Monitoring Point	PID Peak (ppm)	Flow rate (l/hr)		Differential borehole Pressure (Pa)	Time for flow to equalise (sec)	Methane (%v/v)		%LEL		Carbon dioxide (%v/v)		Carbon monoxide (ppmv)		Hydrogen sulphide (ppmv)		Oxygen (%v/v)		Run time (min)	Product thickness (mm)	Water level (mbgl)	Depth of well (m)	Reduced level (mAOD)	Water level (mAOD)	Response zone range (m)	Comments
		Peak	Steady			Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady								
WS01	0.5	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	1.1	1.1	<0.1	<0.1	<0.1	<0.1	20.1	20.1	4	NR	ND	3.10				
WS03	0.7	0.2	<0.1	0	10	<0.1	<0.1	<0.1	<0.1	2.4	2.3	<0.1	<0.1	<0.1	<0.1	14.4	14.4	4	NR	ND	3.11				
WS07	0.5	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	0.3	0.3	<0.1	<0.1	<0.1	<0.1	18.9	18.9	4	NR	ND	3.07				
Max	0.7	0.2	0.0	0		0.0	0.0	0.0	0.0	2.4	2.3	0	0	0	0	20.1	20.1		0.0	0.00	3.11	0.00	0.00		
Min	0.5	0.2	0.0	0		0.0	0.0	0.0	0.0	0.3	0.3	0	0	0	0	14.4	14.4		0.0	0.00	3.07	0.00	0.00		

ND - Not detected
NR - Not recorded

METEOROLOGICAL AND SITE INFORMATION: (Put X in front of selected or enter data as applicable)

State of ground:	Dry	Moist	Wet	Snow	Frozen
Wind:	Calm	Light	Moderate	Strong	
Cloud cover:	None	Slight	Cloudy	Overcast	
Precipitation:	None	Slight	Moderate	Heavy	
Time monitoring performed:	Start		End		
Barometric pressure (mbar):	Start	1010	End	1010	
Pressure trend:	Falling	Steady	Rising		
Air temperature (degree C):	Before	28	After	28	

INSTRUMENTATION TECHNICAL SPECIFICATIONS:

Ground gas meter:	Gasdata GFM 430	Serial No: 10356			
Gas range:	CH4: 0 - 100%	CO2: 0 - 100%	O2: 0 -25%		
Gas flow range:	+30/-10 l/hr				
Differential pressure:	+300/-30 Pa				
Date of last calibration:	26/04/2017				
Date of next calibration:	Apr-18				

PID:	PhoCheck Tiger	Serial No: 107622
Calibrated range:	0-99 ppm	
Calibration gas:	Isobutylene	
Response time:	2 seconds	
Accuracy:	0.1 ppm	
Date of last calibration:	10/11/2016	
Date of next calibration:	Nov-17	

Gas Monitoring Records



Job details:
Client: EcoNRG
Site: Ashton Old Road
Date: 02/06/2017

Job No: ASH1867
Visit No: 4 of 6
Operator: W. Perry
Project Manager: RC

	Volatiles	Flow Data				Gas Concentrations												Well and Water Data							
Monitoring Point	PID Peak (ppm)	Flow rate (l/hr)		Differential borehole Pressure (Pa)	Time for flow to equalise (sec)	Methane (%v/v)		%LEL		Carbon dioxide (%v/v)		Carbon monoxide (ppmv)		Hydrogen sulphide (ppmv)		Oxygen (%v/v)		Run time (min)	Product thickness (mm)	Water level (mbgl)	Depth of well (m)	Reduced level (mAOD)	Water level (mAOD)	Response zone range (m)	Comments
		Peak	Steady			Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady								
WS01	0.2	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	2.1	2.1	<0.1	<0.1	<0.1	<0.1	16.4	16.4	4	NR	ND	3.10				
WS03	0.3	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	1.9	1.9	<0.1	<0.1	<0.1	<0.1	17.5	17.5	4	NR	ND	3.11				
WS07	0.5	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	0.6	0.6	<0.1	<0.1	<0.1	<0.1	19.4	19.4	4	NR	ND	3.07				
Max	0.5	0.0	0.0	0		0.0	0.0	0.0	0.0	2.1	2.1	0	0	0	0	19.4	19.4		0.0	0.00	3.11	0.00	0.00		
Min	0.2	0.0	0.0	0		0.0	0.0	0.0	0.0	0.6	0.6	0	0	0	0	16.4	16.4		0.0	0.00	3.07	0.00	0.00		

ND - Not detected
NR - Not recorded

METEOROLOGICAL AND SITE INFORMATION: (Put X in front of selected or enter data as applicable)

State of ground:	Dry	Moist	Wet	Snow	Frozen
Wind:	Calm	Light	Moderate	Strong	
Cloud cover:	None	Slight	Cloudy	Overcast	
Precipitation:	None	Slight	Moderate	Heavy	
Time monitoring performed:	Start	11:05	End	11:20	
Barometric pressure (mbar):	Start	1008	End	1008	
Pressure trend:	Falling	Steady	Rising		
Air temperature (degree C):	Before	15	After	15	

INSTRUMENTATION TECHNICAL SPECIFICATIONS:

Ground gas meter:	Gasdata GFM 430	Serial No: 10356			
Gas range:	CH4: 0 - 100%	CO2: 0 - 100%	O2: 0 -25%		
Gas flow range:	+30/-10 l/hr				
Differential pressure:	+300/-30 Pa				
Date of last calibration:	26/04/2017				
Date of next calibration:	Apr-18				

PID:	PhoCheck Tiger	Serial No: 107622
Calibrated range:	0-99 ppm	
Calibration gas:	Isobutylene	
Response time:	2 seconds	
Accuracy:	0.1 ppm	
Date of last calibration:	10/11/2016	
Date of next calibration:	Nov-17	

Gas Monitoring Records



Job details:
Client: EcoNRG
Site: Ashton Old Road
Date: 09/06/2017

Job No: ASH1867
Visit No: 5 of 6
Operator: J. Dyer, K. Latka
Project Manager: RC

	Volatiles	Flow Data				Gas Concentrations												Well and Water Data							
Monitoring Point	PID Peak (ppm)	Flow rate (l/hr)		Differential borehole Pressure (Pa)	Time for flow to equalise (sec)	Methane (%v/v)		%LEL		Carbon dioxide (%v/v)		Carbon monoxide (ppmv)		Hydrogen sulphide (ppmv)		Oxygen (%v/v)		Run time (min)	Product thickness (mm)	Water level (mbgl)	Depth of well (m)	Reduced level (mAOD)	Water level (mAOD)	Response zone range (m)	Comments
		Peak	Steady			Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady								
WS01	0.3	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	20.7	20.7	4	NR	2.16	3.10				
WS03	0.2	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	0.9	0.9	<0.1	<0.1	<0.1	<0.1	19.2	19.2	4	NR	ND	3.11				
WS07	0.3	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	20.6	20.6	4	NR	ND	3.07				
																									Standing water in centre of ste.
Max	0.3	0.0	0.0	0		0.0	0.0	0.0	0.0	0.9	0.9	0	0	0	0	20.7	20.7		0.0	2.16	3.11	0.00	0.00		
Min	0.2	0.0	0.0	0		0.0	0.0	0.0	0.0	0.9	0.9	0	0	0	0	19.2	19.2		0.0	2.16	3.07	0.00	0.00		

ND - Not detected
NR - Not recorded

METEOROLOGICAL AND SITE INFORMATION: (Put X in front of selected or enter data as applicable)

State of ground:	Dry	Moist	Wet	Snow	Frozen
Wind:	Calm	Light	Moderate	Strong	
Cloud cover:	None	Slight	Cloudy	Overcast	
Precipitation:	None	Slight	Moderate	Heavy	
Time monitoring performed:	Start	14:30	End	14:52	
Barometric pressure (mbar):	Start	1001	End	1000	
Pressure trend:	Falling	Steady	Rising		
Air temperature (degree C):	Before	18	After	18	

INSTRUMENTATION TECHNICAL SPECIFICATIONS:

Ground gas meter:	Gasdata GFM 430	Serial No: 10356			
Gas range:	CH4: 0 - 100%	CO2: 0 - 100%	O2: 0 -25%		
Gas flow range:	+30/-10 l/hr				
Differential pressure:	+300/-30 Pa				
Date of last calibration:	26/04/2017				
Date of next calibration:	Apr-18				

PID:	PhoCheck Tiger	Serial No: 109691
Calibrated range:	0-99 ppm	
Calibration gas:	Isobutylene	
Response time:	2 seconds	
Accuracy:	0.1 ppm	
Date of last calibration:	10/11/2016	
Date of next calibration:	Nov-17	

Gas Monitoring Records



Job details:
Client: EcoNRG
Site: Ashton Old Road
Date: 16/06/2017

Job No: ASH1867
Visit No: 6 of 6
Operator: K. Latka
Project Manager: RC

	Volatiles	Flow Data				Gas Concentrations												Well and Water Data							
Monitoring Point	PID Peak (ppm)	Flow rate (l/hr)		Differential borehole Pressure (Pa)	Time for flow to equalise (sec)	Methane (%v/v)		%LEL		Carbon dioxide (%v/v)		Carbon monoxide (ppmv)		Hydrogen sulphide (ppmv)		Oxygen (%v/v)		Run time (min)	Product thickness (mm)	Water level (mbgl)	Depth of well (m)	Reduced level (mAOD)	Water level (mAOD)	Response zone range (m)	Comments
		Peak	Steady			Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Peak	Steady	Min.	Steady								
WS01	0.2	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	3.5	3.5	<0.1	<0.1	<0.1	<0.1	14.9	14.9	4	NR	ND	3.10				
WS03	0.2	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	0.9	0.9	<0.1	<0.1	<0.1	<0.1	19.5	19.5	4	NR	ND	3.11				
WS07	0.3	<0.1	<0.1	0	-	<0.1	<0.1	<0.1	<0.1	2.6	2.6	<0.1	<0.1	<0.1	<0.1	11.2	11.2	4	NR	ND	3.07				
Max	0.3	0.0	0.0	0		0.0	0.0	0.0	0.0	3.5	3.5	0	0	0	0	19.5	19.5		0.0	0.00	3.11	0.00	0.00		
Min	0.2	0.0	0.0	0		0.0	0.0	0.0	0.0	0.9	0.9	0	0	0	0	11.2	11.2		0.0	0.00	3.07	0.00	0.00		

ND - Not detected
NR - Not recorded

METEOROLOGICAL AND SITE INFORMATION: (Put X in front of selected or enter data as applicable)

State of ground:	Dry	Moist	Wet	Snow	Frozen
Wind:	Calm	Light	Moderate	Strong	
Cloud cover:	None	Slight	Cloudy	Overcast	
Precipitation:	None	Slight	Moderate	Heavy	
Time monitoring performed:	Start	11:40	End	12:09	
Barometric pressure (mbar):	Start	1016	End	1016	
Pressure trend:	Falling	Steady	Rising		
Air temperature (degree C):	Before	22	After	22	


INSTRUMENTATION TECHNICAL SPECIFICATIONS:

Ground gas meter:	Gasdata GFM 430	Serial No: 10356			
Gas range:	CH4: 0 - 100%	CO2: 0 - 100%	O2: 0 -25%		
Gas flow range:	+30/-10 l/hr				
Differential pressure:	+300/-30 Pa				
Date of last calibration:	26/04/2017				
Date of next calibration:	Apr-18				

PID:	PhoCheck Tiger	Serial No: 107622
Calibrated range:	0-99 ppm	
Calibration gas:	Isobutylene	
Response time:	2 seconds	
Accuracy:	0.1 ppm	
Date of last calibration:	10/11/2016	
Date of next calibration:	Nov-17	

TEST DATE AND CONDITIONS	
Date	09/02/2017
Atmospheric Pressure	1011 mB
Ambient Temp	21.4 °C
EnviroNics Serial No.	n/a

GAS DATA LTD



Pegasus House
Seven Stars Estate
Wheler Rd.
Coventry
CV3 4LB

Tel: 024 76 303311

Fax: 024 76 307711

LMS FINAL INSPECTION & CALIBRATION CERTIFICATE

INSTRUMENT DETAILS		
Serial No	5071	CUSTOMER
S/W Version	G3.18v-LTBX	T & P Regeneration

INSTRUMENT CHECKS			
Keyboard	✓	Clock Set / Running	✓
Pump In/Out	✓	Labels Fitted	✓
Display Contrast	✓	Recalibration Due	09/02/2018

GASES					
CH4		CO2		O2	
Test %	Reading %	Test %	Reading %	Test %	Reading
0 accept <= 0.1	0	0 accept <= 0.1	0	0 accept <= 0.1	0.1
6.8 accept 6.6-7.0	6.8	3.7 accept 3.5-3.9	3.6	21 accept 20.5-21.2	20.9
52 accept 50.0-54.0	53	42.0 accept 39.0-45.0	40		

PRESSURES			
Absolute/Relative		Differential	
Atmos accept current +/-1	1011	0.0	x
Atmos + 50 mbar accept current +48- +52	1062	+30 mbar accept 29.5- 30.5	x
Atmos - 50 mbar accept current -48-- 52	961	-30 mbar accept -29.5-- 30.5	x

TEMPERATURE	
Applied °C	Reading °C
0 accept -0.1-+0.1	0
25 accept 24.5-25.5	25
40 accept 37.5-40.5	40.3

OPTIONS					
Borehole Flow (see other Side)	✓	LEL	✓	Temp Probe (see above)	x
Extraction Flow	x			Toxic Gasses (see other Side)	✓

PACKING						
Charger	UK ✓	US	Euro	Sample Pipe	Standard	Flow ✓
Manual		x		Serial Cable		x
Leather Bag		✓		Software		x
Strap		✓		Cal Certificate		✓

TEST DATE AND CONDITIONS	
Date	09/02/2017
Atmospheric Pressure	1011 mB
Ambient Temp	21.4 °C
Envionics Serial No.	n/a

GAS DATA LTD



Pegasus House
Seven Stars Estate
Wheler Rd.
Coventry
CV3 4LB

Tel: 024 76 303311

Fax: 024 76 307711

LMS FINAL INSPECTION & CALIBRATION CERTIFICATE (OPTIONS)

Toxic Gasses			
Gas Type	Range	Tested @	Reading
H2S	200ppm	200ppm	200ppm
CO	1000ppm	400ppm	401ppm

Cross Gas Effects					
Applied gas		Readings			
Type	Concentration	Toxic 1: H2S	Toxic 2: CO	Toxic 3:	Toxic 4:
H2S	200ppm	200ppm	1.7ppm		
CO	400ppm	7.0ppm	401ppm		

Flow Tests - Low Range Option					
Target Flow	-5 L/Hr	0 L/Hr	5 L/Hr	10 L/Hr	20 L/Hr
Applied	-5	0.0	5	10	20
Flow Reading	-5.1 accept applied +/- 0.5	0.0 accept applied +/- 0.0	5 accept applied +/-0.5	10 accept applied +/-0.7	20 accept applied +/-3.0
dp Applied (Pa)	-13	0.0	13	30	76
dp Reading (Pa)	-13 accept applied +/-5	0.0 accept applied +/-0.0	13 accept applied +/-5	30 accept applied +/-10	76 accept applied +/-20
Flow Tests - High Range Option					
Target Flow	-30 L/Hr	0 L/Hr	30 L/Hr	60 L/Hr	120 L/Hr
Applied	-30	0.0	30	60	120
Flow Reading	x accept applied +/-3.0	0.0 accept applied +/-0.0	x accept applied +/-3.0	x accept applied +/-4.0	x accept applied +/-15
dp Applied (Pa)	x	0.0	x	x	x
dp Reading (Pa)	x accept applied +/-15	0.0 accept applied +/-0.0	x accept applied +/-15	x accept applied +/-50	x accept applied +/-200

Tested

Approved



VAN WALT
Monitoring your needs

Outwards Sales Checklist

PID Lite Checklist and Calibration

Serial Number 595-001381
Sales Customer & Company T&P Regeneration Ltd

	Reading	Target	Acceptable	Pass
100ppm Isobutylene gas	100.1	100	$\pm 10\%$ *	✓
Fresh Air	0.1	0.0	$\pm 10\%$ *	✓

This PID was calibrated to manufacturers standards and was within acceptable range on the day of calibration. The MiniRAE Lite can keep calibration for up to 30 days. If measurements become unstable re-calibrate the PID using the Isobutylene gas provided. * On bump test after calibration

Maintenance Checks

Comments

- ☒ PID Turns on/off
- ☒ Internal pump functioning
- ☒ PAT test date on charger
- ☒ Pump stall test

Checklist

Comments

- ☒ MiniRAE Lite
- ☒ Screwdriver & Allen key
- ☒ Cleaning kit
- ☒ Serial PC lead
- ☒ Charging Adaptor x 4
- ☒ Alkaline Battery Pack
- ☒ Manual and Quick Start Guide
- ☒ Use of PID Information sheet
- ☒ Hard Case / Soft Case
- ☒ Water Trap
- ☒ Tamper sticker intact

Signed: [Signature] Name: Tom Basset Date: 12/7/16



Calibration Certificate and Quality Control Checklist

Production Order Number: 13322045 **Sales Order Number:** 12304819 / 10
Customer Number: 1128205 **Customer:** Van Walt Limited
Part Number: 059-A126-000
Unit Type: MiniRAE Lite059-A126-000
Serial Number: 595-001381
Comment:

GAS	SPAN	CYLINDER LOT
C4H8	100 ppm	1904136

Final Inspection:

Does the unit power on? YES
Do sensor types match configuration? YES
Any error message after power on? NO

QC Stamp:



Calibration Date: 09/06/2016

TEST DATE AND CONDITIONS	
Date	26/04/2017
Atmospheric Pressure	1002 mB
Ambient Temp	22.4 °C
Envionics Serial No.	n/a
Gas Cylinder Certification No.	53484/5016

GAS DATA LTD

Pegasus House
Seven Stars Estate
Wheler Rd
Coventry
CV3 4LB
Tel 02476303311 Fax 02476307711



GFM430-1 / 2 FINAL INSPECTION & CALIBRATION CHECK CERTIFICATE

PRESSURE CHECKS							
Calibration Pressure		Instrument Pressure Channels Read					
Pressure @	Applied Pressure	Atmospheric [Ap] (mB)	tol. (mB)	Static [Sp] (mB)	tol. (mB)		
All ports	current atmospheric	1002	+/-2.0	0.0	0.0		
Ap port (internal)	+800mB(a)	799	+/-5.0	0.0	0.0		
	+1200mB(a)	1200	+/-5.0	0.0	0.0		
Gas IN Port	+50mB(g)			0.0	+/-2.0		
	-100mB(g)			0.0	+/-2.0		

FLOW CHECKS					
Calibration Flow		Instrument Flow Channels Read			
Applied Flow	Applied Pressure (Pa)	Flow [Flow] (l/hour)	tol. (l/hour)	Differential Pressure [Dp] (Pa)	tol. (Pa)
-30.0 l/hour	-195	-28.5	+/-3.0	-185	+/-50
-3.0 l/hour	-15	-2.6	+/-1.0	-13	+/-6
0.0 l/hour	0.0	0.0	0.0	0.0	+/-0.5
+3.0 l/hour	17	2.8	+/-0.5	16	+/-3
+30.0 l/hour	284	28.6	+/-3.0	272	+/-50
+60.0 l/hour	800	57.9	+/-6.0	768	+/-130
+90.0 l/hour	1514	87.1	+/-9.0	1460	+/-250

TEMPERATURE CHECK		
Calibration Temperature	Instrument Temperature Channel Read	
Applied Equivalent Temperature	Temperature [Temp] (°C)	tol. (°C)
-10.0 °C	-10.0	+/- 2.0
0.0 °C	0.0	+/- 1.0
30.0 °C	30.0	+/- 1.0
60.0 °C	60.0	+/- 1.0
100.0 °C	100.0	+/- 1.0

TEST DATE AND CONDITIONS	
Date	26.4.17
Atmospheric Pressure	1002 mB
Ambient Temp	22.4 °C
EnviroNics Serial No.	N/A

GAS DATA LTD

Pegasus House
Seven Stars Estate
Wheler Rd
Coventry
CV3 4LB
Tel 02476303311 Fax 02476307711



GFM430 -1 OUTWARD INSPECTION & QUALITY CHECK SHEET

INSTRUMENT DETAILS			
SO Number	Instrument Type	Instrument Serial Number + SW Version	Job Number(s)
316823	GFM 430	10356 - G430-00.0024/0013	10356 030417

Calibration Technician

Date 26.4.17

Inspection Technician

Date 28.4.17

INSTRUMENT CHECKS		Pass (P), Fail (F) or not applicable (NA)	INSTRUMENT PACKING LIST		Tick if included
Function Tests	Dust Caps Fitted	P	Instrument		✓
	Keyboard Test (All Keys)	P	Leather Case		✓
	Backlight	P	Instrument Strap		✓
	Clock Set / Running	P	AC Battery Charger (UK)		
	Comms Test	P	AC Battery Charger (EURO)		N/A
	Pump Flow Test (In & Out)	P	AC Battery Charger (US)		N/A
	Overall Leak Test (30mB)	P	AC Battery Charger (AUS)		N/A
	Battery Charge Test	P	Gas Sample Pipe		✓
	Service Date set to?	26.4.18	Carry Case		✓
Channel Test	Data Logging Enabled?	P	Spares Pot		✓
	Verify CH4/LEL	P	Allen Key		✓
	Verify CO2	P	Flow Sample Pipe		✓
	Verify O2	P	Temperature Probe		✓
	Verify LEL	P	Vane Anemometer		✓
	Verify 1 st Option Gas H2S	P	USB Cable		✓
	Verify 2 nd Option Gas CO	P	USB Memory stick		✓
	Verify 3 rd Option Gas	N/A	SiteMan Software Ver 4.1.5		✓
	Verify 4 th Option Gas	N/A	Internal Filter Pack Qty		✓
	Verify Atmospheric pressure	P	External Filter Pack Qty		✓
	Verify static pressure	P	Field Guide		✓
	Verify differential pressure	P	Operation Manual (hard copy)		✓
	Verify flow	P	Extra Items:		
	Verify temperature probe input	P			
	Verify vane anemometer input	P			
DataBase Checks	Jobcard(s) completed and signed	P	Comments:		
	Jobcard(s) booked off database	P			
	Calibration certificate completed	P			
	Complete & print QI record	N/A			
Label Checks	No. of Calibration label fitted	4008075			
	Warranty label fitted	N/A			
	H2S Range from Sales Order	5000 ppm			
	H2S Range from Cal Cert	5000 ppm			
	Over-range value correct?	P			

CALIBRATION CERTIFICATE NO: 59175

ISSUED BY: SHAWCITY LIMITED
DATE: 10th November 2016

APPROVED SIGNATORY:



NAME: Frank Izzo

CUSTOMER: Ground-Gas Solutions Ltd
INSTRUMENT: Phocheck Tiger
SERIAL NUMBER: T-107622CALIBRATION METHOD: CM03
AMBIENT CONDITIONS: 20°C $\pm$ 2°C and 50% ($\pm$ 20%) RH

Prior to calibration the instrument was allowed to stabilise in the laboratory for at least 30 minutes.
The instrument was calibrated by exposing the sensor to known values of gas concentrations.
All gases were sampled through the complete probe and in line filter, where applicable.
The reference value is that generated by the certified source and the indicated value is that measured by the instrument.

CALIBRATION RESULTS


GAS	LOT No	REF. VALUE	INDICATED VALUE
Isobutylene	508632	100 ppm	100 ppm
Isobutylene	S110103	1000 ppm	1000 ppm

COMMENTS:

The reported uncertainty is based on a standard uncertainty multiplied by a coverage factor of $k=2$.
This provides a level of confidence of uncertainty of approximately 95%.
The uncertainty of measurement is $\pm 2\%$
The results indicate that the instrument conforms to the applicable parts of the published specification.

HEALTH & SAFETY, OCCUPATIONAL HYGIENE AND ENVIRONMENTAL MONITORING INSTRUMENTS

Tel: 01793 780622
www.shawcity.co.ukInstrument House, 91-92 Shrivenham Hundred Business Park
Watchfield, Oxfordshire, SN6 8TYFax: 01793 784466
service@shawcity.co.uk



service@shawcity.co.uk

JOB NUMBER: 59175
INSTRUMENT: Phocheck Tiger

FIRMWARE: 4.33
UPGRADED TO: n/a

[illegible]

SIGNED:

Frucht

DATE: 10th November 2016

CALIBRATION CERTIFICATE NO: 59195

ISSUED BY: SHAWCITY LIMITED
DATE: 10th November 2016

APPROVED SIGNATORY: 

NAME: Frank Izzo

CUSTOMER: Ground-Gas Solutions Ltd
INSTRUMENT: Phocheck Tiger
SERIAL NUMBER: T-109691

CALIBRATION METHOD: CM03
AMBIENT CONDITIONS: 20°C ± 2°C and 50% (± 20%) RH

Prior to calibration the instrument was allowed to stabilise in the laboratory for at least 30 minutes.
The instrument was calibrated by exposing the sensor to known values of gas concentrations.
All gases were sampled through the complete probe and in line filter, where applicable.
The reference value is that generated by the certified source and the indicated value is that measured by the instrument.

CALIBRATION RESULTS

GAS	LOT No	REF. VALUE	INDICATED VALUE
Isobutylene	508632	100 ppm	100 ppm
Isobutylene	S110103	1000 ppm	1000 ppm

COMMENTS:

The reported uncertainty is based on a standard uncertainty multiplied by a coverage factor of $k=2$.
This provides a level of confidence of uncertainty of approximately 95%.
The uncertainty of measurement is ±2 %
The results indicate that the instrument conforms to the applicable parts of the published specification.

HEALTH & SAFETY, OCCUPATIONAL HYGIENE AND ENVIRONMENTAL MONITORING INSTRUMENTS

Tel: 01793 780622
www.shawcity.co.uk

Instrument House, 91-92 Shrivenham Hundred Business Park
Watchfield, Oxfordshire, SN6 8TY

Fax: 01793 784466
service@shawcity.co.uk



JOB NUMBER: 59195
INSTRUMENT: Phocheck Tiger

SERIAL NUMBER: T-109691
DATE RECEIVED: 04/11/2016

FIRMWARE: 4.33
UPGRADED TO: n/a

CUSTOMER: Ground-Gas Solutions Ltd

SIGNED:

TESTS	AS REC'D	AFTER REPAIR
Charging Test	√	
Battery Test	√	
Lamp Test	√	
Air Flow Test	X	√
Switch Test	√	
Moisture Sensitivity	√	
Sensor Test	√	
Alarm Test	√	
PC Comms Test	√	
Datalog Test	n/a	
Display Test	√	
Physical Inspection	X	√
PAT Test	expired	√
Firmware Upgrade	n/a	
Software Upgrade (usb)	√	
Function Test	√	

Pump suction poor and does not stall.
Inlet filter, PID sensor stack, worn sensor seal, probe and nozzle O-rings replaced.
PAT test carried out on charger.
Instrument service, testing, repair and calibration carried out.


TECHNICIAN: Frank Izzo

Fruch.

DATE: 10th November 2016

Appendix G – HazWaste Printout

Waste Classification Report



WBEHJ-48LT7-6JU2Z

Job name

Ashton Old Road

Description/Comments

Project

ASH1867

Site

Waste Stream Template

T&P Waste Stream

Classified by

Name:

Samuel Butcher

Date:

30/06/2017 13:45:07 UTC

Telephone:

01179 277 756

Company:

T&P Regeneration Ltd
Unit 4
Brunel Lock Development, Smeaton Road
Bristol
BS1 6SE

Report

Created by: Samuel Butcher

Created date: 30/06/2017 13:45 UTC

Job summary

#	Sample Name	Depth [m]	Classification Result	Hazard properties	Page
1	WS02	1.00 - 1.20	Hazardous	HP 3(i), HP 7, HP 11	2
2	WS02[1]	1.50 - 1.80	Non Hazardous		5
3	WS03	0.00 - 1.20	Hazardous	HP 14	6
4	WS04	0.50 - 0.80	Hazardous	HP 3(i), HP 7, HP 10, HP 11, HP 14	8
5	WS04[1]	1.50 - 1.70	Non Hazardous		11
6	WS06	0.30 - 0.70	Non Hazardous		13
7	WS07	0.50 - 0.70	Non Hazardous		15
8	WS07[1]	0.70 - 1.00	Non Hazardous		17
9	SS01	0.00 - 0.30	Hazardous	HP 3(i), HP 7, HP 11, HP 14	19
10	WS05	0.30 - 0.60	Non Hazardous		22

Appendices

Appendix A: Classifier defined and non CLP determinands

Appendix B: Rationale for selection of metal species

Appendix C: Version

Page

24

25

26

Classification of sample: WS02

 **Hazardous Waste**
Classified as **17 05 03 ***
in the List of Waste

Sample details

Sample Name:	LoW Code:
WS02	Chapter:
Sample Depth:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
1.00 - 1.20 m	Entry:
	17 05 03 * (Soil and stones containing hazardous substances)

Hazard properties

HP 7: Carcinogenic "waste which induces cancer or increases its incidence"

Hazard Statements hit:

Carc. 1B; H350 "May cause cancer [state route of exposure if it is conclusively proven that no other routes of exposure cause the hazard]."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 0.161%)

HP 11: Mutagenic "waste which may cause a mutation, that is a permanent change in the amount or structure of the genetic material in a cell"

Hazard Statements hit:

Muta. 1B; H340 "May cause genetic defects [state route of exposure if it is conclusively proven that no other routes of exposure cause the hazard]."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 0.161%)

Hazard properties (substances considered hazardous until shown otherwise)

HP 3(i): Flammable "flammable liquid waste: liquid waste having a flash point below 60°C or waste gas oil, diesel and light heating oils having a flash point > 55°C and <= 75°C"

Hazard Statements hit:

Flam. Liq. 3; H226 "Flammable liquid and vapour."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 0.161%)


Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#		Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
		CLP index number	EC Number	CAS Number								
1		arsenic { arsenic trioxide }				26.9 mg/kg	1.32	35.517 mg/kg	0.00355 %	✓		
		033-003-00-0	215-481-4	1327-53-3								
2		cadmium { cadmium sulfide }			1	1.3 mg/kg	1.285	1.671 mg/kg	0.00013 %	✓		
		048-010-00-4	215-147-8	1306-23-6								
3		chromium { chromium(III) oxide }				56.5 mg/kg	1.462	82.578 mg/kg	0.00826 %	✓		
			215-160-9	1308-38-9								

#		Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
		CLP index number	EC Number	CAS Number								
4		copper {  dicopper oxide; copper (I) oxide }			1	119 mg/kg	1.126	133.981 mg/kg	0.0134 %	✓		
	029-002-00-X	215-270-7	1317-39-1									
5		lead { lead chromate }			1	345 mg/kg	1.56	538.136 mg/kg	0.0345 %	✓		
	082-004-00-2	231-846-0	7758-97-6									
6		mercury { mercury dichloride }				<0.5 mg/kg	1.353	<0.677 mg/kg	<0.0000677 %		<LOD	
	080-010-00-X	231-299-8	7487-94-7									
7		nickel { nickel dihydroxide }				34.1 mg/kg	1.579	53.861 mg/kg	0.00539 %	✓		
	028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]									
8		selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				1.3 mg/kg	2.554	3.32 mg/kg	0.000332 %	✓		
	034-002-00-8											
9		zinc { zinc oxide }				309 mg/kg	1.245	384.617 mg/kg	0.0385 %	✓		
	030-013-00-7	215-222-5	1314-13-2									
10		boron {  boron tribromide/trichloride/trifluoride (combined) }				1.3 mg/kg	13.43	17.459 mg/kg	0.00175 %	✓		
			10294-33-4, 10294-34-5, 7637-07-2									
11		pH				7 pH		7 pH	7pH			
			PH									
12		phenol				<1 mg/kg		<1 mg/kg	<0.0001 %		<LOD	
	604-001-00-2	203-632-7	108-95-2									
13		naphthalene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
	601-052-00-2	202-049-5	91-20-3									
14						<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		205-917-1	208-96-8									
15						<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		201-469-6	83-32-9									
16						<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		201-695-5	86-73-7									
17						<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		201-581-5	85-01-8									
18						<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		204-371-1	120-12-7									
19						0.3 mg/kg		0.3 mg/kg	0.00003 %	✓		
		205-912-4	206-44-0									
20						0.3 mg/kg		0.3 mg/kg	0.00003 %	✓		
		204-927-3	129-00-0									
21		benzo[a]anthracene				0.2 mg/kg		0.2 mg/kg	0.00002 %	✓		
	601-033-00-9	200-280-6	56-55-3									
22		chrysene				0.1 mg/kg		0.1 mg/kg	0.00001 %	✓		
	601-048-00-0	205-923-4	218-01-9									
23		benzo[b]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
	601-034-00-4	205-911-9	205-99-2									
24		benzo[k]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
	601-036-00-5	205-916-6	207-08-9									
25		benzo[a]pyrene; benzo[def]chrysene				0.3 mg/kg		0.3 mg/kg	0.00003 %	✓		
	601-032-00-3	200-028-5	50-32-8									
26						<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		205-893-2	193-39-5									
27		dibenz[a,h]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
	601-041-00-2	200-181-8	53-70-3									
28						<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		205-883-8	191-24-2									
29		TPH (C6 to C40) petroleum group				1610 mg/kg		1610 mg/kg	0.161 %	✓		
			TPH									
Total:									0.267 %			

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Hazardous result
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<LOD	Below limit of detection
CLP: Note 1	Only the metal concentration has been used for classification

Classification of sample: WS02[1]

✔ **Non Hazardous Waste**
Classified as **17 05 04**
in the List of Waste

Sample details

Sample Name:	LoW Code:	
WS02[1]	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
1.50 - 1.80 m		

Hazard properties

None identified

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
1	•	TPH (C6 to C40) petroleum group			<5 mg/kg		<5 mg/kg	<0.0005 %		<LOD
			TPH							
Total:								0.0005 %		

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
•	Determinand defined or amended by HazWasteOnline (see Appendix A)
<LOD	Below limit of detection

Classification of sample: WS03

 **Hazardous Waste**
Classified as **17 05 03 ***
in the List of Waste

Sample details

Sample Name:	LoW Code:
WS03	Chapter:
Sample Depth:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
0.00 - 1.20 m	Entry:
	17 05 03 * (Soil and stones containing hazardous substances)

Hazard properties

HP 14: Ecotoxic "waste which presents or may present immediate or delayed risks for one or more sectors of the environment"

Hazard Statements hit:

Aquatic Acute 1; H400 "Very toxic to aquatic life."

Because of determinands:

chromium(III) oxide: (compound conc.: 0.119%)
zinc oxide: (compound conc.: 0.279%)

Aquatic Chronic 1; H410 "Very toxic to aquatic life with long lasting effects."

Because of determinands:

chromium(III) oxide: (compound conc.: 0.119%)
zinc oxide: (compound conc.: 0.279%)

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number								
1	arsenic { arsenic trioxide }				66 mg/kg	1.32	87.141 mg/kg	0.00871 %		✓	
	033-003-00-0	215-481-4	1327-53-3								
2	cadmium { cadmium sulfide }			1	20 mg/kg	1.285	25.705 mg/kg	0.002 %		✓	
	048-010-00-4	215-147-8	1306-23-6								
3	chromium { chromium(III) oxide }				811 mg/kg	1.462	1185.322 mg/kg	0.119 %		✓	
		215-160-9	1308-38-9								
4	copper { dicopper oxide; copper (I) oxide }				301 mg/kg	1.126	338.892 mg/kg	0.0339 %		✓	
	029-002-00-X	215-270-7	1317-39-1								
5	lead { lead chromate }			1	721 mg/kg	1.56	1124.627 mg/kg	0.0721 %		✓	
	082-004-00-2	231-846-0	7758-97-6								
6	mercury { mercury dichloride }				0.5 mg/kg	1.353	0.677 mg/kg	0.0000677 %		✓	
	080-010-00-X	231-299-8	7487-94-7								
7	nickel { nickel dihydroxide }				71.1 mg/kg	1.579	112.302 mg/kg	0.0112 %		✓	
	028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]								
8	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				3.2 mg/kg	2.554	8.172 mg/kg	0.000817 %		✓	
	034-002-00-8										
9	zinc { zinc oxide }				2240 mg/kg	1.245	2788.159 mg/kg	0.279 %		✓	
	030-013-00-7	215-222-5	1314-13-2								

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
10	boron { boron tribromide/trichloride/trifluoride (combined) }				1.1 mg/kg	13.43	14.773 mg/kg	0.00148 %	✓	
			10294-33-4, 10294-34-5, 7637-07-2							
11	pH				7.2 pH		7.2 pH	7.2 pH		
			PH							
12	phenol				<1 mg/kg		<1 mg/kg	<0.0001 %		<LOD
	604-001-00-2	203-632-7	108-95-2							
13	naphthalene				1.2 mg/kg		1.2 mg/kg	0.00012 %	✓	
	601-052-00-2	202-049-5	91-20-3							
14	acenaphthylene				0.2 mg/kg		0.2 mg/kg	0.00002 %	✓	
		205-917-1	208-96-8							
15	acenaphthene				0.6 mg/kg		0.6 mg/kg	0.00006 %	✓	
		201-469-6	83-32-9							
16	fluorene				0.3 mg/kg		0.3 mg/kg	0.00003 %	✓	
		201-695-5	86-73-7							
17	phenanthrene				3.1 mg/kg		3.1 mg/kg	0.00031 %	✓	
		201-581-5	85-01-8							
18	anthracene				0.6 mg/kg		0.6 mg/kg	0.00006 %	✓	
		204-371-1	120-12-7							
19	fluoranthene				5.3 mg/kg		5.3 mg/kg	0.00053 %	✓	
		205-912-4	206-44-0							
20	pyrene				5.2 mg/kg		5.2 mg/kg	0.00052 %	✓	
		204-927-3	129-00-0							
21	benzo[a]anthracene				2.9 mg/kg		2.9 mg/kg	0.00029 %	✓	
	601-033-00-9	200-280-6	56-55-3							
22	chrysene				3.8 mg/kg		3.8 mg/kg	0.00038 %	✓	
	601-048-00-0	205-923-4	218-01-9							
23	benzo[b]fluoranthene				2.9 mg/kg		2.9 mg/kg	0.00029 %	✓	
	601-034-00-4	205-911-9	205-99-2							
24	benzo[k]fluoranthene				2.6 mg/kg		2.6 mg/kg	0.00026 %	✓	
	601-036-00-5	205-916-6	207-08-9							
25	benzo[a]pyrene; benzo[def]chrysene				2.9 mg/kg		2.9 mg/kg	0.00029 %	✓	
	601-032-00-3	200-028-5	50-32-8							
26	indeno[123-cd]pyrene				2.2 mg/kg		2.2 mg/kg	0.00022 %	✓	
		205-893-2	193-39-5							
27	dibenz[a,h]anthracene				0.5 mg/kg		0.5 mg/kg	0.00005 %	✓	
	601-041-00-2	200-181-8	53-70-3							
28	benzo[ghi]perylene				2.4 mg/kg		2.4 mg/kg	0.00024 %	✓	
		205-883-8	191-24-2							
Total:								0.531 %		

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Hazardous result
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<LOD	Below limit of detection
CLP: Note 1	Only the metal concentration has been used for classification

Classification of sample: WS04

 **Hazardous Waste**
Classified as **17 05 03 ***
in the List of Waste

Sample details

Sample Name:	LoW Code:
WS04	Chapter: 17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry: 17 05 03 * (Soil and stones containing hazardous substances)
0.50 - 0.80 m	

Hazard properties

HP 7: Carcinogenic "waste which induces cancer or increases its incidence"

Hazard Statements hit:

Carc. 1B; H350 "May cause cancer [state route of exposure if it is conclusively proven that no other routes of exposure cause the hazard]."

Because of determinands:

lead chromate: (Note 1 conc.: 0.403%)

TPH (C6 to C40) petroleum group: (conc.: 0.299%)

HP 10: Toxic for reproduction "waste which has adverse effects on sexual function and fertility in adult males and females, as well as developmental toxicity in the offspring"

Hazard Statements hit:

Repr. 1A; H360Df "May damage the unborn child. Suspected of damaging fertility."

Because of determinand:

lead chromate: (Note 1 conc.: 0.403%)

HP 11: Mutagenic "waste which may cause a mutation, that is a permanent change in the amount or structure of the genetic material in a cell"

Hazard Statements hit:

Muta. 1B; H340 "May cause genetic defects [state route of exposure if it is conclusively proven that no other routes of exposure cause the hazard]."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 0.299%)

HP 14: Ecotoxic "waste which presents or may present immediate or delayed risks for one or more sectors of the environment"

Hazard Statements hit:

Aquatic Acute 1; H400 "Very toxic to aquatic life."

Because of determinands:

lead chromate: (Note 1 conc.: 0.403%)

zinc oxide: (compound conc.: 0.306%)

Aquatic Chronic 1; H410 "Very toxic to aquatic life with long lasting effects."

Because of determinands:

lead chromate: (Note 1 conc.: 0.403%)

zinc oxide: (compound conc.: 0.306%)

Hazard properties (substances considered hazardous until shown otherwise)

HP 3(i): Flammable "flammable liquid waste: liquid waste having a flash point below 60°C or waste gas oil, diesel and light heating oils having a flash point > 55°C and <= 75°C"

Hazard Statements hit:

Flam. Liq. 3; H226 "Flammable liquid and vapour."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 0.299%)

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number									
1	arsenic { arsenic trioxide }	033-003-00-0	215-481-4	1327-53-3	23.8	mg/kg	1.32	31.424	mg/kg	0.00314 %	✓	
2	cadmium { cadmium sulfide }	048-010-00-4	215-147-8	1306-23-6	21.8	mg/kg	1.285	28.018	mg/kg	0.00218 %	✓	
3	chromium { chromium(III) oxide }	215-160-9	1308-38-9		84.7	mg/kg	1.462	123.794	mg/kg	0.0124 %	✓	
4	copper { dicopper oxide; copper (I) oxide }	029-002-00-X	215-270-7	1317-39-1	355	mg/kg	1.126	399.69	mg/kg	0.04 %	✓	
5	lead { lead chromate }	082-004-00-2	231-846-0	7758-97-6	4030	mg/kg	1.56	6286.055	mg/kg	0.403 %	✓	
6	mercury { mercury dichloride }	080-010-00-X	231-299-8	7487-94-7	<0.5	mg/kg	1.353	<0.677	mg/kg	<0.0000677 %		<LOD
7	nickel { nickel dihydroxide }	028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]	76.9	mg/kg	1.579	121.464	mg/kg	0.0121 %	✓	
8	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }	034-002-00-8			1.9	mg/kg	2.554	4.852	mg/kg	0.000485 %	✓	
9	zinc { zinc oxide }	030-013-00-7	215-222-5	1314-13-2	2460	mg/kg	1.245	3061.996	mg/kg	0.306 %	✓	
10	boron { boron tribromide/trichloride/trifluoride (combined) }		10294-33-4, 10294-34-5, 7637-07-2		1.1	mg/kg	13.43	14.773	mg/kg	0.00148 %	✓	
11	pH		PH		7.2	pH		7.2	pH	7.2 pH		
12	phenol	604-001-00-2	203-632-7	108-95-2	<1	mg/kg		<1	mg/kg	<0.0001 %		<LOD
13	naphthalene	601-052-00-2	202-049-5	91-20-3	0.5	mg/kg		0.5	mg/kg	0.00005 %	✓	
14	acenaphthylene	205-917-1	208-96-8		<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
15	acenaphthene	201-469-6	83-32-9		0.5	mg/kg		0.5	mg/kg	0.00005 %	✓	
16	fluorene	201-695-5	86-73-7		0.4	mg/kg		0.4	mg/kg	0.00004 %	✓	
17	phenanthrene	201-581-5	85-01-8		2.9	mg/kg		2.9	mg/kg	0.00029 %	✓	
18	anthracene	204-371-1	120-12-7		0.7	mg/kg		0.7	mg/kg	0.00007 %	✓	
19	fluoranthene	205-912-4	206-44-0		4	mg/kg		4	mg/kg	0.0004 %	✓	

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
20	pyrene				5.2 mg/kg		5.2 mg/kg	0.00052 %	✓	
		204-927-3	129-00-0							
21	benzo[a]anthracene				2.8 mg/kg		2.8 mg/kg	0.00028 %	✓	
	601-033-00-9	200-280-6	56-55-3							
22	chrysene				4.2 mg/kg		4.2 mg/kg	0.00042 %	✓	
	601-048-00-0	205-923-4	218-01-9							
23	benzo[b]fluoranthene				5.1 mg/kg		5.1 mg/kg	0.00051 %	✓	
	601-034-00-4	205-911-9	205-99-2							
24	benzo[k]fluoranthene				4.1 mg/kg		4.1 mg/kg	0.00041 %	✓	
	601-036-00-5	205-916-6	207-08-9							
25	benzo[a]pyrene; benzo[def]chrysene				6.1 mg/kg		6.1 mg/kg	0.00061 %	✓	
	601-032-00-3	200-028-5	50-32-8							
26	indeno[123-cd]pyrene				5.1 mg/kg		5.1 mg/kg	0.00051 %	✓	
		205-893-2	193-39-5							
27	dibenz[a,h]anthracene				2.4 mg/kg		2.4 mg/kg	0.00024 %	✓	
	601-041-00-2	200-181-8	53-70-3							
28	benzo[ghi]perylene				5 mg/kg		5 mg/kg	0.0005 %	✓	
		205-883-8	191-24-2							
29	TPH (C6 to C40) petroleum group				2990 mg/kg		2990 mg/kg	0.299 %	✓	
			TPH							
Total:								1.085 %		

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Hazardous result
•	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<LOD	Below limit of detection
CLP: Note 1	Only the metal concentration has been used for classification

Classification of sample: WS04[1]

✔ **Non Hazardous Waste**
Classified as **17 05 04**
in the List of Waste

Sample details

Sample Name:	LoW Code:	
WS04[1]	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
1.50 - 1.70 m		

Hazard properties

None identified

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				9.6 mg/kg	1.32	12.675 mg/kg	0.00127 %	✓	
	033-003-00-0	215-481-4	1327-53-3							
2	cadmium { cadmium sulfide }			1	0.5 mg/kg	1.285	0.643 mg/kg	0.00005 %	✓	
	048-010-00-4	215-147-8	1306-23-6							
3	chromium { chromium(III) oxide }				48.5 mg/kg	1.462	70.885 mg/kg	0.00709 %	✓	
		215-160-9	1308-38-9							
4	copper { dicopper oxide; copper (I) oxide }				35.2 mg/kg	1.126	39.631 mg/kg	0.00396 %	✓	
	029-002-00-X	215-270-7	1317-39-1							
5	lead { lead chromate }			1	26.7 mg/kg	1.56	41.647 mg/kg	0.00267 %	✓	
	082-004-00-2	231-846-0	7758-97-6							
6	mercury { mercury dichloride }				<0.5 mg/kg	1.353	<0.677 mg/kg	<0.0000677 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
7	nickel { nickel dihydroxide }				46.9 mg/kg	1.579	74.079 mg/kg	0.00741 %	✓	
	028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]							
8	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<1 mg/kg	2.554	<2.554 mg/kg	<0.000255 %		<LOD
	034-002-00-8									
9	zinc { zinc oxide }				107 mg/kg	1.245	133.184 mg/kg	0.0133 %	✓	
	030-013-00-7	215-222-5	1314-13-2							
10	boron { boron tribromide/trichloride/trifluoride (combined) }				0.6 mg/kg	13.43	8.058 mg/kg	0.000806 %	✓	
			10294-33-4, 10294-34-5, 7637-07-2							
11	pH				7.6 pH		7.6 pH	7.6 pH		
			PH							
12	phenol				<1 mg/kg		<1 mg/kg	<0.0001 %		<LOD
	604-001-00-2	203-632-7	108-95-2							
13	naphthalene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3							
14	acenaphthylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8							

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
15	acenaphthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-469-6	83-32-9							
16	fluorene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-695-5	86-73-7							
17	phenanthrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		201-581-5	85-01-8							
18	anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		204-371-1	120-12-7							
19	fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-912-4	206-44-0							
20	pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		204-927-3	129-00-0							
21	benzo[a]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-033-00-9	200-280-6	56-55-3							
22	chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-048-00-0	205-923-4	218-01-9							
23	benzo[b]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-034-00-4	205-911-9	205-99-2							
24	benzo[k]fluoranthene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-036-00-5	205-916-6	207-08-9							
25	benzo[a]pyrene; benzo[def]chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-032-00-3	200-028-5	50-32-8							
26	indeno[123-cd]pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-893-2	193-39-5							
27	dibenz[a,h]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
	601-041-00-2	200-181-8	53-70-3							
28	benzo[ghi]perylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD
		205-883-8	191-24-2							
Total:								0.0372 %		

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<LOD	Below limit of detection
CLP: Note 1	Only the metal concentration has been used for classification

Classification of sample: WS06

✔ **Non Hazardous Waste**
Classified as **17 05 04**
in the List of Waste

Sample details

Sample Name:	LoW Code:	
WS06	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
0.30 - 0.70 m		

Hazard properties

None identified

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
1	arsenic { arsenic trioxide }				7 mg/kg	1.32	9.242 mg/kg	0.000924 %	✓	
	033-003-00-0	215-481-4	1327-53-3							
2	cadmium { cadmium sulfide }			1	1.1 mg/kg	1.285	1.414 mg/kg	0.00011 %	✓	
	048-010-00-4	215-147-8	1306-23-6							
3	chromium { chromium(III) oxide }				22.1 mg/kg	1.462	32.3 mg/kg	0.00323 %	✓	
		215-160-9	1308-38-9							
4	copper { dicopper oxide; copper (I) oxide }				67.3 mg/kg	1.126	75.772 mg/kg	0.00758 %	✓	
	029-002-00-X	215-270-7	1317-39-1							
5	lead { lead chromate }			1	352 mg/kg	1.56	549.055 mg/kg	0.0352 %	✓	
	082-004-00-2	231-846-0	7758-97-6							
6	mercury { mercury dichloride }				<0.5 mg/kg	1.353	<0.677 mg/kg	<0.0000677 %		<LOD
	080-010-00-X	231-299-8	7487-94-7							
7	nickel { nickel dihydroxide }				17.8 mg/kg	1.579	28.115 mg/kg	0.00281 %	✓	
	028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]							
8	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<1 mg/kg	2.554	<2.554 mg/kg	<0.000255 %		<LOD
	034-002-00-8									
9	zinc { zinc oxide }				283 mg/kg	1.245	352.254 mg/kg	0.0352 %	✓	
	030-013-00-7	215-222-5	1314-13-2							
10	boron { boron tribromide/trichloride/trifluoride (combined) }				0.5 mg/kg	13.43	6.715 mg/kg	0.000672 %	✓	
			10294-33-4, 10294-34-5, 7637-07-2							
11	pH				9 pH		9 pH	9pH		
			PH							
12	phenol				<1 mg/kg		<1 mg/kg	<0.0001 %		<LOD
	604-001-00-2	203-632-7	108-95-2							
13	naphthalene				0.2 mg/kg		0.2 mg/kg	0.00002 %	✓	
	601-052-00-2	202-049-5	91-20-3							
14	acenaphthylene				0.2 mg/kg		0.2 mg/kg	0.00002 %	✓	
		205-917-1	208-96-8							

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number								
15	acenaphthene	201-469-6	83-32-9		0.2 mg/kg		0.2	mg/kg	0.00002 %	✓	
16	fluorene	201-695-5	86-73-7		0.3 mg/kg		0.3	mg/kg	0.00003 %	✓	
17	phenanthrene	201-581-5	85-01-8		1.2 mg/kg		1.2	mg/kg	0.00012 %	✓	
18	anthracene	204-371-1	120-12-7		0.3 mg/kg		0.3	mg/kg	0.00003 %	✓	
19	fluoranthene	205-912-4	206-44-0		3.1 mg/kg		3.1	mg/kg	0.00031 %	✓	
20	pyrene	204-927-3	129-00-0		5 mg/kg		5	mg/kg	0.0005 %	✓	
21	benzo[a]anthracene	601-033-00-9	200-280-6		1.4 mg/kg		1.4	mg/kg	0.00014 %	✓	
22	chrysene	601-048-00-0	205-923-4		3.9 mg/kg		3.9	mg/kg	0.00039 %	✓	
23	benzo[b]fluoranthene	601-034-00-4	205-911-9		1.7 mg/kg		1.7	mg/kg	0.00017 %	✓	
24	benzo[k]fluoranthene	601-036-00-5	205-916-6		3.1 mg/kg		3.1	mg/kg	0.00031 %	✓	
25	benzo[a]pyrene; benzo[def]chrysene	601-032-00-3	200-028-5		2.5 mg/kg		2.5	mg/kg	0.00025 %	✓	
26	indeno[123-cd]pyrene	205-893-2	193-39-5		3.2 mg/kg		3.2	mg/kg	0.00032 %	✓	
27	dibenz[a,h]anthracene	601-041-00-2	200-181-8		1.7 mg/kg		1.7	mg/kg	0.00017 %	✓	
28	benzo[ghi]perylene	205-883-8	191-24-2		2.7 mg/kg		2.7	mg/kg	0.00027 %	✓	
Total:									0.0892 %		

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
•	Determinand defined or amended by HazWasteOnline (see Appendix A)
•	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<LOD	Below limit of detection
CLP: Note 1	Only the metal concentration has been used for classification

Classification of sample: WS07

✔ **Non Hazardous Waste**
Classified as **17 05 04**
in the List of Waste

Sample details

Sample Name:	LoW Code:	
WS07	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry:	17 05 04 (Soil and stones other than those mentioned in 17 05 03)
0.50 - 0.70 m		

Hazard properties

None identified

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#		Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
		CLP index number	EC Number	CAS Number									
1		arsenic { arsenic trioxide }				8.7	mg/kg	1.32	11.487	mg/kg	0.00115 %	✓	
	033-003-00-0	215-481-4	1327-53-3										
2		cadmium { cadmium sulfide }			1	<0.5	mg/kg	1.285	<0.643	mg/kg	<0.00005 %		<LOD
	048-010-00-4	215-147-8	1306-23-6										
3		chromium { chromium(III) oxide }				21.4	mg/kg	1.462	31.277	mg/kg	0.00313 %	✓	
		215-160-9	1308-38-9										
4		copper { dicopper oxide; copper (I) oxide }				26.2	mg/kg	1.126	29.498	mg/kg	0.00295 %	✓	
	029-002-00-X	215-270-7	1317-39-1										
5		lead { lead chromate }			1	142	mg/kg	1.56	221.494	mg/kg	0.0142 %	✓	
	082-004-00-2	231-846-0	7758-97-6										
6		mercury { mercury dichloride }				<0.5	mg/kg	1.353	<0.677	mg/kg	<0.0000677 %		<LOD
	080-010-00-X	231-299-8	7487-94-7										
7		nickel { nickel dihydroxide }				12.8	mg/kg	1.579	20.218	mg/kg	0.00202 %	✓	
	028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]										
8		selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<1	mg/kg	2.554	<2.554	mg/kg	<0.000255 %		<LOD
	034-002-00-8												
9		zinc { zinc oxide }				68.3	mg/kg	1.245	85.014	mg/kg	0.0085 %	✓	
	030-013-00-7	215-222-5	1314-13-2										
10		boron { boron tribromide/trichloride/trifluoride (combined) }				1.2	mg/kg	13.43	16.116	mg/kg	0.00161 %	✓	
			10294-33-4, 10294-34-5, 7637-07-2										
11		pH				8.3	pH		8.3	pH	8.3 pH		
			PH										
12		phenol				<1	mg/kg		<1	mg/kg	<0.0001 %		<LOD
	604-001-00-2	203-632-7	108-95-2										
13		naphthalene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3										
14		acenaphthylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8										

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number								
15	acenaphthene	201-469-6	83-32-9		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
16	fluorene	201-695-5	86-73-7		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
17	phenanthrene	201-581-5	85-01-8		0.2 mg/kg		0.2 mg/kg	0.00002 %		✓	
18	anthracene	204-371-1	120-12-7		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
19	fluoranthene	205-912-4	206-44-0		0.3 mg/kg		0.3 mg/kg	0.00003 %		✓	
20	pyrene	204-927-3	129-00-0		0.4 mg/kg		0.4 mg/kg	0.00004 %		✓	
21	benzo[a]anthracene	601-033-00-9	200-280-6		0.3 mg/kg		0.3 mg/kg	0.00003 %		✓	
22	chrysene	601-048-00-0	205-923-4		0.3 mg/kg		0.3 mg/kg	0.00003 %		✓	
23	benzo[b]fluoranthene	601-034-00-4	205-911-9		0.3 mg/kg		0.3 mg/kg	0.00003 %		✓	
24	benzo[k]fluoranthene	601-036-00-5	205-916-6		0.2 mg/kg		0.2 mg/kg	0.00002 %		✓	
25	benzo[a]pyrene; benzo[def]chrysene	601-032-00-3	200-028-5		0.2 mg/kg		0.2 mg/kg	0.00002 %		✓	
26	indeno[123-cd]pyrene	205-893-2	193-39-5		0.5 mg/kg		0.5 mg/kg	0.00005 %		✓	
27	dibenz[a,h]anthracene	601-041-00-2	200-181-8		0.2 mg/kg		0.2 mg/kg	0.00002 %		✓	
28	benzo[ghi]perylene	205-883-8	191-24-2		0.4 mg/kg		0.4 mg/kg	0.00004 %		✓	
Total:									0.0344 %		

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
	Determinand defined or amended by HazWasteOnline (see Appendix A)
	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<LOD	Below limit of detection
CLP: Note 1	Only the metal concentration has been used for classification

Classification of sample: WS07[1]

✔ **Non Hazardous Waste**
Classified as **17 05 04**
in the List of Waste

Sample details

Sample Name:	LoW Code:
WS07[1]	Chapter:
Sample Depth:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
0.70 - 1.00 m	Entry:
	17 05 04 (Soil and stones other than those mentioned in 17 05 03)

Hazard properties

None identified

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#		Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
		CLP index number	EC Number	CAS Number									
1		arsenic { arsenic trioxide }				9.9	mg/kg	1.32	13.071	mg/kg	0.00131 %	✓	
	033-003-00-0	215-481-4	1327-53-3										
2		cadmium { cadmium sulfide }			1	<0.5	mg/kg	1.285	<0.643	mg/kg	<0.00005 %		<LOD
	048-010-00-4	215-147-8	1306-23-6										
3		chromium { chromium(III) oxide }				42.3	mg/kg	1.462	61.824	mg/kg	0.00618 %	✓	
		215-160-9	1308-38-9										
4		copper { dicopper oxide; copper (I) oxide }				36.4	mg/kg	1.126	40.982	mg/kg	0.0041 %	✓	
	029-002-00-X	215-270-7	1317-39-1										
5		lead { lead chromate }			1	23.5	mg/kg	1.56	36.656	mg/kg	0.00235 %	✓	
	082-004-00-2	231-846-0	7758-97-6										
6		mercury { mercury dichloride }				<0.5	mg/kg	1.353	<0.677	mg/kg	<0.0000677 %		<LOD
	080-010-00-X	231-299-8	7487-94-7										
7		nickel { nickel dihydroxide }				36.8	mg/kg	1.579	58.126	mg/kg	0.00581 %	✓	
	028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]										
8		selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				<1	mg/kg	2.554	<2.554	mg/kg	<0.000255 %		<LOD
	034-002-00-8												
9		zinc { zinc oxide }				78.1	mg/kg	1.245	97.212	mg/kg	0.00972 %	✓	
	030-013-00-7	215-222-5	1314-13-2										
10		boron { boron tribromide/trichloride/trifluoride (combined) }				1	mg/kg	13.43	13.43	mg/kg	0.00134 %	✓	
			10294-33-4, 10294-34-5, 7637-07-2										
11		pH				7.6	pH		7.6	pH	7.6 pH		
			PH										
12		phenol				<1	mg/kg		<1	mg/kg	<0.0001 %		<LOD
	604-001-00-2	203-632-7	108-95-2										
13		naphthalene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
	601-052-00-2	202-049-5	91-20-3										
14		acenaphthylene				<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
		205-917-1	208-96-8										

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number								
15	acenaphthene	201-469-6	83-32-9		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
16	fluorene	201-695-5	86-73-7		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
17	phenanthrene	201-581-5	85-01-8		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
18	anthracene	204-371-1	120-12-7		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
19	fluoranthene	205-912-4	206-44-0		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
20	pyrene	204-927-3	129-00-0		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
21	benzo[a]anthracene	601-033-00-9	200-280-6		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
22	chrysene	601-048-00-0	205-923-4		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
23	benzo[b]fluoranthene	601-034-00-4	205-911-9		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
24	benzo[k]fluoranthene	601-036-00-5	205-916-6		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
25	benzo[a]pyrene; benzo[def]chrysene	601-032-00-3	200-028-5		<0.1 mg/kg		<0.1 mg/kg	<0.00001 %			<LOD
26	indeno[123-cd]pyrene	205-893-2	193-39-5		0.2 mg/kg		0.2 mg/kg	0.00002 %		✓	
27	dibenz[a,h]anthracene	601-041-00-2	200-181-8		0.6 mg/kg		0.6 mg/kg	0.00006 %		✓	
28	benzo[ghi]perylene	205-883-8	191-24-2		0.3 mg/kg		0.3 mg/kg	0.00003 %		✓	
Total:									0.0315 %		

Key

	User supplied data
	Determinand values ignored for classification, see column 'Conc. Not Used' for reason
•	Determinand defined or amended by HazWasteOnline (see Appendix A)
•	Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
<LOD	Below limit of detection
CLP: Note 1	Only the metal concentration has been used for classification

Classification of sample: SS01

 **Hazardous Waste**
Classified as **17 05 03 ***
in the List of Waste

Sample details

Sample Name:	LoW Code:	
SS01	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	Entry:	17 05 03 * (Soil and stones containing hazardous substances)
0.00 - 0.30 m		

Hazard properties

HP 7: Carcinogenic "waste which induces cancer or increases its incidence"

Hazard Statements hit:

Carc. 1B; H350 "May cause cancer [state route of exposure if it is conclusively proven that no other routes of exposure cause the hazard]."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 2.44%)

HP 11: Mutagenic "waste which may cause a mutation, that is a permanent change in the amount or structure of the genetic material in a cell"

Hazard Statements hit:

Muta. 1B; H340 "May cause genetic defects [state route of exposure if it is conclusively proven that no other routes of exposure cause the hazard]."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 2.44%)

HP 14: Ecotoxic "waste which presents or may present immediate or delayed risks for one or more sectors of the environment"

Hazard Statements hit:

Aquatic Acute 1; H400 "Very toxic to aquatic life."

Because of determinand:

zinc oxide: (compound conc.: 0.122%)

Aquatic Chronic 1; H410 "Very toxic to aquatic life with long lasting effects."

Because of determinand:

zinc oxide: (compound conc.: 0.122%)

Aquatic Chronic 2; H411 "Toxic to aquatic life with long lasting effects."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 2.44%)

Hazard properties (substances considered hazardous until shown otherwise)

HP 3(i): Flammable "flammable liquid waste: liquid waste having a flash point below 60°C or waste gas oil, diesel and light heating oils having a flash point > 55°C and <= 75°C"

Hazard Statements hit:

Flam. Liq. 3; H226 "Flammable liquid and vapour."

Because of determinand:

TPH (C6 to C40) petroleum group: (conc.: 2.44%)

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#	Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number									
1	arsenic { arsenic trioxide }	033-003-00-0	215-481-4	1327-53-3	49.2	mg/kg	1.32	64.96	mg/kg	0.0065 %	✓	
2	cadmium { cadmium sulfide }	048-010-00-4	215-147-8	1306-23-6								
3	chromium { chromium(III) oxide }	215-160-9	1308-38-9		69.4	mg/kg	1.462	101.432	mg/kg	0.0101 %	✓	
4	copper { dicopper oxide; copper (I) oxide }	029-002-00-X	215-270-7	1317-39-1	499	mg/kg	1.126	561.818	mg/kg	0.0562 %	✓	
5	lead { lead chromate }	082-004-00-2	231-846-0	7758-97-6	348	mg/kg	1.56	542.816	mg/kg	0.0348 %	✓	
6	mercury { mercury dichloride }	080-010-00-X	231-299-8	7487-94-7	<0.5	mg/kg	1.353	<0.677	mg/kg	<0.0000677 %		<LOD
7	nickel { nickel dihydroxide }	028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]	100	mg/kg	1.579	157.95	mg/kg	0.0158 %	✓	
8	selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }	034-002-00-8			<1	mg/kg	2.554	<2.554	mg/kg	<0.000255 %		<LOD
9	zinc { zinc oxide }	030-013-00-7	215-222-5	1314-13-2	983	mg/kg	1.245	1223.554	mg/kg	0.122 %	✓	
10	boron { boron tribromide/trichloride/trifluoride (combined) }		10294-33-4, 10294-34-5, 7637-07-2		0.7	mg/kg	13.43	9.401	mg/kg	0.00094 %	✓	
11	pH		pH		7.5	pH		7.5	pH	7.5 pH		
12	phenol	604-001-00-2	203-632-7	108-95-2	<1	mg/kg		<1	mg/kg	<0.0001 %		<LOD
13	naphthalene	601-052-00-2	202-049-5	91-20-3	<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
14	acenaphthylene	205-917-1	208-96-8		0.1	mg/kg		0.1	mg/kg	0.00001 %	✓	
15	acenaphthene	201-469-6	83-32-9		<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
16	fluorene	201-695-5	86-73-7		<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
17	phenanthrene	201-581-5	85-01-8		<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
18	anthracene	204-371-1	120-12-7		<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
19	fluoranthene	205-912-4	206-44-0		1.2	mg/kg		1.2	mg/kg	0.00012 %	✓	
20	pyrene	204-927-3	129-00-0		1.9	mg/kg		1.9	mg/kg	0.00019 %	✓	
21	benzo[a]anthracene	601-033-00-9	200-280-6	56-55-3	<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
22	chrysene	601-048-00-0	205-923-4	218-01-9	<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
23	benzo[b]fluoranthene	601-034-00-4	205-911-9	205-99-2	<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD
24	benzo[k]fluoranthene	601-036-00-5	205-916-6	207-08-9	<0.1	mg/kg		<0.1	mg/kg	<0.00001 %		<LOD

#		Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
		CLP index number	EC Number	CAS Number								
25		benzo[a]pyrene; benzo[def]chrysene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		601-032-00-3	200-028-5	50-32-8								
26	■	indeno[123-cd]pyrene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
			205-893-2	193-39-5								
27		dibenz[a,h]anthracene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
		601-041-00-2	200-181-8	53-70-3								
28	■	benzo[ghi]perylene				<0.1 mg/kg		<0.1 mg/kg	<0.00001 %		<LOD	
			205-883-8	191-24-2								
29	■	TPH (C6 to C40) petroleum group				24400 mg/kg		24400 mg/kg	2.44 %	✓		
				TPH								
Total: 2.688 %												

Key

- User supplied data
- Determinand values ignored for classification, see column 'Conc. Not Used' for reason
- Hazardous result
- Determinand defined or amended by HazWasteOnline (see Appendix A)
- Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
- <LOD** Below limit of detection
- CLP: Note 1 Only the metal concentration has been used for classification

Classification of sample: WS05

✔ **Non Hazardous Waste**
Classified as **17 05 04**
in the List of Waste

Sample details

Sample Name:	WS05	LoW Code:	Chapter:	17: Construction and Demolition Wastes (including excavated soil from contaminated sites)
Sample Depth:	0.30 - 0.60 m	Entry:		17 05 04 (Soil and stones other than those mentioned in 17 05 03)

Hazard properties

None identified

Determinands

Moisture content: 0% Dry Weight Moisture Correction applied (MC)

#		Determinand			CLP Note	User entered data		Conv. Factor	Compound conc.		Classification value	MC Applied	Conc. Not Used
		CLP index number	EC Number	CAS Number									
1		arsenic { arsenic trioxide }			1	22.6	mg/kg	1.32	29.839	mg/kg	0.00298 %	✓	
		033-003-00-0	215-481-4	1327-53-3									
2		cadmium { cadmium sulfide }			1	1	mg/kg	1.285	1.285	mg/kg	0.0001 %	✓	
		048-010-00-4	215-147-8	1306-23-6									
3		chromium { chromium(III) oxide }				34	mg/kg	1.462	49.693	mg/kg	0.00497 %	✓	
			215-160-9	1308-38-9									
4		copper { dicopper oxide; copper (I) oxide }				160	mg/kg	1.126	180.142	mg/kg	0.018 %	✓	
		029-002-00-X	215-270-7	1317-39-1									
5		lead { lead chromate }			1	392	mg/kg	1.56	611.448	mg/kg	0.0392 %	✓	
		082-004-00-2	231-846-0	7758-97-6									
6		mercury { mercury dichloride }				<0.5	mg/kg	1.353	<0.677	mg/kg	<0.0000677 %		<LOD
		080-010-00-X	231-299-8	7487-94-7									
7		nickel { nickel dihydroxide }				27.3	mg/kg	1.579	43.12	mg/kg	0.00431 %	✓	
		028-008-00-X	235-008-5 [1] 234-348-1 [2]	12054-48-7 [1] 11113-74-9 [2]									
8		selenium { selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex }				1.1	mg/kg	2.554	2.809	mg/kg	0.000281 %	✓	
		034-002-00-8											
9		zinc { zinc oxide }				314	mg/kg	1.245	390.84	mg/kg	0.0391 %	✓	
		030-013-00-7	215-222-5	1314-13-2									
10		boron { boron tribromide/trichloride/trifluoride (combined) }				1.1	mg/kg	13.43	14.773	mg/kg	0.00148 %	✓	
				10294-33-4, 10294-34-5, 7637-07-2									
11		pH				9.2	pH		9.2	pH	9.2 pH		
				PH									
12		phenol				<1	mg/kg		<1	mg/kg	<0.0001 %		<LOD
		604-001-00-2	203-632-7	108-95-2									
13		naphthalene				0.5	mg/kg		0.5	mg/kg	0.00005 %	✓	
		601-052-00-2	202-049-5	91-20-3									
14		acenaphthylene				0.2	mg/kg		0.2	mg/kg	0.00002 %	✓	
			205-917-1	208-96-8									

#	Determinand			CLP Note	User entered data	Conv. Factor	Compound conc.	Classification value	MC Applied	Conc. Not Used
	CLP index number	EC Number	CAS Number							
15	acenaphthene	201-469-6	83-32-9		0.7 mg/kg		0.7 mg/kg	0.00007 %	✓	
16	fluorene	201-695-5	86-73-7		0.5 mg/kg		0.5 mg/kg	0.00005 %	✓	
17	phenanthrene	201-581-5	85-01-8		6.6 mg/kg		6.6 mg/kg	0.00066 %	✓	
18	anthracene	204-371-1	120-12-7		1.9 mg/kg		1.9 mg/kg	0.00019 %	✓	
19	fluoranthene	205-912-4	206-44-0		10.5 mg/kg		10.5 mg/kg	0.00105 %	✓	
20	pyrene	204-927-3	129-00-0		9.3 mg/kg		9.3 mg/kg	0.00093 %	✓	
21	benzo[a]anthracene	601-033-00-9	200-280-6		5 mg/kg		5 mg/kg	0.0005 %	✓	
22	chrysene	601-048-00-0	205-923-4		6.1 mg/kg		6.1 mg/kg	0.00061 %	✓	
23	benzo[b]fluoranthene	601-034-00-4	205-911-9		4.6 mg/kg		4.6 mg/kg	0.00046 %	✓	
24	benzo[k]fluoranthene	601-036-00-5	205-916-6		5.1 mg/kg		5.1 mg/kg	0.00051 %	✓	
25	benzo[a]pyrene; benzo[def]chrysene	601-032-00-3	200-028-5		5 mg/kg		5 mg/kg	0.0005 %	✓	
26	indeno[123-cd]pyrene	205-893-2	193-39-5		3.5 mg/kg		3.5 mg/kg	0.00035 %	✓	
27	dibenz[a,h]anthracene	601-041-00-2	200-181-8		1 mg/kg		1 mg/kg	0.0001 %	✓	
28	benzo[ghi]perylene	205-883-8	191-24-2		3.7 mg/kg		3.7 mg/kg	0.00037 %	✓	
Total:								0.117 %		

Key

- User supplied data
- Determinand values ignored for classification, see column 'Conc. Not Used' for reason
- Determinand defined or amended by HazWasteOnline (see Appendix A)
- Speciated Determinand - Unless the Determinand is Note 1, the Conversion Factor is used to calculate the compound concentration
- <LOD** Below limit of detection
- CLP: Note 1 Only the metal concentration has been used for classification

Appendix A: Classifier defined and non CLP determinands

■ **chromium(III) oxide** (EC Number: 215-160-9, CAS Number: 1308-38-9)

Conversion factor: 1.462

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 17/07/2015

Hazard Statements: Acute Tox. 4 H332 , Acute Tox. 4 H302 , Eye Irrit. 2 H319 , STOT SE 3 H335 , Skin Irrit. 2 H315 , Resp. Sens. 1 H334 , Skin Sens. 1 H317 , Repr. 1B H360FD , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

■ **dicopper oxide; copper (I) oxide** (EC Number: 215-270-7, CAS Number: 1317-39-1)

CLP index number: 029-002-00-X

Data source: Regulation (EU) 2016/1179 of 19 July 2016 (ATP9)

Additional Hazard Statement(s): None.

Reason for additional Hazards Statement(s)/Risk Phrase(s):

10/10/2016 - N R50/53 risk phrase sourced from: WM3 v1 still uses ecotoxic risk phrases

10/10/2016 - N R50/53 >= 0.25 % risk phrase sourced from: WM3 v1 still uses ecotoxic risk phrases

■ **boron tribromide/trichloride/trifluoride (combined)** (CAS Number: 10294-33-4, 10294-34-5, 7637-07-2)

Conversion factor: 13.43

Description/Comments: Combines the hazard statements and the average of the conversion factors for boron tribromide, boron trichloride and boron trifluoride

Data source: N/A

Data source date: 06/08/2015

Hazard Statements: EUH014 , Acute Tox. 2 H330 , Acute Tox. 2 H300 , Skin Corr. 1A H314 , Skin Corr. 1B H314

■ **pH** (CAS Number: PH)

Description/Comments: Appendix C4

Data source: WM3 1st Edition 2015

Data source date: 25/05/2015

Hazard Statements: None.

■ **acenaphthylene** (EC Number: 205-917-1, CAS Number: 208-96-8)

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 17/07/2015

Hazard Statements: Acute Tox. 4 H302 , Acute Tox. 1 H330 , Acute Tox. 1 H310 , Eye Irrit. 2 H319 , STOT SE 3 H335 , Skin Irrit. 2 H315

■ **acenaphthene** (EC Number: 201-469-6, CAS Number: 83-32-9)

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 17/07/2015

Hazard Statements: Eye Irrit. 2 H319 , STOT SE 3 H335 , Skin Irrit. 2 H315 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410 , Aquatic Chronic 2 H411

■ **fluorene** (EC Number: 201-695-5, CAS Number: 86-73-7)

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 06/08/2015

Hazard Statements: Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

■ **phenanthrene** (EC Number: 201-581-5, CAS Number: 85-01-8)

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 06/08/2015

Hazard Statements: Acute Tox. 4 H302 , Eye Irrit. 2 H319 , STOT SE 3 H335 , Carc. 2 H351 , Skin Sens. 1 H317 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410 , Skin Irrit. 2 H315

■ **anthracene** (EC Number: 204-371-1, CAS Number: 120-12-7)

Description/Comments: Data from C&L Inventory Database

Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>

Data source date: 17/07/2015

Hazard Statements: Eye Irrit. 2 H319 , STOT SE 3 H335 , Skin Irrit. 2 H315 , Skin Sens. 1 H317 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

▪ **fluoranthene** (EC Number: 205-912-4, CAS Number: 206-44-0)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 21/08/2015
Hazard Statements: Acute Tox. 4 H302 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

▪ **pyrene** (EC Number: 204-927-3, CAS Number: 129-00-0)

Description/Comments: Data from C&L Inventory Database; SDS Sigma Aldrich 2014
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 21/08/2015
Hazard Statements: Skin Irrit. 2 H315 , Eye Irrit. 2 H319 , STOT SE 3 H335 , Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

▪ **indeno[123-cd]pyrene** (EC Number: 205-893-2, CAS Number: 193-39-5)

Description/Comments: Data from C&L Inventory Database
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 06/08/2015
Hazard Statements: Carc. 2 H351

▪ **benzo[ghi]perylene** (EC Number: 205-883-8, CAS Number: 191-24-2)

Description/Comments: Data from C&L Inventory Database; SDS Sigma Aldrich 28/02/2015
Data source: <http://echa.europa.eu/web/guest/information-on-chemicals/cl-inventory-database>
Data source date: 23/07/2015
Hazard Statements: Aquatic Acute 1 H400 , Aquatic Chronic 1 H410

▪ **TPH (C6 to C40) petroleum group** (CAS Number: TPH)

Description/Comments: Hazard statements taken from WM3 1st Edition 2015; Risk phrases: WM2 3rd Edition 2013
Data source: WM3 1st Edition 2015
Data source date: 25/05/2015
Hazard Statements: Flam. Liq. 3 H226 , Asp. Tox. 1 H304 , STOT RE 2 H373 , Muta. 1B H340 , Carc. 1B H350 , Repr. 2 H361d , Aquatic Chronic 2 H411

Appendix B: Rationale for selection of metal species

arsenic {arsenic trioxide}

Worst case species based on risk phrases

cadmium {cadmium sulfide}

Worst case species based on risk phrases

chromium {chromium(III) oxide}

Concentrations of CH not high enough for the creation of CH(VI)

copper {dicopper oxide; copper (I) oxide}

Most likely common species

lead {lead chromate}

Worst case species based on risk phrases

mercury {mercury dichloride}

Worst case species based on risk phrases

nickel {nickel dihydroxide}

Worst case species based on risk phrases

selenium {selenium compounds with the exception of cadmium sulphoselenide and those specified elsewhere in this Annex}

Worst case species based on risk phrases

zinc {zinc oxide}

Concentration of chromium not high enough for creation of zinc chromate.

boron {boron tribromide/trichloride/trifluoride (combined)}

Worst case species based on risk phrases

Appendix C: Version

HazWasteOnline Classification Engine: **WM3 1st Edition, May 2015, HP14 using CLP**

HazWasteOnline Classification Engine Version: 2017.180.3351.6750 (29 Jun 2017)

HazWasteOnline Database: 2017.180.3351.6750 (29 Jun 2017)

This classification utilises the following guidance and legislation:

WM3 - Waste Classification - May 2015

CLP Regulation - Regulation 1272/2008/EC of 16 December 2008

1st ATP - Regulation 790/2009/EC of 10 August 2009

2nd ATP - Regulation 286/2011/EC of 10 March 2011

3rd ATP - Regulation 618/2012/EU of 10 July 2012

4th ATP - Regulation 487/2013/EU of 8 May 2013

Correction to 1st ATP - Regulation 758/2013/EU of 7 August 2013

5th ATP - Regulation 944/2013/EU of 2 October 2013

6th ATP - Regulation 605/2014/EU of 5 June 2014

WFD Annex III replacement - Regulation 1357/2014/EU of 18 December 2014

Revised List of Wastes 2014 - Decision 2014/955/EU of 18 December 2014

7th ATP - Regulation 2015/1221/EU of 24 July 2015

8th ATP - Regulation (EU) 2016/918 of 19 May 2016

9th ATP - Regulation (EU) 2016/1179 of 19 July 2016

10th ATP - Regulation (EU) 2017/776 of 4 May 2017

POPs Regulation 2004 - Regulation 850/2004/EC of 29 April 2004

1st ATP to POPs Regulation - Regulation 756/2010/EU of 24 August 2010

2nd ATP to POPs Regulation - Regulation 757/2010/EU of 24 August 2010

Appendix H – Statistical Assessment

	A	B	C	D	E	F	G
1	Outlier Tests for Selected Uncensored Variables						
2	User Selected Options						
3	Date/Time of Computation		ProUCL 5.129/06/2017 18:09:10				
4			From File ASH1867				
5			Full Precision OFF				
6							
7							
8	Dixon's Outlier Test for Lead						
9							
10	Number of Observations = 7						
11	10% critical value: 0.434						
12	5% critical value: 0.507						
13	1% critical value: 0.637						
14							
15	1. Observation Value 4030 is a Potential Outlier (Upper Tail)?						
16							
17	Test Statistic: 0.851						
18							
19	For 10% significance level, 4030 is an outlier.						
20	For 5% significance level, 4030 is an outlier.						
21	For 1% significance level, 4030 is an outlier.						
22							
23	2. Observation Value 142 is a Potential Outlier (Lower Tail)?						
24							
25	Test Statistic: 0.052						
26							
27	For 10% significance level, 142 is not an outlier.						
28	For 5% significance level, 142 is not an outlier.						
29	For 1% significance level, 142 is not an outlier.						
30							

	A	B	C	D	E	F	G	H	I	J	K	L
1	Normal UCL Statistics for Uncensored Full Data Sets											
2												
3	User Selected Options											
4	Date/Time of Computation			ProUCL 5.129/06/2017 18:27:09								
5	From File			ASH1867								
6	Full Precision			OFF								
7	Confidence Coefficient			95%								
8												
9												
10	Lead											
11												
12	General Statistics											
13	Total Number of Observations				6		Number of Distinct Observations				6	
14							Number of Missing Observations				1	
15	Minimum				142		Mean				383.3	
16	Maximum				721		Median				350	
17	SD				187.6		SD of logged Data				0.519	
18	Coefficient of Variation				0.489		Skewness				1.104	
19												
20	Note: Sample size is small (e.g., <10), if data are collected using ISM approach, you should use											
21	guidance provided in ITRC Tech Reg Guide on ISM (ITRC, 2012) to compute statistics of interest.											
22	For example, you may want to use Chebyshev UCL to estimate EPC (ITRC, 2012).											
23	Chebyshev UCL can be computed using the Nonparametric and All UCL Options of ProUCL 5.1											
24												
25	Normal GOF Test											
26	Shapiro Wilk Test Statistic				0.846		Shapiro Wilk GOF Test					
27	5% Shapiro Wilk Critical Value				0.788		Data appear Normal at 5% Significance Level					
28	Lilliefors Test Statistic				0.315		Lilliefors GOF Test					
29	5% Lilliefors Critical Value				0.325		Data appear Normal at 5% Significance Level					
30	Data appear Normal at 5% Significance Level											
31												
32	Assuming Normal Distribution											
33	95% Normal UCL					95% UCLs (Adjusted for Skewness)						
34	95% Student's-t UCL				537.7		95% Adjusted-CLT UCL (Chen-1995)				546.2	
35							95% Modified-t UCL (Johnson-1978)				543.4	
36												
37	Suggested UCL to Use											
38	95% Student's-t UCL				537.7							
39												
40	Note: Suggestions regarding the selection of a 95% UCL are provided to help the user to select the most appropriate 95% UCL.											
41	Recommendations are based upon data size, data distribution, and skewness.											
42	These recommendations are based upon the results of the simulation studies summarized in Singh, Maichle, and Lee (2006).											
43	However, simulations results will not cover all Real World data sets; for additional insight the user may want to consult a statistician.											
44												