

Appendix B - Glossary

Abbreviation	Term	Explanation
DBH	Diameter at Breast Height	The diameter of the tree trunk in question, 'breast height' is taken to be 1.3 metres above ground level. Multi-stem trees have their stems measured separately and indicated as so in the tree schedule. Trees with abnormal growths, branch unions or other obstructions at 1.3 m will have their measurements taken immediately below said obstructions.
RPA	Root Protection Area	The area in metres squared of the potential underground rooting constraints
AMS	Arboricultural Method Statement	This dictates the procedure for works to be carried out around the protected trees
RPA	Root Protection Area	Circular area surrounding tree with a radius based on the DBH of the tree, as calculated in BS 5837:2012. RPA Radius = 12 x DBH
AIA	Arboricultural Impact Assessment	What will the impact be on the trees with the proposed development
VTa	Visual Tree Assessment	A system of tree inspection devised by Claus Mattheck using visual signs to read the body language of trees & aid with the diagnosis of potential defects.
TPP	Tree Protection Plan	This describes the process on how the work is to be carried out around the trees
BS5837 2012	British Standards	British Standard 5837:2012 <i>Trees in relation to design, demolition & construction - Recommendations.</i>
	Codominant stem	Two stems on a tree which can suggest a weakened union
	V union with bark inclusion	Usually with a codominant stem, as above but with up to an additional 42% weak union
Y	Young	Tree which has not yet established a significant rooting structure in the ground & has not developed a significant branching structure - its form is largely 'whip' like in nature & it could normally be easily transplanted or replaced.
EM	Early Mature	Tree which has established a significant rooting structure & has developed a noticeable internal scaffold structure, it differs from a mature version of its species only in size but not in relative proportions of its structure. Trees in this age class will still be developing significantly in height & spread.
M	Mature	Tree which has established a significant root-plate & which is over 50% of the way through its usual life expectancy. Trees in this age class will still be developing significantly in spread but less significantly in height.
OM	Over Mature	Tree which has fully established & will no longer be able to continue increasing in size due to its age, it may be showing signs of decline such as localised dieback but does not need to do so by definition. However it should be expected that signs of structural deterioration will soon become apparent.
V	Veteran	Tree which is showing veteran tree characteristics such as very significant crown retrenchment, extensive internal cavitation & possess significant cultural, ecological &/or historical value. Size is a common indicator of these characteristics but is not an essential requirement, for example, ancient coppices may possess veteran tree characteristics but may have a stunted form. Age is a stronger indicator but again not essential as veteran characteristics can be encouraged in younger trees.
-	Minor Deadwood	Deadwood under 50 mm in diameter
-	Major Deadwood	Deadwood which is equal to or greater than 50 mm in diameter
-	Retrenchment	Retrenchment: progressive reduction in the size of the crown of an old tree, by means of the dieback or breakage of twigs and small branches, accompanied by the enhanced development of the lower or inner parts of the crown.