

North Manchester General Hospital
- Visual Specification for Temporary Car Parks
and Multi-Storey Car Park

Rev	Description	Date	Edited By	Checked By	Approved By
00	Issued for Comments	04/12/20	SK	JG	JG
01	Revised	17/12/20	LB	JG	JG
P01	Issued for Review	21/05/21	YZ	JG	JG
P02	Issue for Stage 4	20/07/21	YZ	JG	JG
C01	Issue for Stage 5	06/06/22	PL	JG	JG

Hard Materials For Temporary Car Parks (TCP01, TCP05)



- Hard Materials**
To be read in conjunction with Landscape Specification
20200-GIL-MSCP-EX-SP-L-0501
- 1. **Q23/225** Resin bound gravel to footpath in TCP01. Colour options. From top to bottom, Blue Granite (in the specification).
 - 2. **Q50/190** Steel Bollard in TCP01, galvanised or powder coated finish (RAL7016) with reflection band. Finish to be confirmed by MFT.
 - 3. **Q41/130** Pedestrian Guardrail in TCP05, galvanised.

Hard Materials For Multi-Storey Car Park (MSCP)



- Hard Materials**
To be read in conjunction with Landscape Specification
20200-GIL-MSCP-EX-SP-L-0501
- 1. Precast concrete steps at MSCP with contrast nosing to BS 8300
 - 2. **Q41/240** Steel handrails to steps and ramp at MSCP, galvanised or powder coated (RAL7016). Finish to be confirmed by MFT.
 - 3. **Q25/320** Corduroy hazard warning paving to top and bottom of steps at MSCP.
 - 4. **Q41/130** Pedestrian Guardrail next to MSCP, galvanised.
 - 5. **Q50/210** External cycle stands to the main entrance of MSCP, stainless steel with baseplate.

Soft Materials For MSCP

Planting for MSCP

To be read in conjunction with Landscape Specification

20200-GIL-MSCP-EX-SP-L-0501 and Planting Plan 20200-GIL-INZ-EX-DR-L-0402

- 1. Trees Proposed - Acer Rubrum
- 2. Trees Proposed - Prunus serrula
- 3. Wildflower Seeding
- 4-10. Ornamental Planting

Species Include:

Lavandula, Mahonia japonica, Prunus mugo mops, Euonymus fortunei Emerald Gaiety, Hebe Sutherlandii, Viburnum, Vinca Minor.

