





PLAN AT 6th FLOOR LEVEL Scale 1:100

VRF SCHEDULE									
Superior Air Solutions Ltd ventilation solutions Project No Project Name Schedule Ref: Revision Purpose of Revision C1210 Bridgewater House VRF Schedule - 6th Floor Level P2 For Comment									
FCU Reference	Room Ref	Indoor Unit Type	Indoor Unit Model	Unit Capacity	Unit Capacity	Electrical		Outdoor Unit Model	Outdoor Unit Reference
				Cooling	Heating	(V / Hz)	(A)		
(kW)				(kW)	(kW)				
AC1-001	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50	PURY-P700YSNW-A1	CU-001
AC1-002	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-003	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-004	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-005	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-006	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-007	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-008	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-009	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-010	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC1-011	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50	PURY-P350YSNW-A	CU-002
AC2-001	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC2-002	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC2-003	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC2-004	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC2-005	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
AC2-006	Open Plan	FCU	PEFY-P63VMA-E	7.10	8.00	230	50		
Designer/Approved				Description				Date	
PS CH				Initial schedule issued for comment				17.05.22	
PS CH				schedule update				16.06.22	

HRU SCHEDULE									
Superior Air Solutions Ltd ventilation solutions Project No Project Name Schedule Ref: Revision Purpose of Revision C1210 Bridgewater House HRU Schedule - 6th Floor Level P1 For Comment									
FCU Reference	Room Ref	Indoor Unit Type	Indoor Unit Model	Air Volume (SP4)		Electrical		Outdoor Unit Model	Outdoor Unit Reference
				(m3/h)	(l/s)	(V / Hz)	(A)		
HRU-001 to 005	Open Plan	Lossnay HRU	LGH-100RVX-E	1000.00	278.00	230	50	N/A	N/A
Designer/Approved				Description				Date	
PS CH				Initial schedule issued for comment				17.05.22	



- EQUIPMENT LEGEND
- VRF TYPE IN THE CEILING FAN COIL UNIT
 - HEAT RECOVERY UNIT
 - SWIRL TYPE SUPPLY AIR GRILLE
 - DX REFRIGERATION PIPEWORK
 - VOLUME CONTROL DAMPER
 - AC REMOTE CONTROLLER
 - AC CENTRAL CONTROLLER
 - AIR VOLUME l/s
 - AIR VELOCITY m/s
 - PRESSURE DROP Pa/m
 - DUCT SIZE mm

- CONDENSING UNIT SCHEDULE
- CU-001 SYSTEM 1 - PURY-P700YSNW-A1
 - CU-002 SYSTEM 2 - PURY-P350YSNW-A1
- NOTES
- CONDENSATE DRAIN HEADER TO BE 1 1/2" PLASTIC PIPE WITH ALL FAN COILS CONNECTION TO HEADER IN 3/2" PIPE.
 - CONDENSATE DRAINS TO CONNECT TO LOCAL DRAIN STACK WITHIN THE TOILET AREA.
 - FIRE DAMPER TO BE INSTALLED AS REQUIRED BY THE FIRE STRATEGY LAYOUTS.
 - PRIMARY AIR VOLUMES FROM HEAT RECOVERY UNITS ARE BASED ON SP4 SETTING
 - SECONDARY AIR VOLUMES FROM FAN COIL UNITS ARE BASED ON MEDIUM SETTING

Revision P1 P2

Client AXI

Project Bridgewater House
Whitworth Street
Manchester

Title Ventilation and Comfort Cooling Layout
6th Floor Level

Superior Air Solutions Ltd
14 Booths Drive, Urmston, Manchester. M41 8PF.
Tel: 0161 613 2215
www.superiorairsolutions.co.uk

Drawn by P.S. Checked by C.H. Scale 1:50 Sheet Size A1 Date 17.10.17

Drawing No. C1210/M02 Revision P2