

Curtins Consulting

Merchant Exchange
17-19 Whitworth Street West
Manchester M1 5WG

Date 02/07/2022 09:41
File Proposed Drainage East 2...

Micro Drainage

Designed by Marta.Wolska
Checked by

Network 2018.1.1

Page 3



STORM SEWER DESIGN by the Modified Rational Method

Network Design Table for SW East

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
SB10.000	11.210	0.430	26.1	0.017	5.00	0.0	0.600	o	225	Pipe/Conduit	
SB10.001	7.771	0.300	25.9	0.023	0.00	0.0	0.600	o	225	Pipe/Conduit	
SB10.002	7.461	0.300	24.9	0.016	0.00	0.0	0.600	o	225	Pipe/Conduit	
SB10.003	5.631	0.056	100.0	0.035	0.00	0.0	0.600	o	225	Pipe/Conduit	
SB11.000	11.900	0.238	50.0	0.026	5.00	0.0	0.600	o	150	Pipe/Conduit	
SB12.000	7.758	0.140	55.4	0.047	5.00	0.0	0.600	o	150	Pipe/Conduit	
SB11.001	7.422	0.074	100.3	0.054	0.00	0.0	0.600	o	150	Pipe/Conduit	
SB1.009	8.659	0.022	393.6	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
SB1.010	6.486	0.016	400.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
SB1.011	8.391	0.140	60.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	
SB1.012	19.412	0.216	90.0	0.000	0.00	0.0	0.600	o	300	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
SB10.000	0.00	5.07	73.819	0.017	0.0	0.0	0.0	2.57	102.3	0.0
SB10.001	0.00	5.12	73.389	0.040	0.0	0.0	0.0	2.58	102.6	0.0
SB10.002	0.00	5.17	73.089	0.056	0.0	0.0	0.0	2.63	104.8	0.0
SB10.003	0.00	5.24	72.789	0.091	0.0	0.0	0.0	1.31	52.0	0.0
SB11.000	0.00	5.14	72.740	0.026	0.0	0.0	0.0	1.43	25.2	0.0
SB12.000	0.00	5.10	73.090	0.047	0.0	0.0	0.0	1.35	23.9	0.0
SB11.001	0.00	5.26	72.502	0.127	0.0	0.0	0.0	1.00	17.7	0.0
SB1.009	0.00	8.01	71.300	0.774	0.0	0.0	0.0	0.79	55.6	0.0
SB1.010	0.00	8.15	71.278	0.774	0.0	0.0	0.0	0.78	55.1	0.0
SB1.011	0.00	8.22	71.262	0.774	0.0	0.0	0.0	2.03	143.7	0.0
SB1.012	0.00	8.41	71.122	0.774	0.0	0.0	0.0	1.66	117.2	0.0

©1982-2018 Innovyze

Curtins Consulting		Page 6
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 02/07/2022 09:41 File Proposed Drainage East 2...	Designed by Marta.Wolska Checked by	
Micro Drainage	Network 2018.1.1	

PIPELINE SCHEDULES for SW East

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
SB1.000	o	150	SB1A	79.617	78.860	0.607	Open Manhole	450
SB1.001	o	300	SB1	79.583	78.430	0.853	Open Manhole	1200
SB2.000	o	225	SB2	79.610	78.600	0.785	Open Manhole	450
SB2.001	o	225	SB3	79.692	78.408	1.059	Open Manhole	1200
SB1.002	o	300	SB4	79.618	78.174	1.144	Open Manhole	1500
SB3.000	o	150	SB4A	79.686	78.550	0.986	Open Manhole	450
SB1.003	o	300	JUN	79.605	78.163	1.142	Junction	
SB4.000	o	150	SB9	79.605	78.480	0.975	Open Manhole	450
SB4.001	o	225	SB10	79.605	78.328	1.052	Open Manhole	450
SB4.002	o	225	SB11	79.702	78.108	1.369	Open Manhole	1200
SB5.000	o	150	SB13A	79.722	78.550	1.022	Open Manhole	450

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
SB1.000	28.049	100.2	SB1	79.583	78.580	0.853	Open Manhole	1200
SB1.001	14.050	54.9	SB4	79.618	78.174	1.144	Open Manhole	1500
SB2.000	19.199	100.0	SB3	79.692	78.408	1.059	Open Manhole	1200
SB2.001	15.918	100.0	SB4	79.618	78.249	1.144	Open Manhole	1500
SB1.002	3.021	300.0	JUN	79.605	78.164	1.141	Junction	
SB3.000	5.784	24.4	JUN	79.605	78.313	1.142	Junction	
SB1.003	60.557	300.0	SB13	79.653	77.961	1.392	Open Manhole	1500
SB4.000	7.680	99.7	SB10	79.605	78.403	1.052	Open Manhole	450
SB4.001	33.049	150.0	SB11	79.702	78.108	1.369	Open Manhole	1200
SB4.002	24.980	145.2	SB13	79.653	77.936	1.492	Open Manhole	1500
SB5.000	12.159	100.0	SB13	79.653	78.428	1.075	Open Manhole	1500

Curtins Consulting		Page 11
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 02/07/2022 09:41	Designed by Marta.Wolska	
File Proposed Drainage East 2...	Checked by	
Micro Drainage		Network 2018.1.1

Online Controls for SW East

Complex Manhole: SB24, DS/PN: SB1.011, Volume (m³): 9.5

Hydro-Brake® Optimum

Unit Reference	MD-SHE-0279-4800-1800-4800
Design Head (m)	1.800
Design Flow (l/s)	48.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	279
Invert Level (m)	71.262
Minimum Outlet Pipe Diameter (mm)	300
Suggested Manhole Diameter (mm)	2100

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.800	48.0	Kick-Flo®	1.222	39.8
Flush-Flo™	0.559	48.0	Mean Flow over Head Range	-	41.1

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	8.8	1.200	40.7	3.000	61.4	7.000	92.7
0.200	28.8	1.400	42.5	3.500	66.2	7.500	95.9
0.300	45.0	1.600	45.4	4.000	70.6	8.000	98.9
0.400	47.1	1.800	48.0	4.500	74.8	8.500	101.9
0.500	47.9	2.000	50.5	5.000	78.7	9.000	104.8
0.600	48.0	2.200	52.9	5.500	82.4	9.500	107.6
0.800	47.1	2.400	55.1	6.000	86.0		
1.000	45.3	2.600	57.3	6.500	89.4		

Orifice

Diameter (m) 0.145 Discharge Coefficient 0.600 Invert Level (m) 72.462

Curtins Consulting			Page 13						
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG									
Date 02/07/2022 09:41		Designed by Marta.Wolska							
File Proposed Drainage East 2...		Checked by							
Micro Drainage		Network 2018.1.1							
1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for SW East									
Simulation Criteria									
Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000									
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000									
Hot Start Level (mm) 0 Inlet Coefficient 0.800									
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000									
Foul Sewage per hectare (l/s) 0.000									
Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0									
Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0									
Synthetic Rainfall Details									
Rainfall Model FSR Ratio R 0.348									
Region England and Wales Cv (Summer) 0.750									
M5-60 (mm) 18.500 Cv (Winter) 0.840									
Margin for Flood Risk Warning (mm) 300.0									
Analysis Timestep 2.5 Second Increment (Extended)									
DTS Status OFF									
DVD Status ON									
Inertia Status ON									
Profile(s) Summer and Winter									
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440									
Return Period(s) (years) 1, 30, 100									
Climate Change (%) 0, 0, 40									
Water									
PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Level (m)
SB1.000	SB1A	15 Winter	1	+0%	100/15 Summer				78.891
SB1.001	SB1	15 Winter	1	+0%	100/15 Summer				78.473
SB2.000	SB2	15 Winter	1	+0%	100/15 Summer				78.638
SB2.001	SB3	15 Winter	1	+0%	100/15 Summer				78.472
SB1.002	SB4	15 Winter	1	+0%	30/15 Summer				78.296
SB3.000	SB4A	15 Winter	1	+0%	100/15 Summer				78.583
SB1.003	JUN	15 Winter	1	+0%	30/15 Winter				78.290
SB4.000	SB9	15 Winter	1	+0%	100/15 Summer				78.518
SB4.001	SB10	15 Winter	1	+0%	100/15 Summer				78.379
SB4.002	SB11	15 Winter	1	+0%	30/15 Summer				78.185
SB5.000	SB13A	15 Winter	1	+0%	100/15 Summer				78.593
SB1.004	SB13	15 Winter	1	+0%	30/15 Summer				78.044
SB6.000	SB14A	15 Winter	1	+0%	100/15 Summer				78.592
SB6.001	SB14B	15 Winter	1	+0%	30/15 Winter				78.427
©1982-2018 Innovyze									

SW East

SB1.005	SB14	15	Winter	1	+0%	30/15	Summer	77.993
SB7.000	SB16	15	Winter	1	+0%			78.043
SB8.000	SB18	15	Winter	1	+0%			78.046
SB1.006	SB15	15	Winter	1	+0%	100/15	Summer	73.673
SB9.000	SB19A	15	Winter	1	+0%	100/15	Summer	74.334
SB9.001	SB19B	15	Winter	1	+0%	30/15	Summer	74.155
SB1.007	SB19	15	Winter	1	+0%	100/15	Summer	73.451
SB1.008	SB20	15	Winter	1	+0%	100/15	Summer	73.176
SB10.000	SB21A	15	Winter	1	+0%			73.843
SB10.001	SB21B	15	Winter	1	+0%	100/60	Winter	73.424
SB10.002	SB21	15	Winter	1	+0%	100/30	Winter	73.131
SB10.003	SB22	15	Winter	1	+0%	100/15	Summer	72.873
SB11.000	SB23A	15	Winter	1	+0%	30/15	Summer	72.777
SB12.000	SB23B	15	Winter	1	+0%	100/15	Summer	73.144
SB11.001	SB23C	15	Winter	1	+0%	30/15	Summer	72.619
SB1.009	SB23	15	Winter	1	+0%	1/15	Summer	71.659
SB1.010	TANK	2	Winter	1	+0%	30/15	Summer	71.546
SB1.011	SB24	30	Winter	1	+0%	30/15	Summer	71.524
SB1.012	CB1	30	Winter	1	+0%			71.254

SB1.005	SB14	-0.101	0.000	0.77	43.5	OK
SB7.000	SB16	-0.107	0.000	0.18	2.9	OK
SB8.000	SB18	-0.104	0.000	0.20	3.3	OK
SB1.006	SB15	-0.167	0.000	0.40	47.8	OK
SB9.000	SB19A	-0.091	0.000	0.32	5.3	OK
SB9.001	SB19B	-0.070	0.000	0.55	8.5	OK
SB1.007	SB19	-0.162	0.000	0.43	55.4	OK
SB1.008	SB20	-0.177	0.000	0.35	55.5	OK
SB10.000	SB21A	-0.201	0.000	0.02	2.1	OK
SB10.001	SB21B	-0.190	0.000	0.06	4.5	OK
SB10.002	SB21	-0.183	0.000	0.08	6.1	OK
SB10.003	SB22	-0.141	0.000	0.29	9.7	OK
SB11.000	SB23A	-0.113	0.000	0.14	3.2	OK
SB12.000	SB23B	-0.096	0.000	0.28	5.8	OK
SB11.001	SB23C	-0.033	0.000	0.95	14.4	OK
SB1.009	SB23	0.059	0.000	2.09	77.0	SURCHARGED
SB1.010	TANK 2	-0.032	0.000	0.97	40.8	OK
SB1.011	SB24	-0.038	0.000	0.44	40.9	OK

Curtins Consulting		Page 17
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 02/07/2022 09:41		
File Proposed Drainage East 2...		
Micro Drainage		Network 2018.1.1
<u>30 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for SW East</u>		
<u>Simulation Criteria</u>		
Areal Reduction Factor 1.000 Additional Flow - % of Total Flow 0.000		
Hot Start (mins) 0 MADD Factor * 10m³/ha Storage 2.000		
Hot Start Level (mm) 0 Inlet Coefficient 0.800		
Manhole Headloss Coeff (Global) 0.500 Flow per Person per Day (l/per/day) 0.000		
Foul Sewage per hectare (l/s) 0.000		
Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0		
Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0		
<u>Synthetic Rainfall Details</u>		
Rainfall Model FSR Ratio R 0.348		
Region England and Wales Cv (Summer) 0.750		
M5-60 (mm) 18.500 Cv (Winter) 0.840		
Margin for Flood Risk Warning (mm) 300.0		
Analysis Timestep 2.5 Second Increment (Extended)		
DTS Status OFF		
DVD Status ON		
Inertia Status ON		
Profile(s) Summer and Winter		
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440		
Return Period(s) (years) 1, 30, 100		
Climate Change (%) 0, 0, 40		

Curtins Consulting		Page 18
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 02/07/2022 09:41	Designed by Marta.Wolska	
File Proposed Drainage East 2...	Checked by	
Micro Drainage		Network 2018.1.1


30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for SW East

PN	US/MH Name	Surcharged		Flooded		Pipe Flow (l/s)	Status	Level Exceeded
		Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)			
SB1.000	SB1A	-0.101	0.000	0.23		3.8	OK	
SB1.001	SB1	-0.192	0.000	0.14		17.5	OK	
SB2.000	SB2	-0.165	0.000	0.16		7.4	OK	
SB2.001	SB3	-0.078	0.000	0.50		23.0	OK	
SB1.002	SB4	0.054	0.000	0.65		33.0	SURCHARGED	
SB3.000	SB4A	-0.097	0.000	0.27		8.1	OK	
SB1.003	JUN	0.001	0.000	0.88		55.9	SURCHARGED*	
SB4.000	SB9	-0.088	0.000	0.35		5.4	OK	
SB4.001	SB10	-0.116	0.000	0.31		12.5	OK	
SB4.002	SB11	0.081	0.000	0.61		24.1	SURCHARGED	
SB5.000	SB13A	-0.079	0.000	0.45		7.2	OK	
SB1.004	SB13	0.199	0.000	1.40		77.9	SURCHARGED	
SB6.000	SB14A	-0.082	0.000	0.41		6.8	OK	
SB6.001	SB14B	0.008	0.000	0.90		22.7	SURCHARGED	

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for SW East

									Water
	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Level
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	(m)
SB1.005	SB14	15 Winter	30	+0%	30/15 Summer				78.229
SB7.000	SB16	15 Winter	30	+0%					78.071
SB8.000	SB18	15 Winter	30	+0%					78.075
SB1.006	SB15	15 Winter	30	+0%	100/15 Summer				73.766
SB9.000	SB19A	15 Winter	30	+0%	100/15 Summer				74.412
SB9.001	SB19B	15 Winter	30	+0%	30/15 Summer				74.295
SB1.007	SB19	15 Winter	30	+0%	100/15 Summer				73.571
SB1.008	SB20	15 Winter	30	+0%	100/15 Summer				73.259
SB10.000	SB21A	15 Winter	30	+0%					73.854
SB10.001	SB21B	15 Winter	30	+0%	100/60 Winter				73.449
SB10.002	SB21	15 Winter	30	+0%	100/30 Winter				73.162
SB10.003	SB22	15 Winter	30	+0%	100/15 Summer				72.951
SB11.000	SB23A	15 Winter	30	+0%	30/15 Summer				73.066
SB12.000	SB23B	15 Winter	30	+0%	100/15 Summer				73.182
SB11.001	SB23C	15 Winter	30	+0%	30/15 Summer				73.037
SB1.009	SB23	30 Winter	30	+0%	1/15 Summer				72.239
SB1.010	TANK 2	30 Winter	30	+0%	30/15 Summer				72.124
SB1.011	SB24	30 Winter	30	+0%	30/15 Summer				72.101
SB1.012	CB1	120 Summer	30	+0%					71.267

PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Pipe	Status	Level
		Depth (m)	Volume (m³)			Flow (l/s)		Exceeded
SB1.005	SB14	0.135	0.000	1.71		96.5	SURCHARGED	
SB7.000	SB16	-0.079	0.000	0.45		7.2	OK	
SB8.000	SB18	-0.075	0.000	0.50		8.1	OK	
SB1.006	SB15	-0.074	0.000	0.91		108.3	OK	
SB9.000	SB19A	-0.013	0.000	0.76		12.8	OK	
SB9.001	SB19B	0.070	0.000	1.40		21.5	SURCHARGED	
SB1.007	SB19	-0.043	0.000	1.00		127.4	OK	
SB1.008	SB20	-0.093	0.000	0.82		127.9	OK	
SB10.000	SB21A	-0.190	0.000	0.06		5.1	OK	
SB10.001	SB21B	-0.165	0.000	0.16		12.4	OK	
SB10.002	SB21	-0.152	0.000	0.23		17.5	OK	
SB10.003	SB22	-0.063	0.000	0.86		28.7	OK	
SB11.000	SB23A	0.176	0.000	0.34		7.8	SURCHARGED	
SB12.000	SB23B	-0.058	0.000	0.68		14.1	OK	
SB11.001	SB23C	0.385	0.000	2.47		37.7	SURCHARGED	
SB1.009	SB23	0.639	0.000	4.31		159.0	SURCHARGED	
SB1.010	TANK 2	0.546	0.000	1.23		51.7	SURCHARGED	
SB1.011	SB24	0.540	0.000	0.51		48.0	SURCHARGED	

Curtins Consulting		Page 21
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 02/07/2022 09:41 File Proposed Drainage East 2...		
Designed by Marta.Wolska Checked by		
Micro Drainage		Network 2018.1.1

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for SW East

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	1	Number of Storage Structures	1	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.348
Region	England and Wales	Cv (Summer)	0.750
M5-60 (mm)	18.500	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
SB1.000	SB1A	15 Winter	100	+40%	100/15 Summer				79.402
SB1.001	SB1	15 Winter	100	+40%	100/15 Summer				79.371
SB2.000	SB2	15 Winter	100	+40%	100/15 Summer				79.463
SB2.001	SB3	15 Winter	100	+40%	100/15 Summer				79.442
SB1.002	SB4	15 Winter	100	+40%	30/15 Summer				79.353
SB3.000	SB4A	15 Winter	100	+40%	100/15 Summer				79.319
SB1.003	JUN	15 Winter	100	+40%	30/15 Winter				78.464
SB4.000	SB9	15 Winter	100	+40%	100/15 Summer				79.199
SB4.001	SB10	15 Winter	100	+40%	100/15 Summer				79.175
SB4.002	SB11	15 Winter	100	+40%	30/15 Summer				79.126
SB5.000	SB13A	15 Winter	100	+40%	100/15 Summer				79.019
SB1.004	SB13	15 Winter	100	+40%	30/15 Summer				78.967
SB6.000	SB14A	15 Winter	100	+40%	100/15 Summer				79.552
SB6.001	SB14B	15 Winter	100	+40%	30/15 Winter				79.476

©1982-2018 Innovyze

Curtins Consulting		Page 22
Merchant Exchange 17-19 Whitworth Street West Manchester M1 5WG		
Date 02/07/2022 09:41	Designed by Marta.Wolska	
File Proposed Drainage East 2...	Checked by	
Micro Drainage		Network 2018.1.1

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for SW East

PN	US/MH Name	Surcharged		Flooded	Flow / Cap.	Overflow (l/s)	Pipe	Status	Level
		Depth (m)	Volume (m³)	Flow			Flow (l/s)		Exceeded
SB1.000	SB1A	0.392	0.000	0.36		6.2	FLOOD	RISK	
SB1.001	SB1	0.641	0.000	0.18		22.4	FLOOD	RISK	
SB2.000	SB2	0.638	0.000	0.22		10.3	FLOOD	RISK	
SB2.001	SB3	0.809	0.000	0.60		27.4	FLOOD	RISK	
SB1.002	SB4	0.879	0.000	0.94		48.0	FLOOD	RISK	
SB3.000	SB4A	0.619	0.000	0.39		11.8	SURCHARGED		
SB1.003	JUN	0.001	0.000	1.21		77.4	SURCHARGED*		
SB4.000	SB9	0.569	0.000	0.52		8.0	SURCHARGED		
SB4.001	SB10	0.622	0.000	0.45		17.8	SURCHARGED		
SB4.002	SB11	0.794	0.000	1.01		39.9	SURCHARGED		
SB5.000	SB13A	0.319	0.000	0.74		12.0	SURCHARGED		
SB1.004	SB13	0.807	0.000	2.23		123.9	SURCHARGED		
SB6.000	SB14A	0.852	0.000	0.69		11.5	FLOOD	RISK	
SB6.001	SB14B	0.959	0.000	1.42		35.8	FLOOD	RISK	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for SW East

									Water
	US/MH		Return	Climate	First (X)	First (Y)	First (Z)	Overflow	Level
PN	Name	Storm	Period	Change	Surcharge	Flood	Overflow	Act.	(m)
SB1.005	SB14	15 Winter	100	+40%	30/15 Summer				78.632
SB7.000	SB16	15 Winter	100	+40%					78.104
SB8.000	SB18	15 Winter	100	+40%					78.112
SB1.006	SB15	15 Winter	100	+40%	100/15 Summer				75.142
SB9.000	SB19A	15 Winter	100	+40%	100/15 Summer				74.902
SB9.001	SB19B	15 Winter	100	+40%	30/15 Summer				74.777
SB1.007	SB19	15 Winter	100	+40%	100/15 Summer				74.654
SB1.008	SB20	15 Winter	100	+40%	100/15 Summer				74.053
SB10.000	SB21A	15 Winter	100	+40%					73.868
SB10.001	SB21B	60 Winter	100	+40%	100/60 Winter				73.862
SB10.002	SB21	60 Winter	100	+40%	100/30 Winter				73.858
SB10.003	SB22	60 Winter	100	+40%	100/15 Summer				73.853
SB11.000	SB23A	15 Winter	100	+40%	30/15 Summer				74.010
SB12.000	SB23B	15 Winter	100	+40%	100/15 Summer				74.102
SB11.001	SB23C	15 Winter	100	+40%	30/15 Summer				73.945
SB1.009	SB23	60 Winter	100	+40%	1/15 Summer				73.847
SB1.010	TANK 2	60 Winter	100	+40%	30/15 Summer				73.704
SB1.011	SB24	60 Winter	100	+40%	30/15 Summer				73.561
SB1.012	CB1	60 Winter	100	+40%					71.351

PN	US/MH Name	Surcharged	Flooded	Flow / Cap.	Overflow (l/s)	Pipe	Status	Level
		Depth (m)	Volume (m³)			Flow (l/s)		Exceeded
SB1.005	SB14	0.538	0.000	2.86		161.9	SURCHARGED	
SB7.000	SB16	-0.046	0.000	0.81		13.0	OK	
SB8.000	SB18	-0.038	0.000	0.90		14.7	OK	
SB1.006	SB15	1.302	0.000	1.48		177.0	SURCHARGED	
SB9.000	SB19A	0.477	0.000	1.25		20.9	SURCHARGED	
SB9.001	SB19B	0.552	0.000	2.32		35.5	SURCHARGED	
SB1.007	SB19	1.041	0.000	1.53		195.5	FLOOD RISK	
SB1.008	SB20	0.701	0.000	1.24		193.6	SURCHARGED	
SB10.000	SB21A	-0.176	0.000	0.11		9.3	OK	
SB10.001	SB21B	0.248	0.000	0.16		12.0	SURCHARGED	
SB10.002	SB21	0.544	0.000	0.22		16.8	SURCHARGED	
SB10.003	SB22	0.839	0.000	0.82		27.4	SURCHARGED	
SB11.000	SB23A	1.120	0.000	0.54		12.3	SURCHARGED	
SB12.000	SB23B	0.862	0.000	1.08		22.3	SURCHARGED	
SB11.001	SB23C	1.293	0.000	3.81		58.1	SURCHARGED	
SB1.009	SB23	2.247	0.000	5.18		191.1	SURCHARGED	
SB1.010	TANK 2	2.126	0.000	2.35		98.7	SURCHARGED	
SB1.011	SB24	1.999	0.000	1.02		95.4	SURCHARGED	

