



LUMINAIRE SCHEDULE

REFERENCE	MODEL & MANUFACTURER	IMAGE
L1	BOLLARD LUMINAIRE 1000MM HEIGHT 4000K, 13.8W, 1512lm, 80.8lm/W, CRI>80	
L2	ASYMMETRIC BOLLARD LUMINAIRE 1000MM HEIGHT, 180° DISTRIBUTION 4000K, 9.1W, 687lm, 75.5lm/W, CRI>80	
L3	WALL-MOUNTED DOWNLIGHT 4000K, 17W, 1373lm, 80.8lm/W, CRI>80	
L4	WALL-MOUNTED BULKHEAD WITH HOOD 4000K, 14.2W, 1008lm, 71lm/W, CRI>80	
L5	POLE-TOP LUMINAIRE 5000MM HEIGHT, WIDE FLOOD DISTRIBUTION 4000K, 35W, 2862lm, 81.8lm/W, CRI>80	
L6	SURFACE MOUNTED LINEAR FITTING 1000MM LENGTH, WIDE BEAM 4000K, 22W, 3020lm, 137.3lm/W, CRI>80	

INDICATIVE IMAGES - MANUFACTURER TBC

Notes:

- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS, SPECIFICATIONS, SCHEDULES AND BUILDING MODELS INCLUDING SCHEMATICS. THE CONTRACTOR SHALL REFER TO THE ARCHITECTS DRAWINGS FOR SETTING OUT DETAILS/DIMENSIONS.
- THE ELECTRICAL SERVICES INSTALLATIONS ARE DESIGNED TO COMPLY FULLY WITH THE BUILDING REGULATIONS STANDARDS, AND ARE DESIGNED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE CIBSE GUIDES, AS ISSUED BY THE CHARTERED INSTITUTION OF BUILDING SERVICES ENGINEERS.
- REFER TO THE ARCHITECTS DRAWINGS FOR DETAILS OF ALL BUILDING FIRE COMPARTMENTATION BARRIERS. ANY SERVICES PENETRATING THE FIRE COMPARTMENT SHALL BE FIRE SEALED USING THE APPROVED PENETRATION DETAIL.
- ALL PENETRATIONS THROUGH FIRE WALLS SHALL BE FIRE STOPPED TO MAINTAIN THE FIRE INTEGRITY OF THE FIRE WALL. ALL SLAB PENETRATIONS TO HAVE FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE RATED SLAB. THE CONTRACTOR SHALL MAKE GOOD ALL PENETRATIONS TO THE APPROVAL OF BUILDING CONTROL.
- THIS DRAWING SHALL NOT BE USED FOR INSTALLATION. THE ELECTRICAL SERVICES CONTRACTOR SHALL BE RESPONSIBLE FOR PRODUCTION OF COORDINATED INSTALLATION DRAWINGS CHECKED WITH ACTUAL SITE DIMENSIONS.
- ALL DIMENSIONS WHERE INDICATED ARE IN MILLIMETRES UNLESS STATED OTHERWISE. ALL DIMENSIONS SHALL BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY WORKS.
- ALL CABLES TO BE WITHIN VOIDS UNLESS OTHERWISE STATED.
- THE EMERGENCY LIGHTING SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH BS5266 PART 1.
- SIGNAGE SHALL BE TO BS5499 PART 4.

Legend:

- CIRCULAR LUMINAIRE
- CIRCULAR WALL LUMINAIRE
- COLUMN LUMINAIRE

P04	08/06/22	AUJ	DMS	MAS	Incorporating comments and new site layout
P03	05/05/22	DMS	DMS	MAS	Existing retained column lighting added
P02	28/04/22	AUJ	DMS	MAS	Updated for new site layout
P01	08/04/22	ARG	AUJ	MAS	Initial Issue

Rev	Date	By	Chk	Aprvd	Description
-----	------	----	-----	-------	-------------

PROJECT
Land to the West of Rodney Street
Manchester

CLIENT



www.methodllp.com Bristol Tel: 0117 203 5160

DRAWING TITLE
External Lighting Layout
Site Plan

STATUS
S2 - FOR INFORMATION

DATE	SCALE	DRWN BY	CHK BY	APVD BY
04.04.22	1:250 - A1	ARG	AUJ	MAS

DRAWING NUMBER	REVISION No.
RODSTA-MET-ZZ-00-DR-E-6350	S2 - P03

Scaling Note: Do NOT scale from this drawing.

SAFETY, HEALTH & ENVIRONMENTAL INFORMATION
FOR DETAILS OF SITE-WIDE AND GENERAL RISKS, TO BE READ IN CONJUNCTION WITH THESE NOTES, SEE THE CONTRACT DOCUMENTS AND, WHERE WORKS ARE NOTIFIABLE, THE PRE-CONSTRUCTION INFORMATION
IN ADDITION TO THE RISKS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING RISKS AND INFORMATION:
CONSTRUCTION: C1. C2. C3.
DISMANTLING/DEMOLITION (FUTURE): D1. D2. D3.
IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION. INSTALLATION DRAWINGS SHOULD BE PRODUCED BY THE CONTRACTOR AND AGREED WITH THE CLIENT TEAM PRIOR TO ANY INSTALLATION WORK

THIS DRAWING SHALL BE PRINTED IN COLOUR