

DO NOT SCALE FROM THIS DRAWING

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH
ALL OTHER HBL DRAWINGS ISSUED FOR THIS PROJECT

Node ID	Eastng (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Width (mm)	Node Type	MH Type	Connections	Link ID	IL (m)	Dia (mm)	Link Type
1	384630.129	390770.705	36.000	1.000				RWP		0	1.000	35.000	100 Circular
2	384639.943	390781.680	35.600	0.745	450		Manhole	Inspection Chamber		1	1.000	34.655	100 Circular
3	384638.889	390771.548	36.000	1.300				RWP		0	1.001	34.655	100 Circular
4	384644.395	390777.711	35.700	1.062			Junction			0	2.000	34.700	100 Circular
5	384643.016	390767.861	36.000	1.300				RWP		1	1.001	34.659	100 Circular
6	384648.522	390774.024	35.800	1.324			Junction			2	2.000	34.638	100 Circular
7	384647.142	390764.174	36.000	1.300				RWP		0	1.002	34.659	100 Circular
8	384652.648	390770.337	35.900	1.586			Junction			0	3.000	34.700	100 Circular
9	384648.129	390754.878	36.000	1.300				RWP		1	1.003	34.497	100 Circular
10	384657.816	390765.721	36.000	1.861	450		Manhole	Inspection Chamber		2	4.000	34.314	100 Circular
11	384661.269	390769.014	36.000	2.009	1050		Manhole	Precast Concrete		1	1.004	34.139	100 Circular
12	384650.490	390792.266	34.340	0.495				RWP		0	1.005	34.139	100 Circular
13	384642.838	390782.767	35.600	1.877	450		Manhole	Inspection Chamber		1	1.005	33.991	100 Circular
14	384655.798	390769.715	35.900	2.361	450		Manhole	Inspection Chamber		0	1.006	33.845	100 Circular
15	384662.064	390771.144	36.000	2.525	450		Manhole	Inspection Chamber		1	6.000	33.723	100 Circular
16	384659.118	390782.743	34.340	0.495				RWP		0	6.001	33.723	100 Circular
17	384666.306	390775.207	35.950	2.534	450		Manhole	Inspection Chamber		1	6.001	33.539	100 Circular
18	384662.108	390787.932	34.340	0.495				RWP		0	6.002	33.539	100 Circular
19	384667.157	390778.446	35.950	2.713	1050		Manhole	Precast Concrete		1	16.002	33.475	100 Circular
20	384659.118	390782.743	34.340	0.495				RWP		0	6.003	33.475	100 Circular
21	384666.306	390775.207	35.950	2.534	450		Manhole	Inspection Chamber		0	7.000	33.845	100 Circular
22	384653.065	390789.611	34.340	0.495				RWP		1	6.003	33.416	100 Circular
23	384653.984	390796.244	34.340	0.495				RWP		0	7.000	33.420	100 Circular
24	384667.563	390799.514	37.000	3.746	450		Manhole	Inspection Chamber		1	6.004	33.416	100 Circular
25	384661.746	390797.892	34.190	0.495			Manhole	Inspection Chamber		0	8.000	33.362	100 Circular
26	384663.064	390796.510	34.190	0.528	450		Manhole	Inspection Chamber		2	8.000	33.362	100 Circular
27	384667.563	390799.514	37.000	3.746	450		Manhole	Inspection Chamber		0	1.007	33.237	225 Circular
28	384683.745	390790.452	36.000	2.879	1200		Manhole	Precast Concrete		1	1.007	33.121	225 Circular
29	384683.745	390790.452	36.000	2.879	1200		Manhole	Precast Concrete		2	9.000	33.194	150 Circular
30	384653.065	390789.611	34.340	0.495				RWP		0	1.008	33.121	225 Circular
31	384653.984	390796.244	34.340	0.495				RWP		0	10.000	33.845	100 Circular
32	384658.850	390795.129	34.340	0.595			Junction			0	11.000	33.845	100 Circular
33	384661.746	390797.892	34.190	0.495			Manhole	Inspection Chamber		1	10.000	33.745	100 Circular
34	384663.064	390796.510	34.190	0.528	450		Manhole	Inspection Chamber		2	11.000	33.745	100 Circular
35	384661.746	390797.892	34.190	0.495			Manhole	Inspection Chamber		0	10.001	33.745	100 Circular
36	384663.064	390796.510	34.190	0.528	450		Manhole	Inspection Chamber		1	10.001	33.695	100 Circular
37	384667.563	390799.514	37.000	3.746	450		Manhole	Inspection Chamber		0	10.002	33.695	100 Circular
38	384663.064	390796.510	34.190	0.528	450		Manhole	Inspection Chamber		1	10.002	33.662	100 Circular
39	384667.563	390799.514	37.000	3.746	450		Manhole	Inspection Chamber		0	10.003	33.662	100 Circular
40	384671.339	390803.247	35.700	3.016	1200		Manhole	Precast Concrete		0	11.003	33.304	100 Circular
41	384671.339	390803.247	35.700	3.016	1200		Manhole	Precast Concrete		1	10.004	33.254	150 Circular
42	384671.339	390803.247	35.700	3.016	1200		Manhole	Precast Concrete		2	11.009	33.685	225 Circular
43	384671.339	390803.247	35.700	3.016	1200		Manhole	Precast Concrete		0	10.004	33.194	150 Circular
44	384675.876	390807.575	35.700	3.080	1200		Manhole	Precast Concrete		1	10.010	33.634	150 Circular
45	384675.876	390807.575	35.700	3.080	1200		Manhole	Precast Concrete		0	1.010	32.620	150 Circular
46	384675.876	390807.575	35.700	3.080	1200		Manhole	Precast Concrete		1	1.010	32.620	150 Circular
47	384675.876	390807.575	35.700	3.080	1200		Manhole	Precast Concrete		0	9.000	33.375	150 Circular
48	384675.876	390807.575	35.700	3.080	1200		Manhole	Precast Concrete		1	1.008	33.109	225 Circular
49	384675.876	390807.575	35.700	3.080	1200		Manhole	Precast Concrete		0	1.009	32.734	225 Circular

C03	DEC'20	AP	UPDATED IN LINE WITH DRAINAGE LAYOUT	AP	ALS
C02	DEC'20	AP	MINOR AMENDMENTS TO RWP LOCATIONS	AP	ALS
C01	JUL'20	HM	ISSUED FOR CONSTRUCTION	ALS	ALS
T1	NOV'19	AP	SCHEDULE UPDATED	AP	ALS
T0	SEP'19	HM	ISSUED FOR TENDER	ALS	ALS
REV.	DATE	DRAWN	DESCRIPTION	CHKD	APPRO
STATUS DESCRIPTION				STATUS	
APPROVED				A1	

APPROVED

A1



PROJECT

PROPOSED RESIDENTIAL DEVELOPMENT
THE LIMES, DIDSBURY

DRAWING TITLE

PROPOSED SURFACE WATER MANHOLE SCHEDULE

CLIENT

PROPERTY ALLIANCE GROUP

HBL REF. 6633	DATE JULY 2019	SCALE(S) 1:250	A1
DRAWN LB	CHECKED AP	APPROVED AP	
DRAWING No. 6633-HBL-XX-XX-DR-D-0302			REV. C03