

1:20 @ A3



1. Semi mature tree 30-35cm girth.
2. Root watering/aeration system - Rootrain Civic by Green Blue Urban, size and installation to manufacturer's recommendations. **Refer to spec clause Q31/512A**
3. Mulch layer around semi mature tree 75mm depth, 1500mm diameter. Mulch specification to match surrounding planting mulch. **Refer to spec clause Q31/493A**
4. Mulch layer around adjacent planting 50mm depth.
5. Landscape Topsoil. **Refer to spec clause Q28A/210**
6. Landscape Subsoil. Typically 950mm, 300mm minimum between base of rootball and top of deadman kerb stone. **Refer to spec clause Q28A/215**
7. Platypus tree anchoring system. Confirm with Manufacturer, recommended size of Deadman for each size of tree. **Refer to spec clause Q31/528**
8. Clean washed gravel drainage layer. **Refer to spec clause Q31/515A**
9. If sides of excavation are found to be Glacial Till, increase 500mm dimension from rootball to 700mm.
10. Soft landscape & tree trench adjacent to tree pit. Build up and specification varies according to location.
11. If when constructing the tree pit sandstone or clay alluvium/ glacial till is present at the base of tree pit. Contractor to carry out percolation test BRE 365.

- Do not scale from this drawing. All setting out, levels and dimensions to be agreed on site. The dimensions of all materials must be checked on site before use. The setting out drawing must be read with the relevant specification details and detail drawings. Order of construction and setting out to be agreed on site.
- This drawing is copyright protected and may not be reproduced in whole or part without written permission from the author. All rights reserved. © 2014 J. Stated. Sendings are present in the area. Contractor to establish the precise line and depth of all services prior to commencing any excavation work.
- All structural concrete building work to Engineer's details & specs. All drawings are British Standard drawings. All dimensions in millimetres unless otherwise stated.
- Dwgs not to be scaled. Use dimensioned measurements only. Contractor to check and confirm.
- All discrepancies must be reported to and resolved by the Landscape Architect before work commences.
- All works and materials to be in accordance with all relevant UK statutory legislation and to comply with all relevant Codes of Practice & British Standards.

All annotations in italics are provided by the Project engineers.

P01	24.03.26	Stage 3	SEW
Rev	Date	Reason for Issue	Chk

Scale Bar



Mayfield Medlock Ltd

Mayfield Phase 1_
Public Realm

Typical Soft Landscape Details

Tree Pit - <30cm Girth Tree

Project Number 0436	Status STAGE 3		
Scale at A3 1:20	Date 24.03.06		
Drawn by TH	Checked by SEW		
<table border="1"> <tr> <td>Drawing Number 0198_MAY-SEW-N01-1000-DR-L-203504</td> <td>Revision P01</td> </tr> </table>		Drawing Number 0198_MAY-SEW-N01-1000-DR-L-203504	Revision P01
Drawing Number 0198_MAY-SEW-N01-1000-DR-L-203504	Revision P01		