



1 EXT-307 REMOVABLE BENCH PLAN
1:10




2 EXT-307 REMOVABLE BENCH FRONT ELEVATION
1:10


Original height of bench seating 470mm



3 EXT-307 REMOVABLE BENCH SIDE ELEVATION 380mm
1:10




4 EXT-307 REMOVABLE BENCH SIDE ELEVATION 480mm
1:10



5 EXT-307 REMOVABLE BENCH SIDE ELEVATION 580mm
1:10




6 EXT-307 REMOVABLE BENCH ARMREST FIXING
1:4



7 EXT-305 REMOVABLE BENCH FIXING DETAIL
1:4

REV	DATE	DESCRIPTION
01	24/03/2024	ISSUED FOR CONSTRUCTION
02	24/03/2024	ISSUED FOR CONSTRUCTION - SERVICE VARIANTS
03	24/03/2024	ISSUED FOR CONSTRUCTION
04	24/03/2024	ISSUED FOR CONSTRUCTION
05	24/03/2024	ISSUED FOR CONSTRUCTION



NOTES:
1. BENCH PLANS DETAILS ARE INDICATIVE ONLY & REFER TO SUPPLIER'S SPECIFICATION FOR CONSTRUCTION. SUPPLIER'S SPECIFICATION TO FOLLOW SUPPLIER'S SPECIFICATION FOR THE PRODUCT.



POPULOUS[®]
14 BLANDFORD COURT, MANCHESTER, M4 6BT, ENGLAND
TELEPHONE: 0161 275 1111 FAX: 0161 275 1112
ALL RIGHTS RESERVED. NO PART OF THIS PUBLICATION MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT PERMISSION IN WRITING FROM POPULOUS.

PROJECT NAME:
MCFC - NORTH EXPANSION


DRAWING TITLE:
LANDSCAPE
STREET FURNITURE
TYPICAL BENCH DETAILS

STATUS	REV	DATE	PROJECT NO.
A5	5		4348
DATE	SCALE	SHEET	
24/03/2024	As indicated	A1	
DRAWN	CHECKED	APPROVED	
SA	TJ	MT	
PROJECT	LOCATION	DATE	TYPE
NSE-POP-ZZ-ZZ-DO-L		000694	C04

For the number of different bench height:

- 10 benches at 480mm seat height
- 2 benches at 380mm seat height
- 2 benches at 580mm seat height


Please find the markup below for locations.



EXT-305 REMOVABLE BENCHES



PRODUCT: SOLID SKIRT BLOCK BENCH
SUPPLIER: STREETLIFE
DIMENSIONS: 2050x600mm
(WITH BACKREST AND 316L STAINLESS STEEL ARMREST)



		In respect of street furniture the Contractor has included for the following. Please also refer to annex 1.6.54 for a marked up drawing
C 170	Street Furniture	Streetlife
		Straight bench Cumaru with galv support structure incl arm/back rests to City Square (14no.)
		Straight bench Cumaru with galv support structure incl arm/back rests to route to arena queueing area (2no – 4.1m and 14.35m)
		Shrub planters 900 x 1800 x 900 (13no.)
		Shrub planter (northeast hotel corner) 1200x 22470x400 (1no)
		Tree grilles to City Square (6no.)
		Clear bag litter bins Glassdon (14no.)
		The Contractor has not included for the picnic benches indicated near the squash centre ramp. Any loose furniture to be provided by the Employer

EXT-305	Removable bench - Type1	2050x600	Steel and FSC® Hardwood Slats, weatherproof treated	Brown
EXT-307	Removable bench - Type2	2050x600	Steel and FSC® Hardwood Slats, weatherproof treated	Brown
		Solid Skirt Block Bench	Streetlife	
		Solid Skirt Block Bench	Streetlife	11no. set of Hardwood backrest and 316L stainless steel armrest

Arm rests have been changed to comply with accessibility requirements, arm rest is still stainless but now includes timber capping over to the improve grip.

SOL-SKT-205-55-PC-CU-H48 + Full VBR

Straight bench in Cumaru with full Vertical Backrest, support structure in powder coated steel in RAL 7016 *Anthracite Grey*

Specifications:

- Material seat -**CU: untreated FSC® 100% Cumaru hardwood**
- Hardwood fading naturally to silver/grey, fully recyclable
- Dimension hardwood slats 7×7 cm, spacing slats 20 mm
- Material support structure -**PC: steel with a double powder coating in RAL 7016 *Anthracite Grey***
- Delivery: assembled
- Installation: invisibly surface mounted
- Designed by Streetlife in the Netherlands

ARM-T-ST-CU

Custom armrest in stainless steel (top mounted) with timber beam to top
ca. 30×6×20 cm (l×w×h)

Contract finish to seating base is galvanised in the contract , there will be an uplift if we need to finish in RAL 7016 Anthracite Grey to Populous drawing, please see derogation item description or confirm to retain the galvanised finish



Following images are for illustrative purposes only!



Solid Skirt Block Benches (custom design in quote)



Square tree planter in powder coated steel in RAL 7016 *Anthracite Grey*
ca. 180×90×90 cm (l×w×h)

Specifications:

- Material -**PC: Corten steel, finished with a double powder coating in RAL 7016 *Anthracite Grey***
- Fitted with drainage holes and internal provisions for root ball anchoring
- Treetec® Bottom Up recommended
- Delivery: fully assembled
- Installation: easy to relocate due to 7 cm high, recessed forklift provisions
- Designed by Streetlife in the Netherlands

