Hatch indicates S278 area

Pin kerb retained along interface of Highways works.

Pin kerb removed and paving made good once advertising sign is removed.

LOADING ONLY

LOADING ONLY

Allowance to be made for making good of existing paving following removal of temporary pin kerb.

01 02 03 04 05 06

E01 E04 E05 E06 E09 E10 E12

Key

MSCP Boundary

Republic Construction Boundary

S278 Permanent Highways

Edge Types

E01 Edge Type 01
Description: Proposed Rigid Metal Edge.
Please refer to spec clause Q10/200A

E04 Edge Type 04
Description: Proposed textured concrete flush kerb.
Please refer to spec clause Q10/112

E05 Edge Type 05
Description: Proposed textured concrete upstand kerb.
Please refer to refer to spec clause Q10/112A

E06 Edge Type 06
Description: Proposed textured concrete drop kerb for transition
Please refer to refer to spec clause Q10/112B

E09 Edge Type 09
Description: Concrete pin kerb.
Please refer to spec clause Q10/112C

E10 Edge Type 10
Description: Reclaimed Cobble Edging to Planting beds
Please refer to spec clause Q10/125A

E11 Edge Type 11
Description: Indicative slot drain to form edge. Refer to engineer's information.

E12 Edge Type 12
Description: Edge installed by Republic. Contractor to confirm.

Interface Detail Locations - Refer to the following drawings for details:
0198_MAY-SEW-N01-1000-DR-L-203102

01

General Notes

No implied licence exists. This drawing should not be used to calculate areas for any contractual purpose.
Do not scale this drawing for construction purposes. All dimensions to be checked on site by the contractor and such dimensions to be their responsibility.
All work must comply with relevant British Standards and Building Regulations requirements. Drawing errors and omissions to be reported to the architect.

Notes

Do not scale from this drawing

All setting out, levels and dimensions to be agreed on site.

The dimensions of all materials must be checked on site before being laid out.

This drawing must be read with the relevant specification clauses and detail drawings

Order of construction and setting out to be agreed on site.

This drawing is copyright protected and may not be reproduced in whole or part without written authority.

All Dimensions are in millimetres unless Otherwise Stated

Services are present in the area. Contractor to establish the precise line and Depth of all services prior to commencing any excavation works.

All structural concrete/ building work to Engineer's details & dwgs

All dimensions are to finished surface levels

All sub-surface build-ups to Engineer's details

Dwgs not to be scaled. Used dimensioned measurements only. Contractor to check and confirm.

All discrepancies must be reported to and resolved by the Landscape Architect before works commence

All works and materials to be in accordance with current applicable statutory legislation and to comply with all relevant Codes of Practice & British Standards.

Stage 3 Status:

Please note this information is not fully coordinated. Only limited engineering was made available during Stage 3 design. The Contractor is to develop their Final proposals based on SEW Design Drawings and Specifications. The Contractors Design Proposals shall include details of their Design, Programming, Method Statements and coordination with all other works. The Contractor is to forward their Final Proposals to SEW to confirm that they meet with SEW Employer's Requirement Proposals.

Rev	Date	Reason for Issue	
P01	24/03/26	STAGE 3	SEW

Current revision **P01**

Keyplan

Scale Bar
@ 1:250 — 10m

Studio Egret West
3 Brewhouse Yard
London, EC1V 4JQ
hello@egretwest.com
+44 (0) 20 7549 1730

Client
Mayfield Medlock Limited

Project
Mayfield Phase 1_Public Realm

Drawing Title
Kerbs & Edges GA

SEW Project Number	Status
0198_MAY	**Stage 3**
Scale at A1	Date
1 : 250	**07/08/23**
Drawn by	Checked by
TH	**SEW**

Drawing Number
0198_MAY-SEW-N01-1000-DR-L-201102