

Sparkle Street

EMERGENCY SITE EVACUATION PLAN

Evacuation routes would be as follows:- During the construction works element of site activities emergency exits would be from 2 site gates with clear passage to assembly points.

Gates 1 and 2 and turnstile are indicated as highlighted

The office will hold the a site grab bag which will include the following



This is the COSHH stores for the flammable liquids required for plant during these works, this will be supplied with multiple fire extinguishers, spill kits and MSDS paperwork for all materials.

Emergency exits are to be from the turnstile which will be accessible throughout the working day.

The maximum number of operatives on site during these works will be 150

The assembly points designated are large enough to allow the number of personnel to safely assemble away from any further danger whilst emergency services attend.

Emergency alarm is to be raised by means of biosite if an item of concern is found, Supervisor is to decide from the location of item which is the safest assembly point to use and safely escort the site operatives to this point whilst also ensuring the site gate is secured to avoid access and contact emergency services as required.

