PLANT SCHEDULE

TREE PLANTING - ORNAMENTAL

Abb	Species	Girth	Type	Root	Total
Cm	Cornus mas	Multi-stem	300-350cm	RB	3
Ck	Cladrastis kentukea	Multi-stem	350-400cm	RB	7

* Multi-stem to be clear stem to 150cm height (Umbrella form) al standard trees to be 200cm clear stem

ORNAMENTAL SHRUB AND HERBACEOUS PLANTING

Abb	Species	Size	Height (cm)	Density	Total
AM	Achillea 'Moonshine'	3L	20-30	5 sq.m	52
CFC	Carex comans 'Frosted Curls'	3L	20-30	5 sq.m	52
CbRR	Carex buchananii 'Red Rooster'	3L	20-30	5 sq.m	25
Eh	Euonymus harlequin	3L	20-30	5 sq.m	43
HPP	Heuchera 'Palace Purple'	3L	20-30	5 sq.m	45
HWG	Hebe 'White Gem'	3L	20-30	5 sq.m	16
DcG	Deschampsia 'Goldtau'	3L	20-30	5 sq.m	22
EM	Echinacea purpurea 'Magnus'	3L	20-30	5 sq.m	23
GKW	Geranium clarkei 'Kashmir White'	3L	20-30	5 sq.m	33
KB	Kniphofia 'Brimstone'	3L	20-30	5 sq.m	17
LA	Lavandula x intermedia 'Alba'	3L	30-40	5 sq.m	27
RG	Rudbeckia 'Goldsturm'	3L	20-30	5 sq.m	46
SnC	Salvia nemorosa 'Caradonna'	3L	20-30	5 sq.m	40

SPECIMENS

Abb	Species	Size	Height (cm)	Density	Total
CaKF	Calamagrostis x acutiflora 'Karl Foerster'	15L	60-80cm	Specimen	12
PmM	Pinus mugo 'Mops'	15L	60-80cm	Specimen	1
StP	Stipa 'Ponytails'	15L	40-60cm	Specimen	15

CLIMBERS

Abb	Species	Size	Height (cm)	Density	Total
LpS	Lonicera periclymenum 'Serotina'	15L	40-60cm	Specimen	7
Vc	Vitis coignetia	15L	40-60cm	Specimen	7

BULBS - 70sq.m. - Roof Terrace Planting Beds

Abb	Species	Type	Density	Total
ALB	Allium 'Lavender Bubbles'	Bulb	15sq.m.	69
AGB	Allium amplectens 'Graceful Beauty'	Bulb	15sq.m.	54
NIF	Narcissus 'Ice Follies'	Bulb	15sq.m.	81

LEGEND

SOFT LANDSCAPE

Proposed Ornamental Flowering Trees
Trees to comprise multi-stem, umbrella form trees, 350-400cm height, with 2m clear stem.

Proposed Small Trees
Trees within central planter 10-12cm girth Selected Standard, 300-350cm height, with 2m clear stem.

Proposed Ornamental Planting
Shrubs and herbeaceous plants to be planted as 3L pots at 3-5 per sq.m with 15/25L specimens and climbers to soften the built form and provide seasonal interest. Bulbs to be planted in natural swathes in herbaceous planting only.

GENERAL PLANTING NOTES:

1. Plant handling at the nursery, and during transit up to delivery, shall be in accordance with 'Plant Handling', the booklet published by the Committee for Plant Supply and Establishment (CPSE). The contractor shall comply with clauses 3 & 4 of the above booklet (obtained from the Horticulture Trades Association, 19 High Street, Theale, Reading, Berks RG7 5H) which refers to the receipt, unloading and temporary storage of plants.

2. Plants shall be first class examples of their species or variety, free from all pests and diseases, with good fibrous root systems and materially undamaged (refer to relevant sections of BS3936 Parts 1-4 'Specification of Nursery Stock').

3. All planting is to be in general compliance with BS4428: 1989 'Code of Practice for general landscape operations.

4. Shrub and Herbaceous beds - All shrub beds to have min 450mm depth of good quality topsoil to BS3882:2015 free from rubble and stones with a free draining base Shrubs to be planted in pits which are large enough to accommodate the size of the pot, incorporate a slow release shrub fertiliser to the back fill material.

Climbers
Climbers to be installed with canes and ties to promote initial vertical growth up pergolas.

Once planted all beds are to be mulched with 75mm depth of medium grade bark mulch

5. Bulbs - Bulbs to be planted in natural swathes of roughly 100 of the same species within roof terrace shrub and herbaceous beds. Bulbs to be planted in areas of herbaceous planting only to avoid competition with shrubs. The smaller Allium 'Lavender Bubbles' to be planted to the front of beds only.

6. Tree Planting - All tree pits to be planted with peat free compost at 7 Ltrs / pit with additional mycorrhizal fungi component incorporated into topsoil. All tree pits to have 450mm topsoil backfill above subsoil backfill (base broken out to facilitate drainage with 100mm drainage stone to base) and to be staked using 100mm dia short stakes and secured to the tree with rubber webbing tie and spacer. All tree pits to be installed with irrigation pipes.

Mycorrhizal fungi component to be of UK origin including bio-additives. To contain spores, mycelium, dried plant root containing mycelium and attapulgite clay, colonised by mycelium. Product should not contain fertilisers. Additives should be proven to enhance mycorrhizal colonisation.

i) Multi-stem - 350-400cm, tall to be planted in pits 700 x 700 x 600mm deep. To be planted with double stake.

ii) Multi-stem- 300-350cm tall, to be planted in pits 600 x 600 x 500mm deep. To be planted with underground guy anchor with min 3 stakes under rootball or SASMCB Arborguy strapped anchor system c/w ground anchors.

Trees in Roof Terrace Raised Beds
To be planted into min. 800mm depth by mounding soil surface to no more than a 1:5 slope. To be planted with underground guy anchor with min 3 stakes under rootball or SASMCB Arborguy strapped anchor system c/w ground anchors.

7. All Trees, shrubs and herbaceous planting to be watered in the first year of establishment during periods of drought and the base of newly planted trees and shrubs to be maintained weed free until established to reduce competition.

8. The contractor must ascertain himself/herself of the exact location of underground services prior to carrying out any works on site.



REVISION NOTES

Rev. A
Additional secure gate added, bird and bat box amendments
GBS 23/05/25

Rev. B
Revised inline with new layout
NN 05/01/26

Rev. C
Scale bar and north point added
NN 20/01/26

DEP LANDSCAPE ARCHITECTURE LTD
2 COMMERCIAL STREET
MANCHESTER, M15 4RQ
T: 0161 2419878
E: info@dep.co.uk
W: www.dep.co.uk

Client
Everest Pharmacy Limited

Project
Lane End Road, Burnage

Description
Planting Plan

Status
Planning

Scale	Drawn
1:100@A2	GBS/TR

Job number	Drawing number	Date	Revision
5490	05	April '25	C

Copyright DEP Landscape Architecture Ltd

All levels and dimensions to be checked on site by contractor prior to commencement; Any variations to be reported to the client. This drawing is to be read in conjunction with all others relating to the project and all information derived accordingly; any anomolies to be reported to the client. Do not scale from this drawing. Use figured dimensions only. Work shown on this drawings to be carried out in accordance with current British Standards and Codes of Practice.

© Copyright to DEP Landscape Architecture Limited. The information shown on this drawing shall not be reproduced or copied in any form without prior written consent from DEP Landscape Architecture Limited.