

MCFC Project Taverna

Flood Risk Assessment

0165-CAL-XX-XX-RP-C-0001-P01

For : Manchester City Football Club

Calibre

w: www.calibre-consulting.co.uk

e: info@calibre-consulting.co.uk

Calibre Consulting Engineers Ltd
Registered in England No 15570950

Civil
Structural
Highways
Geotechnical

DOCUMENT ISSUE REGISTER

Document Reference		0165-CAL-XX-XX-RP-C-0001			
Document Title		Flood Risk Assessment			
<i>Status</i>	<i>Revision</i>	<i>Date of Issue</i>	<i>Author</i>	<i>Checked</i>	<i>Approved</i>
For Information	DRAFT	06/01/2026	RH	SB	RH
For Information	P01	04/03/2026	RH	SB	RH

CONTENTS:

1.0 INTRODUCTION

- 1.1 Background & Relevant Planning Policy / Guidance Documents
- 1.2 Standards and Limitations

2.0 CURRENT SITUATION

- 2.1 Site Location and Description
- 2.2 Hydrology and Flooding
- 2.3 Existing Sewers

3.0 PROPOSED DEVELOPMENT

- 3.1 Development Proposals
- 3.2 Surface Water Drainage
- 3.3 National Planning Policy Framework and Technical Guidance
- 3.4 Potential Mitigation Measures
- 3.5 Safe Access and Egress
- 3.6 Surface Water Exceedance Routes
- 3.7 Foul Water Drainage

4.0 SUMMARY

- 4.1 Flooding
- 4.2 Flood Risk Management Measures
- 4.3 Off Site Impacts
- 4.4 Residual Risk

APPENDICES

Appendix 1	Proposed Masterplan
Appendix 2	Environment Agency Maps
Appendix 3	Topographical Survey
Appendix 4	Proposed Levels & Overland Flood Routes

1.0 INTRODUCTION

1.1 Background & Relevant Planning Policy / Guidance Documents

1.1.1 Calibre Consulting Engineers Ltd have been commissioned by Manchester City Football Club to undertake a Flood Risk Assessment for its proposed development site east of the existing stadium.

1.1.2 The objective of this document is to identify potential flooding issues together with any consequent implications for the proposed development of the site. Flood risk mitigation measures are outlined as appropriate. Drainage strategy proposals are not included and are to form part of a separate Sustainable Drainage Strategy document. The Flood Risk Assessment is to be read in conjunction with the Sustainable Drainage Strategy.

1.1.3 The document has been prepared in accordance with the National Planning Policy Framework (last updated on 7 February 2025 - clauses 161 to 164 and 170 to 180 inclusive), the National Planning Practice Guidance: Flood Risk and Coastal Change and the pro-forma guidance contained in the following documents:

1.1.3.1 Greater Manchester Combined Authority (GMCA) Level 1 Strategic Flood Risk Assessment by JBA Consulting dated March 2019.

1.1.3.2 Manchester City, Salford City and Trafford Councils Level 2 Hybrid SFRA dated March 2011.

1.1.3.3 DEFRA / Environment Agency publication SC030219 'Rainfall Runoff Management for Developments' dated October 2013.

-
- 1.1.3.4 DEFRA Non-Statutory Technical Standards for Sustainable Drainage Systems – July 2025
 - 1.1.3.5 'Framework and Guidance for Assessing and Managing Flood Risk for New Development' (FD2320/TR2).
 - 1.1.3.6 'Flood Risks to People Methodology' (FD2321/TR1).
 - 1.1.3.7 'Supplementary Note on Flood Hazard Ratings and Thresholds for Development Planning and Control Purpose – Clarification of Table 13.1 of FD2320/TR2 and Figure 3.2 of FD2321/TR1'.

1.2 Standards & Limitations

- 1.2.1 This report has been prepared solely for use by Manchester City Football Club.
- 1.2.2 It shall not be relied upon or transferred to any other party without the prior written authorisation of Calibre Consulting Engineers Ltd.
- 1.2.3 The findings and opinions in the report are based on information derived from a variety of different sources. Calibre Consulting Engineers Ltd do not accept any liability for the accuracy or otherwise of any information provided by third parties.
- 1.2.4 It should be noted that some of the aspects considered in this study may be subject to change with time. Therefore, if the development is delayed or postponed, consideration may need to be given to reviewing such issues to

confirm that no changes have taken place, either at the site or within relevant legislation.

- 1.2.5 Further consultations with statutory bodies are likely as the scheme progresses. It should be noted that even where responses have been received from Regulators, these could be subject to change at a later date.

2.0 CURRENT SITUATION

2.1 Site Location and Description

- 2.1.1 The circa 0.63 hectare site is located in East Manchester, West of Alan Turing Way and within the outer perimeter of the MCFC stadium boundary, approximately 3km to the east of Manchester city centre at National Grid reference 386944, 398737 as shown on the below site location extracts.




Figure 1: Site Location

- 2.1.2 The trapezoidal shaped brownfield site is bounded by Alan Turing Way to the east, the metrolink / Ashton canal to the north, and the existing MCFC car park to the south and west boundaries.
- 2.1.3 The existing site is broadly level, but with a slight trend from east to west. Along the eastern boundary the levels pick up with Alan Turing Way raised slightly above the site level. Max site level is circa 63 at the far eastern edge with the lowest level circa 61m AOD at the north west corner. A copy of the topographical survey can be found in Appendix 3.




Figure 2: Topographical Survey with approx. site boundary shown

2.2 Hydrology and Flooding

The following section identifies the various sources of flooding at the proposed site location based on the available data.

2.2.1 Rivers & Seas

2.2.1.1 Current available Environment Agency flood mapping information indicates that the site lies wholly within Flood Zone 1, inclusive of climate change. Accordingly the site has <0.1% annual probability of flooding



Figure 3: EA Fluvial Flood map extract

2.2.2 Surface Water

2.2.2.1 The EA flood mapping data indicates areas which are at risk of surface water flooding for the high (3.33%), medium (1%) and low (0.1%) risk scenarios. The map data reveals that there is a small area of the

southern site boundary which is at risk of surface water flooding in the low, medium and high risk events. See figure 4 below for details of the low risk scenario




Figure 4: EA Surface Water Flood Map extents (low risk scenario)

- 2.2.2.2 The above noted flood risk is noted to be contained within an area of the red line boundary where no new development is taking place – the red line boundary extends to the centre of the access road to the south, and includes the existing sprinkler tank area. These areas are to remain as existing, and hence there are to be no level changes what may impact offsite flood routes in this area. In addition to this, given the proposed use is less vulnerable, and the building footprint along with new areas of external hard and soft landscaping are outside the area of surface water flood risk, no mitigation is deemed required.
- 2.2.2.3 Separate to the above, given that this main access to the south off Alan Turing Way is affected by surface water flooding. Consideration needs to be given in relation to establishing a safe access and egress point from the site. Extent and depths (up to 20cm) are presented in figure 5 below. It is noted that in the medium risk scenario, the depths are more isolated with the actual site access appearing clear of flooding.




Figure 5: EA Surface Water Flood Map extents & depths (all scenarios)

2.2.3 Reservoirs

The EA maps confirm that there is no risk of flooding of the site from reservoirs.

2.2.4 Groundwater

2.2.4.1 Groundwater flood risk has been assessed using the Enviro+Geo Insight report by Groundsure. The assessed risk for whole of the site, is 'low'.




Figure 6: Groundsure report extract designating groundwater flooding risk

2.2.5 Historic Flooding Events

- 2.2.5.1 From a review of the Enviro+Geo insight report by Groundsure, there are no records of historic flooding within 250m of the site. This data is sourced from both the Environment Agency and Natural Resources Wales.
- 2.2.5.2 The GMCA Levels 1 SFRA contains a map of UU recorded historical flooding events. The level of detail of the recorded incidents are aggregated into 100m² squares and are low on level of detail it is not therefore possible to conclude whether there have been any recorded flooding incidents which have affected the site.
- 2.2.5.3 The GMCA Levels 1 SFRA also contains maps indicating EA Historic Flooding / recorded flood outlines. Whilst this is presented on a broad scale, there are no areas of historic flooding recorded at the site



Figure 7: EA flooding records; UU historical flooding.

2.2.6 Critical Drainage Areas

- 2.2.6.1 The Manchester City, Salford City and Trafford Councils Level 2 Hybrid SFRA indicates that the site sits within the 'Conurbation Core' critical drainage area. Given the location within a Critical Drainage Area, this triggers the requirement for an FRA on this site which would otherwise not be required.

2.3 Existing Sewers

2.3.1 Various sewers are present in the vicinity of the site and are noted below:

- 2.3.1.1 A 900mm diameter combined water sewer running east to west through the centre of the site. Depth of circa 7-8m.
- 2.3.1.2 A 900mm diameter combined water sewer running north to south immediately to the west of the site boundary. Depth circa 7-8m.
- 2.3.1.3 A 2100mm dia surface water culvert running east to west through the centre of the site at a depth of circa 12m.

3.0 PROPOSED DEVELOPMENT

3.1 Development Proposals

- 3.1.1 Proposed development consists of the construction of an immersive events space with associated external hard and soft landscaping to the perimeter. Refer to Appendix 2 for details.

3.2 Surface Water Drainage

- 3.2.1 Surface water drainage proposals fall outside the scope of this Flood Risk Assessment – refer to the separate Sustainable Drainage Strategy report prepared by Calibre Consulting (Ref 0165-CAL-XX-XX-RP-C-0002) for further details.

3.3 National Planning Policy Framework and Technical Guidance

- 3.3.1 The proposed site usage is classes as 'less vulnerable' in Table 2 of the Flood Risk and Coastal Change guidance. 'Less vulnerable' developments in Flood Zone 1 are classed as appropriate according to Table 3 of the Flood Risk and Coastal Change guidance.
- 3.3.2 Types of flooding that could affect the site are defined in section 2.2. The risks identified in section 2.2 are addressed in the following sections.

3.4 Potential Mitigation Measures

3.4.1 Rivers & Seas

The site is situated in Flood Zone 1 and therefore at <0.1% chance of annual flooding from Rivers and Seas.

3.4.2 Surface Water

As noted in 2.2.2, a small portion of the southern site boundary is affected by surfaedc water flooding though this is isolated and outside of areas of new development. The proposed building is less vulnerable, and no mitigation measures are therefore deemed to be required.

3.4.3 Reservoir

There is no risk of flooding from reservoirs.

3.4.4 Groundwater

Ground water flooding is noted as low risk, no further action is therefore deemed necessary.

3.4.5 Historical Flooding

There are no records of historical flooding at the site.

3.5 Safe Access and Egress

- 3.5.1 A small area of surface water flooding is identified at the main entrance off Alan Turing Way. The flooding is within a localised depression and depths <20cm are not recorded beyond the depression. Accordingly, it is expected that the entrance road will not be impacted by flood water >20cm in the medium risk scenario. In reference to FD2320/TR2 (as figure 8 below) at depths of 0.2m, velocities of up to 0.5m/s can be tolerated for a flood hazard rating of 0.75 (very low hazard). Accordingly, safe access and egress is anticipated from Alan Turing Way.
- 3.5.2 Note that a secondary alternative means of emergency access is also available from the north west corner of the site via the Etihad campus and onto Joe Mercer Way

HR	Depth of flooding - d (m)												
	DF = 0.5				DF = 1								
Velocity v (m/s)	0.05	0.10	0.20	0.25	0.30	0.40	0.50	0.60	0.80	1.00	1.50	2.00	2.50
0.0	0.03+0.5= = 0.53	0.05+0.5= = 0.55	0.10+0.5= = 0.60	0.13+0.5= = 0.63	0.15+1.0= = 1.15	0.20+1.0= = 1.20	0.25+1.0= = 1.25	0.30+1.0= = 1.30	0.40+1.0= = 1.40	0.50+1.0= = 1.50	0.75+1.0= = 1.75	1.00+1.0= = 2.00	1.25+1.0= = 2.25
0.1	0.03+0.5= = 0.53	0.06+0.5= = 0.56	0.12+0.5= = 0.62	0.15+0.5= = 0.65	0.18+1.0= = 1.18	0.24+1.0= = 1.24	0.30+1.0= = 1.30	0.36+1.0= = 1.36	0.48+1.0= = 1.48	0.60+1.0= = 1.60	0.90+1.0= = 1.90	1.20+1.0= = 2.20	1.50+1.0= = 2.55
0.3	0.04+0.5= = 0.54	0.08+0.5= = 0.58	0.15+0.5= = 0.65	0.19+0.5= = 0.69	0.23+1.0= = 1.23	0.30+1.0= = 1.30	0.38+1.0= = 1.38	0.45+1.0= = 1.45	0.60+1.0= = 1.60	0.75+1.0= = 1.75	1.13+1.0= = 2.13	1.50+1.0= = 2.50	1.88+1.0= = 2.88
0.5	0.05+0.5= = 0.55	0.10+0.5= = 0.60	0.20+0.5= = 0.70	0.25+0.5= = 0.75	0.30+1.0= = 1.30	0.40+1.0= = 1.40	0.50+1.0= = 1.50	0.60+1.0= = 1.60	0.80+1.0= = 1.80	1.00+1.0= = 2.00	1.50+1.0= = 2.50	2.00+1.0= = 3.00	2.50+1.0= = 3.50
1.0	0.08+0.5= = 0.58	0.15+0.5= = 0.65	0.30+0.5= = 0.80	0.38+0.5= = 0.88	0.45+1.0= = 1.45	0.60+1.0= = 1.60	0.75+1.0= = 1.75	0.90+1.0= = 1.90	1.20+1.0= = 2.20	1.50+1.0= = 2.50	2.25+1.0= = 3.25	3.00+1.0= = 4.00	3.75+1.0= = 4.75
1.5	0.10+0.5= = 0.60	0.20+0.5= = 0.70	0.40+0.5= = 0.90	0.50+0.5= = 1.00	0.60+1.0= = 1.60	0.80+1.0= = 1.80	1.00+1.0= = 2.00	1.20+1.0= = 2.20	1.60+1.0= = 2.60	2.00+1.0= = 3.00	3.00+1.0= = 4.00	4.00+1.0= = 5.00	5.00+1.0= = 6.00
2.0	0.13+0.5= = 0.63	0.25+0.5= = 0.75	0.50+0.5= = 1.00	0.63+0.5= = 1.13	0.75+1.0= = 1.75	1.00+1.0= = 2.00	1.25+1.0= = 2.25	1.50+1.0= = 2.50	2.00+1.0= = 3.00	3.50	4.75	6.00	7.25
2.5	0.15+0.5= = 0.65	0.30+0.5= = 0.80	0.60+0.5= = 1.10	0.75+0.5= = 1.25	0.90+1.0= = 1.90	1.20+1.0= = 2.20	1.50+1.0= = 2.50	1.80+1.0= = 2.80	3.40	4.00	5.50	7.00	8.50
3.0	0.18+0.5= = 0.68	0.35+0.5= = 0.85	0.70+0.5= = 1.20	0.88+0.5= = 1.38	1.05+1.0= = 2.05	1.40+1.0= = 2.40	1.75+1.0= = 2.75	3.10	3.80	4.50	6.25	8.00	9.75
3.5	0.20+0.5= = 0.70	0.40+0.5= = 0.90	0.80+0.5= = 1.30	1.00+0.5= = 1.50	1.20+1.0= = 2.20	1.60+1.0= = 2.60	3.00	3.40	4.20	5.00	7.00	9.00	11.00
4.0	0.23+0.5= = 0.73	0.45+0.5= = 0.95	0.90+0.5= = 1.40	1.13+0.5= = 1.63	1.35+1.0= = 2.35	1.80+1.0= = 2.80	3.25	3.70	4.60	5.50	7.75	10.00	12.25
4.5	0.25+0.5= = 0.75	0.50+0.5= = 1.00	1.00+0.5= = 1.50	1.25+0.5= = 1.75	1.50+1.0= = 2.50	2.00+1.0= = 3.00	3.50	4.00	5.00	6.00	8.50	11.00	13.50
5.0	0.28+0.5= = 0.78	0.60+0.5= = 1.10	1.10+0.5= = 1.60	1.38+0.5= = 1.88	1.65+1.0= = 2.65	3.20	3.75	4.30	5.40	6.50	9.25	12.00	14.75
Flood Hazard Rating (HR)		Colour Code	Hazard to People Classification										
Less than 0.75			Very low hazard - Caution										
0.75 to 1.25			Danger for some – includes children, the elderly and the infirm										
1.25 to 2.0			Danger for most – includes the general public										
More than 2.0			Danger for all – includes the emergency services										

Figure 8: Hazard to people classification using Hazard Rating (FD2320/TR2).

3.6 Surface Water Exceedance Routes

3.6.1 With regard to surface water exceedance routes, the site topography has a slight trend from east to west. Post development levels are close to existing site levels, and therefore in the event of extreme flood events or drainage failure, overland flooding will be directed away from the buildings, towards the north east onto private land. Proposed levels and overland flood drawings are contained in Appendix 5.

3.7 Foul Water Drainage

Foul water drainage is beyond the scope of this report and is included within the Sustainable Drainage Strategy Assessment.

4.0 SUMMARY

4.1 Flooding

- 4.1.1 The development platform is shown to lie in flood zone 1, with isolated risk of surface water flooding that has been deemed to not impact the development, no risk of reservoir flooding and low risk of groundwater flooding. Accordingly, flood risk on the site is considered very low.
- 4.1.2 There are no specific minimum floor levels required, though the building is to be set such that ground levels fall away from the building, with surrounding levels set such that a build up of water would not occur in the event of a drainage blockage.

4.2 Flood Risk Management Measures

A site management Health and Safety document should be prepared in respect of the site.

4.3 Off Site Impacts


- 4.3.1.1 The proposed site drainage (refer to the Sustainable Drainage Strategy Report) is designed such that there are no offsite flows up to the 1 in 100 year event + climate change event.
- 4.3.1.2 Overland flooding trends from east to west onto private land with runoff directed away from buildings.

4.4 Residual Risk

A post-development safe emergency access is available via the east entrance off Alan Turing Way, though shallow surface flooding is expected in the medium risk scenarios. A secondary access is available from Joe Mercer way to the west.

APPENDICES

Appendix 1 – Proposed Masterplan



Proposed Lighting Column
Functional pole mounted lighting. Specification TBC

Proposed In-ground up-lighting
Specification TBC

Existing levels
+61.85

Proposed levels
+61.85

Proposed Gradient
1:60

© This drawing is copyright protected and may not be reproduced in whole or part without written authority from the owner.

NOTES:

1. Do not scale from this drawing.
2. Always work to noted dimensions.
3. All dimensions are in millimetres unless otherwise stated.
4. All setting out, levels and dimensions to be agreed on site.
5. The dimensions of all materials must be checked on site before being laid out.
6. This drawing must be read with the relevant specification clauses and detail drawings.
7. Order of construction and setting out to be agreed on site.

Key

- Ornamental Planting**
Mixed shrub, herbaceous perennial and ornamental grass planting (plant species to be into existing North Stand works)
Notes: 300mm topsoil over 400mm subsoil
- Rain Garden Planting**
Rain garden suitable planting mix
Notes: 300mm topsoil over 400mm subsoil
- Climbers**
Tensile wire system with climbing plants to soften and screen the new substation enclosure. Twining climber species - final extent to be coordinated with substation ventilation requirements
- Proposed Street tree**
Semi-mature tree
20-25cm girth
Notes: 300mm topsoil over 600mm subsoil
- Existing Tree**
- Surface Type 1**
Initially concrete with large format precast concrete banding to arrival plaza
- Surface Type 2**
Concrete block paving to footpath around the perimeter of the building. Specification to be in keeping with the North Stand development
- Surface Type 3**
Tarmac to access road to match existing surfacing on North Stand development
- Surface Type 4**
Filter Drain along northern edge of access road to form part of the drainage strategy
- Surface Type 5**
Reinforced grass to sprinkler house access point
- Large pre cast concrete planters**
Placed in the arrival plaza, the raised concrete planters help soften the entrance facade and allow people to perch on the planter edge
- Fixed Bullard**
To form HVM line. Specification TBC
- Fixed Concrete Block**
Fixed concrete block with gabion cladding / artwork to improve appearance. To form HVM line. Specification TBC
- Timber Post and rail fence**
1.2m high to the northern edge of the access road
Product TBC
- Bin Store**
Steel frame with timber uprights and lockable gates.
Product TBC
- Proposed Lighting Column**
Column mounted projectors. Specification TBC
- Area to Remain as Existing**
- Emerging Context Under North Stand Public Realm Works**

P05	02/03/26	Incorporating Architects Comments	CB	SC
P04	27/02/26	Planning	CB	SPL
P03	30/01/26	Review and comment	CB	SPL
P02	28/01/26	For Review and Comment	CB	SPL
P01	22/01/26	For Review and Comment	CB	SPL

Revision	Date	Description	Drawn	Apprv.
----------	------	-------------	-------	--------

PLANIT

Manchester | London | Liverpool | Leeds | Standish

Manchester
2 Back Grafton Street,
Altrincham,
Cheshire,
WA14 1DY

W: plant-it.com
E: info@plant-it.com
T: 0161 928 9281

Client Manchester City Football Club

Project Project Taverna

Drg Title Landscape General Arrangement

Created on 09-01-26
Created by CB
Approved by SPL

Scale 1:250
Size A2
Workstage Planning

Drg No. 3679.3-PLA-XX-XX-DR-L-0001
Suitability Revision S2 P05
© Plant I.E. Limited

Appendix 2 – Environment Agency Maps

Flood map for planning

Your reference
Unspecified

Location (easting/northing)
386926/398717

Created
4 March 2026 19:33

Your selected location is in flood zone 1, an area with a low probability of flooding.

You will need to do a flood risk assessment if your site is **any of the following**:

- bigger than 1 hectare (ha)
- in an area with critical drainage problems as notified by the Environment Agency
- identified as being at increased flood risk in future by the local authority's strategic flood risk assessment
- at risk from other sources of flooding (such as surface water or reservoirs) and its development would increase the vulnerability of its use (such as constructing an office on an undeveloped site or converting a shop to a dwelling)

Notes

The flood map for planning shows river and sea flooding data only. It doesn't include other sources of flooding. It is for use in development planning and flood risk assessments.

This information relates to the selected location and is not specific to any property within it. The map is updated regularly and is correct at the time of printing.

Flood risk data is covered by the Open Government Licence which sets out the terms and conditions for using government data. <https://www.nationalarchives.gov.uk/doc/open-government-licence/version/3>

Use of the address and mapping data is subject to Ordnance Survey public viewing terms under Crown copyright and database rights 2026 AC0000807064. <https://flood-map-for-planning.service.gov.uk/os-terms>



Flood map for planning

Your reference

Unspecified

Location (easting/northing)

386926/398717


Scale

1:2,500

Created

4 Mar 2026 19:33

-  Selected area
-  Flood zone 3
-  Flood zone 2
-  Flood zone 1
-  Flood defence
-  Main river
-  Water storage area


0 20 40 60m

Get data for your location

Add or edit a location boundary

[Show](#)

Datasets

Surface water

[Hide](#)

☐ Flood zones 2 and 3

☒ Surface water

☐ None

Annual likelihood of flooding

1 in 30

[Hide](#)

☒ 1 in 30

☐ 1 in 100

☐ 1 in 1000

Map features

None selected

[Show](#)


Key



Flood extent



Location
boundary



Get data for your location

Add or edit a location boundary

[Show](#)

Datasets

Surface water

[Hide](#)

☐ Flood zones 2 and 3

☒ Surface water

☐ None

Annual likelihood of flooding

1 in 100

[Hide](#)

☐ 1 in 30

☒ 1 in 100

☐ 1 in 1000

Map features

None selected

[Show](#)


Key



Flood extent



Location
boundary



Get data for your location

Add or edit a location boundary

[Show](#)

Datasets

Surface water

[Hide](#)

☐ Flood zones 2 and 3

☒ Surface water

☐ None

Annual likelihood of flooding

1 in 1000

[Hide](#)

☐ 1 in 30

☐ 1 in 100

☒ 1 in 1000

Map features

None selected

[Show](#)


Key




Flood extent




Location
boundary



Appendix 3 – Topographical Survey



Appendix 4 – Proposed Levels & Overland Flood Routes



Levels GA Legend

+22.880


Proposed Spot Level

Major Contour (0.5m)

Minor Contour (0.1m)

-1.58

Direction & Gradient of Fall



Notes

1. All dimensions are in millimetres unless noted otherwise
2. All levels shown are in metres unless noted otherwise
3. This drawing is to be read in conjunction with all relevant Architectural & Service Engineer drawings
4. Do not scale from this drawing. Figured dimensions to be worked to in all cases. If in doubt, contact the Engineer
5. CDM (2015) - This drawing is to be read in conjunction with the Designers Risk Assessment produced for the project

P02	03/26	Updated masterplan	RH
P01	02/26	Preliminary issue	RH
Rev	Date	Description	Drawn

Drawing Status

PRELIMINARY

Contract

PROJECT TAVERNA
MANCHESTER CITY FOOTBALL CLUB

Drawing Title

EXTERNAL LEVELS GA

Scales	Date	Drawn	Checked
1200 (A1)	01/2026	RH	SB
Project	Origin	Zone	Level
0165 - CAL - EX - 00 - DR - C - 0101 - P01			




OVERLAND FLOODING:

Drawing opposite indicates the overland flood routes of the site post development. Flood routes are those which would occur in an extreme rainfall event, classed as any event exceeding the maximum design event of 1 in 100 years + 45% climate change.

Overland flooding is directed away from the building on all elevations towards the perimeter, then flowing toward the surrounding private hardstanding within the wider development, which trends north westwards.

Notes

1. All dimensions are in millimetres unless noted otherwise
2. All levels shown are in metres unless noted otherwise
3. This drawing is to be read in conjunction with all relevant Architectural & Service Engineer drawings
4. Do not scale from this drawing. Figured dimensions to be worked to in all cases. If in doubt, contact the Engineer
5. CDM (2015) - This drawing is to be read in conjunction with the Designers Risk Assessment produced for the project



P01	02/26	Preliminary issue					RH
Rev	Date	Description					Drawn
Drawing Status:							
PRELIMINARY							
Contract							
PROJECT TAVERNA							
MANCHESTER CITY FOOTBALL CLUB							
Drawing Title:							
OVERLAND FLOODING GA							
(EXTREME EVENTS)							
Scales		Date		Drawn		Checked	
1:200		(A1) 01/2026		RH		SB	
Project	Origin	Zone	Level	Type	Role	Number	Rev'n
0165 - CAL - EX - 00 - DR - C - 0203 - P02							