




LEGEND

- PLANNING BOUNDARY
- NT02 BOUNDARY
- EXISTING COMBINED SEWER
- SEWER TO BE ABANDONED
- DIVERTED COMBINED SEWER
- PERMEABLE PAVEMENT WITH HARDCAPE DRAINJOINT
- ATTENUATION TANK
- SURFACE WATER DRAIN
- SW MANHOLE/ INSPECTION CHAMBER/ CATCHPIT
- RAINWATER PIPE & 1500 CONNECTION
- DRAINAGE CHANNEL
- ACO SLOT DRAIN & SUMP UNIT
- FILTER DRAIN WITH CATCHPIT & PERFORATED PIPE
- YARD GULLY & 1100 CONNECTION
- FOUL WATER DRAIN
- FW MANHOLE/ INSPECTION CHAMBER
- FOUL WATER POP-UP & 1100 UNO
- S104 SW SEWER & MANHOLE
- S104 FW SEWER & MANHOLE

THIS DRAWING IS THE PROPERTY OF RgCp. COPYRIGHT IS RESERVED BY THEM AND THE DRAWING IS ISSUED ON THE CONDITION THAT IT IS NOT COPIED, REPRODUCED, RETAINED OR DISCLOSED TO ANY UNAUTHORISED PERSON EITHER WHOLLY OR IN PART WITHOUT THE WRITTEN CONSENT OF RgCp

NOTES

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL ARCHITECTS, ENGINEERS AND SPECIALIST DRAWINGS AND SPECIFICATIONS.
- ANY DISCREPANCIES SHOULD BE REPORTED TO THE ENGINEER IMMEDIATELY SO THAT CLARIFICATION CAN BE SOUGHT PRIOR TO THE COMMENCEMENT OF WORK.
- BEFORE STARTING ANY WORKS, CONTRACTOR TO CHECK INVERT LEVELS AND POSITIONS OF EXISTING DRAINS, SEWERS, INSPECTIONS CHAMBERS AND MANHOLES AGAINST INFORMATION SHOWN ON THIS DRAWING.
- ROCKER PIPES ARE TO BE PROVIDED AT ALL CONCRETE CASED INTERFACES.
- CLASS 2 CONCRETE SURROUND TO BE PROVIDED FOR PIPES WITH COVER LESS THAN 1.2m ABOVE THE CROWN OF THE PIPE FOR ROADS AND 0.8m FOR SOFT AND PEDESTRIAN AREAS ONLY AND UNDER ALL FOUNDATIONS AND WHERE PIPES LAID WITHIN 1m OF FOUNDATIONS.
- CONNECTIONS TO EXISTING PUBLIC SEWERS IN ACCORDANCE WITH UNITED UTILITIES REQUIREMENTS, TO BE APPROVED / AGREED WITH THE WATER AUTHORITY.
- PROPOSED COVER LEVELS ARE APPROXIMATE AND SHALL BE CHECKED BY THE CONTRACTOR ON SITE TO SUIT THE EXACT FINISHED LEVEL AND GRADIENT.
- ALL DRAINAGE WORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE LOCAL AUTHORITY AND IN CONJUNCTION WITH ALL RELEVANT BRITISH STANDARDS, CODES OF PRACTICE AND SEWERS FOR ADOPTION 7th EDITION.
- ACCESS COVERS AND FRAMES SHALL COMPLY WITH THE LOADINGS SPECIFIED AND TO BS EN 124 AND KITEMARKED OR F RECESSED COVERS ARE SPECIFIED THEN IN ACCORDANCE WITH FACTA ASSOCIATION EQUIVALENT. ALLOW FOR RECESS MANHOLE COVERS TO ACCEPT LANDSCAPE ARCHITECT FINISHES TO ALL NON-ASPHALT EXTERNAL AREAS.
- THE PROPOSED BUILDING LAYOUTS SHOWN ON THIS DRAWING ARE FOR INFORMATION ONLY. REFER TO ARCHITECTS PLANS FOR PRECISE LOCATION SETTING OUT INFORMATION AND DETAILS.
- FOR SETTING OUT DIMENSIONS OF SSS, SVPS, RWP'S, FLOOR GULLIES & OTHER DRAINAGE POP UP LOCATIONS, REFER TO ARCHITECTS OR MECHANICAL & ELECTRICAL ENGINEERS DRAWINGS.
- ALL DRAINAGE PIPEWORK SHOWN SHALL BE 100mm DIAMETER FOR FOUL AND 150mm FOR SURFACE WATER UNLESS NOTED OTHERWISE. ALL DRAINAGE PIPEWORK SHALL BE LAID SOFFIT TO SOFFIT UNLESS OTHERWISE STATED.
- ALL UNDERSLAB DRAINAGE SHALL BE LAID AT GRADIENTS OF 1:80 MIN. FOR FOUL PIPEWORK AND 1:100 MIN. FOR SURFACE WATER UNLESS NOTED OTHERWISE. ALL UNDERSLAB DRAINAGE SHALL BE CLEAR OF FOUNDATIONS UNLESS SHOWN OTHERWISE. USE OF SHORT LONG RADIUS BENDS IS ACCEPTABLE PROVIDED THEY ARE KEPT TO A MINIMUM AND USED WHERE UNAVOIDABLE.
- AT LEAST ONE SOIL PIPE AT THE HEAD OF EACH FOUL RUN SHALL BE VENTED TO THE ATMOSPHERE. ALL RAINWATER PIPES SHALL HAVE ABOVE GROUND RODDING ACCESS.
- ALL PRIVATE DRAINAGE PIPEWORK FOR FOUL AND SURFACE WATER SYSTEMS HAVE BEEN DESIGNED ON THE BASIS OF UPVC TO BS EN 1401-1, UNLESS NOTED OTHERWISE.
- CONCRETE ENCASUREMENT OF THE PIPEWORK SHALL BE REQUIRED WHERE THE VERTICAL CLEARANCE BETWEEN TWO PIPES CROSSING IS LESS THAN 300mm.
- WHERE NEW DRAINAGE IS SITUATED WITHIN 5 METRES OF NEW OR EXISTING TREES THE PIPEWORK SHALL BE ENCASED IN CONCRETE TO REDUCE THE RISK OF ROOT INGRESS.
- ALL NEW DRAINAGE INSTALLATIONS TOGETHER WITH ANY EXISTING DRAINAGE RETAINED SHALL BE JETTED AND CCTV SURVEYED UPON COMPLETION. CONTRACTOR TO ENSURE THAT THE DRAINAGE SYSTEM IS FULLY OPERATIONAL, FREE OF EXCESS DEBRIS/SILT AND ALL IDENTIFIED FAULTS RECTIFIED.
- ATTENUATION STORAGE CALCULATIONS INCLUDE CLIMATE CHANGE ALLOWANCE OF 40% IN ACCORDANCE WITH CURRENT ENVIRONMENT AGENCY GUIDELINES.

REV	DATE	DETAILS	DRN	CHK
P03	17/12/2024	COORDINATION	ARJ	JAS
P02	22/11/2024	COORDINATION	ARJ	JAS
P01	15/11/2024	FIRST ISSUE	ARJ	JAS

DRAWING STATUS: **PRELIMINARY**

RIBA STAGE: **STAGE 4**

RgC CONSULTING

Commercial Wharf
6 Commercial Street
Manchester M15 4PZ
T 0161 214 5390
W rocconsulting.com

DRAWN	DATE	SCALE
ARJ	OCT 24	1:200

CHECKED	DATE	THE ABOVE SCALES APPLY WHEN PLOTTED AT 1:1 SIZE -DO NOT SCALE-
PAW	OCT 24	

APPRVD.	DATE	EMAIL FOR DRAWINGS
JAS	OCT 24	info@rocconsulting.com

CLIENT: **FAR EAST CONSORTIUM INTERNATIONAL LTD**

PROJECT TITLE: **REDBANK DEVELOPMENT**

DRAWING TITLE: **FW & SW DRAINAGE GENERAL ARRANGEMENT BLOCK 2B**

DRAWING No.	REV.
RDB/ROC/2B/XX/DR/C/83/0500	P03

4328 RgCp Ltd.

WORK IN PROGRESS

ALL INFORMATION ON THIS DRAWING IS SUBJECT TO CHANGE AS THE SCHEME IS DEVELOPED AS THE FOLLOWING INFORMATION IS EITHER YET TO BE FINALISED.

- SW DISCHARGE CONSENT APPLICATION
- SW S104 AGREEMENT & TECHNICAL APPROVAL
- FW S106 AGREEMENT & TECHNICAL APPROVAL
- LANDSCAPE/ EXTERNAL WORKS LEVELS
- LANDSCAPE/ EXTERNAL WORKS FINISHES

NOTE:
REFER TO ROC S104 DRAWINGS FOR
DETAILS OF OFF-SITE DRAINAGE

FLOW CONTROL CHAMBER (S2.18) WITH INTEGRAL
HYDROBRAKE OPTIMUM OR EQUIVALENT APPROVED.
REF: MD-SHE-0193-2310-2300-2310
QMAX: 23.1 l/s. HEAD: 2.3m, CL: 31.47m IL: 28.34m
(22 l/s/ha) (1.05ha) (NT02 & NT03)

PROPOSED ACO STORMBRIXX HD GEOCELLULAR ATTENUATION
TANK OR EQUIVALENT APPROVED. VOL MAX: 160m³. 16.87m x 5.42m
1.84m DEEP. IL 28.80m. POSITION OF TANK TBC PENDING FURTHER
COORDINATION WITH LANDSCAPE/ SITE WIDE SERVICES

NEW MANHOLE ON EXISTING PUBLIC COMBINED SEWER.
UPSTREAM LENGTH TO BE ABANDONED AND REMOVED.
SUBJECT TO S116/ S106 APPLICATION TO UNITED UTILITIES

PROPOSED MANHOLE FOR FUTURE
CONNECTION FROM NT03 DEVELOPMENT

PERMEABLE PAVING TO DISCHARGE VIA PERMAVOID
DIFFUSER UNITS LOCATED WITHIN OPEN GRADED
SUB-BASE. DETAILS TBC PENDING FURTHER
CO-ORDINATION

CENTRAL 2250 PERFORATED RIDGITREAT PIPE
BY POLYPIPE LAID IN NARROW TRENCH FOR
DISPERSAL/ CONVEYANCE/ TREATMENT OF
SURFACE WATER RUN-OFF FROM PERMEABLE
PAVEMENT ABOVE.