



TOTAL SITE AREA:	0.148ha
ESTIMATED STORAGE REQUIREMENTS:	60m³
(A VALUE OF 60m ³ IS ESTIMATED VIA SIMULATION OF A SIMPLIFIED NETWORK FOR YR+45% CC FOR CRITICAL STORM USING FEH RAINFALL METHODOLOGY)	
TOTAL STORAGE PROVIDED VIA ATTENUATION TANK:	60m³

TOTAL SITE AREA:	0.148ha
ESTIMATED STORAGE REQUIREMENTS:	60m³
(A VALUE OF 60m³ IS ESTIMATED VIA SIMULATION OF A SIMPLIFIED NETWORK FOR YR+45% CC FOR CRITICAL STORM USING FEH RAINFALL METHODOLOGY)	
TOTAL STORAGE PROVIDED VIA ATTENUATION TANK:	60m³

TOTAL STORAGE PROVIDED VIA ATTENUATION TANK: 60m³

INDICATIVE LOCATION OF EXISTING UL
COMBINED MANHOLE

DEPTH OF BETWEEN 4.14m AND 4.69m
(INFORMATION PROVIDED BY UU VIA EMAIL ON
14.05.2024)

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECT'S AND ENGINEER'S DRAWINGS AND THE SPECIFICATIONS.
2. THIS DRAWING SHOULD NOT BE SCALED.
3. ALL DIMENSIONS ARE TO BE VERIFIED BY THE CONTRACTOR ON SITE.
4. ALL DISCREPANCIES SHOULD BE REPORTED TO C.A./E.A. PRIOR TO THE COMMENCEMENT OF WORKS.

© CIVIC ENGINEERS LIMITED

NOTES:

1. SITE PLAN PROVIDED BY CODA ARCHITECTS, RECEIVED 19TH APRIL 2024.
2. COVER LEVELS APPROX BASED ON THE PROPOSED FFL PROVIDED BY CODA ARCHITECTURE ON THE 4TH APRIL 2024, DRAWING 2565-CDA-00-SL-DR-A-2602.
3. DROP DOWN LOCATIONS PROVIDED BY CODA ARCHITECTS, RECEIVED SEPTEMBER 2024, DRAWING 2565-CDA-01-XX-DR-A-0600.

KEY:

EXISTING UU SEWER

EXISTING UU MAIN

EXISTING MH

PROPOSED SURFACE WATER MH/IC

PROPOSED FOUL WATER MH/IC

PROPOSED COMBINED MH

PROPOSED SW SEWER

PROPOSED SLOT DRAIN

PROPOSED ATTENUATION TANK

PROPOSED FW SEWER

PROPOSED WASH DOWN GULLY

PROPOSED CW SEWER

PROPOSED BACK DROP

PROPOSED RODDING EYE

SITE BOUNDARY

PROPOSED FILTER DRAIN

PROPOSED PERFORATED PIPE

*SLOT DRAINS PROPOSED AT
ENTRANCES AND CHANNEL DRAINS
ELSE WHERE

THIS DRAWING REPRESENTS THE LAST VERSION
ISSUED FOR CONSTRUCTION. THE DRAWING HAS NOT
BEEN VERIFIED BY SITE SURVEY AND ALLOWABLE
CONSTRUCTION TOLERANCES MAY HAVE RESULTED IN
DIFFERENCES BETWEEN THIS DRAWING AND THE
FINISHED INSTALLATION

12/02/26	003	FINAL CONSTRUCTION ISSUE		CFK	CFK
29/11/24	002	UPDATED TO SUIT AEDI COMMENTS		CER	JF
25/11/24	010	ISSUED FOR CONSTRUCTION		CER	JF
18/11/24	T01	ATTENTION TASK DESIGN		CER	JF
14/10/24	T09	SADDLE CONNECTION ISSUED TO UIU		CER	JF
25/09/24	T08	REDUCED NO OF CHAMBERS		CER	JF
19/07/24	T07	ISSUED IN RESPONSE TO PLANNING QUERY			
04/07/24	T06	UPDATED TO SUIT AEDI COMMENTS	NL	CER	
25/06/24	T05	UPDATED FOLLOWING LFA COMMENTS		CER	JF
14/05/24	T04	EXISTING SEWER DIMS ADDED	CER	CER	
13/05/24	T03	ADDITIONAL EXISTING CW SEWER ADDED		CER	JF
02/05/24	T02	INVERT LEVELS EXISTING		CER	JF
19/04/24	T01	FIRST ISSUE		NL	CER
DATE	REV	DESCRIPTION		DRAWN	CHKD



CIVIC
ENGINEERS

civicingineers.com

PROJECT

ARDWICK GREEN

TITLE

GENERAL DRAINAGE ARRANGEMENT

DRAWING STATUS				STATUS CODE	
CONSTRUCTION					
CE PROJECT No.	SCALE @ A1	DATE CREATED	DRAWN	CHECKED	
2075	1:200	27.02.24	CER	PM	
DRAWING No.				REV	
2075-CIV-XX-XX-D-C-30001				C03	