Level 8 - Sunlight House

Number	Programme	Area
8.01	Reception	30 m²
8.02	Meeting Rooms	33 m²
8.03	Support Services	18 m²
8.04	Open Plan Office Areas	114 m²
8.05	Amenity	49 m²
8.06	Meeting Rooms	26 m²
8.07	Offices	27 m²
8.08	Offices	27 m²
8.09	Support Services	27 m²
8.10	MEP Services	4 m²
8.11	MEP Services	11 m²
8.12	Support Services	45 m²
8.13	Open Plan Office Areas	105 m²
8.14	Open Plan Office Areas	76 m²
8.15	Open Plan Office Areas	32 m²
8.16	Reception	8 m²
8.17	Circulation	57 m²
8.18	Circulation	13 m²

FLOOR FINISH LEGEND:

- FF-001 Carpet Tile - Dark Grey Interface - Ice Breaker - 4282002 Granite
- FF-002 Carpet Tile - Grey Interface - Ice Breaker - 4282023 Amethyst
- FF-003 Carpet Tile - Greige Interface - Ice Breaker - 4282022 Mushroom
- FF-004 Carpet Tile - Blue Interface - Heuga 727 - 4122299 Indigo
- FF-101 Luxury Vinyl Tile Amtico - Spacia - SS5W2504 Honey Oak
- FF-102 Safety Flooring - Tarkett - Safetred Universal R11: Venus
- FF-103 Slip Resistant Vinyl Nora - Noraplan - Ultra Grip - Grey 6015
- FF-104 Anti-Static Vinyl Tile Nora - Noraplan - Astro EC - Grey 6007
- FF-105 Print Room Flooring Nora by Interface Iona 6919
- FE-01 Existing Parquet Floor
- SK-001a Existing Skirting
- SK-001b Existing cable management trunking
- SK-002 Proposed Skirting (to match existing decorative skirting)
- SK-003 Proposed Trunking (to match existing cable management trunking)
- TH-001 Proposed Threshold Strips (Black Rubber)



1 Level 08 - Proposed Floor Finishes Plan
1 : 100

100mm on Original

Print Date: 13/03/2026 2:16:05 pm

NOTES:

This drawing is produced for use in this project only and may not be used for any other purpose. Arcadis (UK) accept no liability for the use of this drawing other than the purpose for which it was intended in connection with this project as recorded on the title block fields 'Purpose of Issue' and 'File Status Code'.
This drawing may not be reproduced in any form without prior written agreement.

RESPONSIBILITY IS NOT ACCEPTED FOR OTHERS SCALING DIRECTLY FROM THIS DRAWING. DO NOT SCALE FROM THIS DRAWING, USE WRITTEN DIMENSIONS ONLY.

Existing building information based on measured survey data which is included within the Appendices of end of Stage Reports – Contractor to undertaken localised checks following strip-out for technical design and coordination, in conjunction with review of Landlord O&M Information.

LEGEND:

Out of Scope

NOTE 01:
100mm level change between core areas and office areas

Rev	Date	Description	Prod.	Chk.	Rvd.	App.
L02	13/03/26	LBC Submission	CC/MD	GR	JO	LC
L01	03/12/25	LBC Submission	SC/JB	JO	LC	GH/KP

Client:
Government Property Agency

ARCADIS
Registered office: 80 Fenchurch Street, London EC3M 4BT
Coordinating office: 80 Fenchurch Street, London EC3M 4BT
www.arcadis.com

Project:
Sunlight House - Floors 7 and 8

Site
Sunlight House, Little Quay Street, Manchester M3 3HP

Drawing Title:
Level 08 - Proposed Floor Finishes Plan

Designed: ARCADIS	Signed: ARCADIS	Date: 13MAR26
Drawn: CC/MD	Signed: CC/MD	Date: 13MAR26
Checked: GR	Signed: GR	Date: 13MAR26
Reviewed: JO	Signed: JO	Date: 13MAR26
Approved: LC	Signed: LC	Date: 13MAR26

Design Stage: Listed Building Consent

Original Size: A1	Grid:	Datum:
Suitability Code: A3	Scale: As indicated	Project Number: 30279810

Suitability Description: OFFICIAL-SENSITIVE

Listed Building Consent Submission

Drawing Number: 30279810-ARC-MAN-08-DR-AR-O1602
Revision: L02

© Copyright reserved