






 EARTH ENVIRONMENTAL & GEOTECHNICAL A Technics Group Company		Project Title: Derby Street, Cheetham Hill				WS01																																																								
		Project Number: A6542		Client: Lapas Chowdhury																																																										
		GL (mAOD): 53		N Coord: 399952		E Coord: 383995																																																								
Date: 03/12/2025		Method: Window Sampler		Driller: PM Sampling		Logged By: LJ																																																								
Depth (m)	Type	Test Result	Level	Legend	Depth (m)	Description	Water	Standpipe																																																						
0.35	ES	S N=5 (1,1,1,2)	52.6		0.40	MADE GROUND: Dark brown locally red sandy very gravelly CLAY. Gravel is angular to subrounded fine to coarse of brick, concrete, limestone, clinker, glass and wood. MADE GROUND: Dark brown sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of brick, concrete and sandstone.																																																								
1.20	ES		52.00		1.00																																																									
1.50	ES																																																													
		S N=11 (2,2,3,4)	51.00		2.00																																																									
2.40	D		50.7		2.30																																																									
2.80	D																																																													
		S N=27 (6,6,7,8)	50.00		3.00	Stiff brown slightly sandy slightly gravelly CLAY. Gravel is angular to subrounded fine to coarse of mudstone.																																																								
3.60	D																																																													
		S pp 50/245mm	49.3		3.70	End Of Borehole At 3.70 m																																																								
			49.00		4.00																																																									
			48.00		5.00																																																									
			47.00		6.00																																																									
KEY D - Disturbed Sample B - Bulk Sample U - Undisturbed W - Water Sample S - Standard Penetration Test C - Cone Penetration Test N - Penetration Test 'N' Value V - Hand Shear Vane kPa  - Groundwater Strike  - Groundwater Level			REMARKS 1. Position cleared with CAT + GENNY 2. Hand dug pit to a depth of 1.00mbgl 3. No waterstrike encountered 4. WS terminated at 3.70mbgl due to SPT refusal Scale: 1:40			Water Strikes <table border="1"> <thead> <tr> <th>Date</th> <th>Strike</th> <th>Level</th> <th>Minutes</th> <th>Casing</th> <th>Sealed</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table> <table border="1"> <thead> <tr> <th colspan="3">Daily Log Of Depths</th> <th colspan="3">Chiselling</th> </tr> <tr> <th>Date</th> <th>Casing</th> <th>Water</th> <th>From</th> <th>To</th> <th>Hours</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>			Date	Strike	Level	Minutes	Casing	Sealed																									Daily Log Of Depths			Chiselling			Date	Casing	Water	From	To	Hours												
Date	Strike	Level	Minutes	Casing	Sealed																																																									
Daily Log Of Depths			Chiselling																																																											
Date	Casing	Water	From	To	Hours																																																									

EARTH ENVIRONMENTAL & GEOTECHNICAL A Technics Group Company			Project Title: Derby Street, Cheetham Hill				WS02	
			Project Number: A6542		Client: Lapas Chowdhury			
			GL (mAOD): 53		N Coord: 399934		E Coord: 384003	
Date: 03/12/2025			Method: Window Sampler		Driller: PM Sampling		Logged By: LJ	
Depth (m)	Type	Test Result	Level	Legend	Depth (m)	Description	Water	Standpipe
2.10 								

		Project Title: Derby Street, Cheetham Hill				WS03	
		Project Number: A6542		Client: Lapas Chowdhury			
		GL (mAOD): 52		N Coord: 399940		E Coord: 383991	
Date: 03/12/2025		Method: Window Sampler		Driller: PM Sampling		Logged By: LJ	

Depth (m)	Type	Test Result	Level	Legend	Depth (m)	Description	Water	Standpipe
0.80	ES	S N=4 (0,1,2,1)	51.81		0.19	MADE GROUND: Black ASPHALT		
			51.62		0.38	MADE GROUND: Light grey sandy GRAVEL. Gravel is subangular to subrounded fine to coarse of sandstone.		
			51.00		1.00	MADE GROUND: Red COBBLES of red brick.		
			50.7		1.30	MADE GROUND: Dark brown locally red sandy gravelly CLAY. Gravel is angular to subrounded fine to coarse of brick.		
3.10	D	S N=2 (0,0,1,1)	50.00		2.00	MADE GROUND: Light grey clayey sandy GRAVEL. Gravel is angular to subrounded fine to coarse of brick, sandstone and concrete.		
4.10	D	S N=11 (3,3,3,2)	49.00		3.00	MADE GROUND: Dark brown slightly sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to coarse of brick and sandstone.		
5.10	D	S N=8 (2,2,2,2)	48.00		4.00	3.00 - 4.00 40% Recovery		
		S N=8 (1,2,3,2)	47.00		5.00	MADE GROUND: Dark brown sandy slightly gravelly CLAY. Gravel is subangular to subrounded fine to medium of brick and sandstone.		
		S N=14 (3,3,4,4)	46.00		6.00	4.00 - 5.00 10% Recovery		
						5.00 - 6.00 40% Recovery		
						End Of Borehole At 6.00 m		

KEY D - Disturbed Sample B - Bulk Sample U - Undisturbed W - Water Sample S - Standard Penetration Test C - Cone Penetration Test N - Penetration Test 'N' Value V - Hand Shear Vane kPa  - Groundwater Strike  - Groundwater Level		REMARKS 1. Position cleared with CAT + GENNY 2. Hand dug pit to a depth of 1.00mbgl 3. No waterstrike encountered 4. WS terminated at 6.00m due to achieving target depth Scale: 1:40	Water Strikes <table border="1"> <tr> <th>Date</th> <th>Strike</th> <th>Level</th> <th>Minutes</th> <th>Casing</th> <th>Sealed</th> </tr> <tr> <td>03/12/2025</td> <td>5</td> <td></td> <td>0</td> <td></td> <td></td> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </table> Daily Log Of Depths <table border="1"> <tr> <th>Date</th> <th>Casing</th> <th>Water</th> <th>From</th> <th>To</th> <th>Hours</th> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </table>	Date	Strike	Level	Minutes	Casing	Sealed	03/12/2025	5		0															Date	Casing	Water	From	To	Hours												
Date	Strike	Level	Minutes	Casing	Sealed																																								
03/12/2025	5		0																																										
Date	Casing	Water	From	To	Hours																																								

 EARTH ENVIRONMENTAL & GEOTECHNICAL A Technics Group Company		Project Title: Derby Street, Cheetham Hill				WS04	
		Project Number: A6542		Client: Lapas Chowdhury			
		GL (mAOD): 52		N Coord: 399925		E Coord: 383994	
Date: 03/12/2025		Method: Cable Percussion		Driller: PM Sampling		Logged By: LJ	

Depth (m)	Type	Test Result	Level	Legend	Depth (m)	Description	Water	Standpipe
0.50	ES		51.78		0.22	MADE GROUND: Black ASPHALT MADE GROUND: Grey CONCRETE MADE GROUND: Light grey gravelly SAND. Gravel is subangular fine to coarse of sandstone.		