Studio Egret West

**0424 Pigeon Triangle**
**Planting Schedule**
**Status: PLANNING**

**Doc No. 0424-SEW-ZZ-ZZ-SH-L-002000**

## Revision Record

| Revision | Date | Reason for Issue | Description of updates | Issued by |
|---|---|---|---|---|
| P01 | 05.12.25 | PLANNING | | SEW |
| | | | | |

Studio Egret West

**0424 Pigeon Triangle**
**Planting Schedule**
**Status: PLANNING**

**Doc No. 0424-SEW-ZZ-ZZ-SH-L-002000**

## Tree Planting
Refer to plan 0424-SEW-ZZ-ZZ-DR-L-005200

Tree Planting - Pigeon Triangle

The trees are already purchased by the client and being stored and cared for by Lanes Nursery.

| Abb | Name | Form | Height (cm) | Spread (cm) | Quantity | Note |
|---|---|---|---|---|---|---|
| AxP | *Aronia x prunifolia* | Multi Stem | 350-400 | 200-300 | 1 | |
| Bn | *Betula nigra* | Multi Stem | 450-500 | N/A | 1 | |
| Bn | *Betula nigra* | Standard | 700 | 300 | 1 | |
| Sa | *Salix alba* | Pollarded | 550 | 180 | 1 | |
| Me | *Mespilus germanica* | Quarter-Standard | 250 | 375 | 1 | |
| JrP | *Juglans regia 'Purpurea'* | Multi Stem | 600-700 | 200-300 | 1 | |
| CcFP | *Cercis canadensis 'Forest Pansy'* | Multi Stem | 300-350 | 175-200 | 1 | |
| CmP | *Corylus maxima 'Purpurea'* | Multi Stem | 500 | 350 | 1 | |
| Hr | *Hippophae rhamnoides* | Multi Stem | 500-600 | 200-300 | 1 | |
| CpP | *Crataegus persimilis 'Prunifolia'* | Multi Stem | 450 | 275 | 1 | |
| Df | *Decaisnea fargesii* | Multi Stem | 175-200 | 175-200 | 1 | |
| BP | *Betula pendula* | Multistem | 700-800 | 150-175 | 1 | |

Tree Planting - Baring Street Verge

The trees are already purchased by the client and being stored and cared for by Lanes Nursery.

| Abb | Name | Form | Height (cm) | Spread (cm) | Quantity | Note |
|---|---|---|---|---|---|---|
| BP | *Betula Pendula* | Multistem | n/a | n/a | 1 | |
| Bpa | *Broussonetia papyrifera* | Multistem | 300-350 | 200-300 | 1 | |
| Ck | *Cornus kousa* | Multistem | 500 | 250 | 1 | |
| Hd | *Hovenia dulcis* | Multistem | 400-500 | 200-300 | 1 | |
| Pt | *Poncirus trifoliata* | Multistem | 250-300 | n/a | 1 | |
| Th | *Tilia henryana* | Multistem | 400-500 | 300-400 | 1 | |
| TsF | *Toona sinensis 'Flamingo'* | Multistem | 400-500 | 150-200 | 1 | |

Studio Egret West

**0424 Pigeon Triangle**
**Planting Schedule**
**Status: PLANNING**

**Doc No. 0424-SEW-ZZ-ZZ-SH-L-002000**

Bed 01
Refer to plan 0424-SEW-ZZ-ZZ-DR-L-005200

Herbaceous Perennials

| Abb | Name | Root | Container | Quantity |
|---|---|---|---|---|
| EW | *Euphorbia Wulfenii* | C | 5L | 20 |
| Ek | *Erigeron karvinskianus* | C | 9cm | 38 |
| TB | *Thymus 'Bressingham'* | C | 9cm | 18 |
| GITH | *Gaura lindheimeri 'The Bride'* | C | 2L | 26 |

The above species of perennials will be planted as per the labelled planting plan.
Final setting out to be agreed with Landscape Architect prior to planting.

Shrubs

| Abb | Name | Eventual height | Eventual Spread | Quantity |
|---|---|---|---|---|
| Rn2 | *Ribes nigrum (2)* | 1.5m | 1.5m | 1 |
| Ps3 | *Prunus spinosa (3)* | 3m | 3m | 1 |
| Rr4 | *Ribes rubrum (4)* | 2m | 1.5m | 1 |
| Rr | *Ribes rubrum* | 2m | 1.5m | 1 |
| Rg | *Rosa glauca* | 2m | 2m | 1 |
| Cc | *Cornus cappucino* | 3m | 3m | 1 |

The above shrubs are already purchased by the client and being stored and cared for by Lanes Nursery.

Mix 01a - Crevice Arrival

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| Eb | *Erigeron karvinskianus* | C | 9cm | 7 | 20% | 8 | |
| Em | *Euphorbia myrsinites* | C | 9cm | 7 | 20% | 8 | |
| OvC | *Origanum vulgare 'Compactum'* | C | 9cm | 7 | 10% | 4 | |
| Sa | *Sedum acre* | C | 9cm | 7 | 20% | 8 | |
| St | *Sempervivum tectorum* | C | 9cm | 7 | 20% | 8 | |
| Tb | *Thymus 'Bressingham'* | C | 9cm | 7 | 10% | 4 | |

Plant randomly within the planting bed. Plants should be tucked within rocks creating an irregular pattern.
Final setting out to be agreed with Landscape Architect prior to planting.

Mix 01b - Block Garden

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| ACF | *Acanthus 'Colin's Folly'* | C | 2L | 9 | 10% | 54 | |
| ACG | *Achillia 'Cloth of Gold'* | C | 9cm | 9 | 10% | 54 | |
| Am | *Alchemilla mollis* | C | 9cm | 9 | 10% | 54 | |
| Cd | *Carex divulsa* | C | 9cm | 9 | 10% | 54 | |
| Ch | *Cyclamen hederifolium* | C | 9cm | 9 | 5% | 27 | |
| CnBC | *Calaminta nepeta 'Blue Cloud'* | C | 9cm | 9 | 5% | 27 | |
| GA | *Geranium macrorrhizum 'Album'* | C | 9cm | 9 | 10% | 54 | |
| Hxh | *Helleborus × hybridus* | C | 2L | 9 | 5% | 27 | |
| Ln | *Luzula nivea* | C | 9cm | 9 | 5% | 27 | |
| Pm | *Pseudodictamnus mediterraneus* | C | 2L | 9 | 10% | 54 | |
| Pv | *Primula vulgaris* | C | 9cm | 9 | 5% | 27 | |
| Sa | *Sesleria autumnalis* | C | 9cm | 9 | 5% | 27 | |
| Sc | *Santolina chamaecyparissus* | C | 2L | 9 | 10% | 54 | |

Plant randomly in single-species groups of 5-7 within the planting bed. Final setting out to be agreed with Landscape Architect prior to planting.

Mix 01c - Block Garden Shade

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| ACF | *Acanthus 'Colin's Folly'* | C | 2L | 9 | 10% | 14 | |
| Am | *Alchemilla mollis* | C | 9cm | 9 | 10% | 14 | |
| Cd | *Carex divulsa* | C | 9cm | 9 | 10% | 14 | |
| Ch | *Cyclamen hederifolium* | C | 9cm | 9 | 10% | 14 | |
| Exr | *Epimedium × Rubrum* | C | 9cm | 9 | 5% | 7 | |
| GA | *Geranium macrorrhizum 'Album'* | C | 9cm | 9 | 10% | 14 | |
| Hxh | *Helleborus × hybridus* | C | 2L | 9 | 10% | 14 | |
| Ln | *Luzula nivea* | C | 9cm | 9 | 10% | 14 | |
| Pv | *Primula vulgaris* | C | 9cm | 9 | 10% | 14 | |
| Rp | *Rubus pentalobus* | C | 9cm | 9 | 5% | 7 | |
| Sa | *Sesleria autumnalis* | C | 9cm | 9 | 10% | 14 | |

Plant randomly in single-species groups of 5-7 within the planting bed. Final setting out to be agreed with Landscape Architect prior to planting.

Mix 01d - Edge Mix

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| Ag | *Aethionema grandiflorum* | C | 9cm | 9 | 20% | 4 | |
| Am | *Alchemilla mollis* | C | 9cm | 9 | 20% | 4 | |
| CnBC | *Calamintha nepeta 'Blue Cloud'* | C | 9cm | 9 | 20% | 4 | |
| Ek | *Erigeron karvinskianus* | C | 9cm | 9 | 25% | 4 | |
| Hs | *Helictotrichon sempervirens* | C | 2L | 9 | 15% | 3 | |

Plant randomly within the planting bed. Final setting out to be agreed with Landscape Architect prior to planting.

Bulbs

| Abb | Name | Grade | Density /m2 | Distribution | Quantity |
|---|---|---|---|---|---|
| CRG | *Crocus 'Ruby Giant'* | 5/+ | 150 | 100% | 2701 |

Final setting out to be agreed with Landscape Architect prior to planting.

Studio Egret West

**0424 Pigeon Triangle**
**Planting Schedule**
**Status: PLANNING**

**Doc No. 0424-SEW-ZZ-ZZ-SH-L-002000**

Bed 02
Refer to plan 0424-SEW-ZZ-ZZ-DR-L-005200

Herbaceous Perennials

| Abb | Name | Root | Container | Quantity |
|---|---|---|---|---|
| EW | *Euphorbia Wulfenii* | C | 5L | 11 |
| Ls | *Lythrum salicaria* | C | 2L | 22 |
| Ek | *Erigeron karvinskianus* | C | 9cm | 15 |
| TB | *Thymus 'Bressingham'* | C | 9cm | 7 |
| Hg | *Herniaria glabra* | C | 9cm | 18 |
| Ls | *Leptinella squalida* | C | 9cm | 15 |

The above species of perennials will be planted as per the labelled planting plan.
Final setting out to be agreed with Landscape Architect prior to planting.

Shrubs

| Abb | Name | Eventual height | Eventual Spread | Quantity |
|---|---|---|---|---|
| Sbb | *Sambucus 'Black Beauty'* | 5m | 3m | 1 |
| Rc2 | *Rosa canina (2)* | 3m | 2m | 1 |
| Se | *Salix elegans* | 8-12m | 4-8m | 1 |

The above shrubs are already purchased by the client and being stored and cared for by Lanes Nursery.

Mix 02a - Willow Wetland

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| Am | *Alchemilla mollis* | C | 9cm | 9 | 10% | 20 | |
| Av | *Aquilegia vulgaris* | C | 9cm | 9 | 15% | 30 | |
| BaS | *Bistorta affinis 'Superba'* | C | 9cm | 9 | 10% | 20 | |
| GTT | *Geum 'Totally Tangerine'* | C | 2L | 9 | 10% | 20 | |
| IBA | *Iris'Benton Apollo'* | C | 2L | 9 | 10% | 20 | |
| PvS | *Panicum virgatum 'Shenandoah'* | C | 9cm | 9 | 10% | 20 | |
| RfG | *Rudbeckia fulgida 'Goldsturm'* | C | 2L | 9 | 10% | 20 | |
| Sc | *Sesleria caerulea* | C | 9cm | 9 | 15% | 30 | |
| Vv | *Veronicastrum virginicum* | C | 9cm | 9 | 10% | 20 | |

Plant randomly in single-species groups of 3-5 within the planting bed.
Final setting out to be agreed with Landscape Architect prior to planting.

Mix 02b - Crevice Arrival

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| Eb | *Erigeron karvinskianus* | C | 9cm | 7 | 20% | 8 | |
| Em | *Euphorbia myrsinites* | C | 9cm | 7 | 20% | 8 | |
| OvC | *Origanum vulgare 'Compactum'* | C | 9cm | 7 | 10% | 4 | |
| Sa | *Sedum acre* | C | 9cm | 7 | 20% | 8 | |
| St | *Sempervivum tectorum* | C | 9cm | 7 | 20% | 8 | |
| TB | *Thymus 'Bressingham'* | C | 9cm | 7 | 10% | 4 | |

Plant randomly in single-species groups of 3-5 within the planting bed. Plants should be tucked within rocks creating an irregular pattern.
Final setting out to be agreed with Landscape Architect prior to planting.

Mix 02c - Block Garden (Path Edge)

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| ACG | *Achillia 'Cloth of Gold'* | C | 9cm | 9 | 12% | 18 | |
| Am | *Alchemilla mollis* | C | 9cm | 9 | 12% | 18 | |
| Cd | *Carex divulsa* | C | 9cm | 9 | 10% | 16 | |
| CnBC | *Calaminta nepeta 'Blue Cloud'* | C | 9cm | 9 | 12% | 18 | |
| GA | *Geranium macrorrhizum 'Album'* | C | 9cm | 9 | 15% | 23 | |
| Hxh | *Helleborus × hybridus* | C | 2L | 9 | 12% | 18 | |
| Pm | *Pseudodictamnus mediterraneus* | C | 2L | 9 | 15% | 23 | |
| Sc | *Santolina chamaecyparissus* | C | 2L | 9 | 12% | 18 | |

Plant randomly in single-species groups of 5-7 within the planting bed. Plants should be tucked within rocks creating an irregular pattern.

Bulbs

| Abb | Name | Grade | Density /m2 | Distribution | Quantity |
|---|---|---|---|---|---|
| Cq | *Camassia quamash* | 6/+ | 30 | 100% | 249 |

Final setting out to be agreed with Landscape Architect prior to planting.

Studio Egret West

**0424 Pigeon Triangle**
**Planting Schedule**
**Status: PLANNING**

**Doc No. 0424-SEW-ZZ-ZZ-SH-L-002000**

## Bed 03
Refer to plan 0424-SEW-ZZ-ZZ-DR-L-005200

### Herbaceous Perennials

| Abb | Name | Root | Container | Quantity |
|---|---|---|---|---|
| Ch | *Crocosmia 'Hellfire'* | C | 5L | 32 |
| IBA | *Iris'Benton Apollo'* | C | 2L | 32 |
| Ek | *Erigeron karvinskianus* | C | 9cm | 43 |
| TB | *Thymus 'Bressingham'* | C | 9cm | 33 |
| Hg | *Herniaria glabra* | C | 9cm | 7 |
| Ls | *Leptinella squalida* | C | 9cm | 5 |

The above species of perennials will be planted as per the labelled planting plan.
Final setting out to be agreed with Landscape Architect prior to planting.

### Shrubs

| Abb | Name | Eventual height | Eventual Spread | Quantity |
|---|---|---|---|---|
| Rc3 | *Rosa canina (3)* | 1.5m | 1.5m | 1 |
| Cd | *Cornus drummondii* | 5-7m | 3-4.5m | 1 |

The above shrubs are already purchased by the client and being stored and cared for by Lanes Nursery.

### Mix 03a - Orange Mix

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| Ac | *Astrantia 'Claret'* | C | 2L | 9 | 15% | 42 | |
| AcG | *Achillia 'Cloth of Gold'* | C | 9cm | 9 | 5% | 14 | |
| Al | *Anemanthele lessoniana* | C | 2L | 9 | 10% | 28 | |
| Am | *Alchemilla mollis* | C | 9cm | 9 | 5% | 14 | |
| AmRV | *Achillia millefolium 'Red Velvet'* | C | 9cm | 9 | 15% | 42 | |
| Bm | *Briza media* | C | 9cm | 9 | 5% | 14 | |
| Cv | *Chrysogonum virginianum* | C | 2L | 9 | 5% | 14 | |
| ETT | *Echinacea 'Tiki Torch'* | C | 2L | 9 | 10% | 28 | |
| GTT | *Geum 'Totally Tangerine'* | C | 2L | 9 | 10% | 28 | |
| Hxh | *Helleborus x hybridus* | C | 2L | 9 | 5% | 14 | |
| Ln | *Luzula nivea* | C | 2L | 9 | 5% | 14 | |
| St | *Stipa tenuissima* | C | 9cm | 9 | 5% | 14 | |
| TgR | *Tellima Grandiflora Rubra* | C | 9cm | 9 | 5% | 14 | |

Plant randomly in single-species groups of 3-5 within the planting bed. Final setting out to be agreed with Landscape Architect prior to planting.

### Mix 03b - Edge Mix

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| Ag | *Aethionema grandiflorum* | C | 9cm | 9 | 20% | 9 | |
| Am | *Alchemilla mollis* | C | 9cm | 9 | 20% | 9 | |
| CnBC | *Calamintha nepeta 'Blue Cloud'* | C | 9cm | 9 | 20% | 9 | |
| Ek | *Erigeron karvinskianus* | C | 9cm | 9 | 25% | 12 | |
| Hs | *Helictotrichon sempervirens* | C | 2L | 9 | 15% | 8 | |

Plant randomly within the planting bed. Final setting out to be agreed with Landscape Architect prior to planting.

### Mix 03c - Crevice Arrival

| Abb | Name | Root | Container | Density /m2 | Distribution | Quantity | Note |
|---|---|---|---|---|---|---|---|
| Eb | *Erigeron karvinskianus* | C | 9cm | 7 | 20% | 2 | |
| Em | *Euphorbia myrsinites* | C | 9cm | 7 | 20% | 2 | |
| OvC | *Origanum vulgare 'Compactum'* | C | 9cm | 7 | 10% | 1 | |
| Sa | *Sedum acre* | C | 9cm | 7 | 20% | 2 | |
| St | *Sempervivum tectorum* | C | 9cm | 7 | 20% | 2 | |
| TB | *Thymus 'Bressingham'* | C | 9cm | 7 | 10% | 1 | |

Plant randomly within the planting bed. Plants should be tucked within rocks creating an irregular pattern.
Final setting out to be agreed with Landscape Architect prior to planting.

### Bulbs

| Abb | Name | Grade | Density /m2 | Distribution | Quantity |
|---|---|---|---|---|---|
| NPE | *Narcissus 'Pheasant's Eye'* | 12/14+ | 60 | 50% | 268 |
| Ns | *Nectaroscordum siculum* | 7/+ | 80 | 50% | 358 |

Final setting out of plants to be agreed with Landscape Architect prior to planting

Studio Egret West

**0424 Pigeon Triangle**
**Planting Schedule**
**Status: PLANNING**

**Doc No. 0424-SEW-ZZ-ZZ-SH-L-002000**

Bed 04
Refer to plan 0424-SEW-ZZ-ZZ-DR-L-005200

Woodland Turf Mix

| Abb | Name | Supplier | Area |
|---|---|---|---|
| WF | *Woodland Fringe* | Pictorial Meadows | 57.8m2 |
| PH | *Purple Haze* | Pictorial Meadows | 39.1m2 |

The above planted turf will be planted as per the labelled planting plan.
Final setting out to be agreed with Landscape Architect prior to planting.

Shrubs

| Abb | Name | Eventual height | Eventual Spread | Quantity |
|---|---|---|---|---|
| Cm | *Crateagus monogyna* | 4-8m | 4-8m | 1 |
| Cp | *Crateagus prunifolia* | 4-8m | 8m+ | 1 |
| Ps2 | *Prunus spinosa (2)* | 2.5-4m | 2.5-4m | 1 |
| Ps | *Prunus spinosa* | 2.5-4m | 2.5-4m | 1 |
| Rn | *Ribes nigrum* | 1-1.5m | 1-1.5m | 1 |
| Rr3 | *Ribes rubrum (3)* | 1.5-2.5m | 1-1.5m | 1 |
| Rrx2 | *Ribes rubrum x2 (Two Shrubs)* | 1.5-2.5m | 1-1.5m | 2 |
| Rc | *Rosa canina* | 2.5-4m | 1.5-2.5m | 1 |
| Ck | *Cornus kousa* | 4-8m | 4-8m | 1 |

The above shrubs are already purchased by the client and being stored and cared for by Lanes Nursery.
Shrubs shown with strikethrough are available however eventual grown has limited placement within planting.