

1. ALL PIPEWORK TO BE CROSS BONDED IN ACCORDANCE WITH BS5767 I
2. AC PIPEWORK IN VOIDS/RISERS/BOXING SHALL BE THERMALLY INSULATED AND PRESSURE TESTED PRIOR TO SEALING IN
3. ALL PRESSURE TESTING TO BE WITNESS, TEST PRESSURE TO BE 1.5 TIME OPERATING PRESSURE AND HELD FOR 6 HOURS, ANY RE-TEST TO BE AS ABOVE.
4. SYSTEMS ARE ALL TO BE TRIPLE VACUUMED
5. COMMISSIONING TO BE BY THE MANUFACTURER / DISTRIBUTOR
6. GRAVITY CONDENSATE 20MM TO ALL INDOOR UNITS WITH INLINE DRY TRAP IN VERTICAL LOCATION - TO BE RUN TO BATHROOM DRAINAGE
7. SPECIAL ATTENTION TO CO-ORDINATION WITH OTHER SERVICES DUE TO LIMITED VOID SPACE
8. CEILING ACCESS DOOR NUMBERS AND LOCATIONS TO BE CONFIRMED BY INSTALLER
9. ALL SERVICES SHALL BE IDENTIFIED IN ACCORDANCE WITH BS1710:2014.
10. ALL PIPEWORK PASSING THROUGH FIRE BARRIERS SHALL BE PROTECTED TO THE APPROPRIATE STANDARD
11. WALL CONTROLLER LOCATIONS TO ARCHITECT DRAWING.
12. SEASONAL COMMISSIONING BY THE MANUFACTURER / DISTRIBUTOR TO BE INCLUDED FOR BREEM
13. SERVICING TO BE BASED ON TWO VISIT POST FC
14. OXYGEN FREE NITROGEN TO BE USED WHEN BRAISING PIPEWORK
15. CENTRALISED CONTROLLER FOR OVERALL SETUP - LOCATED AT SIDE OF RECEPTION

1. ALL AC PIPEWORK IS COPPER
2. ALL PIPEWORK WILL BE ENCLOSED IN 13mm WALL THICKNESS CLASS O ELASTOMERIC INSULATION, CLOSED-CELL NITRILE RUBBER

DETAIL	BUILDERS WORK OPENING:
(A)	1 PIPE = 16mm PER PIPE. 1 PIPE = 13mm PER PIPE. 1 PIPE = 9.5mm PER PIPE. Opening : 150mmWx 100mmH
(B)	8 PIPES = 19mm PER PIPE. 8 PIPES = 16mm PER PIPE. 8 PIPES = 13mm PER PIPE. Opening : 1100mmWx 100mmH
(C)	4 PIPES = 19mm PER PIPE. 4 PIPES = 16mm PER PIPE. 4 PIPES = 13mm PER PIPE. Opening : 600mmWx 100mmH
(D)	2 PIPES = 19mm PER PIPE 3 PIPES = 16mm PER PIPE. 3 PIPES = 13mm PER PIPE. 1 PIPE = 9.5mm PER PIPE Opening : 450mmWx 100mmH
(E)	2 PIPES = 16mm PER PIPE. 2 PIPES = 13mm PER PIPE. 2 PIPES = 9.5mm PER PIPE. Opening : 300mmWx 100mmH
(F)	1 PIPE = 19mm PER PIPE. 1 PIPE = 16mm PER PIPE. 1 PIPE = 13mm PER PIPE. Opening : 150mmWx 100mmH
(G)	3 PIPES = 19mm PER PIPE. 3 PIPES = 16mm PER PIPE. 3 PIPES = 13mm PER PIPE. Opening : 450mmWx 100mmH
(H)	3 PIPES = 19mm PER PIPE. 4 PIPES = 16mm PER PIPE. 4 PIPES = 13mm PER PIPE. 1 PIPE = 9.5mm PER PIPE. Opening : 600mmWx 100mmH



REV	DATE	DESCRIPTION	DRW	ENG
P01	03.11.2025	FIRST ISSUE	PD	PD
P02	11.11.2025	PIPE SIZE DETAIL ADDED	JC	JC
P03	15.11.2025	TENDER ISSUE	PD	PD
P04	22.12.2025	TENDER ISSUE UPDATE	PD	PD

<div style="display: flex; justify-content: space-between; align-items: center;"> <div> <p>Client MITCHELLS & BUTLERS Pic</p> </div> <div style="border: 1px solid black; padding: 5px; text-align: center;"> <p>Mitchells & Butlers</p> </div> </div>					
<p>BMT Project No. / Project Region B3322 / KC MANCHESTER</p>					
<p>Project Address INNKEEPERS COLLECTION 1-4 YORK STREET (BROWNS) MANCHESTER</p>					
<p>Drawing Title MECHANICAL INSTALLATION AC THIRD FLOOR</p>					
Job No.	Originator	Zone	Level	Type	Role
B3322	BMT	ZZ	03	DR	M
System Classification		Drawing No.		Suitability	Revision
Ss_60_40_17_71_2030		D2		P04	
Drawn	Engineer	Date	Scale	Size	
PD	PD	03.11.2025	1:100	A1	

**BUILDING
MANAGEMENT
TECHNOLOGY**

**9208 MELTON ROAD
 THURMASTON
 LEICS,
 LE4 8UR
 TEL: (0165) 244 0331
 E-MAIL: <firstname.surname>@bmt-trd.co.uk>**