

ALM100 SCREW-ON
& SNAP-ON CAPPINGS

ALM HEAVY DUTY
GLASS STOP

NEW 50mm WIDE
TIMBER CURB x
HEIGHT TO SUIT
MINIMUM 150mm
UPSTAND ABOVE
MAIN ROOF FINISH

2mm ALUMINIUM
SIDE FLASHING

MINIMUM 150mm

INDICATIVE ONLY
NEW INSULATION
ON EXISTING ROOF

28.8mm DG UNIT
WITH STEPPED
BOTTOM EDGE

ALM100 CARRIER RAIL

ALM100/2 BOX, BAR
LENGTH TO BE CUT
IN ON SITE TO SUIT

DG DRAUGHT FILLET

15mm INTERNAL
FINISH BY OTHERS

NEW IKO ULTRA PREVENT
ROOF FINISH BY OTHERS
NOMINAL 8-10mm THICK.
LAID ON TOP OF VARYING
THICKNESS INSULATION,
UP & OVER ONTO THE
TOP SURFACE OF CURB,
ROOF FINISH MINIMUM
150mm BELOW TOP OF
NEW TIMBER CURB ROOF
FINISH

REV:	DESCRIPTION:	BY:	DATE:
------	--------------	-----	-------

STATUS: FOR APPROVAL



Rooflights & Atriums Ltd
Suite 3, 2nd Floor, Didsbury House,
748-754 Wilmslow Road, Manchester M20 2DW
07908 441 987
E Mail: will@rooflightsandatriums.co.uk
Web: www.rooflightsandatriums.co.uk

CLIENT: CRESCENT ROOFING LTD
SUITE 6, LEVEL 4 ARRIVE, TOMORROW
BUILDING, MEDIA CITY, MANCHESTER,
M50 2AB

SITE: BRUNSWICK MILL, BRADFORD ROAD,
MANCHESTER, M40 7EZ

TITLE: 16 No. MONOPITCH REPLACEMENT
ROOFLIGHTS - BOTTOM SECTION THROUGH

SCALE AT A3: 1:2	DATE: 6.10.2025	DRAWN: LMS	CHECKED: WB
PROJECT NO: SC20561	DRAWING NO: 05	REVISION: —	