

Furniture Schedule Scheme		
Furniture Type	Count	
1 - New Furniture		
Dining Chair	60	
Dining Table	20	
Lounge Chair	2	
Poseur Table	2	
Stool	19	
2 - Retained/Refurbished Furniture		
Existing Bar Stool	8	
Settle	1	

Joinery Schedule Scheme		
Joinery Type	Length (mm)	
2 - Retained/Refurbished Joinery Items		
Fixed Shelving	9200	

Flooring Schedule Scheme		
Floor Type	Area (m²)	
1 - New Flooring		
Ceramic	259.79	
Entrance Matting	3.03	
Existing Bar Safety Floor	6.61	
Existing Cellar WC Floor Tiles	15.09	
Existing Kitchen Safety Floor	53.45	
Existing Parquet Floor	138.77	
Stone	48.10	
Vinyl	19.34	

Lighting Schedule Scheme		
Light Type	Count	
1 - New Lighting Fixture		
Directional Spotlight	1	
Flush Light	9	
Pendant Light	3	
Recessed Light	6	
Wall Light	1	
2 - Retained/Refurbished Lighting Fixture		
Table Lamp	4	
Flush Light	18	
Light Point Fixture	75	
Multi Pendant Light	10	
Pendant Light	5	
Recessed Light	22	

General Notes

Drawing produced utilising matterport scan and cloud point data. Follow link to access Matterport walk through of site:
<https://my.matterport.com/show/?m=1EH4Z2n3Hx>

Contractor is advised not to scale from the supplied drawings. Contractor to check all dims onsite prior to producing fee quotes and/or manufacture of joinery items.

Client is advised to appoint a certified quantity surveyor to prepare all cost documents.

Client is advised to instruct full load test of site to ensure incoming load and existing phases are adequate to provide power to lift and new new electrical equipment on site.

Client is advised to instruct a heritage expert to assist in the preparation and submission of listed building application in relation to all proposed works.

Client is advised that MGI cannot guarantee the success of any listed building application submitted to the local authority and accept no liability in relation to abortive fees in the event of a listed building application refusal.

Client is advised to instruct Structural engineer at early stages of project preparation to ensure required structural elements are accurately budgeted for.

FF&E Status Colour Code Key

☐ Contractor Procured New Item

☐ Client Item To Be Refurbished and/or Retained

Floor Colour Code Hatch Key

☐ Carpets

☐ Ceramic

☐ Entrance Matting


☐ External Surfaces

☐ Safety Flooring


☐ Stone

☐ Timber

☐ Vinyl



01 - First Floor (Proposed) 1 : 50



Ground Floor (Proposed) 1 : 50

PRODUCT REFERENCE IMAGES



Ogee Moulding B1423 by WRP Mouldings

Early Victorian - RD01600 - Anaglypta

Keswick 600 x 605mm Cast Iron Style Traditional 3 Column Anthracite Radiator

Keswick 600 x 1370mm Cast Iron Style Traditional 3 Column Anthracite Radiator

Front Bar Gantry by Bar-Fittings.com - in antique Brass

Reeded Glass Globe to bar gantry indicated above

B 14.11.2025 revisions to first floor WC provision to suit MLL requirements.

A 22.05.2025 First floor WC layout revised at Stuart Burley's instruction

1 XXXXXX First Issue for Information

Rev	Date	Notes
1	14.11.2025	First Issue for Information

Drawing Number: 0002.1

Drawing Title: Proposed Planning GA

Product: Mr Thomas's Chop House, Manchester

Client: Kieron Dunne - Punch Pubs

Job Number	Size	Scale
3180	A1	1 : 50
Drawn	Approved	Date
CIP	///	06.11.2024

mgi

THIS DRAWING REMAINS THE COPYRIGHT OF MGI PARTNERS (A TRADING NAME OF MILLION GROUP LTD.) AND IT MUST BE COMPILED OR APPROVED BY WRITTEN CONSENT. ALL RIGHTS OUT. DIMENSIONS AND LEVELS SHOULD ONLY BE TAKEN FROM THE PROVIDED DIMENSION VALUES STATED ON THIS DRAWING. NO ATTEMPT SHOULD BE MADE TO SCALE FROM THE DRAWING. MGI PARTNERS ALWAYS ARE IF YOU REQUIRE MORE INFORMATION.

ALL INFORMATION BETWEEN DRAWING AND SITE CONDITIONS ARE TO BE REPORTED TO MGI PARTNERS IMMEDIATELY. ALL CONTRACTORS MUST VISIT THE SITE AND ARE SOLELY RESPONSIBLE FOR TAKING AND CHECKING ALL DIMENSIONS AND AREA TO THE WORK THEY ARE REQUIRED TO CARRY OUT.

THIS DRAWING MUST NOT BE USED ON SITE UNLESS ISSUED FOR CONSTRUCTION.