

SITE PLAN 1:150

63_LIGHTING NOTES

01. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS AND DOCUMENTS RELATING TO THE MECHANICAL AND ELECTRICAL INSTALLATIONS.
02. ALL DIMENSIONS WHERE SHOWN ARE IN MILLIMETERS /METERS. THIS DRAWING SHALL NOT BE SCALED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CHECKING ALL DIMENSIONS THROUGH SITE MEASUREMENTS PRIOR TO COMMENCEMENT OF THE WORKS.
03. ALL OTHER DISCIPLINES' SPECIFICATIONS SHALL BE READ IN CONJUNCTION WITH THE HURSTWOOD ENVIRONMENTAL BUILDING SERVICES SPECIFICATION AND DRAWINGS AS WELL AS ARCHITECTS, STRUCTURAL ENGINEER'S, ACOUSTIC ENGINEER'S AND FIRE CONSULTANTS'. ANY DISCREPANCIES BETWEEN ANY DOCUMENT, DRAWING OR SCHEDULE SHOULD BE CLARIFIED AT TENDER OR THE MOST COST ONEROUS OPTION SHALL BE DEEMED TO HAVE BEEN ALLOWED FOR.
04. TEST KEYS ARE TO BE PROVIDED ADJACENT THE DISTRIBUTION BOARD. THE OPERATION OF THE SWITCH/FAIER DOES NOT EFFECT THE GENERAL LIGHTING.
05. LUMINAIRE TYPES AND SPECIFICATIONS ARE PERFORMANCE SPECIFICATION AND TYPES ONLY AND FOR PRELIMINARY REVIEW AND ARE NOT FINAL SELECTIONS.
06. THE CALCULATION MODEL SHALL BE RECALCULATED TO REFLECT FINAL LUMINAIRE SELECTIONS AND BE CARRIED OUT PRIOR TO ORDERING OF ANY LUMINAIRES.
07. ALL LUMINAIRES TYPES SHALL BE REVIEWED IN LINE WITH FINAL BUILDING ARCHITECTS AND LANDSCAPE ARCHITECTS DETAILS.
08. UPVC IN-GROUND DUCTING BURIED AT MINIMUM DEPTH OF 450MM TO TOP OF DUCTING AND ASSOCIATED HEAVY DUTY DRAW PITS SHALL BE INCLUDED.
09. LAND LORDS LIGHTING TO AMENITY AREAS SHALL BE CONTROLLED BY CONTACTOR/TIMECLOCK/PHOTOCELL ARRANGEMENT. LUMINAIRES FOR DOMESTIC DWELLINGS SHALL FEATURE INTEGRAL MICROWAVE PIR SENSOR.

63_LIGHTING LEGEND

- X1 — TYPE X1 - ANSELL WOLF WALL PACK. LED 3000K IP66 BLACK. PHOTOCELL/MICROWAVE REQUIRED FOR DWELLINGS. 'E' DENOTES 3 HOUR EMERGENCY VERSION.
- X2 — TYPE X2 - ANSELL AVIO BOLLARD LUMINAIRE.
- X3 — TYPE X3 - SELUX - OLIVIO 5m HIGH COLUMN DOWNLIGHT.
- X4 — TYPE X4 - SLV LED INGROUND FEATURE PLANTING UPLIGHTER/WASHER.
- X5 — TYPE X5 - AURALED - IP65 SURFACE MOUNTED LINEAR LUMINAIRE | 9W 2000LM 3K BLACK. PHOTOCELL/MICROWAVE REQUIRED FOR BIN STORES. 'E' DENOTES 3 HOUR EMERGENCY VERSION.
- X6 — TYPE X6 - INGROUND LINEAR / RECESSED WALL MOUNTED STEP LIGHT.
- TYPE X6 - IP68 RECESSED RGB LED STRIP LIGHTING SET WITHIN FURNITURE
- TYPE X7 - STEP LIGHTING.
- TYPE X8 - HANDRAIL LIGHTING
- RS4 — TYPE RS4 - EXISTING FITTING TO BE REMOVED OR RE INSTATED.
- S — STREET LIGHT

NOTES

Do not scale from this drawing as lines may stretch in copying

REVISION	DATE	PURPOSE	DRAWN
E			
D			
C			
B			
A			

Client: Edencroft Building Services
Project: Downtown Victoria North
TITLE: External Lighting Proposals- Illuminance Values

REVISION	DWG No. :	SCALE
X	LS0890-DVN-EX-P02	1:250 @ A1
	DATE Oct '25 / DRAWN BY LS	CHECKED BY LS

Luminous Solutions
LIGHTING CONSULTANCY

Arch Suite
The Old Corn Mill
Bullhouse Mill
Millhouse Green
Sheffield
S36 9NN
Tel: 03304 609585
www.luminoussolutions.co.uk

INSTITUTION OF LIGHTING PROFESSIONALS