DOOR SCHEDULE

stephenson hamilton risley
STUDIO

project : Apartments 101 and 102, Paragon Mill
job number : 7710
document : 7710-Door schedule P02.xlsx
sheet : GROUND FLOOR
revision : P02

for door number and swing refer to (04)0000 series
for door type refer to (32)000 series
for ironmongery refer to separate schedule and comments where noted
for lintel type refer to schedule by engineer
the door handing is the side at which the door is hinged when viewed from the pull side
the left hand jamb is the left hand side of the door when viewed from the pull side
all door undercuts assumed 3mm unless confirmed otherwise by MEP

Door Number	Door Type	Room Name	Door frame throat (mm)	Min clear door width required (door stop to ironmongery)	structural opening ABOVE FFL		door undercut	Configuration			leaf size			handing		fire rated	Integrated lock	touch latch	soft close/catch	frame type	door finish	architrave type	ironmongery type (all to AD Part M)		notes
					Height (mm)	Width (mm)	undercut (mm)	Single	Double	Leaf and a Half	Height (mm)	Width (mm)	Thickness (mm)	Left	Right								pull handle / push plate / kick plate	floor mounted door stop	
Ground Floor Level - GF Proposed																									
D-001	as existing	front door	na	as existing	as existing	as existing	as existing	✓			as existing	as existing	as existing			as existing				as existing	as existing	as existing		✓	As existing door - not to be removed
D-002	DOR-100	utility room	na	na	2100	1010	3	✓			2040	926	44		✓	**FD30**		✓	✓	hardwood	paint finish	paint MDF		✓	**Eclisse SINGLE FIRE-RATED Pocket Door System (Rev F)** Finished wall thickness 100mm. Door: JELD-WEN RANGE Paint grade premium door - White primed. - finished pre hanging.
D-003	DOR-101	toilet within en-suite	na	na	To be calculated pre order	810	3	✓			2512 NB to be calculated pre order	726	44		✓	na	✓	✓	✓	hardwood	paint finish	n/a		✓	**Portman architrave free kit.** P5700 reinforcing kit required. Finished wall thickness 125mm. Architrave to match door into master bedroom on bedroom side. Door: Portman primed flush door - finished pre hanging.
D-004	DOR-101	en-suite	na	na	To be calculated pre order	910	3	✓			2512 NB to be calculated pre order	826	44		✓	na	✓	✓	✓	hardwood	paint finish	n/a		✓	**Portman architrave free kit.** P5700 reinforcing kit required. Finished wall thickness 125mm. Door: Portman primed flush door - finished pre hanging.
D-005	DOR-100	master bedroom	na	na	2100	1010	3	✓			2040	926	44		✓	**FD30**	✓	✓	✓	hardwood	paint finish	paint MDF		✓	**Eclisse SINGLE FIRE-RATED Pocket Door System (Rev F)** Finished wall thickness 100mm. Door: JELD-WEN RANGE Paint grade premium door - White primed. - finished pre hanging.
D-006	DOR-102	study	na	na	2100	1010	3	✓			2040	826	44	✓		**FD30**				hardwood	paint finish	paint MDF		✓	Architrave to match existing within corridor
D-007	DOR-102	bedroom 02	na	na	2100	1010	3	✓			2040	826	44	✓		**FD30**				hardwood	paint finish	paint MDF		✓	Architrave to match existing within corridor
D-008	DOR-102	bedroom 03	na	na	2100	1010	3	✓			2040	826	44	✓		**FD30**				hardwood	paint finish	paint MDF		✓	Architrave to match existing within corridor
D-009	DOR-101	living space	na	na	To be calculated pre order	To be calculated pre order	3	✓			2430 NB to be calculated pre order	1500	44		✓	**FD30**		✓	✓	hardwood	paint finish	n/a		✓	**Portman Fire Rated - FD30 door.** P5700 reinforcing kit required. Finished wall thickness 150mm. Door: Portman primed flush door - finished pre hanging.
D-010	as existing	existing bathroom	na	as existing	as existing	as existing	as existing	✓			as existing	as existing	as existing		✓	as existing				as existing	as existing	as existing		✓	As existing door - not to be removed

® stephenson hamilton risley STUDIO ltd. for terms and conditions refer to www.shr.studio