Do not scale from this drawing. Drawing is the property of The University of Manchester. Drawing is not to be copied or used in any manner without permission. Check all dimensions on site before commencing any work or shop drawings.

DOOR E
FROM
REPORT

CONTRACTOR TO REMOVE EURO
CYLINDER AND REPLACE
WITH L100 LOCK CASE AND HANDLE

CONTRACTOR TO SUPPLY AND INSTALL
HUB. POSITION TO BE CONFIRMED

CONTRACTOR TO INCLUDE TO
RE-COMMISSION EXISTING DOOR LOCK

EXISTING PUSH BAR FIRE EXIT

DOOR C
FROM REPORT
NO WORKS REQUIRED

DOOR N
FROM REPORT
NO WORKS REQUIRED

CONTRACTOR TO REMOVE EURO
CYLINDER AND REPLACE
WITH L100 LOCK CASE AND HANDLE

DOOR B
FROM REPORT

EXISTING AUTO DOOR OPENER

EXISTING POWER AND DATA

THE CONTRACTOR SHALL INCLUDE TO
REPLACE THE EXISTING CONTROLLER
WITH A NEW SPC CONTROLLER

EXISTING PERIO HUB

CONTRACTOR TO SUPPLY AND INSTALL:-
- UNSWTCHED FUSED CONNECTION UNIT.
- DATA POINT.
- CONTROLLER(SPC)

CONTRACTOR TO SUPPLY AND INSTALL
HUB. POSITION TO BE CONFIRMED

G.017
C1
BALANCE
10.96

G.018
C2
BALANCE
30.88

G.002
G.4
OFFICE
23.61

G.003
G.6
OFFICE
31.47

G.022
S1
BALANCE
4.33

G.011
-
STORAGE
.23

G.012
-
BALANCE
9.90

G.013
-
STORAGE
6.30

G.021
C5
BALANCE
4.63

G.010
-
STORAGE
.70

G.009
G.10
COMMUNAL
9.95

G.029
-
BALANCE
.56

G.008
G.7
OFFICE
36.33

G.004
G.3
OFFICE
31.22

G.019
C3
BALANCE
45.22

G.020
C4
BALANCE
20.53

G.026
L1
BALANCE
2.41

G.025
S6
BALANCE
2.88

G.007
G.9
OFFICE
67.85

G.006
G.8
OFFICE
28.70

G.024
S5
BALANCE
2.84

G.023
S3
BALANCE
2.48

G.005
G.2
OFFICE
63.17

G.027
S7
BALANCE
1.72

G.016
-
BALANCE
19.96

G.015
-
BALANCE
7.57

G.014
G.1
COMMUNAL
2.81

DL
HUB
PB
CT
13

NOTES

1. DO NOT SCALE FROM THIS DRAWING.
2. ALL MEASUREMENTS ARE IN MILLIMETERS UNLESS STATED OTHERWISE.
3. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE SPECIFICATION AND ALL RELEVANT ARCHITECTURAL, ELECTRICAL, MECHANICAL AND STRUCTURAL DRAWINGS.
4. (c) UNIVERSITY OF MANCHESTER. THIS DRAWING MUST NOT BE REPRODUCED WITHOUT PERMISSION.
5. DIRECTORATE OF ESTATES AND FACILITIES TO BE NOTIFIED OF ANY DISCREPANCIES.

KEY

- CAT 5E NETWORK POINTS
- SWITCHED FUSED CONNECTION UNIT
- 2 COMPARTMENT GALVANISED TRUNKING
- AXIS M4328-P 360 FISHEYE CAMERA 12MP
- AXIS P3268-LVE DOME CAMERA 8MP (to be set to corridor mode)

Rev	Description	Date	By	Chk'd	Auth

MANCHESTER 1824
The University of Manchester
Directorate of Estates and Facilities
Beyer Building
The University of Manchester
Oxford Road
Manchester
M13 9PL

Drawing Status: TENDER

Project: PN9300
PROPOSED ACCESS CONTROL AND CCTV

Building Name: CHRISTIE BUILDING
Building No.: 006AA

Site Name: OXFORD ROAD

Sub Site Name: MAIN QUAD

Drawing Title: GROUND FLOOR PLAN

PM	Drawn	Checked	Authorised
JW	RT	RT	-

Scale @A1	Date	Date	Date
1:50	18/07/07	16/10/17	-

Drawing No.: E02
Revision: -

Original Drawing Paper Size 841mm x 594mm