There have been concerns regarding a large Sycamore dropping branches into the carpark, risking vehicle damage. There are also mixed species trees encroaching over parking spaces.

To crown raise the mixed species trees around the site perimeter, predominantly Sycamore, back to kerb line to a height of 4 metres, or as high as can be achieved without removing any major structural limbs, to reduce the risk of vehicle damage. We will access the large Sycamore, highlighted in yellow on the attached map, using ropes and harness. Branches will be individually pruned and lowered into a segregated drop zone using LOLER certified rigging equipment. We will remove all dead wood over 100mm in diameter from the Sycamore to reduce the risk of falling branches





