© LP SWIFT ELECTRICAL CONTRACTORS
This drawing is the property of LP Swift Ltd, it must not be copied or reproduced or divulged to anyone without written permission.



Legend	
A	600x600 LED Recessed Backlit Panel - Dimmable OX-TPA-WS2-6x6NW/LG (20W)
AE	600x600 LED Recessed Backlit Panel - Dimmable OX-TPA-WS2-6x6NW/LG (20W) EM
B	600x600 LED Recessed Backlit Panel - Dimmable OX-TPA-WS2-6x6NW/LG (30W)
BE	600x600 LED Recessed Backlit Panel - Dimmable OX-TPA-WS2-6x6NW/LG (30W)
C	Circular LED Downlight H65-PRO-WS-230TC (25W)
CE	Circular LED Downlight - Emergency H65-PRO-WS-230TC (25W) EM 25 W
OE	Circular LED Downlight H65-PRO-WS-180TC (17W)
F	1500mm Surface Mounted Batton - Dimmable EDUPACAC-WS-1500NW (40W)
FE	1500mm Surface Mounted Batton Dimmable - Emergency EDUPACAC-WS-1500NW (40W) EM
EXIT	Emergency Exit Sign QBOX 1W
EM	Emergency Bulkhead QBRICK 3H 1W
EX1	External Bulkhead - With PIR & Timeclock URBAN_PATH 7W 2700k (Dark Sky Compliant)
EX2	External Bulkhead with PIR URBAN_PATH 7W 2700k (Dark Sky Compliant)
P	Presense Detection PIR
M	Absense Detection with Daylight & Manual Dimming
	Manual Switch
R	Retractive Switch
EmK	Emergency Key Test Switch
	Fan On/Off Speed controllers
	Wall Mounted Extract Fan - Fed from lighting
	Ceiling Mounted Extract Fan - Fed from lighting

Extract fans shall operate:
a) while the room is occupied
b) for a minimum of 15 minutes after occupants have left the room.

EXTRACT FANS SCHEDULE

REF	LOCATION	MANUFACTURER	MODEL	DESCRIPTION	REF	LOCATION	MANUFACTURER	MODEL	DESCRIPTION
EF01	CLEANERS	MANROSE	QF100S	WALL MOUNTED FAN VIA PIR	EF06	KITCHEN	MANROSE	FLAT150S	WALL MOUNTED FAN VIA PIR
EF02	ACC.WC / SHOWER	MANROSE	FLAT150S	WALL MOUNTED FAN VIA PIR	EF07	MAIN HALL	EXPELAIR	WX12	WALL MOUNTED
EF03	WC	MANROSE	QF100S	CEILING MOUNTED FAN VIA PIR	EF08	MAIN HALL	EXPELAIR	WX12	WALL MOUNTED
EF04	WC	MANROSE	QF100S	CEILING MOUNTED FAN VIA PIR	EF09	MAIN HALL	EXPELAIR	WX12	WALL MOUNTED
EF05	WC	MANROSE	QF100S	CEILING MOUNTED FAN VIA PIR	EF10	MAIN HALL	EXPELAIR	WX12	WALL MOUNTED

REVISIONS

Issue	Date	Description	Drn	Chkd
P01	29/08/25	Preliminary Issue	SG	LS
P02	03/12/25	Layout updated incorporating PTK comments	SG	LS
P03	16/02/26	Layout updated	SG	LS
P04	02/03/26	Layout updated, External lighting added	SG	LS
P05	04/03/26	External lighting updated	SG	LS
C01	31/03/26	Construction Issue	SG	LS
C02	13/04/26	Extract fan heights updated	SG	LS
C03	15/05/26	Extract fan heights omitted	SG	LS
C04	18/05/26	Circuit Referencing updated	SG	LS
C05	28/05/26	GA Plan updated (Kitchen)	SG	LS

Drawing Status:
Construction Issue

Client

Portakabin Group Sales
Huntington
York YO32 9PT

T: 01904 611655
F: 01904 611644
www.portakabin-group.com

LP SWIFT
ELECTRICAL CONTRACTORS LTD

Project
YIF 20 Crumpsall Park

Project No
C2380

Title
Lighting Layout

Status Code	A	Discipline	
Scale	1:50 @ A1		DO NOT SCALE OFF THIS DRAWING
Drawn by	SG	Date	29/08/25
Checked by	LS	Date	29/08/25
CAD Reference:			

File / Drawing Name
C2380-LPS-00-00-DR-E-6301

Rev
C05