

Plant Schedule

QTY	UNIT	CODE	PLANTNAME	STOCK		SPACING
Herbaceous plants						
12	No.	Nep BC	Nepeta "Blue Cloud"	C3L		3/m2
Shrubs						
2	No.	Ham Jel	Hamamelis x intermedia "Jelena"	C3L	30-40cm	3/m2

QTY	UNIT	CODE	PLANTNAME	STOCK	FORM	GIRTH/ HEIGHT
Trees						
1	No.	ACE osa	Acer palmatum 'Osakazuki'	C45-85L	STD	12-14cm
1	No.	ALN GLU ss	Alnus glutinosa	B	STD	10-12cm
10	No.	AME ROB ss	Amelanchier arborea 'Robin Hill'	RB	STD	10-12cm
5	No.	AME LAM ms3	Amelanchier lamarckii	RB	MSTEM3	200-250cm
6	No.	BET NIG msRB	Betula nigra	RB	MSTEM3	200-250cm
5	No.	Bet fas	Betula pendula 'Fastigiata'	RB	STD	10-12cm
26	No.	BET PEN ss	Betula pendula	RB	STD	10-12cm
1	No.	CAR BET ss	Carpinus betulus	B	STD	10-12cm
8	No.	COR COL ss	Corylus colurna	B	STD	10-12cm
1	No.	FAG PU TR	Fagus sylvatica 'Purpurea Tricolor	RB	STD	14-16cm
8	No.	PRU PLE ss	Prunus avium "Plena"	RB	STD	10-12cm
2	No.	PYR CHA xhs	Pyrus calleryana "Chanticleer"	RB	STD	14-16cm
30	No.	SOR STR ss	Sorbus aucuparia "Streetwise"	B	STD	10-12cm
23	No.	TIL STR s10	Tilia cordata "Streetwise"	B	STD	10-12cm
5	No.	TIL COR xhs14	Tilia cordata	RB	STD	14-16cm

QTY	UNIT	CODE	PLANTNAME	STOCK	SIZE
Hedges					
79	m	Euo Gre Hedge	Euonymus japonicus "Green Spire"	C3L	30-40cm
237	No.	Plants spaced @3/m in a Single Row			
609	m	Ilex cren'con' Hedge	Ilex crenata 'Convexa'	C3L	40-60cm
3045	No.	Plants spaced @5/m in a Double Staggered Row			
87	m	Pho Red Hedge	Photinia x fraserii "Red Robin"	C3L	40-60cm
174	No.	Plants spaced @2/m in a Single Row			

PERCENT	QTY	UNIT	PLANTNAME	STOCK	SIZE
Hedge Mixes					
86m NATIVE HEDGEROW MIX planted @5/m in a Double Staggered Row					
10%	43	No.	Acer campestre	B Trans	60-80cm
10%	43	No.	Cornus sanguinea	B Trans	60-80cm
10%	43	No.	Corylus avellana	B Trans	60-80cm
50%	215	No.	Crataegus monogyna	B Trans	125-150cm
5%	22	No.	Prunus spinosa	B Trans	60-80cm
5%	22	No.	Rosa canina	B Trans	60-80cm

PERCENT	QTY	UNIT	PLANTNAME	STOCK	SIZE
Plant Mixes					
Proposed Feature Mixed Planting 1 planted @9/m2					
5%			Hamamelis intermedia	C5L	60-80cm
15%			Deschampsia Cespitosa	C3L	40-60cm
15%			Calamagrostis	C3L	40-60cm
15%			Stipa tenuissima	C3L	40-60cm
10%			Cirsium rivulare	C2L	20-30cm
10%			Verbena bonariensis	C3L	40-60cm
10%			Allium	C2L	20-30cm
10%			Sedum 'Matrona'	C3L	40-60cm
10%			Salvia x sylvestris	C2L	20-30cm
Individual varieties to be planted in groups of approximately 7, larger shrubs as singles.					

Proposed Feature Mixed Planting 2 planted @8/m2				
10%	Allium 'Cristophii'	C2L	20-30cm	
10%	Briza maxima	C2L	Full pot	
10%	Calamagrostis x acutiflora 'Karl Foerster'	C3L	Full pot	
10%	Echinacea purpurea	C3L	Full pot	
10%	Echinops ritro	C1L	Full pot	
10%	Rudbeckia fulgida sullivantii 'Goldsturm'	C3L	Full pot	
10%	Salvia x superba	C1L	40-60cm	
10%	Stipa tenuissima 'Pony Tails'	C2L	Full pot	
10%	Verbena bonariensis	C1L	Full pot	
5%	Crambe cordifolia	C1L	Full pot	
5%	Deschampsia cespitosa 'Goldtau'	C2L	Full pot	
Individual varieties to be planted in groups of approximately 3 or 5. Deschampsia to be planted as singles.				
Proposed Groundcover Planting planted @6/m2				
20%	Bergenia cordifolia	C1L	Full pot	
20%	Galium odoratum	C1L	Full pot	
20%	Geranium 'Johnson's Blue'	C1L	Full pot	
5%	Heuchera 'Key Lime Pie'	C1L	Full pot	
20%	Liriope muscari	C1L	Full pot	
10%	Luzula nivea	C1L	Full pot	
5%	Nepeta racemosa 'Walker's Low'	C1L	Full pot	
Individual varieties to be planted in groups of approximately 3 or 5.				
NATIVE SHRUB MIX planted @2/m2				
20%	Cornus sanguinea	B Trans	60-80cm	
20%	Corylus avellana	B Trans	60-80cm	
20%	Salix caprea	B Trans	60-80cm	
20%	Viburnum opulus	B Trans	60-80cm	
20%	Rhamnus frangula	B Trans	60-80cm	
Individual varieties to be planted in groups of 3-5.				
Proposed Ornamental Shrub Planting planted @3/m2				
15%	Aucuba japonica 'Rozannie'	C3L	30-40cm	
15%	Hebe 'White Gem'	C3L	30-40cm	
15%	Hebe 'Autumn Glory'	C3L	40-60cm	
15%	Prunus laurocerasus 'Otto luyken'	C3L	40-60cm	
10%	Vinca major	C3L	30-40cm	
10%	Viburnum davidii	C3L	30-40cm	
10%	Spiraea japonica 'Little Princess'	C3L	30-40cm	
10%	Sarcococca humilis	C3L	30-40cm	
Individual varieties to be planted in groups of approximately 5-7.				
Proposed Wildflower Meadow planted @3g/m2				
100%	No. Urban Pollinator Mix	Seed		
Seeded at 3g m2 over prepared ground URBAN POLLINATOR MIX from Scotia Seeds				
Polinator Rain Garden planted @5/m2				
15%	12 No. Phlomis tuberosa	C2L	20-30cm	
20%	16 No. Carex pendula	C3L	40-60cm	
15%	12 No. Echinacea purpurea	C3L	40-60cm	
15%	12 No. Crocosmia lucifer	C3L	40-60cm	
15%	12 No. Geranium	C2L	20-30cm	
20%	16 No. Descampsia cespitosa	c 3L	40-60cm	
Individual varieties to be planted in groups of approximately 3-5. Carex to be located centrally within planting b				

Notes and Abbreviations

B	=	Bare root (bagged).
C	=	Container (or pot) grown, followed by size of the container (or pot).
cc	=	Root volume in cubic centimetres
FORM	=	Shape of tree as supplied by the nursery.
QTY	=	Quantity
RB	=	Rootballed (balled and wrapped).
SIZE	=	Height or Spread of juvenile plant.
Std	=	(clear stem) Standard.
STOCK	=	Root condition/protection method eg Bare root.
Trans	=	Transplant (or undercut seedling).

- Refer to specification for further information.
- All plants to be completely hardened off
- Substitutions to be agreed with Landscape Architect.

Do not scale this drawing (printed or electronic version).

Contractors must check all dimensions from site

This drawing is copyright and is for use on this site only. This drawing should be read in conjunction with all relevant consultants drawings and specialist subcontractors / supply chain drawings and specifications.

All works to be carried out in accordance with the latest British Standards / Codes of Practice unless specifically directed otherwise in the specification.

Responsibility for the reproduction of this drawing in paper form, or issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when compared to the original paper or electronic image.

Graphical representations of equipment on this drawing have been co-ordinated, but are approximations only. Please refer to the specifications and / or details for actual sizes and / or specific contractor construction information.

Notes:-

KEY

- **Hedgehog Highway Fence Openings** — To ecologists proposals

Soft Works

- **Existing Vegetation** — To be retained and enhanced
- **Proposed Feature Tree Planting** — Heavy standard.
- **Proposed Standard Tree Planting** — Standard.
- **Proposed Feature Shrub Planting**
- **Proposed Climbing Plants**
- **Proposed Ornamental Hedge Planting** — Single species ornamental shrubs - see schedule for species
- **Proposed Native Hedge Planting** — Native hedgerow mix - See schedule for species
- **Proposed Ornamental Shrub Planting** — Shrub mix - See schedule for species
- **Proposed Native Shrub Planting** — Native shrub mix - See schedule for species
- **Proposed Feature Mixed Planting 1** — Herbaceous, grass & shrub species mix. Herbaceous mix 1- See schedule for species
- **Proposed Feature Mixed Planting 2** — Herbaceous, grass & shrub species mix. Herbaceous mix 2- See schedule for species
- **Proposed Groundcover Planting** — Ornamental groundcover mix- See schedule for species
- **Proposed Wildflower Meadow** — Urban Polinator Mix. See schedule for species
- **SUDs Planting mix** — Refer to planting schedule
- **Proposed Turf Grass** — To amenity spaces and front gardens.
- **Proposed Seeded Amenity Grass** — To rear gardens.

P19	27/04/26	UPDATE	JW	SA
P18	15/04/26	UPDATE	JW	SA
P17	12/01/26	UPDATE	TH	SA
P16	12/01/26	UPDATE	TH	SA
P15	09/01/26	UPDATE	GBS	SA
P14	03/12/25	UPDATE	AG	GBS
P13	04/08/25	MINOR UPDATE	GBS	SA
P12	16/07/25	MINOR UPDATE	GBS	SA
P11	08/07/25	UPDATE	GBS	SA
P10	11/04/25	UPDATE	IG	AL
P09	08/04/25	UPDATE	IG	AL
P08	04/04/25	UPDATE	AL	SA
P07	31/03/25	UPDATE	AL	SA
P06	28/03/25	UPDATE	AL	SA
P05	25/02/25	UPDATE	AL	SA
REV.	DATE	DESCRIPTION	DRAWN	CHK'D

URBAN GREEN

A: Ground Floor, The Tower, Deva City Office Park, Trinity Way, Manchester M3 7BF

T: +44 (0) 161 312 3131

weareurbangreen.co.uk

Client: **KEEPMOAT HOMES**

Project: **THE IRONWORKS LAND AT CRABTREE LANE**

Title: **SOFT LANDSCAPE PLAN**

Issue: **PLANNING**

Drawn:	Checked:	Approved:
IG	AL	SA
Project: UG2791	**Scale @ A1:** 1:500	**Date:** 13/12/24
Dwg No: UG_2791_LAN_SL_DRW_301		**Revision:** P19