

Plant Schedule

QTY	UNIT	CODE	PLANT NAME	STOCK	SIZE	SPACING
Shrubs						
3	No.	Vib opu 10L	Viburnum opulus	C 10L	80-100cm	1/m2

QTY	UNIT	CODE	PLANT NAME	STOCK	FORM	GIRTH/HEIGHT
Trees						
5	No.	MAL SYL ss	Malus sylvestris	B	STD	10-12cm

PERCENT	QTY	UNIT	PLANT NAME	STOCK	SIZE
Plant Mixes					
179m2 CAR PARK SHRUB MIX planted @ 3/m2					
20%	107	No.	Spiraea japonica 'Firelight'	C 2L	30-40cm
20%	107	No.	Lonicera nitida 'Maigrun'	C 2L	30-40cm
20%	107	No.	Hypericum calycinum	C 2L	30-40cm
20%	107	No.	Mahonia aquifolium 'Apollo'	C 2L	30-40cm
10%	54	No.	Cornus alba 'Kesslerringii'	C 2L	40-60cm
10%	54	No.	Cornus sanguinea 'Midwinter Fire'	C 2L	40-60cm
Individual varieties to be planted separately or in small groups of 3-5.					

Notes and Abbreviations

B	=	Bare root (bagged).
C	=	Container (or pot) grown, followed by size of the container (or pot).
FORM	=	Shape of tree as supplied by the nursery.
QTY	=	Quantity
SIZE	=	Height or Spread of juvenile plant.
Std	=	(clear stem) Standard.
STOCK	=	Root condition/protection method eg Bare root.

- Refer to specification for further information.
- All plants to be completely hardened off
- Substitutions to be agreed with Landscape Architect.

Do not scale this drawing (printed or electronic version).

Contractors must check all dimensions from site

This drawing is copyright and is for use on this site only. This drawing should be read in conjunction with all relevant consultants drawings and specialist subcontractors / supply chain drawings and specifications.

All works to be carried out in accordance with the latest British Standards / Codes of Practice unless specifically directed otherwise in the specification.

Responsibility for the reproduction of this drawing in paper form, or issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when comparedto the original paper or electronic image.

Graphical representations of equipment on this drawing have been co-ordinated, but are approximations only. Please refer to the specifications and / or details for actual sizes and / or specific contractor construction information.

Notes:-

KEY

Hard Works

Vehicular Asphalt Surface
Black colour.

Precast Concrete Flag Paving
To engineer specification & recommendation

Black Paladin Fence
With matching gates.

Retaining Wall
Detail to engineer's specification

Soft Works

Proposed Trees

Proposed specimen shrub
C 10L specimen shrub.

Proposed Low Level Shrub Mix Planting

REV.	DATE	DESCRIPTION	DRAWN	CHK'D
P05	02/07/26	AMENDED ISSUE	AG	SW
P04	30/06/23	AMENDED ISSUE	SH	SA
P03	13/01/23	AMENDED ISSUE	TH	SA
P02	31/10/22	AMENDED ISSUE	TH	SA
P01	18/10/22	FIRST ISSUE	TH	SA

U R B A N
G R E E N

A: Ground Floor, The Tower,
Deva City Office Park, Trinity Way,
Manchester M3 7BF

T: +44 (0) 161 312 3131

weareurbangreen.co.uk

Client: STORAGE WORLD

Project: AMBROSE STREET, MANCHESTER

Title: General Arrangement

Issue: PLANNING

Drawn:	Checked:	Approved:
TH	SA	ME

Project:	Scale @ A1:	Date:
UG1754	1:200	17/10/22

Dwg No:	Revision:
UG_1754_LAN_GA_DRW_01	P05