Ref.	Species	Recommendation
T019	Lime *(Tilia sp.)*	Crown lift and remove epicormic to 6m all round. Clear street light. Remove deadwood - greater than 25mm diameter.
T029	Lime *(Tilia sp.)*	Remove epicormic growth up to 5m
T061	Lime *(Tilia sp.)*	Crown reduce by 30% of volume. Remove epicormic to 6m.
T069	Sycamore *(Acer pseudoplatanus)*	Crown lift to 6m all round. Remove deadwood - greater than 25mm diameter. Clear overhead wires/street light. Part crown reduce to clear building by at least 3m.
T073	Sycamore *(Acer pseudoplatanus)*	Crown lift to 6m all round. Remove deadwood - greater than 25mm diameter. Clear overhead wires/street light by at least 2m.
T093	Downy birch *(Betula pubescens)*	Crown lift to 6m all round.
T098	Rowan *(Sorbus aucuparia)*	Fell tree.
T139	Pedunculate oak *(Quercus robur)*	Crown reduce by 30% of volume. Remove deadwood - greater than 25mm diameter.
T148	Japanese cherry *(Prunus sargentii)*	Crown reduce by 50% of length of branches from crown break to tips.
T157	Italian alder *(Alnus cordata)*	Crown lift to 6m all round. Remove epicormic growth up to crown break.
T159	Common hawthorn *(Crataegus monogyna)*	Fell tree.
T063	Silver maple *(Acer saccharinum)*	Crown reduce by 30% of volume including crown lift to 5m all round. Remove deadwood - greater than 25mm diameter.
T164	Downy birch *(Betula pubescens)*	Crown lift to 2.5m all round.
T165	Horse chestnut *(Aesculus hippocastanum)*	Remove epicormic growth up to 6m.
T171	Horse chestnut *(Aesculus hippocastanum)*	Remove epicormic growth up to 6m.
T175	Horse chestnut *(Aesculus hippocastanum)*	Remove epicormic growth up to 6m.
T183	Horse chestnut *(Aesculus hippocastanum)*	Crown lift to 6m all round. Clear street light by at least 2m.
T197	Whitebeam *(Aria edulis)*	Crown lift to 6m over highway. Crown lift to 5m all round. Remove deadwood - greater than 25mm diameter.
T198	Italian alder *(Alnus cordata)*	Crown lift to 6m all round. Part crown reduce property side, longer branches by 2m.
T216	Norway maple 'T318' *(Acer platanoides)*	Remove epicormic growth up to 6m all round, up to apex House side. Remove deadwood - greater than 25mm diameter. Reduce back first limb over roof by 2m.
T265	Silver birch *(Betula pendula)*	Remove epicormic growth up to crown break.
T271	Sycamore *(Acer pseudoplatanus)*	Remove deadwood - greater than 25mm diameter. Crown lift to 6m all round.
T299	Wild cherry *(Prunus avium)*	Crown lift to 6m all round. Remove deadwood - greater than 25mm diameter.
T314	Norway maple 'Rubrum' *(Acer platanoides)*	Crown lift to 6m all round and to roof apex over property.
T320	Italian alder *(Alnus cordata)*	Crown lift to 6m all round.