

Elevation B-B



Section C-C



RISK

Please Refer To BDS-11743-1 Page 01 For Highlighted Risks & Hazards


Legend

- Tube
- Bracing
- Standard
- 12mm Apollo Ring Bolt & Nylon Plug

Limited Drawings showing Flu Locations meaning scaffold may need to be amended to suit site requirements. Scaffold not to exceed maximum parameters shown.

NATIONAL HOUSE


Typical Tie Connection Detail



Exact Bay Lengths & Widths TBC with Calculations

Exact Transom Spacings TBC with Calculations

Sole Pad Detail



Fundamental Notes

TBC

Notes:

This drawing is confidential and is the exclusive property of BDS Ltd. No unauthorised use, copy or disclosure is to be made, and is to be returned upon request.

The customer should check that we have correctly interpreted his/her requirements, and that all loadings, details, erection & dismantling sequences etc, are correct and practicable.

The Main Contractor is to ensure the ground, structure and/or base provided for our scaffold, is adequate to support the imposed loads applied, including the provision for any necessary spreaders.

The design and erection of scaffolds are to conform with the following British Standards and Codes of Practice:

BS2482 Specification for Timber Boards
BS EN 12811-1 Codes of Practice for Access and Working Scaffolds and Special Scaffold Structures in Steel
BS EN 12812-1:2008 Falsework: Performance requirements & general design
TG20:21 Guide to Good Practice for Scaffolding with Tube and Fittings
BS EN 1991-1-1:2002 Eurocode: Actions on Structures - Densities, Self-weight and Imposed Loads
BS EN 1991-1-4:2005 Eurocode: Actions on Structures - Wind
BS EN 13374:2013 Temporary edge protection systems - Product specification, test methods.

MAXIMUM LOADINGS

Independent - 1no. Lift - 1.5kN/m² (150kg/m²)
All inside boards at - 0.75kN/m² (75kg/m²)
Max Wind Load: TBC

THESE LOADINGS MUST NOT BE EXCEEDED
All Loadings Unfactored
No alterations which may effect the scaffolds structural stability to be made without prior written notice from BDS Ltd

Please print all drawings in colour A3 min

Drawing not to scale
dimensions as per drawing

Digital Drawing

Draft Only

Client:

CubicWorks

BDS BUCKLEY DESIGN SOLUTIONS | SCAFFOLD DESIGN SPECIALISTS

T: 0161 532 2806 E: info@buckleydesigns.co.uk

Project: Winters Building, Manchester, M2 7PW

Drawing Title:
Item 1 - Rear Access Independent

Drawn by: Alex Murphy Draft: 01/06/2026
Signed: [redacted] Approval:
Construction:

Calculations by:
Signed: Approval:
Construction:

Checked by: Joe Rigby Draft: 01/06/2026
Signed: [redacted] Approval:
Construction:

Drawing No. 11743-1
Page No. 2

Drawing Scale: N/A

Revisions: