CWC

crookes walker
consulting

One Castlefield, Manchester

Energy & Carbon Statement
P01

Date: 01/07/2026
Ref: 3582-CWC-XX-XX-RP-N-7015

Crookes Walker Consulting Limited is registered in England & Wales | 05011466 |
Registered Office: One Express | 1 George Leigh Street | Ancoats | Manchester | M4 5DL



Revision Record

Date	Reference	Revision	Prepared	Checked	Authorised
17/07/2026	3582-CWC-XX-XX-RP-N-7015	P01	Obaid Rahman	Ben Hawksworth	Ben Hawksworth
			Obaid Rahman	Ben Hawksworth	Ben Hawksworth

Contents

74
1.0 Executive Summary 5
1.1 Energy & Carbon Proforma 5
1.2 Project Overview 6
2.0 Building Fabric & Ventilation 7
2.1 Building Form & Heat Loss Envelope 7
2.2 Elevation Design & Window Proportions 8
2.3 Heated & Unheated Spaces 10
2.4 Fabric Specs & Air Tightness 10
2.5 Ventilation System 11
2.6 Space Heating Demand 12
3.0 Maximise Energy Efficiency 13
3.1 Energy Usage Intensity 13
3.2 Energy Use of Equipment 13
4.0 Renewable Energy Generation 15
4.1 Proposed Renewable Energy Generation 15
4.2 PV Footprint Area 17
4.3 Renewable Energy Balance 17
5.0 Low Carbon Heating 18
5.1 Fossil Fuel Free 18

5.2 Proposed Systems for Space & Water Heating 18
5.3 Summary of Comparison with Other Systems from Low Carbon Heat Appraisal 19
5.4 Proposed Cooling System 20
6.0 Risk of Overheating 21
6.1 Natural Ventilation 21
6.2 Overheating Risk Assessment 21
7.0 Materials 23
7.1 Upfront Embodied Carbon 23
7.1.1 Structural lean design 24
7.1.2 Architectural Lean Design 25
7.1.3 Building Services Lean Design 26
7.2 Life Cycle Carbon Analysis 27
8.0 Offsetting 28
9.0 Appendix 1 – Thermal Line Strategy 29
10.0 Appendix 2: Low Carbon Heat Appraisal 30
11.0 Roof Layout 31
12.0 Appendix 3: Overheating Report 32
13.0 Appendix 4: Whole Life Carbon Analysis 33

1.0 Executive Summary

1.1 Energy & Carbon Proforma

Energy and Carbon Proforma
Residential

Major development *(+10 homes)*

Version 2.0

GMCA GREATER MANCHESTER COMBINED AUTHORITY

Project Name: 1 Castlefield

Application ref:

Date: 02-Jul

Summary sitewide reporting table				
Affordable dwellings?	**No. of resi buildings on site**	**Total resi building footprint area (m^2)**	**Total on-site PV area for resi (m^2)**	**Sitewide PV footprint area (%fp)**
No	2			

	Building ref. name		Block A	Block B		
	Area (m^2 GIA)		37509	16220		
	No. dwellings (per building)		436	156		
	No. affordable dwellings (per building)					
		Target values	**Building 1**	**Building 2**	**Building 3**	**Building 4**
Minimise energy demand	**Space heating demand (kWh/m^2 GIA/yr)**	***≤ 15** (flats) **≤ 20** (houses)*	**19.06**	**9.11**		
	Calculation methodology used to calculate space heating demand and confirmation that this covers all homes/blocks	*Predictive energy model*	Predictive energy model	Predictive energy model		
	Form factor per building	*≤ 2*	0.48	0.74		
	Average external wall U-value (W/m^2K)	*≤ 0.15*	0.12	0.12		
	Average window U-value (W/m^2K)	*≤ 1 (triple)*	1.2	1.2		
	Air permeability rate (m^3/h/m^2 @ 50 Pa)	*≤ 1*	3	3		
Maximise energy efficiency	**Energy use intensity (kWh/m^2 GIA/yr)** *renewables should not be accounted for in the EUI calculation*	***≤ 35***	**57**	**56**		
	Calculation methodology used to calculate energy use intensity and confirmation that this covers all homes/blocks	*Predictive energy model*	Predictive energy model	Predictive energy model		
Use renewable energy	**PV footprint area (% of ground floor space)**	***≥ 40***	**0**	**4.97**		
	Annual renewable energy generation (kWh/m^2 building footprint/yr)	-	0	1.16		
	Renewable energy balance (%)	-	0	2.26		
	Total energy used (kWh/yr)	-	0	832000		
	Total energy generated on-site (kWh/yr)	-	0	18770		
Use low carbon energy	**Fossil fuel free (yes/no)**	***Yes***				
	Heating heat source	*Electric*	Electric	Electric		
	Domestic Hot Water heat source	*Electric*	Electric	Electric		
	Low Carbon Heat Appraisal completed	*Yes*	Electric	Electric		
	Heat network suitability	-				
	Exemption requested	-				
	Efficiency of heating system (SCOP)	*≥ 3.5*	1	1		
	Efficiency of domestic hot water system (SCOP)	*≥ 3.5*	3.3	3.3		
	Carbon content of heat (gCO_2/kWh)	*≤ 100*	70	70		
Reduce overheating risk	**Have Part O overheating requirements been met without the use of mechanical cooling?**	***Yes***	**Yes**	**Yes**		
	If no, how many homes are cooled?	-				
	Has a CIBSE TM59 assessment been carried out using DSY2 and DSY3 weather files? Have any additional passive measures been included as a result?	*Yes*	Yes No	Yes No		
Minimise embodied carbon	**Upfront embodied carbon ($kgCO_2e/m^2GIA$)**	***≤ 500-600***	**382.1**	**392.1**		
	List top three materials with the highest upfront embodied carbon emissions ($kgCO_2e/m^2GIA$): Material 1	-	eady mix concre	ady mix concrete		
	Material 2	-	einforcement ste	inforcement steel		
	Material 3		aluminium framed curtain v	aced precast cladding		
	Lifecycle embodied carbon ($kgCO_2e/m^2GIA$) - *for large major developments only*	-	538.4	562.89		
Offsets	**Offset contribution (£)**	**-**				

1.2 Project Overview

One Castlefield is a proposed residential-led development located on a vacant brownfield site bound by Trentham Street, Ellesmere Street, and Castlefield Locks. The site is located adjacent to Cornbrook Metrolink stop in Manchester, within the wider St George's regeneration area. The site falls within the Castlefield Conservation Area, which has informed the design approach.

The development comprises two buildings with distinct thermal envelopes, referenced throughout this statement and the accompanying Energy and Carbon Proforma as follows:

- Block A: 46-storey residential tower providing 436 dwellings ((172 x 1-bed, 258 x 2-bed, 6 x 3-bed apartments) with a gross internal area of 37,509m^2. The ground floor contains the building lobby, residents' amenity space and back-of-house areas including plant and service zones.
- Block B: 8-storey lower-rise residential building providing 156 dwellings (21 x 1-bed, 96 x 2-bed, 21 x 3-bed, 13 x 4-bed apartments & 2x 2-bed Townhouses) with a gross internal area of 16,220m^2. The ground floor contains the main entrance at the Chester Road / Ellesmere Street corner, residents' amenity space and staff offices.

The development delivers a total of 592 dwellings across a combined GIA of approximately 53,729m^2. Both blocks are residential in use above ground floor level. Ground floor non-residential uses are ancillary to the residential use and comprise residents' amenity and building management functions only.

Both blocks have been modelled in full; all dwellings have been included in the predictive energy assessment and overheating risk assessment.

2.0 Building Fabric & Ventilation

2.1 Building Form & Heat Loss Envelope

The development comprises two buildings of different form and scale, each with its own complete thermal envelope.

Block A is a 46-storey residential tower of compact, roughly rectangular plan form. The tower footprint is relatively modest in relation to its height, resulting in a slender profile that reduces the exposed façade area per unit of floor area on the upper floors.

Building	GIA (m^2)	External Surface Area (m^2)	Form Factor
Block A	37,509	17,940	0.48
Block B	16,220	12,051	0.74

Table 1: Building Form Summary

Block A contains a basement level (B1) housing plant, cycle storage and water storage, which falls outside the heated envelope. The ground floor contains the building lobby, residents' amenity and back-of-house plant areas; the thermal line steps to exclude these unheated back-of-house zones.

Block B is an eight-storey lower-rise building following the line of Ellesmere Street and Trentham Street. Its greater perimeter-to-floor-area ratio results in a higher form factor than Block A, reflecting its more distributed massing. The ground floor contains the main entrance, residents' amenity and management offices, with the thermal envelope drawn to exclude unheated circulation and plant areas.

Both blocks are purely residential above ground floor level.

2.2 Elevation Design & Window Proportions

Block A is a 46-storey tower with a near consistent facade across all four elevations. The facade is organised as a regular vertical banding system comprising:

- Full-height glazed vision panels (clear vision glazing to habitable rooms)
- Insulated back-painted glass spandrel panels concealing floor zones and structure
- Insulated anodised aluminium perforated panels and decorative perforated panels providing secondary screening/solar control at specific bays
- Anodised aluminium perforated panels at the base/podium

The vertical banding pattern is repeated near-identically on all four elevations, the tower's window-to-wall ratio (WWR) does not vary materially by orientation.
At podium/base level, the South elevation incorporates the primary entrance canopy, full-height glazed curtain walling and clear glazed balustrades.

Block B is a 9-storey brick-faced perimeter block with a different, more traditional facade:

- Red/orange stock brickwork with a regular grid of punched window openings (full-height clear vision glazing in fixed proportions) across the lower storeys.
- A recessed brick panel/reveal pattern breaking up the primary brick elevations.
- Two set-back upper storeys in darker, contrasting anodised aluminium metal panelling, louvres and a standing seam metal roof. These storeys house duplex units and private balconies
- Full-height glazed curtain walling and a revolving door at ground-floor entrance/amenity locations.
-

Block B's punched-window brick facade inherently gives a lower, more controlled WWR than Block A's curtain-wall tower:

Block	Façade	Façade WWR	Building Average WWR
A	North	0.4	0.6
	South	0.74	
	East	0.63	
	West	0.61	

Table 2: Block A Window-to-Wall Ratio Summary

Block	Façade	Façade WWR	Building Average WWR
B	North	0.31	0.4
	South	0.3	
	South-West	0.84	
	East	0.33	
	West	0.61	
	East (Courtyard)	0.32	
	West (Courtyard)	0.29	

Table 3: Block B Window-to-Wall Ratio Summary

2.3 Heated & Unheated Spaces

The thermal envelope is given in plan in Appendix 1.

Generally, heat is provided, through decarbonised means, throughout both buildings, with exception to the following zone types where no heat is provided:

1. Store/cupboards.
2. Plantrooms/substation.

2.4 Fabric Specs & Air Tightness

Element	U-value (W/m^2K)
External Wall	0.12 W/m^2K
Internal Wall	Fully Filled
Glazing	1.20 W/m^2K
G-value	0.4
Roof	0.11 W/m^2K
Ground Floor	0.16 W/m^2K
Air permeability	3.00 $m^3/hr/m^2$ @ 50 Pa

Table 4: Fabric Specification

Bridge Type	Psi-value (Ψ)
E2 Lintels	0.02
E3 Sill	0.02
E4 Jamb	0.02
E7 Party Floor between dwellings (in blocks of flats)	0.01
E16 Corner (Normal)	0.02
E18 Party wall between dwellings	0.02

Table 5: Thermal Bridging Summary

2.5 Ventilation System

Ventilation is delivered through mechanical means via dedicated mechanical ventilation heat recovery units servicing each dwelling. These are set to operate continuously delivering background ventilation rates that satisfy Building Regulations Approved Document Part F requirements.

Each unit incorporates high efficiency heat recovery capability and variable speed drives to ensure output matches demand.

Openable panels also afford the opportunity to deliver purge ventilation via natural means in every dwelling.

2.6 Space Heating Demand

The operational energy forecast (ref: 3528-CWC-XX-XX-RP-N-7009 Rev 01) based on CIBSE TM54, gives the space heating demand as:

- Block A: 19.06 kWh/m^2/year.
- Block B: 9.11 kWh/m^2/year.

3.0 Maximise Energy Efficiency

3.1 Energy Usage Intensity

The energy use intensity for Block A is estimated to be 57 kWh/m^2/yr.

The energy use intensity for Block B is estimated to be 56 kWh/m^2/yr.

This is based on the analysis undertaken using approved software IES:VE 2025.2.0.0 using the CIBSE TM54 method and described in document '3258-CWC-XX-XX-RP-N-7007 Rev 01'.

3.2 Energy Use of Equipment

The assumptions used to estimate unregulated energy loads have been derived from authoritative industry sources and expected operational usage.

Inputs were taken from manufacturer's datasheets, CIBSE Guide A, BSRIA Rules of Thumb (2024) 'Mechanical Criteria', NABERS Design for Performance (DfP), and the current BCO (British Council of Offices) recommendations.

Operational profiles (including occupancy, equipment usage, and lighting modulation) were based on CIBSE TM59 & NABERS DfP benchmarks.

Office equipment gains were informed by BCO recommendations.

Domestic hot water (DHW) consumption was taken from the BSRIA Rules of Thumb.

Lift energy was calculated using assuming a cumulative use of two hours a day.

Cooking and catering equipment assumptions were based on conservative allowances together with data from CIBSE Guide A.

For other specific operational profiles not covered by available data, assumptions were made based on the anticipated building use once occupied.

This methodology ensures that all unregulated loads (appliances, catering equipment, plug loads, IT, lifts, and other specialist equipment) are realistically and conservatively represented in the energy calculations.

4.0 Renewable Energy Generation

Only Block B is served by a PV system (serving the upper-level dwellings, and landlord areas).

4.1 Proposed Renewable Energy Generation

Description	Solar PV
Orientation	Varies
Tilt	30°
Peak Output (kWp)	15.7
Panel (max output, type of inverter)	450W (DC-AC)
PV area as per centage of ground floor area	4.97%
Expected annual renewable energy generation	18,770 kWh
Annual renewable energy generation per m^2 GIA	1.16 kWh/m^2_{GIA}
Annual renewable energy generation per m^2 building footprint	10.26 kWh/m^2_{FP}
Balance between total energy use & renewable energy generation	2.6%
Shading constraints	Neighbouring buildings may shade some panels.
Data Source	Approved Document Part L1 & L2 Requirement

Table 6: PV System Specification

The proposed layout of the PV system is:



Figure 1: PV System Layout

The proposed system is based on a DMEGC Solar system, comprising 42 modules.

4.2 PV Footprint Area

The total system area amounts to 91m^2.

4.3 Renewable Energy Balance

The total renewable energy generation amounts to 2.6% of the total anticipated energy use over a year.

5.0 Low Carbon Heating

5.1 Fossil Fuel Free

The development is fossil fuel free. No gas supply is proposed to either block; the existing gas mains serving the site are to be disconnected and purged. There is no combustion of any kind on site for space heating, hot water, or back-up generation. No exemption from the fossil-fuel-free requirement is sought.

5.2 Proposed Systems for Space & Water Heating

The site has been assessed against the GMCA's four location cases and falls into Case 3 - within a Heat and Energy Network Opportunity Area, but not within 500m of any existing or planned low carbon heat network. There are currently no operating low carbon heat networks anywhere in Greater Manchester, and none funded or under construction within range of the site.

The proposed strategy is all-electric across both blocks:

- Space heating: individual electric panel heaters to apartments and circulation areas, with programmer, room thermostat/app and local controls. Frost protection to plant/storerooms via local electric tube heaters.
- Domestic hot water: individual packaged exhaust-air/hot-water heat pumps integral to each dwelling's mechanical extract ventilation (the "KERS MEV" arrangement), recovering heat from extract air to serve local hot water storage. Point-of-use electric water heaters serve isolated WCs/kitchenettes.
- Amenity areas: VRF (air source heat pump) systems providing heating and cooling to shared amenity spaces via fan coil/cassette units, with external condensers in dedicated louvred plant rooms.

A full appraisal of this system against three alternatives has been undertaken and is included at Appendix 2:

- Individual air source heat pumps
- Block-scale communal ASHP with heat interface units (HIUs)
- Notional low carbon heat network.

The key outputs are summarised below.

System	Carbon Emissions (g.CO_2/kWh heat delivered)	Operating Cost (£/dwelling)	Capital Cost (£/unit)
Direct Electric + DHW Heat Pump	≈ 70	≈500-550	≈7,000
Individual ASHP	≈ 35	≈ 270-300	≈ 10,000
Communal ASHP	≈ 50	≈ 300 + Standing Charge	≈ 12,000
Low Carbon Heat Network	100	Network Tariff + Standing Charge	≥ 12,000 + Connection (uncertain)

Table 7: Heating System Appraisal Summary

The blended carbon content of heat for the proposed system is estimated at ≈70gCO_2/kWh, below the 100gCO_2/kWh low-carbon threshold and below the carbon content assumed for a notional opportunity-area network, meeting the GMCA definition of a low carbon heating system.

5.3 Summary of Comparison with Other Systems from Low Carbon Heat Appraisal

The Low Carbon Heat Appraisal (Appendix 2) confirms that Option 2 (individual ASHP) would be the lowest-carbon and most resident-friendly individual solution, and that Options 3 and 4 (communal distribution and the notional heat network) introduce distribution losses, communal overheating risk, and consumer-protection drawbacks (metering/standing charges, no ability to switch supplier), while Option 4 additionally depends on a network that does not currently exist.

The proposed Option 1 has been selected on the balance of:

- Carbon performance below the 100gCO_2/kWh threshold; the lowest capital cost of the options assessed (≈30% below the benchmark).
- Simplicity and long-term reliability of the plant; avoidance of communal pipework and its associated overheating risk.
- Preservation of residents' consumer protection (individual metering, ability to switch supplier, access to regulated tariffs).

This is set against the acknowledged trade-off of higher in-use running costs relative to an ASHP (≈£230/dwelling/yr), which the fabric-first specification (Section 1.4) is intended to mitigate by keeping the underlying heat demand low.

Non-connection to a low carbon heat network is justified on carbon, cost-effectiveness, heating-cost and technical/practical grounds, as set out in full in Section 8 of the LCHA (Appendix 2).

Whilst the proposed system is not the lowest-carbon option available on paper (an ASHP-based solution would be lower), it is the most appropriate on balance of carbon, viability, resident affordability/consumer protection and risk for this development.

5.4 Proposed Cooling System

Cooling is provided to shared amenity areas via the VRF systems described in Section 4.2, serving fan coil/cassette units from external condensers in dedicated plant rooms.

Provision of mechanical cooling within individual dwellings is not necessary (Part O requirements are met without active cooling).

6.0 Risk of Overheating

6.1 Natural Ventilation

The development has been assessed as predominantly naturally ventilated as all occupied rooms (bedrooms, kitchens, living spaces) have openable windows, supplemented by continuous background MVHR (Section 2.5).

Openable apertures are provided to every bedroom and kitchen/living room in both blocks, via a mix of sliding doors, side-hung doors and side-hung windows, none of which are acoustically or otherwise restricted.

As required by Approved Document Part O, window operation is temperature-led rather than manual/fixed: openings begin to open once the space is occupied and the internal temperature reaches 22°C, opening incrementally as temperature rises, reaching fully open at 26°C, and closing back down over the same band as temperature falls. This applies during both daytime and night-time occupied hours; internal doors within apartments are modelled fully open during waking hours (7am–11pm), with entrance doors to communal corridors closed.

No noise restrictions have been assumed to apply to window operation i.e. the assessment does not currently rely on any acoustic constraint limiting purge ventilation.

The façade has solar control glazing with a g-value of 0.4. This enables the admission of desirable solar gains in the winter and omission of undesirable solar gains in the summer.

6.2 Overheating Risk Assessment

The site sits within the Manchester DSY high-emission, 50th-percentile weather scenario. Compliance with Approved Document O is mandatory against the DSY1 weather file, with DSY2 and DSY3 reported for information as advisory, forward-looking stress tests representing more extreme future summers.

The assessment was carried out using full dynamic thermal simulation modelling (IES:VE 2025.1.0.0), undertaken by a qualified Energy Specialist.

The outcome of the assessment shows that both proposed buildings have an acceptable risk of overheating. Though the stress tests under different heat events show that the risk of overheating is likely to materially increase.

A summary of the outcome is given below, with the detailed results available for review in Appendix 4:

Block	Weather File	Status	CIBSE TM52 Criterion 1		Overall Result	Nighttime Temperature	Overall Result
			Bedrooms	Living		Bedrooms	
Block A	DSY1	Mandatory	✓	✓	Pass	✓	Pass
	DSY2	Advisory	✓	×	Fail	✓	Fail
	DSY3	Advisory	✓	×	Fail	×	Fail
Block B	DSY1	Mandatory	✓	✓	Pass	✓	Pass
	DSY2	Advisory	✓	✓	Pass	✓	Pass
	DSY3	Advisory	×	×	Fail	×	Fail

Table 8: Overheating Risk Summary

7.0 Materials

7.1 Upfront Embodied Carbon

Upfront and life cycle embodied carbon for One Castlefield has been assessed by Complete Sustainability Solutions (16/06/2026) using One Click LCA, in accordance with the RICS Whole Life Carbon Assessment for the Built Environment (2023).

As a Large Major development (>150 homes), both upfront (A1–A5) and life cycle (A1–C4) embodied carbon have been calculated and reported:

Block	GIFA (m^2)	Total ($kg.CO_2e$)	Intensity ($kg.CO_2e/m^2$)	Target ($kg.CO_2e/m^2$)
A	37,509	14,079,576	382.12	≤600
B	16,220	6,597,334	392.12	≤600

Table 5: Upfront Carbon Summary

Both blocks comfortably meet the GMCA upfront embodied carbon target of ≤600$kgCO_2e/m^2$ GIA for large major residential development. Both sit within LETI Band B (<400$kgCO_2e/m^2$) for 6+ storey residential, approaching LETI's 2030 target Band A (<300$kgCO_2e/m^2$).

A 15% RICS-compliant early-design uncertainty top-up plus a 2% data uncertainty factor have been applied to these figures, appropriate for the current concept design stage.

Top three contributing materials are:

- Block A:
    1. Ready-mix concrete (C50/60, 50% GGBS): 165.06kgCO_2e/m^2 (53.1% of upfront carbon), arising from piled foundations, raft, core walls, columns, transfer structure and floor slabs.
    2. Reinforcement steel (rebar): 33.19kgCO_2e/m^2 (10.7%), required throughout the frame for tensile capacity.
    3. Aluminium-framed curtain wall system: 17.26kgCO_2e/m^2 (5.6%), reflecting the full-height glazed envelope.

- Block B:
    1. Ready-mix concrete (C50/60, 50% GGBS): 169.57kgCO_2e/m^2 (52.7%), from the piled foundations, flat-slab frame, core walls.
    2. Reinforcement steel (rebar): 34.18kgCO_2e/m^2 (10.6%).
    3. Brick-faced precast cladding: 31.03kgCO_2e/m^2 (9.7%).

7.1.1 Structural lean design

Both blocks adopt a reinforced concrete frame on piled foundations, which is the dominant carbon contributor in both cases (≈53% of upfront carbon each).

A key objective of the structural design for the No. 1 Castlefield project was to minimise embodied carbon through a rigorous optioneering process, with particular focus on reducing emissions associated with Modules A1–A3, which represent the largest proportion of the structure's whole-life carbon.

The structural grid and column spacing for both Blocks A and B were carefully assessed and optimised to achieve the most efficient floor arrangement. This enabled the adoption of 220/225 mm reinforced concrete flat slabs throughout the development, minimising slab thickness while maintaining structural performance and buildability. As the floor slabs account for more than 50% of the total embodied carbon of the structural frame, reducing slab thickness resulted in a significant reduction in overall carbon emissions.

The reinforced concrete core in Block A was strategically positioned at the centre of the building to minimise torsional effects under lateral loading. This optimisation reduced the demand on the core walls, allowing wall thicknesses and reinforcement quantities to be minimised without compromising structural performance.

To further reduce embodied carbon, cement replacement was incorporated into the concrete specification wherever practical. This was particularly effective in the foundations, where cement replacement levels of up to 50% were achieved. Concrete strength grades were also carefully selected for each structural element to ensure that only the required performance was specified, thereby minimising cement content, which is the principal contributor to embodied carbon in concrete.

In addition, the introduction of a basement level enabled the foundations of Block A to be founded directly onto the underlying sandstone bedrock. This eliminated the need for piled foundations beneath the building, substantially reducing the quantity of concrete and reinforcement required, while also avoiding the significant carbon emissions associated with piling works.

Through these coordinated design decisions, the structural scheme was optimised to achieve a highly efficient and low-carbon solution while maintaining the project's functional, structural, and commercial objectives.

7.1.2 Architectural Lean Design

The scheme has been developed with a strong emphasis on architectural quality, supported by lean design principles. The proposed buildings respond positively to the site's characteristics and surrounding context, providing a rational and efficient layout that optimises habitable space, natural daylight and ventilation, while supporting high standards of residential amenity.

Located on the edge of Manchester City Centre and adjacent to the major public transport interchange at Cornbrook Station, the development will deliver almost 600 high-quality new homes in a highly sustainable and well-connected location.

For the tower, Block A, a unitised facade system has been adopted to support efficient installation, improve buildability and reduce construction material waste, while delivering a high-performance building envelope. The window-to-wall ratio has been

carefully considered to balance daylight, thermal performance and ventilation through the facade, helping to maintain occupant comfort and operational energy efficiency. The unitised panels have been arranged to create a coherent and refined facade design without relying on excessive material use.

Block B is constructed primarily in clay brickwork to harmonise with its immediate street context. To avoid the brick massing appearing overly dominant, metal facade elements have been focused on the upper areas of the building to break up the overall form. The brick and metal facades have been designed using standard, repeatable components that support material efficiency and internal environmental quality, while creating a contemporary architectural composition that integrates with the surrounding urban context.

Overall, the building demonstrates a lean architectural approach through an efficient, rationalised design that promotes the effective use of resources and helps reduce associated embodied carbon. This has been achieved without compromising the project's functional, performance or aesthetic objectives.

7.1.3 Building Services Lean Design

The building services design has been developed in accordance with lean design principles, seeking to minimise upfront embodied carbon by reducing the quantity of materials and equipment required while maintaining compliance with the client brief.

Passive design measures have been incorporated where appropriate to reduce reliance on building services. These include a high-performance building fabric with low U-values and appropriate solar control through the specification of glazing with low g-values, helping to minimise heating and cooling demands. The building fabric and architectural design therefore support the overall environmental strategy by reducing the energy required to maintain comfortable internal conditions.

The MEP design has also been developed to optimise distribution systems and plant selection. Ductwork layouts have been rationalised to minimise overall duct lengths and associated material use through the strategic location of plant and the adoption of efficient distribution routes where practicable.

Refrigeration systems will be specified to utilise refrigerants with low Global Warming Potential (GWP), reducing the environmental impact associated with refrigerant use. Collectively, these measures contribute to reducing the upfront embodied carbon of the building services installation while maintaining operational performance, maintainability and compliance with the project requirements.

7.2 Life Cycle Carbon Analysis

As a Large Major development, full life cycle embodied carbon (A1–C4) has been calculated for both blocks.

Block	GIFA (m^2)	Total ($kg.CO_2e$)	Intensity ($kg.CO_2e/m^2$)
A	37,509	20,195,168	538.4
B	16,220	9,130,111	562.89

Table 6: Upfront & Lifecycle Embodied Carbon Summary

The uplift from upfront to full life cycle carbon is approximately 166$kgCO_2e/m^2$ for Block A (+43%) and 150$kgCO_2e/m^2$ for Block B (+38%), reflecting in-use replacement (B-stage) and end-of-life (C-stage) impacts over the building's assessed life.

8.0 Offsetting

At the time of submission there is not an adopted or published operational carbon offsetting mechanism or tariff. On this basis, no financial offset contribution is proposed or has been calculated as part of this application.

9.0 Appendix 1 – Thermal Line Strategy

6595_No. 1 Castlefield_502_Thermal Line Drawings

GS 13/07/2026 NTS@A1

KEY:

THERMAL INSULATION LINE

BRIDGEWATER CANAL

CASTLEFIELD LOCKS

B

A

THE TRILOGY

IN-SITU

ELLESMERE STREET

CHESTER ROAD

TRENTHAM STREET

VOX

TRAM LINE

RESIDENT STORAGE

REFUSE STORE

COMMS

WET RISER & PMP RM

SPRKLR/ WATER STRGE

FFL +24000

KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE / PLANT
- COMMERCIAL
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1 0 2.5 5 7.5 12.5M
1:500 @ A3

Drawing Title
BLOCK A & B - LEVEL B1 GENERAL ARRANGEMENT PLAN

Drawing Number



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE / PLANT
- COMMERCIAL
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL
Architect
Denton Corker Marshall LLP
Manner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1
1:500 @ A3
0 2.5 5 7.5 12.5M

Drawing Title
BLOCK A & B - GROUND FLOOR GENERAL ARRANGEMENT PLAN

Drawing Number

BRIDGEWATER CANAL

CASTLEFIELD LOCKS

THE TRILOGY

IN-SITU

ELLESMERE STREET

CHESTER ROAD

RAILWAY LINE

TRAM LINE

TRENTHAM STREET

VOX

B

A

EXTERNAL TERRACE

DN

PROTECTED CORRIDOR

RESIDENT'S AMENITY

FFL + 34000

LINE OF CANOPY

FFL + 33450

2B [4P]

3B [6P]

1B [2P]

2B [4P] TH

SS

E

LS

M

VOID

LINE OF CANOPY

KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE / PLANT
- COMMERCIAL
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect
Denton Corker Marshall LLP
Manner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1
1:500 @ A3
0 2.5 5 7.5 12.5M

Drawing Title
BLOCK A & B - FIRST FLOOR GENERAL ARRANGEMENT PLAN

Drawing Number



No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1
1:500 @ A3
0 2.5 5 7.5 12.5M

Drawing Title
BLOCK A & B - TYPICAL LEVELS 02-05 GENERAL ARRANGEMENT PLAN

Drawing Number



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE / PLANT
- COMMERCIAL
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1
1:500 @ A3
0 2.5 5 7.5 12.5M

Drawing Title
BLOCK A & B - LEVEL 06 GENERAL ARRANGEMENT PLAN

Drawing Number



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE / PLANT
- COMMERCIAL
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL
Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1
1:500 @ A3
0 2.5 5 7.5 12.5M

Drawing Title
BLOCK A & B - LEVEL 07 GENERAL ARRANGEMENT PLAN

Drawing Number



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE / PLANT
- COMMERCIAL
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1
1:500 @ A3
0 2.5 5 7.5 12.5M

Drawing Title
BLOCK A & B - LEVEL 08 GENERAL ARRANGEMENT PLAN

Drawing Number



No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL
Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1 0 2.5 5 7.5 12.5M
1:500 @ A3

Drawing Title
BLOCK A & B - TYPICAL LEVELS 09-44 GENERAL ARRANGEMENT PLAN

Drawing Number



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE / PLANT
- COMMERCIAL
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED


DENTON CORKER MARSHALL
Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1 0 2.5 5 7.5 12.5M
1:500 @ A3

Drawing Title
BLOCK A & B - LEVEL 45 GENERAL ARRANGEMENT PLAN

Drawing Number



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE / PLANT
- COMMERCIAL
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL


Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1
1:500 @ A3
0 2.5 5 7.5 12.5M

Drawing Title
BLOCK A & B - LEVEL 46 LOWER ROOF GENERAL ARRANGEMENT PLAN

Drawing Number



No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

PRINT IN COLOUR

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL
Architect
Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk


Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1 0 2.5 5 7.5 12.5M
1:500 @ A3

Drawing Title
BLOCK A & B - LEVEL 47 UPPER ROOF GENERAL ARRANGEMENT PLAN


Drawing Number

KEY PLAN



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE
- CIRCULATION



No.	Date	Dwn	Chk	App	Revision or reason for issue

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect

Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD


Scale / North Point

1:250 @ A1 0 2.5 5 7.5 12.5M
1:500 @ A3

Drawing Title
PROPOSED SITE SECTION A-A

Drawing Number

KEY PLAN



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue
P01.01	19.02.26	JJ	GS	GS	ISSUED FOR REVIEW
P01.02	19.06.26	JJ	GS	GS	PLANNING ISSUE

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect

Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1 0 2.5 5 7.5 12.5M
1:500 @ A3


Drawing Title
PROPOSED SITE SECTION B-B

Drawing Number
N1C-DCM-ZZ-BB-SE-A-50012

Drawing Purpose
PLANNING

CDE Status **S0** Revision **P01.02**

KEY PLAN



KEY LEGEND

- 1 BED UNIT
- 2 BED UNIT
- 3 BED UNIT
- 4 BED UNIT
- AMENITY
- BACK OF HOUSE
- CIRCULATION

No.	Date	Dwn	Chk	App	Revision or reason for issue
P01.01	19.02.26	JJ	GS	GS	ISSUED FOR REVIEW
P01.02	19.06.26	JJ	GS	GS	PLANNING ISSUE

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

Client
KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect

Denton Corker Marshall LLP
Marriner House, 32-34 Greville Street, London, EC1N 8TB
Old Exchange, 6 St. Ann's Passage, Manchester, M2 6BE
Telephone +44 (0)20 7833 2020 / +44 (0)161 834 3511
Email mail@dentoncorkermarshall.co.uk

Project Title
NO. 1 CASTLEFIELD

Scale / North Point
1:250 @ A1 0 2.5 5 7.5 12.5M
1:500 @ A3

Drawing Title
PROPOSED SITE SECTION C-C

Drawing Number
N1C-DCM-ZZ-CC-SE-A-50013

Drawing Purpose
PLANNING

CDE Status **S0** Revision **P01.02**

10.0 Appendix 2: Low Carbon Heat Appraisal

CWC

crookes walker
consulting





One Castlefield

Castlefield, Manchester

Low Carbon Heat Appraisal

Date: 15/07/2026
Ref: 3582-CWC-XX-XX-RP-N-0002

Crookes Walker Consulting Limited is registered in England & Wales | 05011466 |
Registered Office: One Express | 1 George Leigh Street | Ancoats | Manchester | M4 5DL

Revision Record

Date	Reference	Revision	Prepared By	Checked By	Authorised By
29/06/2026	3582-CWC-XX-XX-RP-N-0002	P01	Ben Hawksworth	Ben Hawksworth	Ben Hawksworth
			Ben Hawksworth	Ben Hawksworth	Ben Hawksworth
15/07/2026	3582-CWC-XX-XX-RP-N-0002	P02	Ben Hawksworth	Ben Hawksworth	Ben Hawksworth
			Ben Hawksworth	Ben Hawksworth	Ben Hawksworth

Contents

1.0 Executive Summary 4
2.0 Introduction and Planning Policy Context 6
2.1 Purpose and scope 6
2.2 Policy JP-S3 and the Net Zero requirement 6
3.0 The Proposed Development 7
4.0 Proposed Energy and Heating Strategy 8
5.0 Heat Network Context and Location Assessment 9
6.0 Heating System Options Considered 10
7.0 Assessment Against the Key Performance Indicators 11
7.1 Environmental performance 12
7.2 Impact on residents 12
7.3 Impact on viability 13
7.4 Infrastructure development 13
8.0 Justification for Non-Connection to a Low Carbon Heat Network 14
9.0 Conclusions and Next Steps 15
Appendix 1 – GMCA Low Carbon Heat KPI Summary (Proposed System) 16
Appendix 2 – Carbon Content of Heat: Calculation Basis 17

1.0 Executive Summary

Crookes Walker Consulting (CWC) have prepared this Low Carbon Heat Appraisal in support of the planning application for One Castlefield, Manchester. The appraisal has been undertaken in-line with the Greater Manchester Combined Authority (GMCA) 'Low carbon heat' guidance (March 2025) and is intended to demonstrate how the proposed development responds to Places for Everyone Policy JP-S3 (Heat and Energy Networks), which is linked to Policy JP-S2 and the Net Zero / Truly Affordable Net Zero (TANZ) requirements.

The proposals for One Castlefield represent a refined residential development, addressing previous scheme shortcomings while maintaining a high-density residential offer.

The site, located adjacent to the A57 Chester Road in Manchester city centre, is strategically positioned within the established Castlefield/St.

George's area. It is well-connected, benefiting from proximity to Bridgewater Canal, mainline railway, tramway and Cornbrook Metrolink Station.

This development is the final phase of the St. George's regeneration. The design has evolved through rigorous pre-application engagement with the Manchester City Council, focusing on creating a high-quality, sustainable solution that responds positively to its local context, contributes to regeneration and aligns with current planning policy for tall buildings and the historic environment.

Previous proposals were unviable due to regulatory changes (fire safety requirements for high-risk buildings necessitating an additional stair core) and design challenges related to site optimisation and amenity provision.

The current design addresses these by consolidating blocks, increasing public and amenity space and strategically reorienting a taller tower to minimise impact on neighbours while creating a landmark. The scheme aims to be a positive visual marker and enhance the streetscape, capitalising on its gateway location and proximity to Cornbrook Metrolink Interchange to encourage sustainable transport.

The proposed heating and hot water strategy is summarised as follows:

- Space heating – individual electric panel heaters within the apartments and circulation areas, with local programmable controls;
- Domestic hot water – individual exhaust-air / hot-water heat pumps within each dwelling, recovering heat from the dwelling's extract ventilation (the 'KERS MEV' arrangement), with local hot water storage;

- Amenity areas – Variable Refrigerant Flow (VRF) air source heat pump systems providing both heating and cooling; and
- Renewables – roof-mounted solar photovoltaic (PV) panels.

The site has been assessed as falling within a GMCA 'Heat and Energy Network Opportunity Area' (Case 3). No low carbon heat network is currently operating, funded or under construction within range of the site, and the GMCA guidance confirms there are presently no operating low carbon heat networks anywhere in Greater Manchester.
The headline outcomes of the appraisal against the GMCA Key Performance Indicators (KPIs) are:

- no fossil fuel is used on site;
- the blended carbon content of heat (delivered) of the proposed system is estimated at circa 70 gCO_2/kWh, which is below the 100 gCO_2/kWh threshold for a 'low carbon heating system' and below the carbon content assumed for a notional low carbon heat network in an opportunity area;
- the proposed system has the lowest indicative capital cost of the options considered; and
- the proposed system is anticipated to carry higher in-use energy costs than an on-site air source heat pump (the recognised trade-off of direct electric space heating), although the fabric-first design keeps the absolute space heating demand, and therefore the cost differential, modest.

On balance, CWC consider that the proposed system delivers low carbon, cost-effective heat that is appropriate to the scale and location of the development, and that an on-site solution is preferable to connection to (or commitment to connect to) a low carbon heat network at this time. The justification for non-connection is set out in Section 8. All costs and performance figures in this appraisal are high level and indicative, provided for comparison purposes only; confirmation of a number of inputs is required as the design progresses (see Section 9).

2.0 Introduction and Planning Policy Context

2.1 Purpose and scope

This appraisal has been prepared to accompany the planning application for One Castlefield and to demonstrate compliance with Policy JP-S3. The GMCA 'Low carbon heat' guidance recommends that a Low Carbon Heat Appraisal is submitted for all major applications, with the level of analysis varying by scale and location. As One Castlefield is a 'large major' application (more than 150 dwellings and/or more than 5,000 m^2 GIA), a detailed appraisal is expected, reporting the predicted performance of the proposed heating system against the KPIs and comparing it with a few relevant alternatives, including a low carbon heat network and an on-site communal heating system.

This appraisal is based on the MEP Emerging Proposals, the Energy Statement, the SAP / Part L compliance assessments and the design information available at this (early) stage. Equipment selections, quantities and costs are indicative and for comparison only; final selections, details and costs will differ following more detailed assessment at the next design stage. CWC's assessment is based on the validity of the information provided.

2.2 Policy JP-S3 and the Net Zero requirement

Policy JP-S3(2) sets an expectation that, within identified Heat and Energy Network Opportunity Areas, new residential developments of 10 dwellings or more (or other development over 1,000 m^2) will connect to an existing or planned heat/energy network, or be designed to enable future connection, and/or install a site-wide or communal heat/energy network solution 'unless it can be demonstrated that there are more effective alternatives for minimising carbon emissions or such connection is not practicable or financially viable'.

The guidance is clear that a building cannot be Net Zero if its heating and hot water system uses fossil fuels, and that a heating system should qualify as 'low carbon' where the carbon content of heat delivered is less than 100 gCO_2/kWh. It also stresses that the chosen system must be affordable for residents, must not compromise consumer protection, and must not contribute to overheating. These considerations are carried through the KPI assessment in Section 7.

3.0 The Proposed Development

The proposals comprise the redevelopment of a circa 0.72 hectare cleared site adjacent to the A57 Chester Road, bounded by Trentham Street, Ellesmere Street, Castlefield Locks, the elevated railway line and a small area of the Bridgewater Canal. The scheme provides 592 residential units (Use Class C3) across two blocks - Block A (ground and first floors plus 44 storeys, circa +168.00m AOD) and Block B (ground floor plus 8 storeys, circa +59.8m AOD) - together with amenity space, landscaping, cycle and car parking and associated works.

A 'fabric first' approach has been adopted, with the building fabric designed to perform substantially better than the Part L (2021) backstop values. The Energy Statement and Part L assessments indicate the following indicative parameters:

- external walls circa 0.12 W/m²K (Part L backstop 0.26);
- roof circa 0.10–0.11 W/m²K (backstop 0.16–0.18);
- ground floor circa 0.16 W/m²K (backstop 0.18);
- windows circa 1.2–1.4 W/m²K; and
- air permeability circa 3 m³/h·m² @ 50 Pa (against a backstop of 8).

The dwellings are reported to achieve EPC band B throughout. This low underlying heat demand is important context for the appraisal: it limits the absolute energy use (and therefore the running-cost penalty) associated with direct electric space heating, which is the principal concern the GMCA guidance raises about that technology.

4.0 Proposed Energy and Heating Strategy

The proposed strategy is all-electric, with no combustion on site. It corresponds to the GMCA guidance archetype of an individual 'hot water heat pump + direct electric' dwelling system, supplemented by VRF heat pumps to the amenity areas. The principal elements are:

- No fossil fuel – there is no proposal for gas to the site; the existing gas mains are to be disconnected and purged.
- Space heating – individual electric panel heaters to the apartments and circulation areas, controlled by programmer, room thermostat / app control and (where relevant) local controls. Frost protection to plant/store rooms via local electric tube heaters.
- Domestic hot water – a packaged hot-water heat pump within each dwelling, integral to the mechanical extract ventilation (the 'KERS MEV' arrangement), recovering low-grade heat from the dwelling's extract air to heat stored hot water. Point-of-use electric water heaters serve isolated WCs / kitchenettes.
- Amenity heating and cooling – VRF (air source heat pump) systems serving the shared amenity areas via fan coil / cassette units, with external condensers located in dedicated louvred plant rooms.
- Renewable generation – roof-mounted solar PV (noted in the SAP assessment as circa 15 kWp to the upper floors / duplex roofs), contributing to the on-site low/zero carbon generation required by Manchester's Local Development Framework (Policy EN 6).

Because the heat sources are electric (direct electric and heat pumps), the strategy is compatible with Net Zero and benefits directly from the continuing decarbonisation of the electricity grid. It should be noted that the thermal modelling and final HVAC strategy remain subject to ongoing design development, and that the acoustic suitability of the external air source / VRF plant is identified in the MEP proposals as a project risk requiring further assessment.

5.0 Heat Network Context and Location Assessment

The GMCA guidance identifies four location 'cases' for major applications, which determine the range of heat network options that must be considered:

- Case 1 – within 500 m of an existing low carbon heat network;
- Case 2 – within 500 m of a planned low carbon heat network;
- Case 3 – within a Heat and Energy Network Opportunity Area; and
- Case 4 – any other location.

One Castlefield is located in central Manchester. On the basis of the Places for Everyone Heat and Energy Network Opportunity Areas mapping, the site is understood to fall within an Opportunity Area, and the development has therefore been assessed as Case 3. This should be confirmed with the Local Planning Authority (LPA), who are best placed to advise whether the site now falls within any emerging, formally designated heat network zone.

The GMCA guidance confirms that there are currently no operating low carbon heat networks anywhere in Greater Manchester. CWC are not aware of any low carbon heat network that is funded or under construction within range of the site. Existing city-centre heat networks are understood to be predominantly gas-fired (boilers and/or gas CHP) and therefore high carbon (likely well in excess of 300 gCO_2/kWh); the guidance is explicit that major applications in the vicinity of such networks should not connect to them.
For a Case 3 site, the guidance requires that a notional low carbon heat network with a carbon content of heat of 100 gCO_2/kWh is included as one of the options assessed (see Section 6). The applicant is not, however, required to install interim communal plant or commit to a future connection unless and until the area is formally designated as a 'heat network zone' – a designation the guidance indicates is unlikely before 2027.

6.0 Heating System Options Considered

In-line with the guidance for a large major application, the proposed system has been compared against a small number of relevant alternatives, including an on-site communal system and a low carbon heat network. The options considered are:

- Option 1 (Proposed) – individual direct electric space heating with individual exhaust-air / hot-water heat pumps for domestic hot water (plus VRF to amenity areas).
- Option 2 (Benchmark) – individual air-to-water air source heat pumps (monobloc) per dwelling, providing space heating and hot water. This is the GMCA 'benchmark' low carbon heating system against which the KPIs are compared.
- Option 3 – a building / block-scale communal air source heat pump system, distributing heat to each dwelling via heat interface units (HIUs).
- Option 4 – connection to a notional low carbon heat network (carbon content 100 gCO_2/kWh), with an interim on-site communal heating system pending the network coming forward.

In summary, Option 2 (individual ASHP) is the lowest-carbon and most resident-friendly individual solution but carries a higher capital cost. Options 3 and 4 introduce communal distribution, which brings distribution heat losses, an overheating risk from communal pipework, communal maintenance, and individual metering / billing with associated standing charges and consumer-protection considerations. Option 4 additionally depends on a network that does not currently exist. The proposed Option 1 minimises capital cost and avoids communal distribution and its associated risks, at the expense of higher in-use energy costs for the space heating element.

7.0 Assessment Against the Key Performance Indicators

The four GMCA performance areas and their eleven KPIs are assessed below, and the options are compared in Table 7.1. The KPI values for the proposed system are summarised in Appendix 1, and the basis of the carbon content of heat calculation is set out in Appendix 2.

Performance / KPI	Option 1 – Proposed (direct electric + HW heat pump)	Option 2 – Benchmark (individual ASHP)	Option 3 – Communal ASHP + HIU	Option 4 – Notional low carbon heat network
Fossil fuel use	No	No	No	No (assumed)
Carbon content of heat (delivered)	circa 70 gCO_2/kWh	circa 35 gCO_2/kWh	circa 50 gCO_2/kWh	100 gCO_2/kWh (max to qualify)
Local pollution	None (no combustion); low refrigerant charge	None; external unit refrigerant + acoustic	None; communal plant acoustic	Depends on energy centre / heat source
Indicative capital cost (£/unit)	circa £7,000	circa £10,000	circa £12,000	≥£12,000 + connection (uncertain)
Additional capital cost vs benchmark	circa −30%	– (benchmark)	circa +20%	Highest
Indicative heating/hot-water energy cost (£/dwelling/yr)	circa £500–550	circa £270–300	circa £300 + standing charge	Network tariff + standing charge
Additional operating cost vs benchmark	circa +£230/yr (higher)	– (benchmark)	Comparable to higher (all-in)	Uncertain; standing-charge risk
Maintenance cost (annualised)	Low (circa £50–80/yr)	circa £120–150/yr	Higher + communal contract	Higher + ESCO charges
Replacement cost (annualised)	Low (circa £100/yr)	circa £270/yr	Higher (incl. plant share)	Higher (incl. plant share)
Connection to low carbon heat network	No	No	No	Yes

Performance / KPI	Option 1 – Proposed (direct electric + HW heat pump)	Option 2 – Benchmark (individual ASHP)	Option 3 – Communal ASHP + HIU	Option 4 – Notional low carbon heat network
Overheating / consumer protection	Low overheating risk; individual supply, can switch supplier	Low overheating risk; individual supply	Overheating risk (communal pipes); metering/billing	Overheating risk; regulated tariff TBC

Table 7.1 – Indicative comparison of heating system options against the GMCA KPIs (high level, for comparison purposes only).

7.1 Environmental performance

Fossil fuel use (KPI 1): none. The development is all-electric and the gas supply is to be disconnected.

Carbon content of heat (KPI 2): the carbon content of heat delivered has been estimated using grid electricity carbon factors averaged over the first 15 years from anticipated completion, in-line with the guidance (which directs the use of HM Treasury Green Book average fuel factors over that period). On this basis an average grid factor of circa 0.10 $kgCO_2/kWh$ (100 gCO_2/kWh) has been adopted, reflecting the continued decarbonisation of the grid (the current SAP 10.2 factor is 0.136 $kgCO_2/kWh$). The space heating element (direct electric, circa 100% efficient) therefore has a carbon content of circa 100 gCO_2/kWh, whilst the hot water element (heat pump, seasonal CoP circa 2.5) is circa 40 gCO_2/kWh. Weighted across the dwelling heat demand, the blended carbon content of heat is estimated at circa 70 gCO_2/kWh – below the 100 gCO_2/kWh low-carbon threshold, and below the 100 gCO_2/kWh assumed for a notional opportunity-area heat network. An individual ASHP solution (Option 2) would be lower still, at circa 35 gCO_2/kWh.

Local pollution (KPI 3): there is no combustion and therefore no local flue emissions. The packaged hot-water heat pumps use a small refrigerant charge; the amenity VRF systems use a larger charge and CWC would recommend low Global Warming Potential (GWP) refrigerants (e.g. R290 / R32), minimised pipe runs and consideration of embodied / whole-life carbon in-line with CIBSE TM65 / TM65.1. The acoustic impact of the external air source plant is to be assessed.

7.2 Impact on residents

Energy, maintenance and replacement costs (KPIs 4–6): the principal trade-off of the proposed system is in-use energy cost. Direct electric space heating uses circa three times more electricity per unit of heat than an air source heat pump, so the space heating element is more expensive to run than the benchmark. On a high-level basis, and given the fabric-first low demand, the heating and hot-water energy cost is estimated at circa £500–550 per dwelling per year, against circa £270–300 for the benchmark individual ASHP – a difference of circa £230 per year (KPI 7). Set against this, the proposed system has lower maintenance and replacement costs (panel heaters are simple, robust and long-lived, with only the hot-water heat pump requiring periodic servicing), and avoids the communal standing / metering charges that a communal system or heat network would levy through the service charge.

Affordability and consumer protection: the GMCA guidance rightly flags the risk of high bills with direct electric heating, and recommends it is generally only accepted in ultra-low-energy homes. CWC consider the risk here is materially mitigated by the fabric-first specification (U-values and air permeability well beyond the Part L backstop), which keeps the space heating demand – and therefore the cost differential – low. The individual, dwelling-level electrical supply also preserves residents' ability to choose and switch energy supplier and to benefit from regulated retail tariffs and (potentially) time-of-use / dynamic pricing, which a communal heat network would not. CWC would recommend that the fabric specification assumed in this appraisal is locked in through the construction contract so that the low running costs are realised in practice.

7.3 Impact on viability

Capital cost (KPIs 8–9): on the GMCA indicative figures the proposed system carries the lowest capital cost of the options (circa £7,000 per unit, against circa £10,000 for the benchmark individual ASHP, circa £12,000 for a communal ASHP, and higher still – plus an uncertain connection cost – for a heat network). The proposed system is therefore circa 30% cheaper than the benchmark, which supports the viability and deliverability of the housing. A specific assessment of capital costs by the project's cost consultant is recommended.

7.4 Infrastructure development

Connection to a low carbon heat network (KPI 10): no. No low carbon heat network is currently operational, funded or within range (see Section 5).

Scale of application (KPI 11): large major – several hundred dwellings across Blocks A, and B (GIA to be confirmed), well above the 150-dwelling / 5,000 m² thresholds.

8.0 Justification for Non-Connection to a Low Carbon Heat Network

As the site is within a Heat and Energy Network Opportunity Area (Case 3), Policy JP-S3 sets an expectation of connection to, or design to enable future connection to, a low carbon heat network unless a more effective, practicable or financially viable alternative can be demonstrated. For a Case 3 site the guidance does not, however, require the applicant to install interim communal plant or commit to connect unless and until the area is formally designated a heat network zone (unlikely before 2027). CWC consider an on-site solution is justified at this time on the following grounds, which align with the four grounds for exemption set out in the guidance:

1. Carbon grounds – there is no low carbon heat network to connect to; existing networks in the vicinity are understood to be high carbon (gas-fired). The proposed on-site system delivers heat at circa 70 gCO_2/kWh, which is below both the 100 gCO_2/kWh low-carbon threshold and the carbon content assumed for a notional opportunity-area network, so an on-site solution is lower carbon than connection to a notional network.
2. Cost-effectiveness grounds – no network operator can provide a robust connection cost because no network exists or is funded. The capital cost of connection plus interim communal plant would not be as cost-effective as the proposed on-site system, which has the lowest indicative capital cost of the options assessed.
3. Heating cost grounds – a communal system or heat network would introduce standing / metering charges and reduce residents' consumer protection (no ability to switch supplier). The proposed individual supply avoids this, and keeps residents on regulated retail tariffs.
4. Technical / practical grounds – there is genuine uncertainty over the deliverability and programme of any future network in this location, and no formal heat network zone designation is in place. It would not be appropriate to constrain the scheme to a communal interim solution, with its attendant distribution losses and overheating risk, on the basis of a network that may not come forward.

CWC are transparent that the proposed system is not the lowest-carbon option available – an on-site communal or individual air source heat pump solution would deliver a lower carbon content of heat. The proposed system has been selected on the balance of carbon (below the low-carbon threshold), capital cost and viability, simplicity and consumer protection for residents, and overheating mitigation (no communal distribution pipework), supported by a fabric-first design that limits the running-cost penalty of direct electric heating. It is also noted that the decision to validate any exemption rests entirely with the LPA, who may accept or refuse it.

9.0 Conclusions and Next Steps

CWC consider that the proposed all-electric heating and hot water strategy for One Castlefield delivers low carbon heat (below the 100 gCO_2/kWh threshold), is cost-effective to install, and is appropriate to the scale and central location of the development. It avoids fossil fuels entirely and is well placed to benefit from grid decarbonisation. The principal residual consideration is the in-use energy cost of direct electric space heating, which CWC consider is acceptably mitigated by the fabric-first design, but which should be kept under review as the design develops.

CWC would recommend the following next steps, to be agreed with the Client, design team and LPA:

- confirm with the LPA the site's status (Opportunity Area / Case 3) and whether it falls within any emerging, formally designated heat network zone;
- confirm the average grid carbon factor and the carbon content of heat with the energy assessor, using the HM Treasury Green Book / DESNZ 15-year forward projections, to firm up the KPI 2 figure;
- develop a dwelling-level energy-cost estimate from the SAP / thermal model to confirm the affordability position (KPIs 4–7) and the running-cost differential against an ASHP;
- lock the fabric-first specification (U-values and air permeability) into the construction contract so the low space heating demand, and hence the low running costs, are realised;
- confirm the acoustic feasibility of the external air source / VRF plant, which is identified as a project risk;
- specify low-GWP refrigerants and consider embodied / whole-life carbon (CIBSE TM65 / TM65.1); and
- obtain capital and operating cost figures from the project cost consultant to replace the indicative figures used here.

This appraisal is high level and for the purposes of demonstrating the approach to Policy JP-S3; the conclusions are based on the validity of the information available at this stage and may be revisited as the design and the policy position (in particular formal heat network zoning) develop.

Appendix 1 – GMCA Low Carbon Heat KPI Summary (Proposed System)

The table below summarises the GMCA KPIs for the proposed system. All figures are indicative and for comparison purposes only.

KPI	Indicator	Unit	Proposed system
1	Fossil fuel use	Yes/No	No
2	Carbon content of heat	gCO_2/kWh	circa 70
3	Local pollution	Description	None (no combustion); low-GWP refrigerant recommended
4	Estimated energy cost (heating & hot water)	£/yr	circa 500–550 / dwelling
5	Estimated maintenance cost	£/yr (annualised)	circa 50–80
6	Estimated replacement cost	£/yr (annualised)	circa 100
7	Additional operating cost vs benchmark	+/- %	higher (circa +£230/yr)
8	Estimated capital cost	£/unit	circa 7,000
9	Additional capital cost vs benchmark	+/- %	circa −30%
10	Connection to low carbon heat network	Yes/No	No
11	Scale of application	m^2 GIA / dwellings	Large major (several hundred dwellings; GIA TBC)

Appendix 2 – Carbon Content of Heat: Calculation Basis

The carbon content of heat delivered combines three factors: the carbon intensity of the fuel; the efficiency of the heat-generating plant; and distribution / storage losses. The basis adopted is:

- Grid electricity carbon factor – average over the first 15 years from anticipated completion (circa 2028–2043), taken from HM Treasury Green Book / DESNZ projections: circa 0.10 $kgCO_2$/kWh (100 gCO_2/kWh) adopted. The current SAP 10.2 factor is 0.136 $kgCO_2$/kWh; the forward trajectory is steeply downward.
- Space heating (direct electric) – circa 100% efficient, negligible distribution loss: carbon content circa 100 gCO_2/kWh.
- Domestic hot water (exhaust-air / hot-water heat pump) – seasonal CoP assumed circa 2.5: carbon content circa 40 gCO_2/kWh.
- Blend – weighted across the dwelling space-heating and hot-water demand (a fabric-first dwelling has a relatively high hot-water fraction): blended carbon content circa 70 gCO_2/kWh (range circa 65–75).

For comparison, an individual air-to-water ASHP (blended seasonal CoP circa 2.9) would deliver circa 35 gCO_2/kWh, and a communal ASHP at 65°C with distribution losses circa 50 gCO_2/kWh. These figures are indicative and should be confirmed by the energy assessor using project-specific demand splits and the latest Green Book factors.

11.0 Roof Layout



12.0 Appendix 3: Overheating Report

CWC

crookes walker
consulting

1 Castlefield

Manchester

Approved Document Part O
Compliance Report

Date: 27/04/2026
Ref: 3582-CWC-XX-XX-RP-N-7004

Crookes Walker Consulting Limited is registered in England & Wales | 05011466 |
Registered Office: One Express | 1 George Leigh Street | Ancoats | Manchester | M4 5DL



Revision Record

Date	Reference	Revision	Prepared	Checked	Authorised
28/11/2025	3582-CWC-XX-XX-RP-N-7004	P01	Nazhan Nizam	Obaid Rahman	Ben Hawksworth
			NN	OR	BH
27/04/2026	3582-CWC-XX-XX-RP-N-7004	P02	Mohammad Elsarraj	Obaid Rahman	Ben Hawksworth
			ME	OR	BH

Contents

1.0 Executive Summary 5
2.0 Introduction 7
2.1 Site Location 8
2.2 Modelling Disclaimer 10
2.3 Building Layout 11
2.4 Views of Thermal Model 12
3.0 Assessment Targets 13
3.1 Approved Document O 13
3.1.1 Predominantly Naturally Ventilated Zones 14
3.1.2 Communal Corridors 14
3.1.3 Window and Noise Constraints 15
4.0 Inputs 16
4.1 Fabric Parameters 16
4.2 Blinds 16
4.3 Ventilation Strategy 17
4.3.1 Mechanical Ventilation 17
4.3.2 Natural Ventilation 20
4.3.3 Acoustic Considerations 22
4.3.4 Internal Doors 22
5.0 Results 22

6.0 Appendix 1: CIBSE TM59 Prescribed Profiles 24
7.0 Appendix 1: DSY1: TM52 Criterion 1 Bedroom Block A 25
8.0 Appendix 2: DSY 1: Bedroom Night-time Temperature Test Block A 39
9.0 Appendix 3: DSY1: TM52 Criterion 1 Living Block A 53
10.0 Appendix 4: DSY2: TM52 Criterion 1 Bedroom Block A 62
11.0 Appendix 5: DSY 2: Bedroom Night-time Temperature Test Block A 77
12.0 Appendix 6: DSY2: TM52 Criterion 1 Living Block A 92
13.0 Appendix 7: DSY3: TM52 Criterion 1 Bedroom Block A 101
14.0 Appendix 8: DSY 3: Bedroom Night-time Temperature Test Block A 116
15.0 Appendix 9: DSY3: TM52 Criterion 1 Living Block A 131
16.0 Appendix 10: DSY1: TM52 Criterion 1 Bedroom Block B 140
17.0 Appendix 11: DSY 1: Bedroom Night-time Temperature Test Block B 147
18.0 Appendix 12: DSY1: TM52 Criterion 1 Living Block B 154
19.0 Appendix 13: DSY2: TM52 Criterion 1 Bedroom Block B 158
20.0 Appendix 14: DSY2: Bedroom Night-time Temperature Test Block B 165
21.0 Appendix 15: DSY2: TM52 Criterion 1 Living Block B 172
22.0 Appendix 16: DSY3: TM52 Criterion 1 Bedroom Block B 176
23.0 Appendix 17: DSY3: Bedroom Night-time Temperature Test Block B 183
24.0 Appendix 18: DSY3: TM52 Criterion 1 Living Block B 190

1.0 Executive Summary

Crookes Walker Consulting (CWC) have carried out dynamic thermal modelling for the Castlefield residential development in Manchester. The assessment confirms compliance with:

- *Building Regulations (2021 Edition), Approved Document O* (based on CIBSE's Technical Memorandum 59: *Design Methodology for the Assessment of Overheating Risk in Homes* (2017) – 'CIBSE TM59')

The Approved Document Part O, CIBSE TM59, and AVO guide together ensure that the assessment considers both thermal comfort and acoustic constraints. They check that internal temperatures remain within acceptable limits, that overheating risk is acceptable, and that ventilation strategies do not compromise internal noise criteria.

The analysis confirms that compliance with the requirements of Approved Document Part O and AVO guide is achieved. This is based on:

- Building fabrics as per Table 4.
- Ventilation rates outlined in Section 4.3.1.
- Window openings outlined in Sections 4.3.2.

Table 1 below gives a summary of results for bedrooms and living areas respectively.

Block	Weather File	Status	Compliance – CIBSE TM52 Criterion 1		Overall Result	Operative Temperature	Overall Result
			Bedrooms	Living		Bedrooms	
Block A	DSY1	Mandatory	✓	✓	Pass	✓	Pass
	DSY2	Advisory	✓	×	Fail	✓	Pass
	DSY3	Advisory	✓	×	Fail	×	Fail
Block B	DSY1	Mandatory	✓	✓	Pass	✓	Pass
	DSY2	Advisory	✓	✓	Pass	✓	Pass
	DSY3	Advisory	×	×	Fail	×	Fail

Table 1. Results Summary

This assessment will need to be undertaken again if any parameters change from those stated herein.

2.0 Introduction

Crookes Walker Consulting (CWC) have undertaken overheating risk assessment aligned to the Building Regulations Approved Document Part O and *Acoustics, Ventilation and Overheating Residential Design Guide (2020) (AVO)* for the 1 Castlefield residential development located in Manchester.

The Approved Document O, CIBSE TM59, and AVO guide together ensure that the assessment considers both thermal comfort and acoustic constraints. They mandate that internal temperatures remain within acceptable limits, that overheating risk is acceptable, and that ventilation strategies do not exceed internal noise criteria.

Compliance with these requirements is necessary to comply with Approved Document Part O.

2.1 Site Location




Figure 1. Site Location.

The site is in Manchester; therefore the Manchester DSY high emission 50th percentile scenario weather file is used. The assessment is required to demonstrate compliance against the DSY1 weather file, with additional reporting on the building's performance under DSY2 and DSY3 scenarios.

It should be noted that should just a single zone not comply with the assessment criteria, the whole building is deemed non-compliant. if even a single zone is found to fail the overheating criteria, the entire building is deemed at risk of overheating, and therefore compliance must be achieved across all zones.

Detailed results for DSY2 & DSY3 can be found in appendix 5-10 and 14-19 for Blocks A and B respectively.

2.2 Modelling Disclaimer

The building has been modelled with accredited software package IES VE version 2025.1.0.0, which is an approved dynamic simulation software, compliant with CIBSE AM11.

These assessments were undertaken by an Energy Specialist; an individual who has acquired substantial expertise or a recognised qualification for undertaking assessments, designs, and installations of Low and Zero Carbon solutions in the commercial buildings sector and is not professionally connected to a single Low and Zero Carbon technology or manufacturer.

It should be noted that the data generated by this work is obtained using computer simulations. These simulations are the best means of predicting the performance of the building at this stage. Full certainty can only be achieved by measuring the performance of the building and associated systems after a period of use.

Whilst the simulations have been undertaken in good faith using reasonable skill and care, Crookes Walker Consulting Limited can take no responsibility for differences between the computer simulations and the actual performance of the completed building due to the inherent complexity and variability of the physics in a building and its environment.

2.3 Building Layout

Table 2 below confirms the architectural drawings used for the overheating assessment:

Drawing	Revision
N1C-DCM-ZZ-00-PL-A-20000	P01.09
N1C-DCM-ZZ-01-PL-A-20001	P01.07
N1C-DCM-ZZ-06-PL-A-20007	P01.03
N1C-DCM-ZZ-07-PL-A-20003	P01.07
N1C-DCM-ZZ-08-PL-A-20004	P01.07
N1C-DCM-ZZ-45-PL-A-20006	P01.06
N1C-DCM-ZZ-B1-PL-A-20008	P01.02

Table 2. Architectural Drawings.

2.4 Views of Thermal Model




Figure 3: View of Thermal Model

3.0 Assessment Targets

3.1 Approved Document O

The Building Regulations 2010 Approved Document O (2021 edition) is based on CIBSE TM59 (2017) 'Design methodology for the assessment of overheating risk in homes'. This is a standardised approach in predicting overheating risk in residential buildings using prescribed inputs and usage profiles.

The profiles represent domestic usage patterns, as prescribed in CIBSE TM59. They have been developed to evaluate the building design and not to directly mimic usage modes. To prevent deviation from the defined methodology it is not acceptable to alter the CIBSE TM59 set profiles. Full usage profiles are in Appendix A of this document.

Compliance with this assessment methodology does not ensure that people will always be comfortable in their homes, due to variations on the intended use, however it does aim to limit the length of time excessive temperatures are experienced.

All assumptions and mitigations made within this report must form part of the construction contract, or the model will need to be re-run to prove compliance incorporating any changes. Any inclusion of pipework insulation, blinds, openable windows etc. must not be ignored.

3.1.1 Predominantly Naturally Ventilated Zones

The development at 1 Castlefield, Manchester has been assessed as predominantly naturally ventilated as all occupied rooms have openable windows.

For homes that are predominantly naturally ventilated, compliance is based on satisfying the following criteria:

Criterion 1: *The number of hours which ΔT is greater than or equal to one degree (K) during the occupied period should not be more than 3% of the total occupied hours during the non-heating season (May to September inclusive). This is applicable to living, kitchen, and bedroom areas.*

Criterion 2: *For bedrooms only, the operative temperature shall not exceed 26oC for more than 1% of the total number of hours, between 10pm and 7am, throughout the non-heating season (May to September inclusive)*

3.1.2 Communal Corridors

Though compliance is not mandatory, the risk of overheating is required to be reported by CIBSE TM59, and therefore AO Part O, in all communal circulation zones. These zones are deemed to have a high risk of overheating if the operative temperature exceeds 28°C for more than three per cent of annual hours.

3.1.3 Window and Noise Constraints

The assessment assumes that no noise restrictions apply, with window operation available to mitigate overheating during occupied hours.

4.0 Inputs

4.1 Fabric Parameters

Table 3 below displays the proposed building fabrics and glazing properties applied to the thermal model.

Element	Value
External Wall	0.12 W/m^{2}K
Glazing	1.20 W/m^{2}K
G-value	0.4
Roof	0.11 W/m^{2}K
Ground Floor	0.16 W/m^{2}K
Air permeability	3.00 m^3/hr/m^2 @ 50 Pa

Table 3. Fabric Parameters.

4.2 Blinds

Blinds and other internal shading devices are not permitted to be included in the overheating assessments therefore these were omitted in the analyses.

4.3 Ventilation Strategy

4.3.1 Mechanical Ventilation

The ventilation strategy comprises mechanical ventilation with heat recovery (MVHR). Table 4 below displays the baseline ventilation air flow rates assigned in the thermal model for each block. The baseline mechanical air flow rates are on continuously as background ventilation. Heat recovery has been bypassed for this assessment.

For bedrooms and studios, the flow rate begins to increase when the indoor temperature reaches 22 °C, reaches half of the maximum flow rate at 24°C, and reaches the full flow rate at 26°C. Overnight, the night purge operates with a narrower band, beginning at 21.5 °C, rising to half of the maximum flow rate at 22°C, and reaching the full flow rate at 22.5 °C.

For living spaces during occupied hours, the flow rate uses the same 22-to-26-degree activation band as the bedrooms. Overnight, it begins at 20°C, increases to half of the maximum flow rate at 22°C, and reaches the full flow rate at 24°C.

Zone	Mechanical Ventilation Flow Rate (l/s)							
	1B: Supply	1B: Extract	2B: Supply	2B: Extract	3B: Supply	3B: Extract	4B: Supply	4B: Extract
Bedroom	8	-	16	-	24	-	32	-
KLD	13	13	13	13	13	13	13	13
Bathroom	-	8	-	16	-	12	-	32
Total (l/s)	21		29		37		45	

Table 4. Baseline Mechanical Air Flow Rates

Zone	Mechanical Ventilation Flow Rate (l/s)							
	1B: Supply	1B: Extract	2B: Supply	2B: Extract	3B: Supply	3B: Extract	4B: Supply	4B: Extract
Bedroom	21	-	26	-	36	-	36	-
KLD	34	34	29	29	19	19	19	19
Bathroom	-	21	-	26	-	36	-	36
Total (l/s)	55		55		55		55	

Table 5. Total Maximum Mechanical Air Flow Rates Block A

Zone	Mechanical Ventilation Flow Rate (l/s)							
	1B: Supply	1B: Extract	2B: Supply	2B: Extract	3B: Supply	3B: Extract	4B: Supply	4B: Extract
Bedroom	21	-	28	-	40.5	-	42	-
KLD	34	34	27	27	14.5	14.5	13	13
Bathroom	-	21	-	28	-	40.5	-	42
Total (l/s)	55		55		55		55	

Table 6. Total Maximum Mechanical Air Flow Rates Block B

4.3.2 Natural Ventilation

Apertures have been included for all bedrooms and kitchen/living rooms. The window opening types are illustrated by Figure 3 below. The window opening types for bedrooms and kitchen/living rooms compromise sliding doors, side hung doors and side hung windows which are not restricted. The free areas used in the model are consistent with those specified in the architect's document titled *"6595_No1. Castlefield_502_Purge Free Area Mark Up"*.




Figure 3. Bedroom and kitchen/living rooms apertures (Block A top / Block B bottom).

Openings start to open when occupied and the internal temperature reaches 22°C. As the temperature rises, they continue to open incrementally, until fully open at 26°C, as prescribed by Approved Document Part O.

When the internal temperature drops below 26°C, windows will start to close. As the temperature drops, the windows will gradually close until they are fully shut at 22°C.

4.3.3 Acoustic Considerations

The assessment assumes that no noise restrictions apply, with window operation available to support overheating control during occupied hours.

4.3.4 Internal Doors

Internal doors within apartments are included within the Part O assessment and are set to fully open during waking hours (7am – 11pm). Apartment main entrance doors to communal corridors are closed.

5.0 Results

The results of the overheating assessment indicate that all bedrooms and kitchen spaces in the 1 Castlefield residential development comply with the relevant overheating criteria.

Based on the inputs and assumptions detailed in this report, including the adopted ventilation strategy, glazing specifications, and internal gains, the simulated results demonstrate that all modelled spaces achieve compliance under the Approved Document Part O

assessment methodology. This confirms that, with the proposed design inputs, the development has an acceptable risk of overheating during typical summer conditions.

The complete set of zone-by-zone results is provided in Appendix 2-16.

Block	Weather File	Status	Compliance – CIBSE TM52 Criterion 1		Overall Result	Operative Temperature	Overall Result
			Bedrooms	Living		Bedrooms	
Block A	DSY1	Mandatory	✓	✓	Pass	✓	Pass
	DSY2	Advisory	✓	×	Fail	✓	Pass
	DSY3	Advisory	✓	×	Fail	×	Fail
Block B	DSY1	Mandatory	✓	✓	Pass	✓	Pass
	DSY2	Advisory	✓	✓	Pass	✓	Pass
	DSY3	Advisory	×	×	Fail	×	Fail

Table 7. Results Summary

The corridors, in all scenarios, are unlikely to have an unacceptable risk of overheating.

6.0 Appendix 1: CIBSE TM59 Prescribed Profiles

Number of people	Description	Peak Load (W) Sensible	Latent	Period 00–01	01–02	02–03	03-04	04-05	05-06	06-07	07-08	08-09	09-10	10-11	11-12	12-13	13-14	14-15	15-16	16-17	17-18	18-19	19-20	20-21	21-22	22-23	23-24
				Hour-ending 1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
1	Single bedroom occupancy	75	55	0.7	0.7	0.7	0.7	0.7	0.7	0.7	0.7	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.7
2	Double bedroom occupancy	150	110	0.7	0.7	0.7	0.7	0.7	0.7	0.7	0.7	1	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.7
2	Studio occupancy	150	110	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
1	1-bed: living/kitchen occupancy	75	55	0	0	0	0	0	0	0	0	0	1	1	1	1	1	1	1	1	1	1	1	1	1	0	0
1	1-bed: living occupancy	75	55	0	0	0	0	0	0	0	0	0	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0	0
1	1-bed: kitchen occupancy	75	55	0	0	0	0	0	0	0	0	0	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0	0
2	2-bed: living/kitchen occupancy	150	110	0	0	0	0	0	0	0	0	0	1	1	1	1	1	1	1	1	1	1	1	1	1	0	0
2	2-bed: living occupancy	150	110	0	0	0	0	0	0	0	0	0	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0	0
2	2-bed: kitchen occupancy	150	110	0	0	0	0	0	0	0	0	0	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0	0
3	3-bed: living/kitchen occupancy	225	165	0	0	0	0	0	0	0	0	0	1	1	1	1	1	1	1	1	1	1	1	1	1	0	0
3	3-bed: living occupacy	225	165	0	0	0	0	0	0	0	0	0	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0.75	0	0
3	3-bed: kitchen occupancy	225	165	0	0	0	0	0	0	0	0	0	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0.25	0	0
	Single bedroom equipment	80		0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.13
	Double bedroom equipment	80		0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.13	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0.13
	Studio equipment	450		0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.24	0.24	0.24	0.24	0.24	0.24	0.24	0.24	0.24	1	1	0.44	0.44	0.24	0.24
	Living/kitchen equipment	450		0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.19	0.24	0.24	0.24	0.24	0.24	0.24	0.24	0.24	0.24	1	1	0.44	0.44	0.24	0.24
	Living equipment	150		0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.23	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	0.4	1	1	1	1	0.4	0.4
	Kitchen equipment	300		0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	0.17	1	1	0.17	0.17	0.17	0.17
	Lighting profile	2	(W/m²)	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1	1	1	1	0

7.0 Appendix 1: DSY1: TM52 Criterion 1 Bedroom Block A

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.02.01.1B Bedroom	0.00
A.02.02.1B Bedroom	0.03
A.02.03.2B Bedroom	0.65
A.02.03.2B Bedroom	0.00
A.02.04.2B Bedroom	0.46
A.02.04.2B Bedroom	0.71
A.02.05.2B Bedroom	0.52
A.02.05.2B Bedroom	0.22
A.02.06.1B Bedroom	0.03
A.02.07.1B Bedroom	0.00
A.02.08.2B Bedroom	0.00
A.02.08.2B Bedroom	0.00
A.02.09.2B Bedroom	0.00
A.02.09.2B Bedroom	0.03
A.02.10.2B Bedroom	0.00
A.02.10.2B Bedroom	0.00
A.03.01.1B Bedroom	0.00
A.03.02.1B Bedroom	0.05
A.03.03.2B Bedroom	0.00
A.03.03.2B Bedroom	0.71
A.03.04.2B Bedroom	0.79
A.03.04.2B Bedroom	0.49
A.03.05.2B Bedroom	0.27
A.03.05.2B Bedroom	0.57
A.03.06.1B Bedroom	0.03
A.03.07.1B Bedroom	0.00
A.03.08.2B Bedroom	0.00
A.03.08.2B Bedroom	0.00
A.03.09.2B Bedroom	0.00
A.03.09.2B Bedroom	0.03
A.03.10.2B Bedroom	0.00
A.03.10.2B Bedroom	0.00
A.04.01.1B Bedroom	0.00
A.04.02.1B Bedroom	0.05
A.04.03.2B Bedroom	0.65
A.04.03.2B Bedroom	0.00
A.04.04.2B Bedroom	0.46
A.04.04.2B Bedroom	0.76
A.04.05.2B Bedroom	0.52
A.04.05.2B Bedroom	0.27
A.04.06.1B Bedroom	0.03
A.04.07.1B Bedroom	0.00
A.04.08.2B Bedroom	0.00
A.04.08.2B Bedroom	0.00
A.04.09.2B Bedroom	0.00
A.04.09.2B Bedroom	0.03
A.04.10.2B Bedroom	0.00
A.04.10.2B Bedroom	0.00
A.05.01.1B Bedroom	0.00
A.05.02.1B Bedroom	0.05

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.05.03.2B Bedroom	0.65
A.05.03.2B Bedroom	0.00
A.05.04.2B Bedroom	0.46
A.05.04.2B Bedroom	0.76
A.05.05.2B Bedroom	0.52
A.05.05.2B Bedroom	0.27
A.05.06.1B Bedroom	0.03
A.05.07.1B Bedroom	0.00
A.05.08.2B Bedroom	0.00
A.05.08.2B Bedroom	0.00
A.05.09.2B Bedroom	0.03
A.05.09.2B Bedroom	0.00
A.05.10.2B Bedroom	0.00
A.05.10.2B Bedroom	0.00
A.06.01.1B Bedroom	0.00
A.06.02.1B Bedroom	0.05
A.06.03.2B Bedroom	0.65
A.06.03.2B Bedroom	0.00
A.06.04.2B Bedroom	0.46
A.06.04.2B Bedroom	0.76
A.06.05.2B Bedroom	0.52
A.06.05.2B Bedroom	0.27
A.06.06.1B Bedroom	0.03
A.06.07.1B Bedroom	0.00
A.06.08.2B Bedroom	0.00
A.06.08.2B Bedroom	0.00
A.06.09.2B Bedroom	0.03

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.06.09.2B Bedroom	0.00
A.06.10.2B Bedroom	0.00
A.06.10.2B Bedroom	0.00
A.07.01.1B Bedroom	0.00
A.07.02.1B Bedroom	0.08
A.07.03.2B Bedroom	0.00
A.07.03.2B Bedroom	0.65
A.07.04.2B Bedroom	0.76
A.07.04.2B Bedroom	0.46
A.07.05.2B Bedroom	0.52
A.07.05.2B Bedroom	0.27
A.07.06.1B Bedroom	0.03
A.07.07.1B Bedroom	0.00
A.07.08.2B Bedroom	0.00
A.07.08.2B Bedroom	0.00
A.07.09.2B Bedroom	0.03
A.07.09.2B Bedroom	0.00
A.07.10.2B Bedroom	0.00
A.07.10.2B Bedroom	0.00
A.08.01.1B Bedroom	0.00
A.08.02.1B Bedroom	0.08
A.08.03.2B Bedroom	0.65
A.08.03.2B Bedroom	0.00
A.08.04.2B Bedroom	0.46
A.08.04.2B Bedroom	0.76
A.08.05.2B Bedroom	0.30
A.08.05.2B Bedroom	0.52

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.08.06.1B Bedroom	0.03
A.08.07.1B Bedroom	0.00
A.08.08.2B Bedroom	0.00
A.08.08.2B Bedroom	0.00
A.08.09.2B Bedroom	0.03
A.08.09.2B Bedroom	0.00
A.08.10.2B Bedroom	0.00
A.08.10.2B Bedroom	0.00
A.09.01.1B Bedroom	0.00
A.09.02.1B Bedroom	0.08
A.09.03.2B Bedroom	0.00
A.09.03.2B Bedroom	0.65
A.09.04.2B Bedroom	0.76
A.09.04.2B Bedroom	0.46
A.09.05.2B Bedroom	0.52
A.09.05.2B Bedroom	0.30
A.09.06.1B Bedroom	0.03
A.09.07.1B Bedroom	0.00
A.09.08.2B Bedroom	0.00
A.09.08.2B Bedroom	0.00
A.09.09.2B Bedroom	0.03
A.09.09.2B Bedroom	0.00
A.09.10.2B Bedroom	0.00
A.09.10.2B Bedroom	0.00
A.10.01.1B Bedroom	0.00
A.10.02.1B Bedroom	0.08
A.10.03.2B Bedroom	0.65

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.10.03.2B Bedroom	0.00
A.10.04.2B Bedroom	0.76
A.10.04.2B Bedroom	0.46
A.10.05.2B Bedroom	0.27
A.10.05.2B Bedroom	0.52
A.10.06.1B Bedroom	0.03
A.10.07.1B Bedroom	0.00
A.10.08.2B Bedroom	0.00
A.10.08.2B Bedroom	0.00
A.10.09.2B Bedroom	0.00
A.10.09.2B Bedroom	0.03
A.10.10.2B Bedroom	0.00
A.10.10.2B Bedroom	0.00
A.11.01.1B Bedroom	0.00
A.11.02.1B Bedroom	0.08
A.11.03.2B Bedroom	0.71
A.11.03.2B Bedroom	0.00
A.11.04.2B Bedroom	0.76
A.11.04.2B Bedroom	0.46
A.11.05.2B Bedroom	0.27
A.11.05.2B Bedroom	0.52
A.11.06.1B Bedroom	0.03
A.11.07.1B Bedroom	0.00
A.11.08.2B Bedroom	0.00
A.11.08.2B Bedroom	0.00
A.11.09.2B Bedroom	0.03
A.11.09.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.11.10.2B Bedroom	0.00
A.11.10.2B Bedroom	0.00
A.12.01.1B Bedroom	0.00
A.12.02.1B Bedroom	0.05
A.12.03.2B Bedroom	0.71
A.12.03.2B Bedroom	0.00
A.12.04.2B Bedroom	0.79
A.12.04.2B Bedroom	0.46
A.12.05.2B Bedroom	0.25
A.12.05.2B Bedroom	0.46
A.12.06.1B Bedroom	0.00
A.12.07.1B Bedroom	0.00
A.12.08.2B Bedroom	0.00
A.12.08.2B Bedroom	0.00
A.12.09.2B Bedroom	0.00
A.12.09.2B Bedroom	0.00
A.12.10.2B Bedroom	0.00
A.12.10.2B Bedroom	0.00
A.13.01.1B Bedroom	0.30
A.13.02.1B Bedroom	0.14
A.13.03.2B Bedroom	0.25
A.13.03.2B Bedroom	0.76
A.13.05.2B Bedroom	0.49
A.13.05.2B Bedroom	0.30
A.13.06.1B Bedroom	0.00
A.13.07.1B Bedroom	0.00
A.13.08.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.13.08.2B Bedroom	0.00
A.13.09.2B Bedroom	0.00
A.13.09.2B Bedroom	0.00
A.13.10.2B Bedroom	0.00
A.13.10.2B Bedroom	0.00
A.13.13.2B Bedroom	1.09
A.13.13.2B Bedroom	0.54
A.14.01.1B Bedroom	0.00
A.14.02.1B Bedroom	0.03
A.14.03.2B Bedroom	0.00
A.14.03.2B Bedroom	0.65
A.14.04.2B Bedroom	0.76
A.14.04.2B Bedroom	0.44
A.14.05.2B Bedroom	0.25
A.14.05.2B Bedroom	0.41
A.14.06.1B Bedroom	0.00
A.14.07.1B Bedroom	0.00
A.14.08.2B Bedroom	0.00
A.14.08.2B Bedroom	0.00
A.14.09.2B Bedroom	0.00
A.14.09.2B Bedroom	0.00
A.14.10.2B Bedroom	0.00
A.14.10.2B Bedroom	0.00
A.15.01.1B Bedroom	0.00
A.15.02.1B Bedroom	0.03
A.15.03.2B Bedroom	0.00
A.15.03.2B Bedroom	0.63

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.15.04.2B Bedroom	0.68
A.15.04.2B Bedroom	0.44
A.15.05.2B Bedroom	0.41
A.15.05.2B Bedroom	0.22
A.15.06.1B Bedroom	0.00
A.15.07.1B Bedroom	0.00
A.15.08.2B Bedroom	0.00
A.15.08.2B Bedroom	0.00
A.15.09.2B Bedroom	0.00
A.15.09.2B Bedroom	0.00
A.15.10.2B Bedroom	0.00
A.15.10.2B Bedroom	0.00
A.16.01.1B Bedroom	0.00
A.16.02.1B Bedroom	0.03
A.16.03.2B Bedroom	0.54
A.16.03.2B Bedroom	0.00
A.16.04.2B Bedroom	0.65
A.16.04.2B Bedroom	0.44
A.16.05.2B Bedroom	0.44
A.16.05.2B Bedroom	0.25
A.16.06.1B Bedroom	0.00
A.16.07.1B Bedroom	0.00
A.16.08.2B Bedroom	0.00
A.16.08.2B Bedroom	0.00
A.16.09.2B Bedroom	0.00
A.16.09.2B Bedroom	0.00
A.16.10.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.16.10.2B Bedroom	0.00
A.17.01.1B Bedroom	0.00
A.17.02.1B Bedroom	0.00
A.17.03.2B Bedroom	0.00
A.17.03.2B Bedroom	0.00
A.17.04.2B Bedroom	0.00
A.17.04.2B Bedroom	0.00
A.17.05.2B Bedroom	0.00
A.17.05.2B Bedroom	0.00
A.17.06.1B Bedroom	0.00
A.17.07.1B Bedroom	0.00
A.17.08.2B Bedroom	0.00
A.17.08.2B Bedroom	0.00
A.17.09.2B Bedroom	0.00
A.17.09.2B Bedroom	0.00
A.17.10.2B Bedroom	0.00
A.17.10.2B Bedroom	0.00
A.18.01.1B Bedroom	0.00
A.18.02.1B Bedroom	0.00
A.18.03.2B Bedroom	0.00
A.18.03.2B Bedroom	0.00
A.18.04.2B Bedroom	0.00
A.18.04.2B Bedroom	0.00
A.18.05.2B Bedroom	0.00
A.18.05.2B Bedroom	0.00
A.18.06.1B Bedroom	0.00
A.18.07.1B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.18.08.2B Bedroom	0.00
A.18.08.2B Bedroom	0.00
A.18.09.2B Bedroom	0.00
A.18.09.2B Bedroom	0.00
A.18.10.2B Bedroom	0.00
A.18.10.2B Bedroom	0.00
A.19.01.1B Bedroom	0.00
A.19.02.1B Bedroom	0.00
A.19.03.2B Bedroom	0.00
A.19.03.2B Bedroom	0.00
A.19.04.2B Bedroom	0.00
A.19.04.2B Bedroom	0.00
A.19.05.2B Bedroom	0.00
A.19.05.2B Bedroom	0.00
A.19.06.1B Bedroom	0.00
A.19.07.1B Bedroom	0.00
A.19.08.2B Bedroom	0.00
A.19.08.2B Bedroom	0.00
A.19.09.2B Bedroom	0.00
A.19.09.2B Bedroom	0.00
A.19.10.2B Bedroom	0.00
A.19.10.2B Bedroom	0.00
A.20.01.1B Bedroom	0.00
A.20.02.1B Bedroom	0.00
A.20.03.2B Bedroom	0.00
A.20.03.2B Bedroom	0.00
A.20.04.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.20.04.2B Bedroom	0.00
A.20.05.2B Bedroom	0.00
A.20.05.2B Bedroom	0.00
A.20.06.1B Bedroom	0.00
A.20.07.1B Bedroom	0.00
A.20.08.2B Bedroom	0.00
A.20.08.2B Bedroom	0.00
A.20.09.2B Bedroom	0.00
A.20.09.2B Bedroom	0.00
A.20.10.2B Bedroom	0.00
A.20.10.2B Bedroom	0.00
A.21.01.1B Bedroom	0.00
A.21.02.1B Bedroom	0.00
A.21.03.2B Bedroom	0.00
A.21.03.2B Bedroom	0.00
A.21.04.2B Bedroom	0.00
A.21.04.2B Bedroom	0.00
A.21.05.2B Bedroom	0.03
A.21.05.2B Bedroom	0.00
A.21.06.1B Bedroom	0.00
A.21.07.1B Bedroom	0.00
A.21.08.2B Bedroom	0.00
A.21.08.2B Bedroom	0.00
A.21.09.2B Bedroom	0.00
A.21.09.2B Bedroom	0.00
A.21.10.2B Bedroom	0.00
A.21.10.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.22.01.1B Bedroom	0.00
A.22.02.1B Bedroom	0.03
A.22.03.2B Bedroom	0.00
A.22.03.2B Bedroom	0.00
A.22.04.2B Bedroom	0.00
A.22.04.2B Bedroom	0.00
A.22.05.2B Bedroom	0.00
A.22.05.2B Bedroom	0.03
A.22.06.1B Bedroom	0.00
A.22.07.1B Bedroom	0.00
A.22.08.2B Bedroom	0.00
A.22.08.2B Bedroom	0.00
A.22.09.2B Bedroom	0.00
A.22.09.2B Bedroom	0.00
A.22.10.2B Bedroom	0.00
A.22.10.2B Bedroom	0.00
A.23.01.1B Bedroom	0.00
A.23.02.1B Bedroom	0.00
A.23.03.2B Bedroom	0.00
A.23.03.2B Bedroom	0.00
A.23.04.2B Bedroom	0.00
A.23.04.2B Bedroom	0.00
A.23.05.2B Bedroom	0.00
A.23.05.2B Bedroom	0.00
A.23.06.1B Bedroom	0.00
A.23.07.1B Bedroom	0.00
A.23.08.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.23.08.2B Bedroom	0.00
A.23.09.2B Bedroom	0.00
A.23.09.2B Bedroom	0.00
A.23.10.2B Bedroom	0.00
A.23.10.2B Bedroom	0.00
A.24.01.1B Bedroom	0.00
A.24.02.1B Bedroom	0.00
A.24.03.2B Bedroom	0.00
A.24.03.2B Bedroom	0.00
A.24.04.2B Bedroom	0.00
A.24.04.2B Bedroom	0.00
A.24.05.2B Bedroom	0.00
A.24.05.2B Bedroom	0.00
A.24.06.1B Bedroom	0.00
A.24.07.1B Bedroom	0.00
A.24.08.2B Bedroom	0.00
A.24.08.2B Bedroom	0.00
A.24.09.2B Bedroom	0.00
A.24.09.2B Bedroom	0.00
A.24.10.2B Bedroom	0.00
A.24.10.2B Bedroom	0.00
A.25.01.1B Bedroom	0.00
A.25.02.1B Bedroom	0.00
A.25.03.2B Bedroom	0.00
A.25.03.2B Bedroom	0.00
A.25.04.2B Bedroom	0.00
A.25.04.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.25.05.2B Bedroom	0.00
A.25.05.2B Bedroom	0.03
A.25.06.1B Bedroom	0.00
A.25.07.1B Bedroom	0.00
A.25.08.2B Bedroom	0.00
A.25.08.2B Bedroom	0.00
A.25.09.2B Bedroom	0.00
A.25.09.2B Bedroom	0.00
A.25.10.2B Bedroom	0.00
A.25.10.2B Bedroom	0.00
A.26.01.1B Bedroom	0.00
A.26.02.1B Bedroom	0.03
A.26.03.2B Bedroom	0.00
A.26.03.2B Bedroom	0.00
A.26.04.2B Bedroom	0.00
A.26.04.2B Bedroom	0.00
A.26.05.2B Bedroom	0.03
A.26.05.2B Bedroom	0.00
A.26.06.1B Bedroom	0.00
A.26.07.1B Bedroom	0.00
A.26.08.2B Bedroom	0.00
A.26.08.2B Bedroom	0.00
A.26.09.2B Bedroom	0.00
A.26.09.2B Bedroom	0.00
A.26.10.2B Bedroom	0.00
A.26.10.2B Bedroom	0.00
A.27.01.1B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.27.02.1B Bedroom	0.00
A.27.03.2B Bedroom	0.00
A.27.03.2B Bedroom	0.00
A.27.04.2B Bedroom	0.00
A.27.04.2B Bedroom	0.00
A.27.05.2B Bedroom	0.00
A.27.05.2B Bedroom	0.00
A.27.06.1B Bedroom	0.00
A.27.07.1B Bedroom	0.00
A.27.08.2B Bedroom	0.00
A.27.08.2B Bedroom	0.00
A.27.09.2B Bedroom	0.00
A.27.09.2B Bedroom	0.00
A.27.10.2B Bedroom	0.00
A.27.10.2B Bedroom	0.00
A.28.01.1B Bedroom	0.00
A.28.02.1B Bedroom	0.00
A.28.03.2B Bedroom	0.00
A.28.03.2B Bedroom	0.00
A.28.04.2B Bedroom	0.00
A.28.04.2B Bedroom	0.00
A.28.05.2B Bedroom	0.00
A.28.05.2B Bedroom	0.00
A.28.06.1B Bedroom	0.00
A.28.07.1B Bedroom	0.00
A.28.08.2B Bedroom	0.00
A.28.08.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.28.09.2B Bedroom	0.00
A.28.09.2B Bedroom	0.00
A.28.10.2B Bedroom	0.00
A.28.10.2B Bedroom	0.00
A.29.01.1B Bedroom	0.00
A.29.02.1B Bedroom	0.00
A.29.03.2B Bedroom	0.00
A.29.03.2B Bedroom	0.00
A.29.04.2B Bedroom	0.00
A.29.04.2B Bedroom	0.00
A.29.05.2B Bedroom	0.00
A.29.05.2B Bedroom	0.00
A.29.06.1B Bedroom	0.00
A.29.07.1B Bedroom	0.00
A.29.08.2B Bedroom	0.00
A.29.08.2B Bedroom	0.00
A.29.09.2B Bedroom	0.00
A.29.09.2B Bedroom	0.00
A.29.10.2B Bedroom	0.00
A.29.10.2B Bedroom	0.00
A.30.01.1B Bedroom	0.00
A.30.02.1B Bedroom	0.00
A.30.03.2B Bedroom	0.00
A.30.03.2B Bedroom	0.00
A.30.04.2B Bedroom	0.00
A.30.04.2B Bedroom	0.00
A.30.05.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.30.05.2B Bedroom	0.00
A.30.06.1B Bedroom	0.00
A.30.07.1B Bedroom	0.00
A.30.08.2B Bedroom	0.00
A.30.08.2B Bedroom	0.00
A.30.09.2B Bedroom	0.00
A.30.09.2B Bedroom	0.00
A.30.10.2B Bedroom	0.00
A.30.10.2B Bedroom	0.00
A.31.01.1B Bedroom	0.00
A.31.02.1B Bedroom	0.00
A.31.03.2B Bedroom	0.00
A.31.03.2B Bedroom	0.00
A.31.04.2B Bedroom	0.00
A.31.04.2B Bedroom	0.00
A.31.05.2B Bedroom	0.03
A.31.05.2B Bedroom	0.00
A.31.06.1B Bedroom	0.00
A.31.07.1B Bedroom	0.00
A.31.08.2B Bedroom	0.00
A.31.08.2B Bedroom	0.00
A.31.09.2B Bedroom	0.00
A.31.09.2B Bedroom	0.00
A.31.10.2B Bedroom	0.00
A.31.10.2B Bedroom	0.00
A.32.01.1B Bedroom	0.00
A.32.02.1B Bedroom	0.03

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.32.03.2B Bedroom	0.00
A.32.03.2B Bedroom	0.00
A.32.04.2B Bedroom	0.00
A.32.04.2B Bedroom	0.00
A.32.05.2B Bedroom	0.00
A.32.05.2B Bedroom	0.03
A.32.06.1B Bedroom	0.00
A.32.07.1B Bedroom	0.00
A.32.08.2B Bedroom	0.00
A.32.08.2B Bedroom	0.00
A.32.09.2B Bedroom	0.00
A.32.09.2B Bedroom	0.00
A.32.10.2B Bedroom	0.00
A.32.10.2B Bedroom	0.00
A.33.01.1B Bedroom	0.00
A.33.02.1B Bedroom	0.00
A.33.03.2B Bedroom	0.00
A.33.03.2B Bedroom	0.00
A.33.04.2B Bedroom	0.00
A.33.04.2B Bedroom	0.00
A.33.05.2B Bedroom	0.00
A.33.05.2B Bedroom	0.00
A.33.06.1B Bedroom	0.00
A.33.07.1B Bedroom	0.00
A.33.08.2B Bedroom	0.00
A.33.08.2B Bedroom	0.00
A.33.09.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.33.09.2B Bedroom	0.00
A.33.10.2B Bedroom	0.00
A.33.10.2B Bedroom	0.00
A.34.01.1B Bedroom	0.00
A.34.02.1B Bedroom	0.00
A.34.03.2B Bedroom	0.00
A.34.03.2B Bedroom	0.00
A.34.04.2B Bedroom	0.00
A.34.04.2B Bedroom	0.00
A.34.05.2B Bedroom	0.00
A.34.05.2B Bedroom	0.00
A.34.06.1B Bedroom	0.00
A.34.07.1B Bedroom	0.00
A.34.08.2B Bedroom	0.00
A.34.08.2B Bedroom	0.00
A.34.09.2B Bedroom	0.00
A.34.09.2B Bedroom	0.00
A.34.10.2B Bedroom	0.00
A.34.10.2B Bedroom	0.00
A.35.01.1B Bedroom	0.00
A.35.02.1B Bedroom	0.00
A.35.03.2B Bedroom	0.00
A.35.03.2B Bedroom	0.00
A.35.04.2B Bedroom	0.00
A.35.04.2B Bedroom	0.00
A.35.05.2B Bedroom	0.00
A.35.05.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.35.06.1B Bedroom	0.00
A.35.07.1B Bedroom	0.00
A.35.08.2B Bedroom	0.00
A.35.08.2B Bedroom	0.00
A.35.09.2B Bedroom	0.00
A.35.09.2B Bedroom	0.00
A.35.10.2B Bedroom	0.00
A.35.10.2B Bedroom	0.00
A.36.01.1B Bedroom	0.00
A.36.02.1B Bedroom	0.03
A.36.03.2B Bedroom	0.00
A.36.03.2B Bedroom	0.00
A.36.04.2B Bedroom	0.00
A.36.04.2B Bedroom	0.00
A.36.05.2B Bedroom	0.00
A.36.05.2B Bedroom	0.03
A.36.06.1B Bedroom	0.00
A.36.07.1B Bedroom	0.00
A.36.08.2B Bedroom	0.00
A.36.08.2B Bedroom	0.00
A.36.09.2B Bedroom	0.00
A.36.09.2B Bedroom	0.00
A.36.10.2B Bedroom	0.00
A.36.10.2B Bedroom	0.00
A.37.01.1B Bedroom	0.00
A.37.02.1B Bedroom	0.00
A.37.03.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.37.03.2B Bedroom	0.00
A.37.04.2B Bedroom	0.00
A.37.04.2B Bedroom	0.00
A.37.05.2B Bedroom	0.03
A.37.05.2B Bedroom	0.00
A.37.06.1B Bedroom	0.00
A.37.07.1B Bedroom	0.00
A.37.08.2B Bedroom	0.00
A.37.08.2B Bedroom	0.00
A.37.09.2B Bedroom	0.00
A.37.09.2B Bedroom	0.00
A.37.10.2B Bedroom	0.00
A.37.10.2B Bedroom	0.00
A.38.01.1B Bedroom	0.00
A.38.02.1B Bedroom	0.03
A.38.03.2B Bedroom	0.00
A.38.03.2B Bedroom	0.00
A.38.04.2B Bedroom	0.00
A.38.04.2B Bedroom	0.00
A.38.05.2B Bedroom	0.03
A.38.05.2B Bedroom	0.00
A.38.06.1B Bedroom	0.00
A.38.07.1B Bedroom	0.00
A.38.08.2B Bedroom	0.00
A.38.08.2B Bedroom	0.00
A.38.09.2B Bedroom	0.00
A.38.09.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.38.10.2B Bedroom	0.00
A.38.10.2B Bedroom	0.00
A.39.01.1B Bedroom	0.00
A.39.02.1B Bedroom	0.03
A.39.03.2B Bedroom	0.00
A.39.03.2B Bedroom	0.00
A.39.04.2B Bedroom	0.00
A.39.04.2B Bedroom	0.00
A.39.05.2B Bedroom	0.00
A.39.05.2B Bedroom	0.00
A.39.06.1B Bedroom	0.00
A.39.07.1B Bedroom	0.00
A.39.08.2B Bedroom	0.00
A.39.08.2B Bedroom	0.00
A.39.09.2B Bedroom	0.00
A.39.09.2B Bedroom	0.00
A.39.10.2B Bedroom	0.00
A.39.10.2B Bedroom	0.00
A.40.01.1B Bedroom	0.00
A.40.02.1B Bedroom	0.00
A.40.03.2B Bedroom	0.00
A.40.03.2B Bedroom	0.00
A.40.04.2B Bedroom	0.00
A.40.04.2B Bedroom	0.00
A.40.05.2B Bedroom	0.00
A.40.05.2B Bedroom	0.00
A.40.06.1B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.40.07.1B Bedroom	0.00
A.40.08.2B Bedroom	0.00
A.40.08.2B Bedroom	0.00
A.40.09.2B Bedroom	0.00
A.40.09.2B Bedroom	0.00
A.40.10.2B Bedroom	0.00
A.40.10.2B Bedroom	0.00
A.41.01.1B Bedroom	0.00
A.41.02.1B Bedroom	0.00
A.41.03.2B Bedroom	0.00
A.41.03.2B Bedroom	0.00
A.41.04.2B Bedroom	0.00
A.41.04.2B Bedroom	0.00
A.41.05.2B Bedroom	0.03
A.41.05.2B Bedroom	0.00
A.41.06.1B Bedroom	0.00
A.41.07.1B Bedroom	0.00
A.41.08.2B Bedroom	0.00
A.41.08.2B Bedroom	0.00
A.41.09.2B Bedroom	0.00
A.41.09.2B Bedroom	0.00
A.41.10.2B Bedroom	0.00
A.41.10.2B Bedroom	0.00
A.42.01.1B Bedroom	0.00
A.42.02.1B Bedroom	0.03
A.42.03.2B Bedroom	0.00
A.42.03.2B Bedroom	0.05

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.42.04.2B Bedroom	0.00
A.42.04.2B Bedroom	0.00
A.42.05.2B Bedroom	0.03
A.42.05.2B Bedroom	0.00
A.42.06.1B Bedroom	0.00
A.42.07.1B Bedroom	0.00
A.42.08.2B Bedroom	0.00
A.42.08.2B Bedroom	0.00
A.42.09.2B Bedroom	0.00
A.42.09.2B Bedroom	0.00
A.42.10.2B Bedroom	0.00
A.42.10.2B Bedroom	0.00
A.43.01.1B Bedroom	0.00
A.43.02.1B Bedroom	0.03
A.43.03.2B Bedroom	0.00
A.43.03.2B Bedroom	0.00
A.43.04.2B Bedroom	0.00
A.43.04.2B Bedroom	0.00
A.43.05.2B Bedroom	0.00
A.43.05.2B Bedroom	0.03
A.43.06.1B Bedroom	0.00
A.43.07.1B Bedroom	0.00
A.43.08.2B Bedroom	0.00
A.43.08.2B Bedroom	0.00
A.43.09.2B Bedroom	0.00
A.43.09.2B Bedroom	0.00
A.43.10.2B Bedroom	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.43.10.2B Bedroom	0.00
A.44.01.1B Bedroom	0.00
A.44.02.1B Bedroom	0.00
A.44.03.2B Bedroom	0.03
A.44.03.2B Bedroom	0.00
A.44.04.2B Bedroom	0.00
A.44.04.2B Bedroom	0.00
A.44.05.2B Bedroom	0.00
A.44.05.2B Bedroom	0.00
A.44.06.1B Bedroom	0.00
A.44.07.1B Bedroom	0.00
A.44.08.2B Bedroom	0.00
A.44.08.2B Bedroom	0.00
A.44.09.2B Bedroom	0.00
A.44.09.2B Bedroom	0.00
A.44.10.2B Bedroom	0.00
A.44.10.2B Bedroom	0.00
A.45.01.3B Bedroom	0.00
A.45.01.3B Bedroom	0.00
A.45.01.3B Bedroom	0.16
A.45.02.3B Bedroom	0.00
A.45.02.3B Bedroom	0.00
A.45.02.3B Bedroom	0.00
A.45.03.3B Bedroom	0.00
A.45.03.3B Bedroom	0.00
A.45.03.3B Bedroom	0.00
A.45.04.3B Bedroom	0.03

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.45.04.3B Bedroom	0.00
A.45.04.3B Bedroom	0.00
A.45.05.3B Bedroom	0.00
A.45.05.3B Bedroom	0.00
A.45.05.3B Bedroom	0.00
A.45.06.3B Bedroom	0.00
A.45.06.3B Bedroom	0.00
A.45.06.3B Bedroom	0.00

8.0 Appendix 2: DSY 1: Bedroom Night-time Temperature Test Block A

Location	Operative Temperature > 26 (Max 1%)
A.02.01.1B Bedroom	0.57
A.02.02.1B Bedroom	0.05
A.02.03.2B Bedroom	0.05
A.02.03.2B Bedroom	0.08
A.02.04.2B Bedroom	0.11
A.02.04.2B Bedroom	0.11
A.02.05.2B Bedroom	0.08
A.02.05.2B Bedroom	0.05
A.02.06.1B Bedroom	0.05
A.02.07.1B Bedroom	0.11
A.02.08.2B Bedroom	0.08
A.02.08.2B Bedroom	0.11
A.02.09.2B Bedroom	0.03
A.02.09.2B Bedroom	0.05
A.02.10.2B Bedroom	0.08
A.02.10.2B Bedroom	0.08
A.03.01.1B Bedroom	0.11
A.03.02.1B Bedroom	0.05
A.03.03.2B Bedroom	0.11
A.03.03.2B Bedroom	0.08
A.03.04.2B Bedroom	0.11
A.03.04.2B Bedroom	0.16
A.03.05.2B Bedroom	0.11
A.03.05.2B Bedroom	0.14
A.03.06.1B Bedroom	0.05
A.03.07.1B Bedroom	0.11
A.03.08.2B Bedroom	0.08
A.03.08.2B Bedroom	0.14
A.03.09.2B Bedroom	0.03
A.03.09.2B Bedroom	0.05
A.03.10.2B Bedroom	0.11
A.03.10.2B Bedroom	0.11
A.04.01.1B Bedroom	0.11
A.04.02.1B Bedroom	0.08
A.04.03.2B Bedroom	0.08
A.04.03.2B Bedroom	0.11
A.04.04.2B Bedroom	0.14
A.04.04.2B Bedroom	0.08
A.04.05.2B Bedroom	0.11
A.04.05.2B Bedroom	0.08
A.04.06.1B Bedroom	0.05
A.04.07.1B Bedroom	0.11
A.04.08.2B Bedroom	0.08
A.04.08.2B Bedroom	0.14
A.04.09.2B Bedroom	0.03
A.04.09.2B Bedroom	0.05
A.04.10.2B Bedroom	0.11
A.04.10.2B Bedroom	0.14
A.05.01.1B Bedroom	0.11

Location	Operative Temperature > 26 (Max 1%)
A.05.02.1B Bedroom	0.08
A.05.03.2B Bedroom	0.08
A.05.03.2B Bedroom	0.11
A.05.04.2B Bedroom	0.14
A.05.04.2B Bedroom	0.08
A.05.05.2B Bedroom	0.11
A.05.05.2B Bedroom	0.08
A.05.06.1B Bedroom	0.05
A.05.07.1B Bedroom	0.11
A.05.08.2B Bedroom	0.08
A.05.08.2B Bedroom	0.14
A.05.09.2B Bedroom	0.05
A.05.09.2B Bedroom	0.03
A.05.10.2B Bedroom	0.11
A.05.10.2B Bedroom	0.14
A.06.01.1B Bedroom	0.11
A.06.02.1B Bedroom	0.08
A.06.03.2B Bedroom	0.08
A.06.03.2B Bedroom	0.11
A.06.04.2B Bedroom	0.14
A.06.04.2B Bedroom	0.08
A.06.05.2B Bedroom	0.11
A.06.05.2B Bedroom	0.08
A.06.06.1B Bedroom	0.05
A.06.07.1B Bedroom	0.11
A.06.08.2B Bedroom	0.14
A.06.08.2B Bedroom	0.08

Location	Operative Temperature > 26 (Max 1%)
A.06.09.2B Bedroom	0.05
A.06.09.2B Bedroom	0.03
A.06.10.2B Bedroom	0.14
A.06.10.2B Bedroom	0.11
A.07.01.1B Bedroom	0.11
A.07.02.1B Bedroom	0.08
A.07.03.2B Bedroom	0.11
A.07.03.2B Bedroom	0.08
A.07.04.2B Bedroom	0.08
A.07.04.2B Bedroom	0.14
A.07.05.2B Bedroom	0.11
A.07.05.2B Bedroom	0.08
A.07.06.1B Bedroom	0.05
A.07.07.1B Bedroom	0.11
A.07.08.2B Bedroom	0.08
A.07.08.2B Bedroom	0.14
A.07.09.2B Bedroom	0.05
A.07.09.2B Bedroom	0.03
A.07.10.2B Bedroom	0.14
A.07.10.2B Bedroom	0.11
A.08.01.1B Bedroom	0.11
A.08.02.1B Bedroom	0.08
A.08.03.2B Bedroom	0.08
A.08.03.2B Bedroom	0.11
A.08.04.2B Bedroom	0.14
A.08.04.2B Bedroom	0.08
A.08.05.2B Bedroom	0.08

Location	Operative Temperature > 26 (Max 1%)
A.08.05.2B Bedroom	0.11
A.08.06.1B Bedroom	0.05
A.08.07.1B Bedroom	0.11
A.08.08.2B Bedroom	0.08
A.08.08.2B Bedroom	0.14
A.08.09.2B Bedroom	0.05
A.08.09.2B Bedroom	0.03
A.08.10.2B Bedroom	0.14
A.08.10.2B Bedroom	0.11
A.09.01.1B Bedroom	0.11
A.09.02.1B Bedroom	0.08
A.09.03.2B Bedroom	0.11
A.09.03.2B Bedroom	0.08
A.09.04.2B Bedroom	0.08
A.09.04.2B Bedroom	0.14
A.09.05.2B Bedroom	0.11
A.09.05.2B Bedroom	0.08
A.09.06.1B Bedroom	0.05
A.09.07.1B Bedroom	0.11
A.09.08.2B Bedroom	0.08
A.09.08.2B Bedroom	0.14
A.09.09.2B Bedroom	0.05
A.09.09.2B Bedroom	0.03
A.09.10.2B Bedroom	0.11
A.09.10.2B Bedroom	0.14
A.10.01.1B Bedroom	0.11
A.10.02.1B Bedroom	0.08

Location	Operative Temperature > 26 (Max 1%)
A.10.03.2B Bedroom	0.08
A.10.03.2B Bedroom	0.11
A.10.04.2B Bedroom	0.08
A.10.04.2B Bedroom	0.14
A.10.05.2B Bedroom	0.08
A.10.05.2B Bedroom	0.11
A.10.06.1B Bedroom	0.05
A.10.07.1B Bedroom	0.11
A.10.08.2B Bedroom	0.11
A.10.08.2B Bedroom	0.08
A.10.09.2B Bedroom	0.03
A.10.09.2B Bedroom	0.05
A.10.10.2B Bedroom	0.08
A.10.10.2B Bedroom	0.08
A.11.01.1B Bedroom	0.11
A.11.02.1B Bedroom	0.08
A.11.03.2B Bedroom	0.08
A.11.03.2B Bedroom	0.11
A.11.04.2B Bedroom	0.08
A.11.04.2B Bedroom	0.11
A.11.05.2B Bedroom	0.08
A.11.05.2B Bedroom	0.11
A.11.06.1B Bedroom	0.05
A.11.07.1B Bedroom	0.11
A.11.08.2B Bedroom	0.08
A.11.08.2B Bedroom	0.11
A.11.09.2B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.11.09.2B Bedroom	0.03
A.11.10.2B Bedroom	0.08
A.11.10.2B Bedroom	0.08
A.12.01.1B Bedroom	0.14
A.12.02.1B Bedroom	0.08
A.12.03.2B Bedroom	0.08
A.12.03.2B Bedroom	0.11
A.12.04.2B Bedroom	0.08
A.12.04.2B Bedroom	0.14
A.12.05.2B Bedroom	0.08
A.12.05.2B Bedroom	0.11
A.12.06.1B Bedroom	0.05
A.12.07.1B Bedroom	0.11
A.12.08.2B Bedroom	0.11
A.12.08.2B Bedroom	0.08
A.12.09.2B Bedroom	0.05
A.12.09.2B Bedroom	0.03
A.12.10.2B Bedroom	0.08
A.12.10.2B Bedroom	0.08
A.13.01.1B Bedroom	0.14
A.13.02.1B Bedroom	0.16
A.13.03.2B Bedroom	0.19
A.13.03.2B Bedroom	0.08
A.13.05.2B Bedroom	0.14
A.13.05.2B Bedroom	0.14
A.13.06.1B Bedroom	0.11
A.13.07.1B Bedroom	0.14

Location	Operative Temperature > 26 (Max 1%)
A.13.08.2B Bedroom	0.14
A.13.08.2B Bedroom	0.08
A.13.09.2B Bedroom	0.11
A.13.09.2B Bedroom	0.08
A.13.10.2B Bedroom	0.14
A.13.10.2B Bedroom	0.14
A.13.13.2B Bedroom	0.19
A.13.13.2B Bedroom	0.25
A.14.01.1B Bedroom	0.11
A.14.02.1B Bedroom	0.08
A.14.03.2B Bedroom	0.11
A.14.03.2B Bedroom	0.08
A.14.04.2B Bedroom	0.08
A.14.04.2B Bedroom	0.11
A.14.05.2B Bedroom	0.08
A.14.05.2B Bedroom	0.05
A.14.06.1B Bedroom	0.05
A.14.07.1B Bedroom	0.11
A.14.08.2B Bedroom	0.05
A.14.08.2B Bedroom	0.11
A.14.09.2B Bedroom	0.00
A.14.09.2B Bedroom	0.05
A.14.10.2B Bedroom	0.08
A.14.10.2B Bedroom	0.05
A.15.01.1B Bedroom	0.11
A.15.02.1B Bedroom	0.08
A.15.03.2B Bedroom	0.11

Location	Operative Temperature > 26 (Max 1%)
A.15.03.2B Bedroom	0.08
A.15.04.2B Bedroom	0.08
A.15.04.2B Bedroom	0.11
A.15.05.2B Bedroom	0.05
A.15.05.2B Bedroom	0.05
A.15.06.1B Bedroom	0.05
A.15.07.1B Bedroom	0.11
A.15.08.2B Bedroom	0.11
A.15.08.2B Bedroom	0.05
A.15.09.2B Bedroom	0.03
A.15.09.2B Bedroom	0.00
A.15.10.2B Bedroom	0.08
A.15.10.2B Bedroom	0.05
A.16.01.1B Bedroom	0.11
A.16.02.1B Bedroom	0.05
A.16.03.2B Bedroom	0.05
A.16.03.2B Bedroom	0.11
A.16.04.2B Bedroom	0.08
A.16.04.2B Bedroom	0.08
A.16.05.2B Bedroom	0.05
A.16.05.2B Bedroom	0.05
A.16.06.1B Bedroom	0.05
A.16.07.1B Bedroom	0.11
A.16.08.2B Bedroom	0.11
A.16.08.2B Bedroom	0.05
A.16.09.2B Bedroom	0.00
A.16.09.2B Bedroom	0.03

Location	Operative Temperature > 26 (Max 1%)
A.16.10.2B Bedroom	0.05
A.16.10.2B Bedroom	0.08
A.17.01.1B Bedroom	0.11
A.17.02.1B Bedroom	0.05
A.17.03.2B Bedroom	0.11
A.17.03.2B Bedroom	0.03
A.17.04.2B Bedroom	0.05
A.17.04.2B Bedroom	0.05
A.17.05.2B Bedroom	0.05
A.17.05.2B Bedroom	0.05
A.17.06.1B Bedroom	0.05
A.17.07.1B Bedroom	0.11
A.17.08.2B Bedroom	0.11
A.17.08.2B Bedroom	0.05
A.17.09.2B Bedroom	0.03
A.17.09.2B Bedroom	0.00
A.17.10.2B Bedroom	0.05
A.17.10.2B Bedroom	0.08
A.18.01.1B Bedroom	0.08
A.18.02.1B Bedroom	0.05
A.18.03.2B Bedroom	0.03
A.18.03.2B Bedroom	0.11
A.18.04.2B Bedroom	0.05
A.18.04.2B Bedroom	0.05
A.18.05.2B Bedroom	0.05
A.18.05.2B Bedroom	0.05
A.18.06.1B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.18.07.1B Bedroom	0.11
A.18.08.2B Bedroom	0.05
A.18.08.2B Bedroom	0.11
A.18.09.2B Bedroom	0.03
A.18.09.2B Bedroom	0.00
A.18.10.2B Bedroom	0.08
A.18.10.2B Bedroom	0.05
A.19.01.1B Bedroom	0.11
A.19.02.1B Bedroom	0.05
A.19.03.2B Bedroom	0.11
A.19.03.2B Bedroom	0.03
A.19.04.2B Bedroom	0.05
A.19.04.2B Bedroom	0.05
A.19.05.2B Bedroom	0.05
A.19.05.2B Bedroom	0.05
A.19.06.1B Bedroom	0.05
A.19.07.1B Bedroom	0.11
A.19.08.2B Bedroom	0.11
A.19.08.2B Bedroom	0.05
A.19.09.2B Bedroom	0.00
A.19.09.2B Bedroom	0.03
A.19.10.2B Bedroom	0.05
A.19.10.2B Bedroom	0.08
A.20.01.1B Bedroom	0.11
A.20.02.1B Bedroom	0.05
A.20.03.2B Bedroom	0.11
A.20.03.2B Bedroom	0.03

Location	Operative Temperature > 26 (Max 1%)
A.20.04.2B Bedroom	0.05
A.20.04.2B Bedroom	0.05
A.20.05.2B Bedroom	0.05
A.20.05.2B Bedroom	0.05
A.20.06.1B Bedroom	0.05
A.20.07.1B Bedroom	0.11
A.20.08.2B Bedroom	0.11
A.20.08.2B Bedroom	0.05
A.20.09.2B Bedroom	0.03
A.20.09.2B Bedroom	0.00
A.20.10.2B Bedroom	0.08
A.20.10.2B Bedroom	0.05
A.21.01.1B Bedroom	0.08
A.21.02.1B Bedroom	0.05
A.21.03.2B Bedroom	0.11
A.21.03.2B Bedroom	0.03
A.21.04.2B Bedroom	0.08
A.21.04.2B Bedroom	0.05
A.21.05.2B Bedroom	0.05
A.21.05.2B Bedroom	0.05
A.21.06.1B Bedroom	0.05
A.21.07.1B Bedroom	0.11
A.21.08.2B Bedroom	0.11
A.21.08.2B Bedroom	0.05
A.21.09.2B Bedroom	0.00
A.21.09.2B Bedroom	0.03
A.21.10.2B Bedroom	0.08

Location	Operative Temperature > 26 (Max 1%)
A.21.10.2B Bedroom	0.05
A.22.01.1B Bedroom	0.08
A.22.02.1B Bedroom	0.05
A.22.03.2B Bedroom	0.11
A.22.03.2B Bedroom	0.03
A.22.04.2B Bedroom	0.05
A.22.04.2B Bedroom	0.05
A.22.05.2B Bedroom	0.05
A.22.05.2B Bedroom	0.05
A.22.06.1B Bedroom	0.05
A.22.07.1B Bedroom	0.11
A.22.08.2B Bedroom	0.05
A.22.08.2B Bedroom	0.11
A.22.09.2B Bedroom	0.03
A.22.09.2B Bedroom	0.00
A.22.10.2B Bedroom	0.05
A.22.10.2B Bedroom	0.05
A.23.01.1B Bedroom	0.08
A.23.02.1B Bedroom	0.05
A.23.03.2B Bedroom	0.03
A.23.03.2B Bedroom	0.08
A.23.04.2B Bedroom	0.05
A.23.04.2B Bedroom	0.05
A.23.05.2B Bedroom	0.05
A.23.05.2B Bedroom	0.05
A.23.06.1B Bedroom	0.05
A.23.07.1B Bedroom	0.11

Location	Operative Temperature > 26 (Max 1%)
A.23.08.2B Bedroom	0.05
A.23.08.2B Bedroom	0.11
A.23.09.2B Bedroom	0.00
A.23.09.2B Bedroom	0.03
A.23.10.2B Bedroom	0.05
A.23.10.2B Bedroom	0.05
A.24.01.1B Bedroom	0.08
A.24.02.1B Bedroom	0.05
A.24.03.2B Bedroom	0.03
A.24.03.2B Bedroom	0.11
A.24.04.2B Bedroom	0.05
A.24.04.2B Bedroom	0.05
A.24.05.2B Bedroom	0.05
A.24.05.2B Bedroom	0.05
A.24.06.1B Bedroom	0.05
A.24.07.1B Bedroom	0.11
A.24.08.2B Bedroom	0.11
A.24.08.2B Bedroom	0.05
A.24.09.2B Bedroom	0.00
A.24.09.2B Bedroom	0.03
A.24.10.2B Bedroom	0.05
A.24.10.2B Bedroom	0.05
A.25.01.1B Bedroom	0.11
A.25.02.1B Bedroom	0.05
A.25.03.2B Bedroom	0.03
A.25.03.2B Bedroom	0.11
A.25.04.2B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.25.04.2B Bedroom	0.05
A.25.05.2B Bedroom	0.05
A.25.05.2B Bedroom	0.05
A.25.06.1B Bedroom	0.05
A.25.07.1B Bedroom	0.11
A.25.08.2B Bedroom	0.11
A.25.08.2B Bedroom	0.05
A.25.09.2B Bedroom	0.03
A.25.09.2B Bedroom	0.00
A.25.10.2B Bedroom	0.05
A.25.10.2B Bedroom	0.05
A.26.01.1B Bedroom	0.08
A.26.02.1B Bedroom	0.05
A.26.03.2B Bedroom	0.11
A.26.03.2B Bedroom	0.03
A.26.04.2B Bedroom	0.05
A.26.04.2B Bedroom	0.05
A.26.05.2B Bedroom	0.05
A.26.05.2B Bedroom	0.05
A.26.06.1B Bedroom	0.05
A.26.07.1B Bedroom	0.11
A.26.08.2B Bedroom	0.05
A.26.08.2B Bedroom	0.11
A.26.09.2B Bedroom	0.00
A.26.09.2B Bedroom	0.03
A.26.10.2B Bedroom	0.05
A.26.10.2B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.27.01.1B Bedroom	0.08
A.27.02.1B Bedroom	0.05
A.27.03.2B Bedroom	0.08
A.27.03.2B Bedroom	0.03
A.27.04.2B Bedroom	0.05
A.27.04.2B Bedroom	0.05
A.27.05.2B Bedroom	0.05
A.27.05.2B Bedroom	0.05
A.27.06.1B Bedroom	0.05
A.27.07.1B Bedroom	0.11
A.27.08.2B Bedroom	0.11
A.27.08.2B Bedroom	0.05
A.27.09.2B Bedroom	0.03
A.27.09.2B Bedroom	0.00
A.27.10.2B Bedroom	0.05
A.27.10.2B Bedroom	0.05
A.28.01.1B Bedroom	0.08
A.28.02.1B Bedroom	0.05
A.28.03.2B Bedroom	0.03
A.28.03.2B Bedroom	0.11
A.28.04.2B Bedroom	0.05
A.28.04.2B Bedroom	0.05
A.28.05.2B Bedroom	0.05
A.28.05.2B Bedroom	0.05
A.28.06.1B Bedroom	0.05
A.28.07.1B Bedroom	0.11
A.28.08.2B Bedroom	0.11

Location	Operative Temperature > 26 (Max 1%)
A.28.08.2B Bedroom	0.05
A.28.09.2B Bedroom	0.03
A.28.09.2B Bedroom	0.00
A.28.10.2B Bedroom	0.05
A.28.10.2B Bedroom	0.05
A.29.01.1B Bedroom	0.08
A.29.02.1B Bedroom	0.05
A.29.03.2B Bedroom	0.03
A.29.03.2B Bedroom	0.11
A.29.04.2B Bedroom	0.05
A.29.04.2B Bedroom	0.05
A.29.05.2B Bedroom	0.05
A.29.05.2B Bedroom	0.05
A.29.06.1B Bedroom	0.05
A.29.07.1B Bedroom	0.11
A.29.08.2B Bedroom	0.05
A.29.08.2B Bedroom	0.11
A.29.09.2B Bedroom	0.03
A.29.09.2B Bedroom	0.00
A.29.10.2B Bedroom	0.05
A.29.10.2B Bedroom	0.05
A.30.01.1B Bedroom	0.08
A.30.02.1B Bedroom	0.05
A.30.03.2B Bedroom	0.11
A.30.03.2B Bedroom	0.03
A.30.04.2B Bedroom	0.05
A.30.04.2B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.30.05.2B Bedroom	0.05
A.30.05.2B Bedroom	0.05
A.30.06.1B Bedroom	0.05
A.30.07.1B Bedroom	0.11
A.30.08.2B Bedroom	0.05
A.30.08.2B Bedroom	0.11
A.30.09.2B Bedroom	0.03
A.30.09.2B Bedroom	0.00
A.30.10.2B Bedroom	0.05
A.30.10.2B Bedroom	0.05
A.31.01.1B Bedroom	0.08
A.31.02.1B Bedroom	0.05
A.31.03.2B Bedroom	0.08
A.31.03.2B Bedroom	0.03
A.31.04.2B Bedroom	0.05
A.31.04.2B Bedroom	0.05
A.31.05.2B Bedroom	0.05
A.31.05.2B Bedroom	0.05
A.31.06.1B Bedroom	0.05
A.31.07.1B Bedroom	0.11
A.31.08.2B Bedroom	0.11
A.31.08.2B Bedroom	0.05
A.31.09.2B Bedroom	0.03
A.31.09.2B Bedroom	0.00
A.31.10.2B Bedroom	0.05
A.31.10.2B Bedroom	0.05
A.32.01.1B Bedroom	0.08

Location	Operative Temperature > 26 (Max 1%)
A.32.02.1B Bedroom	0.05
A.32.03.2B Bedroom	0.08
A.32.03.2B Bedroom	0.03
A.32.04.2B Bedroom	0.05
A.32.04.2B Bedroom	0.05
A.32.05.2B Bedroom	0.05
A.32.05.2B Bedroom	0.05
A.32.06.1B Bedroom	0.05
A.32.07.1B Bedroom	0.11
A.32.08.2B Bedroom	0.05
A.32.08.2B Bedroom	0.11
A.32.09.2B Bedroom	0.00
A.32.09.2B Bedroom	0.03
A.32.10.2B Bedroom	0.05
A.32.10.2B Bedroom	0.05
A.33.01.1B Bedroom	0.08
A.33.02.1B Bedroom	0.05
A.33.03.2B Bedroom	0.03
A.33.03.2B Bedroom	0.08
A.33.04.2B Bedroom	0.05
A.33.04.2B Bedroom	0.05
A.33.05.2B Bedroom	0.05
A.33.05.2B Bedroom	0.05
A.33.06.1B Bedroom	0.05
A.33.07.1B Bedroom	0.11
A.33.08.2B Bedroom	0.05
A.33.08.2B Bedroom	0.11

Location	Operative Temperature > 26 (Max 1%)
A.33.09.2B Bedroom	0.03
A.33.09.2B Bedroom	0.00
A.33.10.2B Bedroom	0.05
A.33.10.2B Bedroom	0.05
A.34.01.1B Bedroom	0.08
A.34.02.1B Bedroom	0.05
A.34.03.2B Bedroom	0.08
A.34.03.2B Bedroom	0.03
A.34.04.2B Bedroom	0.05
A.34.04.2B Bedroom	0.05
A.34.05.2B Bedroom	0.05
A.34.05.2B Bedroom	0.05
A.34.06.1B Bedroom	0.05
A.34.07.1B Bedroom	0.11
A.34.08.2B Bedroom	0.05
A.34.08.2B Bedroom	0.08
A.34.09.2B Bedroom	0.03
A.34.09.2B Bedroom	0.00
A.34.10.2B Bedroom	0.05
A.34.10.2B Bedroom	0.05
A.35.01.1B Bedroom	0.08
A.35.02.1B Bedroom	0.05
A.35.03.2B Bedroom	0.03
A.35.03.2B Bedroom	0.08
A.35.04.2B Bedroom	0.05
A.35.04.2B Bedroom	0.05
A.35.05.2B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.35.05.2B Bedroom	0.05
A.35.06.1B Bedroom	0.05
A.35.07.1B Bedroom	0.11
A.35.08.2B Bedroom	0.05
A.35.08.2B Bedroom	0.11
A.35.09.2B Bedroom	0.03
A.35.09.2B Bedroom	0.00
A.35.10.2B Bedroom	0.05
A.35.10.2B Bedroom	0.05
A.36.01.1B Bedroom	0.08
A.36.02.1B Bedroom	0.05
A.36.03.2B Bedroom	0.03
A.36.03.2B Bedroom	0.11
A.36.04.2B Bedroom	0.05
A.36.04.2B Bedroom	0.05
A.36.05.2B Bedroom	0.05
A.36.05.2B Bedroom	0.05
A.36.06.1B Bedroom	0.05
A.36.07.1B Bedroom	0.11
A.36.08.2B Bedroom	0.05
A.36.08.2B Bedroom	0.11
A.36.09.2B Bedroom	0.00
A.36.09.2B Bedroom	0.03
A.36.10.2B Bedroom	0.05
A.36.10.2B Bedroom	0.05
A.37.01.1B Bedroom	0.08
A.37.02.1B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.37.03.2B Bedroom	0.08
A.37.03.2B Bedroom	0.03
A.37.04.2B Bedroom	0.05
A.37.04.2B Bedroom	0.05
A.37.05.2B Bedroom	0.05
A.37.05.2B Bedroom	0.05
A.37.06.1B Bedroom	0.05
A.37.07.1B Bedroom	0.11
A.37.08.2B Bedroom	0.05
A.37.08.2B Bedroom	0.11
A.37.09.2B Bedroom	0.03
A.37.09.2B Bedroom	0.00
A.37.10.2B Bedroom	0.05
A.37.10.2B Bedroom	0.05
A.38.01.1B Bedroom	0.08
A.38.02.1B Bedroom	0.05
A.38.03.2B Bedroom	0.08
A.38.03.2B Bedroom	0.03
A.38.04.2B Bedroom	0.05
A.38.04.2B Bedroom	0.05
A.38.05.2B Bedroom	0.05
A.38.05.2B Bedroom	0.05
A.38.06.1B Bedroom	0.05
A.38.07.1B Bedroom	0.11
A.38.08.2B Bedroom	0.05
A.38.08.2B Bedroom	0.11
A.38.09.2B Bedroom	0.00

Location	Operative Temperature > 26 (Max 1%)
A.38.09.2B Bedroom	0.03
A.38.10.2B Bedroom	0.05
A.38.10.2B Bedroom	0.05
A.39.01.1B Bedroom	0.08
A.39.02.1B Bedroom	0.05
A.39.03.2B Bedroom	0.03
A.39.03.2B Bedroom	0.11
A.39.04.2B Bedroom	0.05
A.39.04.2B Bedroom	0.05
A.39.05.2B Bedroom	0.05
A.39.05.2B Bedroom	0.05
A.39.06.1B Bedroom	0.05
A.39.07.1B Bedroom	0.11
A.39.08.2B Bedroom	0.05
A.39.08.2B Bedroom	0.11
A.39.09.2B Bedroom	0.00
A.39.09.2B Bedroom	0.03
A.39.10.2B Bedroom	0.05
A.39.10.2B Bedroom	0.05
A.40.01.1B Bedroom	0.11
A.40.02.1B Bedroom	0.05
A.40.03.2B Bedroom	0.03
A.40.03.2B Bedroom	0.11
A.40.04.2B Bedroom	0.05
A.40.04.2B Bedroom	0.05
A.40.05.2B Bedroom	0.05
A.40.05.2B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.40.06.1B Bedroom	0.05
A.40.07.1B Bedroom	0.11
A.40.08.2B Bedroom	0.05
A.40.08.2B Bedroom	0.11
A.40.09.2B Bedroom	0.03
A.40.09.2B Bedroom	0.00
A.40.10.2B Bedroom	0.05
A.40.10.2B Bedroom	0.05
A.41.01.1B Bedroom	0.11
A.41.02.1B Bedroom	0.05
A.41.03.2B Bedroom	0.03
A.41.03.2B Bedroom	0.11
A.41.04.2B Bedroom	0.05
A.41.04.2B Bedroom	0.05
A.41.05.2B Bedroom	0.05
A.41.05.2B Bedroom	0.05
A.41.06.1B Bedroom	0.05
A.41.07.1B Bedroom	0.11
A.41.08.2B Bedroom	0.05
A.41.08.2B Bedroom	0.11
A.41.09.2B Bedroom	0.00
A.41.09.2B Bedroom	0.03
A.41.10.2B Bedroom	0.05
A.41.10.2B Bedroom	0.05
A.42.01.1B Bedroom	0.11
A.42.02.1B Bedroom	0.05
A.42.03.2B Bedroom	0.11

Location	Operative Temperature > 26 (Max 1%)
A.42.03.2B Bedroom	0.03
A.42.04.2B Bedroom	0.05
A.42.04.2B Bedroom	0.05
A.42.05.2B Bedroom	0.05
A.42.05.2B Bedroom	0.05
A.42.06.1B Bedroom	0.05
A.42.07.1B Bedroom	0.11
A.42.08.2B Bedroom	0.05
A.42.08.2B Bedroom	0.11
A.42.09.2B Bedroom	0.03
A.42.09.2B Bedroom	0.00
A.42.10.2B Bedroom	0.05
A.42.10.2B Bedroom	0.05
A.43.01.1B Bedroom	0.11
A.43.02.1B Bedroom	0.05
A.43.03.2B Bedroom	0.03
A.43.03.2B Bedroom	0.11
A.43.04.2B Bedroom	0.05
A.43.04.2B Bedroom	0.05
A.43.05.2B Bedroom	0.05
A.43.05.2B Bedroom	0.05
A.43.06.1B Bedroom	0.05
A.43.07.1B Bedroom	0.11
A.43.08.2B Bedroom	0.11
A.43.08.2B Bedroom	0.05
A.43.09.2B Bedroom	0.00
A.43.09.2B Bedroom	0.03

Location	Operative Temperature > 26 (Max 1%)
A.43.10.2B Bedroom	0.05
A.43.10.2B Bedroom	0.05
A.44.01.1B Bedroom	0.11
A.44.02.1B Bedroom	0.05
A.44.03.2B Bedroom	0.03
A.44.03.2B Bedroom	0.11
A.44.04.2B Bedroom	0.05
A.44.04.2B Bedroom	0.05
A.44.05.2B Bedroom	0.05
A.44.05.2B Bedroom	0.05
A.44.06.1B Bedroom	0.05
A.44.07.1B Bedroom	0.11
A.44.08.2B Bedroom	0.05
A.44.08.2B Bedroom	0.11
A.44.09.2B Bedroom	0.00
A.44.09.2B Bedroom	0.03
A.44.10.2B Bedroom	0.05
A.44.10.2B Bedroom	0.05
A.45.01.3B Bedroom	0.60
A.45.01.3B Bedroom	0.11
A.45.01.3B Bedroom	0.14
A.45.02.3B Bedroom	0.03
A.45.02.3B Bedroom	0.11
A.45.02.3B Bedroom	0.03
A.45.03.3B Bedroom	0.05
A.45.03.3B Bedroom	0.03
A.45.03.3B Bedroom	0.05

Location	Operative Temperature > 26 (Max 1%)
A.45.04.3B Bedroom	0.14
A.45.04.3B Bedroom	0.08
A.45.04.3B Bedroom	0.63
A.45.05.3B Bedroom	0.03
A.45.05.3B Bedroom	0.00
A.45.05.3B Bedroom	0.00
A.45.06.3B Bedroom	0.11
A.45.06.3B Bedroom	0.05
A.45.06.3B Bedroom	0.05

9.0 Appendix 3: DSY1: TM52 Criterion 1 Living Block A

Location	Operative Temperature > 26 (Max 1%)
A.02.01.1BKLD	0.00
A.02.02.1BKLD	0.00
A.02.03.2BKLD	2.21
A.02.04.2BKLD	0.70
A.02.05.2BKLD	2.51
A.02.06.1BKLD	0.00
A.02.07.1BKLD	0.00
A.02.08.2BKLD	0.05
A.02.09.2BKLD	0.20
A.02.10.2BKLD	0.00
A.03.01.1BKLD	0.00
A.03.02.1BKLD	0.00
A.03.03.2BKLD	2.31
A.03.04.2BKLD	0.75
A.03.05.2BKLD	2.82
A.03.06.1BKLD	0.00
A.03.07.1BKLD	0.00
A.03.08.2BKLD	0.15
A.03.09.2BKLD	0.25
A.03.10.2BKLD	0.00
A.04.01.1BKLD	0.00
A.04.02.1BKLD	0.05
A.04.03.2BKLD	2.31
A.04.04.2BKLD	0.75
A.04.05.2BKLD	2.82
A.04.06.1BKLD	0.00
A.04.07.1BKLD	0.00
A.04.08.2BKLD	0.15
A.04.09.2BKLD	0.35
A.04.10.2BKLD	0.00
A.05.01.1BKLD	0.00
A.05.02.1BKLD	0.05
A.05.03.2BKLD	2.31
A.05.04.2BKLD	0.75
A.05.05.2BKLD	2.77
A.05.06.1BKLD	0.00
A.05.07.1BKLD	0.00
A.05.08.2BKLD	0.15
A.05.09.2BKLD	0.35
A.05.10.2BKLD	0.00
A.06.01.1BKLD	0.00
A.06.02.1BKLD	0.05
A.06.03.2BKLD	2.31
A.06.04.2BKLD	0.75
A.06.05.2BKLD	2.77
A.06.06.1BKLD	0.00
A.06.07.1BKLD	0.00
A.06.08.2BKLD	0.15
A.06.09.2BKLD	0.35
A.06.10.2BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.07.01.1BKLD	0.00
A.07.02.1BKLD	0.05
A.07.03.2BKLD	2.31
A.07.04.2BKLD	0.75
A.07.05.2BKLD	2.77
A.07.06.1BKLD	0.00
A.07.07.1BKLD	0.00
A.07.08.2BKLD	0.15
A.07.09.2BKLD	0.40
A.07.10.2BKLD	0.00
A.08.01.1BKLD	0.00
A.08.02.1BKLD	0.05
A.08.03.2BKLD	2.36
A.08.04.2BKLD	0.75
A.08.05.2BKLD	2.77
A.08.06.1BKLD	0.00
A.08.07.1BKLD	0.00
A.08.08.2BKLD	0.20
A.08.09.2BKLD	0.40
A.08.10.2BKLD	0.00
A.09.01.1BKLD	0.00
A.09.02.1BKLD	0.05
A.09.03.2BKLD	2.41
A.09.04.2BKLD	0.75
A.09.05.2BKLD	2.77
A.09.06.1BKLD	0.00
A.09.07.1BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.09.08.2BKLD	0.20
A.09.09.2BKLD	0.40
A.09.10.2BKLD	0.00
A.10.01.1BKLD	0.00
A.10.02.1BKLD	0.05
A.10.03.2BKLD	2.41
A.10.04.2BKLD	0.75
A.10.05.2BKLD	2.66
A.10.06.1BKLD	0.00
A.10.07.1BKLD	0.00
A.10.08.2BKLD	0.05
A.10.09.2BKLD	0.30
A.10.10.2BKLD	0.00
A.11.01.1BKLD	0.00
A.11.02.1BKLD	0.00
A.11.03.2BKLD	2.46
A.11.04.2BKLD	0.75
A.11.05.2BKLD	2.61
A.11.06.1BKLD	0.00
A.11.07.1BKLD	0.00
A.11.08.2BKLD	0.05
A.11.09.2BKLD	0.25
A.11.10.2BKLD	0.00
A.12.01.1BKLD	0.00
A.12.02.1BKLD	0.00
A.12.03.2BKLD	2.31
A.12.04.2BKLD	0.75

Location	Operative Temperature > 26 (Max 1%)
A.12.05.2BKLD	0.45
A.12.06.1BKLD	0.00
A.12.07.1BKLD	0.00
A.12.08.2BKLD	0.05
A.12.09.2BKLD	0.00
A.12.10.2BKLD	0.00
A.13.01.1BKLD	0.00
A.13.02.1BKLD	0.00
A.13.03.2BKLD	2.87
A.13.05.2BKLD	1.36
A.13.06.1BKLD	0.00
A.13.07.1BKLD	0.00
A.13.08.2BKLD	0.05
A.13.09.2BKLD	0.00
A.13.10.2BKLD	0.00
A.13.13.2BKLD	1.06
A.14.01.1BKLD	0.00
A.14.02.1BKLD	0.00
A.14.03.2BKLD	2.31
A.14.04.2BKLD	0.70
A.14.05.2BKLD	0.45
A.14.06.1BKLD	0.00
A.14.07.1BKLD	0.00
A.14.08.2BKLD	0.00
A.14.09.2BKLD	0.00
A.14.10.2BKLD	0.00
A.15.01.1BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.15.02.1BKLD	0.00
A.15.03.2BKLD	2.26
A.15.04.2BKLD	0.70
A.15.05.2BKLD	0.30
A.15.06.1BKLD	0.00
A.15.07.1BKLD	0.00
A.15.08.2BKLD	0.00
A.15.09.2BKLD	0.00
A.15.10.2BKLD	0.00
A.16.01.1BKLD	0.00
A.16.02.1BKLD	0.00
A.16.03.2BKLD	2.21
A.16.04.2BKLD	0.60
A.16.05.2BKLD	1.16
A.16.06.1BKLD	0.00
A.16.07.1BKLD	0.00
A.16.08.2BKLD	0.00
A.16.09.2BKLD	0.00
A.16.10.2BKLD	0.00
A.17.01.1BKLD	0.00
A.17.02.1BKLD	0.00
A.17.03.2BKLD	0.10
A.17.04.2BKLD	0.00
A.17.05.2BKLD	0.15
A.17.06.1BKLD	0.00
A.17.07.1BKLD	0.00
A.17.08.2BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.17.09.2BKLD	0.00
A.17.10.2BKLD	0.00
A.18.01.1BKLD	0.00
A.18.02.1BKLD	0.00
A.18.03.2BKLD	0.00
A.18.04.2BKLD	0.00
A.18.05.2BKLD	0.05
A.18.06.1BKLD	0.00
A.18.07.1BKLD	0.00
A.18.08.2BKLD	0.00
A.18.09.2BKLD	0.00
A.18.10.2BKLD	0.00
A.19.01.1BKLD	0.00
A.19.02.1BKLD	0.00
A.19.03.2BKLD	0.30
A.19.04.2BKLD	0.00
A.19.05.2BKLD	0.10
A.19.06.1BKLD	0.00
A.19.07.1BKLD	0.00
A.19.08.2BKLD	0.00
A.19.09.2BKLD	0.00
A.19.10.2BKLD	0.00
A.20.01.1BKLD	0.00
A.20.02.1BKLD	0.00
A.20.03.2BKLD	0.00
A.20.04.2BKLD	0.00
A.20.05.2BKLD	0.20

Location	Operative Temperature > 26 (Max 1%)
A.20.06.1BKLD	0.00
A.20.07.1BKLD	0.00
A.20.08.2BKLD	0.05
A.20.09.2BKLD	0.00
A.20.10.2BKLD	0.00
A.21.01.1BKLD	0.00
A.21.02.1BKLD	0.00
A.21.03.2BKLD	0.00
A.21.04.2BKLD	0.00
A.21.05.2BKLD	0.90
A.21.06.1BKLD	0.00
A.21.07.1BKLD	0.00
A.21.08.2BKLD	0.00
A.21.09.2BKLD	0.00
A.21.10.2BKLD	0.00
A.22.01.1BKLD	0.00
A.22.02.1BKLD	0.00
A.22.03.2BKLD	0.30
A.22.04.2BKLD	0.20
A.22.05.2BKLD	1.06
A.22.06.1BKLD	0.00
A.22.07.1BKLD	0.00
A.22.08.2BKLD	0.00
A.22.09.2BKLD	0.00
A.22.10.2BKLD	0.00
A.23.01.1BKLD	0.00
A.23.02.1BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.23.03.2BKLD	0.00
A.23.04.2BKLD	0.00
A.23.05.2BKLD	0.40
A.23.06.1BKLD	0.00
A.23.07.1BKLD	0.00
A.23.08.2BKLD	0.00
A.23.09.2BKLD	0.00
A.23.10.2BKLD	0.00
A.24.01.1BKLD	0.00
A.24.02.1BKLD	0.00
A.24.03.2BKLD	0.60
A.24.04.2BKLD	0.00
A.24.05.2BKLD	0.40
A.24.06.1BKLD	0.00
A.24.07.1BKLD	0.00
A.24.08.2BKLD	0.00
A.24.09.2BKLD	0.00
A.24.10.2BKLD	0.00
A.25.01.1BKLD	0.00
A.25.02.1BKLD	0.00
A.25.03.2BKLD	0.00
A.25.04.2BKLD	0.00
A.25.05.2BKLD	1.01
A.25.06.1BKLD	0.00
A.25.07.1BKLD	0.00
A.25.08.2BKLD	0.00
A.25.09.2BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.25.10.2BKLD	0.00
A.26.01.1BKLD	0.00
A.26.02.1BKLD	0.00
A.26.03.2BKLD	0.35
A.26.04.2BKLD	0.20
A.26.05.2BKLD	1.06
A.26.06.1BKLD	0.00
A.26.07.1BKLD	0.00
A.26.08.2BKLD	0.00
A.26.09.2BKLD	0.00
A.26.10.2BKLD	0.00
A.27.01.1BKLD	0.00
A.27.02.1BKLD	0.00
A.27.03.2BKLD	0.00
A.27.04.2BKLD	0.00
A.27.05.2BKLD	0.40
A.27.06.1BKLD	0.00
A.27.07.1BKLD	0.00
A.27.08.2BKLD	0.00
A.27.09.2BKLD	0.00
A.27.10.2BKLD	0.00
A.28.01.1BKLD	0.00
A.28.02.1BKLD	0.00
A.28.03.2BKLD	0.20
A.28.04.2BKLD	0.20
A.28.05.2BKLD	0.96
A.28.06.1BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.28.07.1BKLD	0.00
A.28.08.2BKLD	0.00
A.28.09.2BKLD	0.00
A.28.10.2BKLD	0.00
A.29.01.1BKLD	0.00
A.29.02.1BKLD	0.00
A.29.03.2BKLD	0.00
A.29.04.2BKLD	0.00
A.29.05.2BKLD	0.50
A.29.06.1BKLD	0.00
A.29.07.1BKLD	0.00
A.29.08.2BKLD	0.05
A.29.09.2BKLD	0.00
A.29.10.2BKLD	0.00
A.30.01.1BKLD	0.00
A.30.02.1BKLD	0.00
A.30.03.2BKLD	0.60
A.30.04.2BKLD	0.00
A.30.05.2BKLD	0.40
A.30.06.1BKLD	0.00
A.30.07.1BKLD	0.00
A.30.08.2BKLD	0.00
A.30.09.2BKLD	0.00
A.30.10.2BKLD	0.00
A.31.01.1BKLD	0.00
A.31.02.1BKLD	0.00
A.31.03.2BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.31.04.2BKLD	0.00
A.31.05.2BKLD	1.01
A.31.06.1BKLD	0.00
A.31.07.1BKLD	0.00
A.31.08.2BKLD	0.00
A.31.09.2BKLD	0.00
A.31.10.2BKLD	0.00
A.32.01.1BKLD	0.00
A.32.02.1BKLD	0.00
A.32.03.2BKLD	0.35
A.32.04.2BKLD	0.20
A.32.05.2BKLD	1.01
A.32.06.1BKLD	0.00
A.32.07.1BKLD	0.00
A.32.08.2BKLD	0.00
A.32.09.2BKLD	0.00
A.32.10.2BKLD	0.00
A.33.01.1BKLD	0.00
A.33.02.1BKLD	0.00
A.33.03.2BKLD	0.60
A.33.04.2BKLD	0.00
A.33.05.2BKLD	0.40
A.33.06.1BKLD	0.00
A.33.07.1BKLD	0.00
A.33.08.2BKLD	0.00
A.33.09.2BKLD	0.00
A.33.10.2BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.34.01.1BKLD	0.00
A.34.02.1BKLD	0.00
A.34.03.2BKLD	0.60
A.34.04.2BKLD	0.00
A.34.05.2BKLD	0.40
A.34.06.1BKLD	0.00
A.34.07.1BKLD	0.00
A.34.08.2BKLD	0.00
A.34.09.2BKLD	0.00
A.34.10.2BKLD	0.00
A.35.01.1BKLD	0.00
A.35.02.1BKLD	0.00
A.35.03.2BKLD	0.20
A.35.04.2BKLD	0.20
A.35.05.2BKLD	0.90
A.35.06.1BKLD	0.00
A.35.07.1BKLD	0.00
A.35.08.2BKLD	0.00
A.35.09.2BKLD	0.00
A.35.10.2BKLD	0.00
A.36.01.1BKLD	0.00
A.36.02.1BKLD	0.00
A.36.03.2BKLD	0.65
A.36.04.2BKLD	0.00
A.36.05.2BKLD	0.55
A.36.06.1BKLD	0.00
A.36.07.1BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.36.08.2BKLD	0.00
A.36.09.2BKLD	0.00
A.36.10.2BKLD	0.00
A.37.01.1BKLD	0.00
A.37.02.1BKLD	0.00
A.37.03.2BKLD	0.25
A.37.04.2BKLD	0.00
A.37.05.2BKLD	0.96
A.37.06.1BKLD	0.00
A.37.07.1BKLD	0.00
A.37.08.2BKLD	0.00
A.37.09.2BKLD	0.00
A.37.10.2BKLD	0.00
A.38.01.1BKLD	0.00
A.38.02.1BKLD	0.00
A.38.03.2BKLD	0.35
A.38.04.2BKLD	0.20
A.38.05.2BKLD	1.01
A.38.06.1BKLD	0.00
A.38.07.1BKLD	0.00
A.38.08.2BKLD	0.00
A.38.09.2BKLD	0.00
A.38.10.2BKLD	0.00
A.39.01.1BKLD	0.00
A.39.02.1BKLD	0.00
A.39.03.2BKLD	0.65
A.39.04.2BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.39.05.2BKLD	0.55
A.39.06.1BKLD	0.00
A.39.07.1BKLD	0.00
A.39.08.2BKLD	0.00
A.39.09.2BKLD	0.00
A.39.10.2BKLD	0.00
A.40.01.1BKLD	0.00
A.40.02.1BKLD	0.00
A.40.03.2BKLD	0.75
A.40.04.2BKLD	0.00
A.40.05.2BKLD	0.45
A.40.06.1BKLD	0.00
A.40.07.1BKLD	0.00
A.40.08.2BKLD	0.05
A.40.09.2BKLD	0.00
A.40.10.2BKLD	0.00
A.41.01.1BKLD	0.00
A.41.02.1BKLD	0.00
A.41.03.2BKLD	0.35
A.41.04.2BKLD	0.00
A.41.05.2BKLD	1.01
A.41.06.1BKLD	0.00
A.41.07.1BKLD	0.00
A.41.08.2BKLD	0.00
A.41.09.2BKLD	0.00
A.41.10.2BKLD	0.00
A.42.01.1BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.42.02.1BKLD	0.00
A.42.03.2BKLD	0.40
A.42.04.2BKLD	0.20
A.42.05.2BKLD	1.11
A.42.06.1BKLD	0.00
A.42.07.1BKLD	0.00
A.42.08.2BKLD	0.00
A.42.09.2BKLD	0.00
A.42.10.2BKLD	0.00
A.43.01.1BKLD	0.00
A.43.02.1BKLD	0.00
A.43.03.2BKLD	0.85
A.43.04.2BKLD	0.00
A.43.05.2BKLD	0.60
A.43.06.1BKLD	0.00
A.43.07.1BKLD	0.00
A.43.08.2BKLD	0.05
A.43.09.2BKLD	0.00
A.43.10.2BKLD	0.00
A.44.01.1BKLD	0.00
A.44.02.1BKLD	0.00
A.44.03.2BKLD	0.35
A.44.04.2BKLD	0.20
A.44.05.2BKLD	1.01
A.44.06.1BKLD	0.00
A.44.07.1BKLD	0.00
A.44.08.2BKLD	0.00

Location	Operative Temperature > 26 (Max 1%)
A.44.09.2BKLD	0.00
A.44.10.2BKLD	0.00
A.45.01.3BKLD	0.00
A.45.02.3BKLD	0.60
A.45.03.3BKLD	0.40
A.45.04.3BKLD	0.00
A.45.05.3BKLD	0.00
A.45.06.3BKLD	0.00

10.0 Appendix 4: DSY2: TM52 Criterion 1 Bedroom Block A

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.02.01.1B Bedroom	0.54
A.02.02.1B Bedroom	0.49
A.02.03.2B Bedroom	1.23
A.02.03.2B Bedroom	0.74
A.02.04.2B Bedroom	1.06
A.02.04.2B Bedroom	1.31
A.02.05.2B Bedroom	0.93
A.02.05.2B Bedroom	0.60
A.02.06.1B Bedroom	0.46
A.02.07.1B Bedroom	0.54
A.02.08.2B Bedroom	0.49
A.02.08.2B Bedroom	0.57
A.02.09.2B Bedroom	0.46
A.02.09.2B Bedroom	0.52
A.02.10.2B Bedroom	0.46
A.02.10.2B Bedroom	0.46
A.03.01.1B Bedroom	0.60
A.03.02.1B Bedroom	0.52
A.03.03.2B Bedroom	0.76
A.03.03.2B Bedroom	1.25
A.03.04.2B Bedroom	1.42
A.03.04.2B Bedroom	1.17
A.03.05.2B Bedroom	0.63
A.03.05.2B Bedroom	0.95
A.03.06.1B Bedroom	0.52
A.03.07.1B Bedroom	0.60
A.03.08.2B Bedroom	0.49
A.03.08.2B Bedroom	0.65
A.03.09.2B Bedroom	0.49
A.03.09.2B Bedroom	0.54
A.03.10.2B Bedroom	0.52
A.03.10.2B Bedroom	0.49
A.04.01.1B Bedroom	0.54
A.04.02.1B Bedroom	0.52
A.04.03.2B Bedroom	1.23
A.04.03.2B Bedroom	0.76
A.04.04.2B Bedroom	1.12
A.04.04.2B Bedroom	1.33
A.04.05.2B Bedroom	0.98
A.04.05.2B Bedroom	0.68
A.04.06.1B Bedroom	0.52
A.04.07.1B Bedroom	0.60
A.04.08.2B Bedroom	0.49
A.04.08.2B Bedroom	0.65
A.04.09.2B Bedroom	0.49
A.04.09.2B Bedroom	0.54

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.04.10.2B Bedroom	0.52
A.04.10.2B Bedroom	0.49
A.05.01.1B Bedroom	0.54
A.05.02.1B Bedroom	0.52
A.05.03.2B Bedroom	1.23
A.05.03.2B Bedroom	0.76
A.05.04.2B Bedroom	1.12
A.05.04.2B Bedroom	1.33
A.05.05.2B Bedroom	0.95
A.05.05.2B Bedroom	0.68
A.05.06.1B Bedroom	0.52
A.05.07.1B Bedroom	0.60
A.05.08.2B Bedroom	0.49
A.05.08.2B Bedroom	0.65
A.05.09.2B Bedroom	0.54
A.05.09.2B Bedroom	0.49
A.05.10.2B Bedroom	0.52
A.05.10.2B Bedroom	0.49
A.06.01.1B Bedroom	0.57
A.06.02.1B Bedroom	0.52
A.06.03.2B Bedroom	1.23
A.06.03.2B Bedroom	0.76
A.06.04.2B Bedroom	1.12
A.06.04.2B Bedroom	1.33
A.06.05.2B Bedroom	0.98

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.06.05.2B Bedroom	0.68
A.06.06.1B Bedroom	0.52
A.06.07.1B Bedroom	0.60
A.06.08.2B Bedroom	0.65
A.06.08.2B Bedroom	0.49
A.06.09.2B Bedroom	0.54
A.06.09.2B Bedroom	0.49
A.06.10.2B Bedroom	0.49
A.06.10.2B Bedroom	0.52
A.07.01.1B Bedroom	0.60
A.07.02.1B Bedroom	0.52
A.07.03.2B Bedroom	0.76
A.07.03.2B Bedroom	1.23
A.07.04.2B Bedroom	1.33
A.07.04.2B Bedroom	1.12
A.07.05.2B Bedroom	0.98
A.07.05.2B Bedroom	0.68
A.07.06.1B Bedroom	0.52
A.07.07.1B Bedroom	0.60
A.07.08.2B Bedroom	0.49
A.07.08.2B Bedroom	0.65
A.07.09.2B Bedroom	0.54
A.07.09.2B Bedroom	0.49
A.07.10.2B Bedroom	0.49
A.07.10.2B Bedroom	0.52

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.08.01.1B Bedroom	0.60
A.08.02.1B Bedroom	0.52
A.08.03.2B Bedroom	1.23
A.08.03.2B Bedroom	0.76
A.08.04.2B Bedroom	1.12
A.08.04.2B Bedroom	1.33
A.08.05.2B Bedroom	0.68
A.08.05.2B Bedroom	0.98
A.08.06.1B Bedroom	0.52
A.08.07.1B Bedroom	0.60
A.08.08.2B Bedroom	0.49
A.08.08.2B Bedroom	0.65
A.08.09.2B Bedroom	0.54
A.08.09.2B Bedroom	0.49
A.08.10.2B Bedroom	0.49
A.08.10.2B Bedroom	0.52
A.09.01.1B Bedroom	0.63
A.09.02.1B Bedroom	0.52
A.09.03.2B Bedroom	0.76
A.09.03.2B Bedroom	1.23
A.09.04.2B Bedroom	1.33
A.09.04.2B Bedroom	1.12
A.09.05.2B Bedroom	0.98
A.09.05.2B Bedroom	0.68
A.09.06.1B Bedroom	0.52

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.09.07.1B Bedroom	0.60
A.09.08.2B Bedroom	0.49
A.09.08.2B Bedroom	0.68
A.09.09.2B Bedroom	0.54
A.09.09.2B Bedroom	0.49
A.09.10.2B Bedroom	0.52
A.09.10.2B Bedroom	0.49
A.10.01.1B Bedroom	0.63
A.10.02.1B Bedroom	0.52
A.10.03.2B Bedroom	1.23
A.10.03.2B Bedroom	0.76
A.10.04.2B Bedroom	1.33
A.10.04.2B Bedroom	1.12
A.10.05.2B Bedroom	0.68
A.10.05.2B Bedroom	0.98
A.10.06.1B Bedroom	0.52
A.10.07.1B Bedroom	0.60
A.10.08.2B Bedroom	0.68
A.10.08.2B Bedroom	0.49
A.10.09.2B Bedroom	0.49
A.10.09.2B Bedroom	0.54
A.10.10.2B Bedroom	0.52
A.10.10.2B Bedroom	0.49
A.11.01.1B Bedroom	0.63
A.11.02.1B Bedroom	0.52

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.11.03.2B Bedroom	1.23
A.11.03.2B Bedroom	0.76
A.11.04.2B Bedroom	1.36
A.11.04.2B Bedroom	1.14
A.11.05.2B Bedroom	0.68
A.11.05.2B Bedroom	0.98
A.11.06.1B Bedroom	0.52
A.11.07.1B Bedroom	0.63
A.11.08.2B Bedroom	0.49
A.11.08.2B Bedroom	0.68
A.11.09.2B Bedroom	0.54
A.11.09.2B Bedroom	0.49
A.11.10.2B Bedroom	0.49
A.11.10.2B Bedroom	0.52
A.12.01.1B Bedroom	0.63
A.12.02.1B Bedroom	0.52
A.12.03.2B Bedroom	1.25
A.12.03.2B Bedroom	0.79
A.12.04.2B Bedroom	1.39
A.12.04.2B Bedroom	1.12
A.12.05.2B Bedroom	0.68
A.12.05.2B Bedroom	0.98
A.12.06.1B Bedroom	0.52
A.12.07.1B Bedroom	0.63
A.12.08.2B Bedroom	0.68

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.12.08.2B Bedroom	0.49
A.12.09.2B Bedroom	0.54
A.12.09.2B Bedroom	0.49
A.12.10.2B Bedroom	0.52
A.12.10.2B Bedroom	0.49
A.13.01.1B Bedroom	0.98
A.13.02.1B Bedroom	0.60
A.13.03.2B Bedroom	1.03
A.13.03.2B Bedroom	1.28
A.13.05.2B Bedroom	0.95
A.13.05.2B Bedroom	0.76
A.13.06.1B Bedroom	0.60
A.13.07.1B Bedroom	1.09
A.13.08.2B Bedroom	0.98
A.13.08.2B Bedroom	0.60
A.13.09.2B Bedroom	0.71
A.13.09.2B Bedroom	0.52
A.13.10.2B Bedroom	0.52
A.13.10.2B Bedroom	0.54
A.13.13.2B Bedroom	1.53
A.13.13.2B Bedroom	1.17
A.14.01.1B Bedroom	0.57
A.14.02.1B Bedroom	0.52
A.14.03.2B Bedroom	0.76
A.14.03.2B Bedroom	1.20

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.14.04.2B Bedroom	1.31
A.14.04.2B Bedroom	1.06
A.14.05.2B Bedroom	0.65
A.14.05.2B Bedroom	0.95
A.14.06.1B Bedroom	0.52
A.14.07.1B Bedroom	0.60
A.14.08.2B Bedroom	0.49
A.14.08.2B Bedroom	0.68
A.14.09.2B Bedroom	0.49
A.14.09.2B Bedroom	0.57
A.14.10.2B Bedroom	0.46
A.14.10.2B Bedroom	0.52
A.15.01.1B Bedroom	0.54
A.15.02.1B Bedroom	0.52
A.15.03.2B Bedroom	0.76
A.15.03.2B Bedroom	1.20
A.15.04.2B Bedroom	1.28
A.15.04.2B Bedroom	1.06
A.15.05.2B Bedroom	0.95
A.15.05.2B Bedroom	0.65
A.15.06.1B Bedroom	0.52
A.15.07.1B Bedroom	0.60
A.15.08.2B Bedroom	0.65
A.15.08.2B Bedroom	0.49
A.15.09.2B Bedroom	0.57

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.15.09.2B Bedroom	0.49
A.15.10.2B Bedroom	0.46
A.15.10.2B Bedroom	0.52
A.16.01.1B Bedroom	0.54
A.16.02.1B Bedroom	0.52
A.16.03.2B Bedroom	1.17
A.16.03.2B Bedroom	0.76
A.16.04.2B Bedroom	1.28
A.16.04.2B Bedroom	1.06
A.16.05.2B Bedroom	0.95
A.16.05.2B Bedroom	0.65
A.16.06.1B Bedroom	0.52
A.16.07.1B Bedroom	0.60
A.16.08.2B Bedroom	0.65
A.16.08.2B Bedroom	0.49
A.16.09.2B Bedroom	0.49
A.16.09.2B Bedroom	0.57
A.16.10.2B Bedroom	0.52
A.16.10.2B Bedroom	0.46
A.17.01.1B Bedroom	0.54
A.17.02.1B Bedroom	0.52
A.17.03.2B Bedroom	0.76
A.17.03.2B Bedroom	1.17
A.17.04.2B Bedroom	1.09
A.17.04.2B Bedroom	1.28

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.17.05.2B Bedroom	0.95
A.17.05.2B Bedroom	0.65
A.17.06.1B Bedroom	0.52
A.17.07.1B Bedroom	0.60
A.17.08.2B Bedroom	0.65
A.17.08.2B Bedroom	0.49
A.17.09.2B Bedroom	0.57
A.17.09.2B Bedroom	0.49
A.17.10.2B Bedroom	0.52
A.17.10.2B Bedroom	0.46
A.18.01.1B Bedroom	0.54
A.18.02.1B Bedroom	0.52
A.18.03.2B Bedroom	1.17
A.18.03.2B Bedroom	0.76
A.18.04.2B Bedroom	1.28
A.18.04.2B Bedroom	1.06
A.18.05.2B Bedroom	0.95
A.18.05.2B Bedroom	0.65
A.18.06.1B Bedroom	0.52
A.18.07.1B Bedroom	0.60
A.18.08.2B Bedroom	0.49
A.18.08.2B Bedroom	0.65
A.18.09.2B Bedroom	0.57
A.18.09.2B Bedroom	0.49
A.18.10.2B Bedroom	0.46

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.18.10.2B Bedroom	0.52
A.19.01.1B Bedroom	0.54
A.19.02.1B Bedroom	0.52
A.19.03.2B Bedroom	0.76
A.19.03.2B Bedroom	1.17
A.19.04.2B Bedroom	1.06
A.19.04.2B Bedroom	1.28
A.19.05.2B Bedroom	0.95
A.19.05.2B Bedroom	0.65
A.19.06.1B Bedroom	0.52
A.19.07.1B Bedroom	0.60
A.19.08.2B Bedroom	0.65
A.19.08.2B Bedroom	0.49
A.19.09.2B Bedroom	0.49
A.19.09.2B Bedroom	0.57
A.19.10.2B Bedroom	0.52
A.19.10.2B Bedroom	0.46
A.20.01.1B Bedroom	0.54
A.20.02.1B Bedroom	0.52
A.20.03.2B Bedroom	0.76
A.20.03.2B Bedroom	1.17
A.20.04.2B Bedroom	1.06
A.20.04.2B Bedroom	1.28
A.20.05.2B Bedroom	0.95
A.20.05.2B Bedroom	0.65

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.20.06.1B Bedroom	0.52
A.20.07.1B Bedroom	0.60
A.20.08.2B Bedroom	0.65
A.20.08.2B Bedroom	0.49
A.20.09.2B Bedroom	0.57
A.20.09.2B Bedroom	0.49
A.20.10.2B Bedroom	0.46
A.20.10.2B Bedroom	0.52
A.21.01.1B Bedroom	0.54
A.21.02.1B Bedroom	0.52
A.21.03.2B Bedroom	0.76
A.21.03.2B Bedroom	1.17
A.21.04.2B Bedroom	1.06
A.21.04.2B Bedroom	1.28
A.21.05.2B Bedroom	0.65
A.21.05.2B Bedroom	0.95
A.21.06.1B Bedroom	0.52
A.21.07.1B Bedroom	0.60
A.21.08.2B Bedroom	0.65
A.21.08.2B Bedroom	0.49
A.21.09.2B Bedroom	0.49
A.21.09.2B Bedroom	0.57
A.21.10.2B Bedroom	0.46
A.21.10.2B Bedroom	0.52
A.22.01.1B Bedroom	0.54

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.22.02.1B Bedroom	0.52
A.22.03.2B Bedroom	0.68
A.22.03.2B Bedroom	1.14
A.22.04.2B Bedroom	1.20
A.22.04.2B Bedroom	1.01
A.22.05.2B Bedroom	0.93
A.22.05.2B Bedroom	0.65
A.22.06.1B Bedroom	0.52
A.22.07.1B Bedroom	0.60
A.22.08.2B Bedroom	0.49
A.22.08.2B Bedroom	0.63
A.22.09.2B Bedroom	0.57
A.22.09.2B Bedroom	0.49
A.22.10.2B Bedroom	0.46
A.22.10.2B Bedroom	0.52
A.23.01.1B Bedroom	0.54
A.23.02.1B Bedroom	0.52
A.23.03.2B Bedroom	1.12
A.23.03.2B Bedroom	0.68
A.23.04.2B Bedroom	1.01
A.23.04.2B Bedroom	1.20
A.23.05.2B Bedroom	0.93
A.23.05.2B Bedroom	0.65
A.23.06.1B Bedroom	0.52
A.23.07.1B Bedroom	0.60

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.23.08.2B Bedroom	0.49
A.23.08.2B Bedroom	0.63
A.23.09.2B Bedroom	0.49
A.23.09.2B Bedroom	0.57
A.23.10.2B Bedroom	0.52
A.23.10.2B Bedroom	0.46
A.24.01.1B Bedroom	0.54
A.24.02.1B Bedroom	0.52
A.24.03.2B Bedroom	1.14
A.24.03.2B Bedroom	0.68
A.24.04.2B Bedroom	1.20
A.24.04.2B Bedroom	0.98
A.24.05.2B Bedroom	0.93
A.24.05.2B Bedroom	0.65
A.24.06.1B Bedroom	0.52
A.24.07.1B Bedroom	0.60
A.24.08.2B Bedroom	0.63
A.24.08.2B Bedroom	0.49
A.24.09.2B Bedroom	0.49
A.24.09.2B Bedroom	0.57
A.24.10.2B Bedroom	0.52
A.24.10.2B Bedroom	0.46
A.25.01.1B Bedroom	0.54
A.25.02.1B Bedroom	0.52
A.25.03.2B Bedroom	1.14

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.25.03.2B Bedroom	0.68
A.25.04.2B Bedroom	1.01
A.25.04.2B Bedroom	1.20
A.25.05.2B Bedroom	0.93
A.25.05.2B Bedroom	0.65
A.25.06.1B Bedroom	0.52
A.25.07.1B Bedroom	0.60
A.25.08.2B Bedroom	0.63
A.25.08.2B Bedroom	0.49
A.25.09.2B Bedroom	0.57
A.25.09.2B Bedroom	0.49
A.25.10.2B Bedroom	0.52
A.25.10.2B Bedroom	0.46
A.26.01.1B Bedroom	0.54
A.26.02.1B Bedroom	0.52
A.26.03.2B Bedroom	0.68
A.26.03.2B Bedroom	1.14
A.26.04.2B Bedroom	0.98
A.26.04.2B Bedroom	1.20
A.26.05.2B Bedroom	0.65
A.26.05.2B Bedroom	0.93
A.26.06.1B Bedroom	0.52
A.26.07.1B Bedroom	0.60
A.26.08.2B Bedroom	0.49
A.26.08.2B Bedroom	0.63

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.26.09.2B Bedroom	0.49
A.26.09.2B Bedroom	0.57
A.26.10.2B Bedroom	0.46
A.26.10.2B Bedroom	0.52
A.27.01.1B Bedroom	0.54
A.27.02.1B Bedroom	0.52
A.27.03.2B Bedroom	0.68
A.27.03.2B Bedroom	1.14
A.27.04.2B Bedroom	1.20
A.27.04.2B Bedroom	1.01
A.27.05.2B Bedroom	0.65
A.27.05.2B Bedroom	0.93
A.27.06.1B Bedroom	0.52
A.27.07.1B Bedroom	0.60
A.27.08.2B Bedroom	0.63
A.27.08.2B Bedroom	0.49
A.27.09.2B Bedroom	0.57
A.27.09.2B Bedroom	0.49
A.27.10.2B Bedroom	0.46
A.27.10.2B Bedroom	0.52
A.28.01.1B Bedroom	0.54
A.28.02.1B Bedroom	0.52
A.28.03.2B Bedroom	1.14
A.28.03.2B Bedroom	0.68
A.28.04.2B Bedroom	1.20

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.28.04.2B Bedroom	0.98
A.28.05.2B Bedroom	0.93
A.28.05.2B Bedroom	0.65
A.28.06.1B Bedroom	0.52
A.28.07.1B Bedroom	0.60
A.28.08.2B Bedroom	0.63
A.28.08.2B Bedroom	0.49
A.28.09.2B Bedroom	0.57
A.28.09.2B Bedroom	0.49
A.28.10.2B Bedroom	0.46
A.28.10.2B Bedroom	0.52
A.29.01.1B Bedroom	0.54
A.29.02.1B Bedroom	0.52
A.29.03.2B Bedroom	1.14
A.29.03.2B Bedroom	0.68
A.29.04.2B Bedroom	1.01
A.29.04.2B Bedroom	1.20
A.29.05.2B Bedroom	0.65
A.29.05.2B Bedroom	0.93
A.29.06.1B Bedroom	0.52
A.29.07.1B Bedroom	0.60
A.29.08.2B Bedroom	0.49
A.29.08.2B Bedroom	0.63
A.29.09.2B Bedroom	0.57
A.29.09.2B Bedroom	0.49

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.29.10.2B Bedroom	0.46
A.29.10.2B Bedroom	0.52
A.30.01.1B Bedroom	0.54
A.30.02.1B Bedroom	0.52
A.30.03.2B Bedroom	0.68
A.30.03.2B Bedroom	1.14
A.30.04.2B Bedroom	1.20
A.30.04.2B Bedroom	0.98
A.30.05.2B Bedroom	0.65
A.30.05.2B Bedroom	0.93
A.30.06.1B Bedroom	0.52
A.30.07.1B Bedroom	0.60
A.30.08.2B Bedroom	0.49
A.30.08.2B Bedroom	0.63
A.30.09.2B Bedroom	0.57
A.30.09.2B Bedroom	0.49
A.30.10.2B Bedroom	0.52
A.30.10.2B Bedroom	0.46
A.31.01.1B Bedroom	0.52
A.31.02.1B Bedroom	0.52
A.31.03.2B Bedroom	0.68
A.31.03.2B Bedroom	1.12
A.31.04.2B Bedroom	1.14
A.31.04.2B Bedroom	0.95
A.31.05.2B Bedroom	0.65

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.31.05.2B Bedroom	0.93
A.31.06.1B Bedroom	0.52
A.31.07.1B Bedroom	0.57
A.31.08.2B Bedroom	0.63
A.31.08.2B Bedroom	0.49
A.31.09.2B Bedroom	0.57
A.31.09.2B Bedroom	0.49
A.31.10.2B Bedroom	0.52
A.31.10.2B Bedroom	0.46
A.32.01.1B Bedroom	0.52
A.32.02.1B Bedroom	0.52
A.32.03.2B Bedroom	0.68
A.32.03.2B Bedroom	1.12
A.32.04.2B Bedroom	1.14
A.32.04.2B Bedroom	0.95
A.32.05.2B Bedroom	0.93
A.32.05.2B Bedroom	0.63
A.32.06.1B Bedroom	0.52
A.32.07.1B Bedroom	0.57
A.32.08.2B Bedroom	0.49
A.32.08.2B Bedroom	0.63
A.32.09.2B Bedroom	0.49
A.32.09.2B Bedroom	0.57
A.32.10.2B Bedroom	0.52
A.32.10.2B Bedroom	0.46

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.33.01.1B Bedroom	0.52
A.33.02.1B Bedroom	0.52
A.33.03.2B Bedroom	1.12
A.33.03.2B Bedroom	0.68
A.33.04.2B Bedroom	1.14
A.33.04.2B Bedroom	0.95
A.33.05.2B Bedroom	0.63
A.33.05.2B Bedroom	0.93
A.33.06.1B Bedroom	0.52
A.33.07.1B Bedroom	0.57
A.33.08.2B Bedroom	0.49
A.33.08.2B Bedroom	0.63
A.33.09.2B Bedroom	0.57
A.33.09.2B Bedroom	0.49
A.33.10.2B Bedroom	0.52
A.33.10.2B Bedroom	0.46
A.34.01.1B Bedroom	0.52
A.34.02.1B Bedroom	0.52
A.34.03.2B Bedroom	0.68
A.34.03.2B Bedroom	1.12
A.34.04.2B Bedroom	0.95
A.34.04.2B Bedroom	1.14
A.34.05.2B Bedroom	0.63
A.34.05.2B Bedroom	0.93
A.34.06.1B Bedroom	0.52

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.34.07.1B Bedroom	0.57
A.34.08.2B Bedroom	0.49
A.34.08.2B Bedroom	0.63
A.34.09.2B Bedroom	0.57
A.34.09.2B Bedroom	0.49
A.34.10.2B Bedroom	0.52
A.34.10.2B Bedroom	0.46
A.35.01.1B Bedroom	0.52
A.35.02.1B Bedroom	0.52
A.35.03.2B Bedroom	1.12
A.35.03.2B Bedroom	0.68
A.35.04.2B Bedroom	1.14
A.35.04.2B Bedroom	0.95
A.35.05.2B Bedroom	0.63
A.35.05.2B Bedroom	0.93
A.35.06.1B Bedroom	0.52
A.35.07.1B Bedroom	0.57
A.35.08.2B Bedroom	0.49
A.35.08.2B Bedroom	0.63
A.35.09.2B Bedroom	0.57
A.35.09.2B Bedroom	0.49
A.35.10.2B Bedroom	0.46
A.35.10.2B Bedroom	0.52
A.36.01.1B Bedroom	0.52
A.36.02.1B Bedroom	0.52

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.36.03.2B Bedroom	1.12
A.36.03.2B Bedroom	0.68
A.36.04.2B Bedroom	1.14
A.36.04.2B Bedroom	0.95
A.36.05.2B Bedroom	0.93
A.36.05.2B Bedroom	0.63
A.36.06.1B Bedroom	0.52
A.36.07.1B Bedroom	0.57
A.36.08.2B Bedroom	0.49
A.36.08.2B Bedroom	0.63
A.36.09.2B Bedroom	0.49
A.36.09.2B Bedroom	0.57
A.36.10.2B Bedroom	0.52
A.36.10.2B Bedroom	0.46
A.37.01.1B Bedroom	0.52
A.37.02.1B Bedroom	0.52
A.37.03.2B Bedroom	0.68
A.37.03.2B Bedroom	1.12
A.37.04.2B Bedroom	0.95
A.37.04.2B Bedroom	1.14
A.37.05.2B Bedroom	0.63
A.37.05.2B Bedroom	0.93
A.37.06.1B Bedroom	0.52
A.37.07.1B Bedroom	0.57
A.37.08.2B Bedroom	0.49

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.37.08.2B Bedroom	0.63
A.37.09.2B Bedroom	0.57
A.37.09.2B Bedroom	0.49
A.37.10.2B Bedroom	0.46
A.37.10.2B Bedroom	0.52
A.38.01.1B Bedroom	0.52
A.38.02.1B Bedroom	0.52
A.38.03.2B Bedroom	0.68
A.38.03.2B Bedroom	1.12
A.38.04.2B Bedroom	0.95
A.38.04.2B Bedroom	1.14
A.38.05.2B Bedroom	0.63
A.38.05.2B Bedroom	0.93
A.38.06.1B Bedroom	0.52
A.38.07.1B Bedroom	0.57
A.38.08.2B Bedroom	0.49
A.38.08.2B Bedroom	0.63
A.38.09.2B Bedroom	0.49
A.38.09.2B Bedroom	0.57
A.38.10.2B Bedroom	0.46
A.38.10.2B Bedroom	0.52
A.39.01.1B Bedroom	0.52
A.39.02.1B Bedroom	0.52
A.39.03.2B Bedroom	1.12
A.39.03.2B Bedroom	0.68

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.39.04.2B Bedroom	0.95
A.39.04.2B Bedroom	1.14
A.39.05.2B Bedroom	0.65
A.39.05.2B Bedroom	0.93
A.39.06.1B Bedroom	0.52
A.39.07.1B Bedroom	0.57
A.39.08.2B Bedroom	0.49
A.39.08.2B Bedroom	0.63
A.39.09.2B Bedroom	0.49
A.39.09.2B Bedroom	0.57
A.39.10.2B Bedroom	0.52
A.39.10.2B Bedroom	0.46
A.40.01.1B Bedroom	0.54
A.40.02.1B Bedroom	0.52
A.40.03.2B Bedroom	1.17
A.40.03.2B Bedroom	0.74
A.40.04.2B Bedroom	1.23
A.40.04.2B Bedroom	1.06
A.40.05.2B Bedroom	0.98
A.40.05.2B Bedroom	0.68
A.40.06.1B Bedroom	0.52
A.40.07.1B Bedroom	0.60
A.40.08.2B Bedroom	0.49
A.40.08.2B Bedroom	0.65
A.40.09.2B Bedroom	0.57

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.40.09.2B Bedroom	0.49
A.40.10.2B Bedroom	0.46
A.40.10.2B Bedroom	0.52
A.41.01.1B Bedroom	0.54
A.41.02.1B Bedroom	0.52
A.41.03.2B Bedroom	1.17
A.41.03.2B Bedroom	0.74
A.41.04.2B Bedroom	1.23
A.41.04.2B Bedroom	1.06
A.41.05.2B Bedroom	0.68
A.41.05.2B Bedroom	0.98
A.41.06.1B Bedroom	0.52
A.41.07.1B Bedroom	0.60
A.41.08.2B Bedroom	0.49
A.41.08.2B Bedroom	0.65
A.41.09.2B Bedroom	0.49
A.41.09.2B Bedroom	0.57
A.41.10.2B Bedroom	0.52
A.41.10.2B Bedroom	0.46
A.42.01.1B Bedroom	0.54
A.42.02.1B Bedroom	0.52
A.42.03.2B Bedroom	0.74
A.42.03.2B Bedroom	1.17
A.42.04.2B Bedroom	1.06
A.42.04.2B Bedroom	1.23

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.42.05.2B Bedroom	0.68
A.42.05.2B Bedroom	0.98
A.42.06.1B Bedroom	0.52
A.42.07.1B Bedroom	0.60
A.42.08.2B Bedroom	0.49
A.42.08.2B Bedroom	0.65
A.42.09.2B Bedroom	0.57
A.42.09.2B Bedroom	0.49
A.42.10.2B Bedroom	0.46
A.42.10.2B Bedroom	0.52
A.43.01.1B Bedroom	0.54
A.43.02.1B Bedroom	0.52
A.43.03.2B Bedroom	1.17
A.43.03.2B Bedroom	0.74
A.43.04.2B Bedroom	1.23
A.43.04.2B Bedroom	1.06
A.43.05.2B Bedroom	0.98
A.43.05.2B Bedroom	0.68
A.43.06.1B Bedroom	0.52
A.43.07.1B Bedroom	0.60
A.43.08.2B Bedroom	0.65
A.43.08.2B Bedroom	0.49
A.43.09.2B Bedroom	0.49
A.43.09.2B Bedroom	0.57
A.43.10.2B Bedroom	0.52

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.43.10.2B Bedroom	0.46
A.44.01.1B Bedroom	0.57
A.44.02.1B Bedroom	0.52
A.44.03.2B Bedroom	1.20
A.44.03.2B Bedroom	0.74
A.44.04.2B Bedroom	1.20
A.44.04.2B Bedroom	0.98
A.44.05.2B Bedroom	0.98
A.44.05.2B Bedroom	0.65
A.44.06.1B Bedroom	0.52
A.44.07.1B Bedroom	0.60
A.44.08.2B Bedroom	0.49
A.44.08.2B Bedroom	0.65
A.44.09.2B Bedroom	0.49
A.44.09.2B Bedroom	0.57
A.44.10.2B Bedroom	0.46
A.44.10.2B Bedroom	0.52
A.45.01.3B Bedroom	0.57
A.45.01.3B Bedroom	0.52
A.45.01.3B Bedroom	1.12
A.45.02.3B Bedroom	1.14
A.45.02.3B Bedroom	0.60
A.45.02.3B Bedroom	1.09
A.45.03.3B Bedroom	0.98
A.45.03.3B Bedroom	0.71

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.45.03.3B Bedroom	0.63
A.45.04.3B Bedroom	0.65
A.45.04.3B Bedroom	0.41
A.45.04.3B Bedroom	0.46
A.45.05.3B Bedroom	0.46
A.45.05.3B Bedroom	0.46
A.45.05.3B Bedroom	0.44
A.45.06.3B Bedroom	0.52
A.45.06.3B Bedroom	0.49
A.45.06.3B Bedroom	0.49

11.0 Appendix 5: DSY 2: Bedroom Night-time Temperature Test Block A

Location	Operative Temperature > 26 (Max 1%)
A.02.01.1B Bedroom	0.57
A.02.02.1B Bedroom	0.22
A.02.03.2B Bedroom	0.27
A.02.03.2B Bedroom	0.25
A.02.04.2B Bedroom	0.27
A.02.04.2B Bedroom	0.25
A.02.05.2B Bedroom	0.25
A.02.05.2B Bedroom	0.25
A.02.06.1B Bedroom	0.22
A.02.07.1B Bedroom	0.22
A.02.08.2B Bedroom	0.25
A.02.08.2B Bedroom	0.22
A.02.09.2B Bedroom	0.25
A.02.09.2B Bedroom	0.22
A.02.10.2B Bedroom	0.25
A.02.10.2B Bedroom	0.25
A.03.01.1B Bedroom	0.27
A.03.02.1B Bedroom	0.27
A.03.03.2B Bedroom	0.33
A.03.03.2B Bedroom	0.30
A.03.04.2B Bedroom	0.27
A.03.04.2B Bedroom	0.35
A.03.05.2B Bedroom	0.27
A.03.05.2B Bedroom	0.27
A.03.06.1B Bedroom	0.25
A.03.07.1B Bedroom	0.25
A.03.08.2B Bedroom	0.30
A.03.08.2B Bedroom	0.33
A.03.09.2B Bedroom	0.30
A.03.09.2B Bedroom	0.27
A.03.10.2B Bedroom	0.27
A.03.10.2B Bedroom	0.33
A.04.01.1B Bedroom	0.27
A.04.02.1B Bedroom	0.27
A.04.03.2B Bedroom	0.30
A.04.03.2B Bedroom	0.30
A.04.04.2B Bedroom	0.35
A.04.04.2B Bedroom	0.27
A.04.05.2B Bedroom	0.27
A.04.05.2B Bedroom	0.27
A.04.06.1B Bedroom	0.25
A.04.07.1B Bedroom	0.25
A.04.08.2B Bedroom	0.30
A.04.08.2B Bedroom	0.30
A.04.09.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.04.09.2B Bedroom	0.27
A.04.10.2B Bedroom	0.27
A.04.10.2B Bedroom	0.33
A.05.01.1B Bedroom	0.27
A.05.02.1B Bedroom	0.27
A.05.03.2B Bedroom	0.30
A.05.03.2B Bedroom	0.30
A.05.04.2B Bedroom	0.35
A.05.04.2B Bedroom	0.27
A.05.05.2B Bedroom	0.27
A.05.05.2B Bedroom	0.27
A.05.06.1B Bedroom	0.25
A.05.07.1B Bedroom	0.25
A.05.08.2B Bedroom	0.30
A.05.08.2B Bedroom	0.30
A.05.09.2B Bedroom	0.27
A.05.09.2B Bedroom	0.27
A.05.10.2B Bedroom	0.27
A.05.10.2B Bedroom	0.33
A.06.01.1B Bedroom	0.27
A.06.02.1B Bedroom	0.27
A.06.03.2B Bedroom	0.30
A.06.03.2B Bedroom	0.30
A.06.04.2B Bedroom	0.35
A.06.04.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.06.05.2B Bedroom	0.27
A.06.05.2B Bedroom	0.27
A.06.06.1B Bedroom	0.25
A.06.07.1B Bedroom	0.25
A.06.08.2B Bedroom	0.30
A.06.08.2B Bedroom	0.30
A.06.09.2B Bedroom	0.27
A.06.09.2B Bedroom	0.27
A.06.10.2B Bedroom	0.33
A.06.10.2B Bedroom	0.27
A.07.01.1B Bedroom	0.27
A.07.02.1B Bedroom	0.27
A.07.03.2B Bedroom	0.30
A.07.03.2B Bedroom	0.30
A.07.04.2B Bedroom	0.27
A.07.04.2B Bedroom	0.35
A.07.05.2B Bedroom	0.27
A.07.05.2B Bedroom	0.27
A.07.06.1B Bedroom	0.25
A.07.07.1B Bedroom	0.25
A.07.08.2B Bedroom	0.30
A.07.08.2B Bedroom	0.30
A.07.09.2B Bedroom	0.27
A.07.09.2B Bedroom	0.27
A.07.10.2B Bedroom	0.33

Location	Operative Temperature > 26 (Max 1%)
A.07.10.2B Bedroom	0.27
A.08.01.1B Bedroom	0.27
A.08.02.1B Bedroom	0.27
A.08.03.2B Bedroom	0.30
A.08.03.2B Bedroom	0.30
A.08.04.2B Bedroom	0.35
A.08.04.2B Bedroom	0.27
A.08.05.2B Bedroom	0.27
A.08.05.2B Bedroom	0.27
A.08.06.1B Bedroom	0.25
A.08.07.1B Bedroom	0.25
A.08.08.2B Bedroom	0.30
A.08.08.2B Bedroom	0.30
A.08.09.2B Bedroom	0.27
A.08.09.2B Bedroom	0.27
A.08.10.2B Bedroom	0.33
A.08.10.2B Bedroom	0.27
A.09.01.1B Bedroom	0.27
A.09.02.1B Bedroom	0.27
A.09.03.2B Bedroom	0.30
A.09.03.2B Bedroom	0.30
A.09.04.2B Bedroom	0.27
A.09.04.2B Bedroom	0.35
A.09.05.2B Bedroom	0.27
A.09.05.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.09.06.1B Bedroom	0.25
A.09.07.1B Bedroom	0.25
A.09.08.2B Bedroom	0.30
A.09.08.2B Bedroom	0.30
A.09.09.2B Bedroom	0.27
A.09.09.2B Bedroom	0.27
A.09.10.2B Bedroom	0.27
A.09.10.2B Bedroom	0.33
A.10.01.1B Bedroom	0.27
A.10.02.1B Bedroom	0.27
A.10.03.2B Bedroom	0.30
A.10.03.2B Bedroom	0.30
A.10.04.2B Bedroom	0.27
A.10.04.2B Bedroom	0.35
A.10.05.2B Bedroom	0.27
A.10.05.2B Bedroom	0.27
A.10.06.1B Bedroom	0.25
A.10.07.1B Bedroom	0.25
A.10.08.2B Bedroom	0.30
A.10.08.2B Bedroom	0.30
A.10.09.2B Bedroom	0.30
A.10.09.2B Bedroom	0.27
A.10.10.2B Bedroom	0.27
A.10.10.2B Bedroom	0.33
A.11.01.1B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.11.02.1B Bedroom	0.27
A.11.03.2B Bedroom	0.30
A.11.03.2B Bedroom	0.30
A.11.04.2B Bedroom	0.27
A.11.04.2B Bedroom	0.35
A.11.05.2B Bedroom	0.27
A.11.05.2B Bedroom	0.27
A.11.06.1B Bedroom	0.25
A.11.07.1B Bedroom	0.25
A.11.08.2B Bedroom	0.30
A.11.08.2B Bedroom	0.30
A.11.09.2B Bedroom	0.27
A.11.09.2B Bedroom	0.30
A.11.10.2B Bedroom	0.33
A.11.10.2B Bedroom	0.27
A.12.01.1B Bedroom	0.27
A.12.02.1B Bedroom	0.27
A.12.03.2B Bedroom	0.30
A.12.03.2B Bedroom	0.30
A.12.04.2B Bedroom	0.30
A.12.04.2B Bedroom	0.35
A.12.05.2B Bedroom	0.27
A.12.05.2B Bedroom	0.27
A.12.06.1B Bedroom	0.25
A.12.07.1B Bedroom	0.25

Location	Operative Temperature > 26 (Max 1%)
A.12.08.2B Bedroom	0.30
A.12.08.2B Bedroom	0.30
A.12.09.2B Bedroom	0.27
A.12.09.2B Bedroom	0.30
A.12.10.2B Bedroom	0.27
A.12.10.2B Bedroom	0.33
A.13.01.1B Bedroom	0.27
A.13.02.1B Bedroom	0.27
A.13.03.2B Bedroom	0.30
A.13.03.2B Bedroom	0.30
A.13.05.2B Bedroom	0.30
A.13.05.2B Bedroom	0.30
A.13.06.1B Bedroom	0.27
A.13.07.1B Bedroom	0.30
A.13.08.2B Bedroom	0.30
A.13.08.2B Bedroom	0.38
A.13.09.2B Bedroom	0.30
A.13.09.2B Bedroom	0.27
A.13.10.2B Bedroom	0.33
A.13.10.2B Bedroom	0.25
A.13.13.2B Bedroom	0.35
A.13.13.2B Bedroom	0.35
A.14.01.1B Bedroom	0.27
A.14.02.1B Bedroom	0.27
A.14.03.2B Bedroom	0.30

Location	Operative Temperature > 26 (Max 1%)
A.14.03.2B Bedroom	0.30
A.14.04.2B Bedroom	0.27
A.14.04.2B Bedroom	0.27
A.14.05.2B Bedroom	0.27
A.14.05.2B Bedroom	0.27
A.14.06.1B Bedroom	0.25
A.14.07.1B Bedroom	0.25
A.14.08.2B Bedroom	0.30
A.14.08.2B Bedroom	0.30
A.14.09.2B Bedroom	0.27
A.14.09.2B Bedroom	0.27
A.14.10.2B Bedroom	0.33
A.14.10.2B Bedroom	0.25
A.15.01.1B Bedroom	0.27
A.15.02.1B Bedroom	0.27
A.15.03.2B Bedroom	0.30
A.15.03.2B Bedroom	0.27
A.15.04.2B Bedroom	0.27
A.15.04.2B Bedroom	0.27
A.15.05.2B Bedroom	0.27
A.15.05.2B Bedroom	0.27
A.15.06.1B Bedroom	0.25
A.15.07.1B Bedroom	0.25
A.15.08.2B Bedroom	0.27
A.15.08.2B Bedroom	0.30

Location	Operative Temperature > 26 (Max 1%)
A.15.09.2B Bedroom	0.27
A.15.09.2B Bedroom	0.27
A.15.10.2B Bedroom	0.33
A.15.10.2B Bedroom	0.25
A.16.01.1B Bedroom	0.27
A.16.02.1B Bedroom	0.27
A.16.03.2B Bedroom	0.27
A.16.03.2B Bedroom	0.30
A.16.04.2B Bedroom	0.27
A.16.04.2B Bedroom	0.27
A.16.05.2B Bedroom	0.27
A.16.05.2B Bedroom	0.27
A.16.06.1B Bedroom	0.25
A.16.07.1B Bedroom	0.25
A.16.08.2B Bedroom	0.27
A.16.08.2B Bedroom	0.30
A.16.09.2B Bedroom	0.27
A.16.09.2B Bedroom	0.27
A.16.10.2B Bedroom	0.25
A.16.10.2B Bedroom	0.33
A.17.01.1B Bedroom	0.27
A.17.02.1B Bedroom	0.27
A.17.03.2B Bedroom	0.30
A.17.03.2B Bedroom	0.27
A.17.04.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.17.04.2B Bedroom	0.27
A.17.05.2B Bedroom	0.27
A.17.05.2B Bedroom	0.27
A.17.06.1B Bedroom	0.25
A.17.07.1B Bedroom	0.25
A.17.08.2B Bedroom	0.27
A.17.08.2B Bedroom	0.30
A.17.09.2B Bedroom	0.27
A.17.09.2B Bedroom	0.27
A.17.10.2B Bedroom	0.25
A.17.10.2B Bedroom	0.33
A.18.01.1B Bedroom	0.27
A.18.02.1B Bedroom	0.27
A.18.03.2B Bedroom	0.27
A.18.03.2B Bedroom	0.30
A.18.04.2B Bedroom	0.27
A.18.04.2B Bedroom	0.27
A.18.05.2B Bedroom	0.27
A.18.05.2B Bedroom	0.27
A.18.06.1B Bedroom	0.25
A.18.07.1B Bedroom	0.25
A.18.08.2B Bedroom	0.30
A.18.08.2B Bedroom	0.27
A.18.09.2B Bedroom	0.27
A.18.09.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.18.10.2B Bedroom	0.30
A.18.10.2B Bedroom	0.25
A.19.01.1B Bedroom	0.27
A.19.02.1B Bedroom	0.27
A.19.03.2B Bedroom	0.30
A.19.03.2B Bedroom	0.27
A.19.04.2B Bedroom	0.27
A.19.04.2B Bedroom	0.27
A.19.05.2B Bedroom	0.27
A.19.05.2B Bedroom	0.27
A.19.06.1B Bedroom	0.25
A.19.07.1B Bedroom	0.25
A.19.08.2B Bedroom	0.27
A.19.08.2B Bedroom	0.30
A.19.09.2B Bedroom	0.27
A.19.09.2B Bedroom	0.27
A.19.10.2B Bedroom	0.25
A.19.10.2B Bedroom	0.33
A.20.01.1B Bedroom	0.27
A.20.02.1B Bedroom	0.27
A.20.03.2B Bedroom	0.30
A.20.03.2B Bedroom	0.27
A.20.04.2B Bedroom	0.27
A.20.04.2B Bedroom	0.27
A.20.05.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.20.05.2B Bedroom	0.27
A.20.06.1B Bedroom	0.25
A.20.07.1B Bedroom	0.25
A.20.08.2B Bedroom	0.27
A.20.08.2B Bedroom	0.30
A.20.09.2B Bedroom	0.27
A.20.09.2B Bedroom	0.27
A.20.10.2B Bedroom	0.33
A.20.10.2B Bedroom	0.25
A.21.01.1B Bedroom	0.27
A.21.02.1B Bedroom	0.27
A.21.03.2B Bedroom	0.30
A.21.03.2B Bedroom	0.27
A.21.04.2B Bedroom	0.27
A.21.04.2B Bedroom	0.27
A.21.05.2B Bedroom	0.27
A.21.05.2B Bedroom	0.27
A.21.06.1B Bedroom	0.25
A.21.07.1B Bedroom	0.25
A.21.08.2B Bedroom	0.27
A.21.08.2B Bedroom	0.30
A.21.09.2B Bedroom	0.27
A.21.09.2B Bedroom	0.27
A.21.10.2B Bedroom	0.30
A.21.10.2B Bedroom	0.25

Location	Operative Temperature > 26 (Max 1%)
A.22.01.1B Bedroom	0.25
A.22.02.1B Bedroom	0.25
A.22.03.2B Bedroom	0.30
A.22.03.2B Bedroom	0.27
A.22.04.2B Bedroom	0.27
A.22.04.2B Bedroom	0.27
A.22.05.2B Bedroom	0.27
A.22.05.2B Bedroom	0.27
A.22.06.1B Bedroom	0.25
A.22.07.1B Bedroom	0.25
A.22.08.2B Bedroom	0.30
A.22.08.2B Bedroom	0.27
A.22.09.2B Bedroom	0.27
A.22.09.2B Bedroom	0.27
A.22.10.2B Bedroom	0.30
A.22.10.2B Bedroom	0.25
A.23.01.1B Bedroom	0.25
A.23.02.1B Bedroom	0.25
A.23.03.2B Bedroom	0.27
A.23.03.2B Bedroom	0.30
A.23.04.2B Bedroom	0.27
A.23.04.2B Bedroom	0.27
A.23.05.2B Bedroom	0.27
A.23.05.2B Bedroom	0.27
A.23.06.1B Bedroom	0.25

Location	Operative Temperature > 26 (Max 1%)
A.23.07.1B Bedroom	0.25
A.23.08.2B Bedroom	0.30
A.23.08.2B Bedroom	0.27
A.23.09.2B Bedroom	0.27
A.23.09.2B Bedroom	0.27
A.23.10.2B Bedroom	0.25
A.23.10.2B Bedroom	0.30
A.24.01.1B Bedroom	0.25
A.24.02.1B Bedroom	0.25
A.24.03.2B Bedroom	0.27
A.24.03.2B Bedroom	0.30
A.24.04.2B Bedroom	0.27
A.24.04.2B Bedroom	0.27
A.24.05.2B Bedroom	0.27
A.24.05.2B Bedroom	0.27
A.24.06.1B Bedroom	0.25
A.24.07.1B Bedroom	0.25
A.24.08.2B Bedroom	0.27
A.24.08.2B Bedroom	0.30
A.24.09.2B Bedroom	0.27
A.24.09.2B Bedroom	0.27
A.24.10.2B Bedroom	0.25
A.24.10.2B Bedroom	0.30
A.25.01.1B Bedroom	0.25
A.25.02.1B Bedroom	0.25

Location	Operative Temperature > 26 (Max 1%)
A.25.03.2B Bedroom	0.27
A.25.03.2B Bedroom	0.30
A.25.04.2B Bedroom	0.27
A.25.04.2B Bedroom	0.27
A.25.05.2B Bedroom	0.27
A.25.05.2B Bedroom	0.27
A.25.06.1B Bedroom	0.25
A.25.07.1B Bedroom	0.25
A.25.08.2B Bedroom	0.27
A.25.08.2B Bedroom	0.30
A.25.09.2B Bedroom	0.27
A.25.09.2B Bedroom	0.27
A.25.10.2B Bedroom	0.25
A.25.10.2B Bedroom	0.30
A.26.01.1B Bedroom	0.25
A.26.02.1B Bedroom	0.25
A.26.03.2B Bedroom	0.30
A.26.03.2B Bedroom	0.27
A.26.04.2B Bedroom	0.27
A.26.04.2B Bedroom	0.27
A.26.05.2B Bedroom	0.27
A.26.05.2B Bedroom	0.27
A.26.06.1B Bedroom	0.25
A.26.07.1B Bedroom	0.25
A.26.08.2B Bedroom	0.30

Location	Operative Temperature > 26 (Max 1%)
A.26.08.2B Bedroom	0.27
A.26.09.2B Bedroom	0.27
A.26.09.2B Bedroom	0.27
A.26.10.2B Bedroom	0.30
A.26.10.2B Bedroom	0.25
A.27.01.1B Bedroom	0.25
A.27.02.1B Bedroom	0.25
A.27.03.2B Bedroom	0.30
A.27.03.2B Bedroom	0.27
A.27.04.2B Bedroom	0.27
A.27.04.2B Bedroom	0.27
A.27.05.2B Bedroom	0.27
A.27.05.2B Bedroom	0.27
A.27.06.1B Bedroom	0.25
A.27.07.1B Bedroom	0.25
A.27.08.2B Bedroom	0.27
A.27.08.2B Bedroom	0.30
A.27.09.2B Bedroom	0.27
A.27.09.2B Bedroom	0.27
A.27.10.2B Bedroom	0.30
A.27.10.2B Bedroom	0.25
A.28.01.1B Bedroom	0.25
A.28.02.1B Bedroom	0.25
A.28.03.2B Bedroom	0.27
A.28.03.2B Bedroom	0.30

Location	Operative Temperature > 26 (Max 1%)
A.28.04.2B Bedroom	0.27
A.28.04.2B Bedroom	0.27
A.28.05.2B Bedroom	0.27
A.28.05.2B Bedroom	0.27
A.28.06.1B Bedroom	0.25
A.28.07.1B Bedroom	0.25
A.28.08.2B Bedroom	0.27
A.28.08.2B Bedroom	0.30
A.28.09.2B Bedroom	0.27
A.28.09.2B Bedroom	0.27
A.28.10.2B Bedroom	0.30
A.28.10.2B Bedroom	0.25
A.29.01.1B Bedroom	0.25
A.29.02.1B Bedroom	0.25
A.29.03.2B Bedroom	0.27
A.29.03.2B Bedroom	0.30
A.29.04.2B Bedroom	0.27
A.29.04.2B Bedroom	0.27
A.29.05.2B Bedroom	0.27
A.29.05.2B Bedroom	0.27
A.29.06.1B Bedroom	0.25
A.29.07.1B Bedroom	0.25
A.29.08.2B Bedroom	0.30
A.29.08.2B Bedroom	0.27
A.29.09.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.29.09.2B Bedroom	0.27
A.29.10.2B Bedroom	0.30
A.29.10.2B Bedroom	0.25
A.30.01.1B Bedroom	0.25
A.30.02.1B Bedroom	0.25
A.30.03.2B Bedroom	0.30
A.30.03.2B Bedroom	0.27
A.30.04.2B Bedroom	0.27
A.30.04.2B Bedroom	0.27
A.30.05.2B Bedroom	0.27
A.30.05.2B Bedroom	0.27
A.30.06.1B Bedroom	0.25
A.30.07.1B Bedroom	0.25
A.30.08.2B Bedroom	0.30
A.30.08.2B Bedroom	0.27
A.30.09.2B Bedroom	0.27
A.30.09.2B Bedroom	0.27
A.30.10.2B Bedroom	0.25
A.30.10.2B Bedroom	0.30
A.31.01.1B Bedroom	0.19
A.31.02.1B Bedroom	0.25
A.31.03.2B Bedroom	0.30
A.31.03.2B Bedroom	0.27
A.31.04.2B Bedroom	0.27
A.31.04.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.31.05.2B Bedroom	0.27
A.31.05.2B Bedroom	0.27
A.31.06.1B Bedroom	0.25
A.31.07.1B Bedroom	0.25
A.31.08.2B Bedroom	0.27
A.31.08.2B Bedroom	0.30
A.31.09.2B Bedroom	0.27
A.31.09.2B Bedroom	0.25
A.31.10.2B Bedroom	0.25
A.31.10.2B Bedroom	0.30
A.32.01.1B Bedroom	0.19
A.32.02.1B Bedroom	0.25
A.32.03.2B Bedroom	0.30
A.32.03.2B Bedroom	0.27
A.32.04.2B Bedroom	0.27
A.32.04.2B Bedroom	0.27
A.32.05.2B Bedroom	0.27
A.32.05.2B Bedroom	0.27
A.32.06.1B Bedroom	0.25
A.32.07.1B Bedroom	0.25
A.32.08.2B Bedroom	0.30
A.32.08.2B Bedroom	0.27
A.32.09.2B Bedroom	0.25
A.32.09.2B Bedroom	0.27
A.32.10.2B Bedroom	0.25

Location	Operative Temperature > 26 (Max 1%)
A.32.10.2B Bedroom	0.30
A.33.01.1B Bedroom	0.19
A.33.02.1B Bedroom	0.25
A.33.03.2B Bedroom	0.27
A.33.03.2B Bedroom	0.30
A.33.04.2B Bedroom	0.27
A.33.04.2B Bedroom	0.27
A.33.05.2B Bedroom	0.27
A.33.05.2B Bedroom	0.27
A.33.06.1B Bedroom	0.25
A.33.07.1B Bedroom	0.25
A.33.08.2B Bedroom	0.30
A.33.08.2B Bedroom	0.27
A.33.09.2B Bedroom	0.27
A.33.09.2B Bedroom	0.25
A.33.10.2B Bedroom	0.25
A.33.10.2B Bedroom	0.30
A.34.01.1B Bedroom	0.19
A.34.02.1B Bedroom	0.25
A.34.03.2B Bedroom	0.30
A.34.03.2B Bedroom	0.27
A.34.04.2B Bedroom	0.27
A.34.04.2B Bedroom	0.27
A.34.05.2B Bedroom	0.27
A.34.05.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.34.06.1B Bedroom	0.25
A.34.07.1B Bedroom	0.25
A.34.08.2B Bedroom	0.30
A.34.08.2B Bedroom	0.27
A.34.09.2B Bedroom	0.27
A.34.09.2B Bedroom	0.25
A.34.10.2B Bedroom	0.25
A.34.10.2B Bedroom	0.30
A.35.01.1B Bedroom	0.19
A.35.02.1B Bedroom	0.25
A.35.03.2B Bedroom	0.27
A.35.03.2B Bedroom	0.30
A.35.04.2B Bedroom	0.27
A.35.04.2B Bedroom	0.27
A.35.05.2B Bedroom	0.27
A.35.05.2B Bedroom	0.27
A.35.06.1B Bedroom	0.25
A.35.07.1B Bedroom	0.25
A.35.08.2B Bedroom	0.30
A.35.08.2B Bedroom	0.27
A.35.09.2B Bedroom	0.27
A.35.09.2B Bedroom	0.25
A.35.10.2B Bedroom	0.30
A.35.10.2B Bedroom	0.25
A.36.01.1B Bedroom	0.19

Location	Operative Temperature > 26 (Max 1%)
A.36.02.1B Bedroom	0.25
A.36.03.2B Bedroom	0.27
A.36.03.2B Bedroom	0.30
A.36.04.2B Bedroom	0.27
A.36.04.2B Bedroom	0.27
A.36.05.2B Bedroom	0.27
A.36.05.2B Bedroom	0.27
A.36.06.1B Bedroom	0.25
A.36.07.1B Bedroom	0.25
A.36.08.2B Bedroom	0.30
A.36.08.2B Bedroom	0.27
A.36.09.2B Bedroom	0.25
A.36.09.2B Bedroom	0.27
A.36.10.2B Bedroom	0.25
A.36.10.2B Bedroom	0.30
A.37.01.1B Bedroom	0.19
A.37.02.1B Bedroom	0.25
A.37.03.2B Bedroom	0.30
A.37.03.2B Bedroom	0.27
A.37.04.2B Bedroom	0.27
A.37.04.2B Bedroom	0.27
A.37.05.2B Bedroom	0.27
A.37.05.2B Bedroom	0.27
A.37.06.1B Bedroom	0.25
A.37.07.1B Bedroom	0.25

Location	Operative Temperature > 26 (Max 1%)
A.37.08.2B Bedroom	0.30
A.37.08.2B Bedroom	0.27
A.37.09.2B Bedroom	0.27
A.37.09.2B Bedroom	0.25
A.37.10.2B Bedroom	0.30
A.37.10.2B Bedroom	0.25
A.38.01.1B Bedroom	0.19
A.38.02.1B Bedroom	0.25
A.38.03.2B Bedroom	0.30
A.38.03.2B Bedroom	0.27
A.38.04.2B Bedroom	0.27
A.38.04.2B Bedroom	0.27
A.38.05.2B Bedroom	0.27
A.38.05.2B Bedroom	0.27
A.38.06.1B Bedroom	0.25
A.38.07.1B Bedroom	0.25
A.38.08.2B Bedroom	0.30
A.38.08.2B Bedroom	0.27
A.38.09.2B Bedroom	0.25
A.38.09.2B Bedroom	0.27
A.38.10.2B Bedroom	0.30
A.38.10.2B Bedroom	0.25
A.39.01.1B Bedroom	0.19
A.39.02.1B Bedroom	0.25
A.39.03.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.39.03.2B Bedroom	0.30
A.39.04.2B Bedroom	0.27
A.39.04.2B Bedroom	0.27
A.39.05.2B Bedroom	0.27
A.39.05.2B Bedroom	0.27
A.39.06.1B Bedroom	0.25
A.39.07.1B Bedroom	0.25
A.39.08.2B Bedroom	0.30
A.39.08.2B Bedroom	0.27
A.39.09.2B Bedroom	0.25
A.39.09.2B Bedroom	0.27
A.39.10.2B Bedroom	0.25
A.39.10.2B Bedroom	0.30
A.40.01.1B Bedroom	0.27
A.40.02.1B Bedroom	0.27
A.40.03.2B Bedroom	0.27
A.40.03.2B Bedroom	0.30
A.40.04.2B Bedroom	0.27
A.40.04.2B Bedroom	0.27
A.40.05.2B Bedroom	0.27
A.40.05.2B Bedroom	0.27
A.40.06.1B Bedroom	0.25
A.40.07.1B Bedroom	0.25
A.40.08.2B Bedroom	0.30
A.40.08.2B Bedroom	0.30

Location	Operative Temperature > 26 (Max 1%)
A.40.09.2B Bedroom	0.27
A.40.09.2B Bedroom	0.27
A.40.10.2B Bedroom	0.30
A.40.10.2B Bedroom	0.25
A.41.01.1B Bedroom	0.27
A.41.02.1B Bedroom	0.27
A.41.03.2B Bedroom	0.27
A.41.03.2B Bedroom	0.30
A.41.04.2B Bedroom	0.27
A.41.04.2B Bedroom	0.27
A.41.05.2B Bedroom	0.27
A.41.05.2B Bedroom	0.27
A.41.06.1B Bedroom	0.25
A.41.07.1B Bedroom	0.25
A.41.08.2B Bedroom	0.30
A.41.08.2B Bedroom	0.30
A.41.09.2B Bedroom	0.27
A.41.09.2B Bedroom	0.27
A.41.10.2B Bedroom	0.25
A.41.10.2B Bedroom	0.33
A.42.01.1B Bedroom	0.27
A.42.02.1B Bedroom	0.27
A.42.03.2B Bedroom	0.30
A.42.03.2B Bedroom	0.30
A.42.04.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.42.04.2B Bedroom	0.27
A.42.05.2B Bedroom	0.27
A.42.05.2B Bedroom	0.27
A.42.06.1B Bedroom	0.25
A.42.07.1B Bedroom	0.25
A.42.08.2B Bedroom	0.30
A.42.08.2B Bedroom	0.30
A.42.09.2B Bedroom	0.27
A.42.09.2B Bedroom	0.27
A.42.10.2B Bedroom	0.30
A.42.10.2B Bedroom	0.25
A.43.01.1B Bedroom	0.27
A.43.02.1B Bedroom	0.27
A.43.03.2B Bedroom	0.27
A.43.03.2B Bedroom	0.30
A.43.04.2B Bedroom	0.27
A.43.04.2B Bedroom	0.27
A.43.05.2B Bedroom	0.27
A.43.05.2B Bedroom	0.27
A.43.06.1B Bedroom	0.25
A.43.07.1B Bedroom	0.25
A.43.08.2B Bedroom	0.30
A.43.08.2B Bedroom	0.30
A.43.09.2B Bedroom	0.27
A.43.09.2B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.43.10.2B Bedroom	0.25
A.43.10.2B Bedroom	0.30
A.44.01.1B Bedroom	0.27
A.44.02.1B Bedroom	0.27
A.44.03.2B Bedroom	0.30
A.44.03.2B Bedroom	0.30
A.44.04.2B Bedroom	0.27
A.44.04.2B Bedroom	0.27
A.44.05.2B Bedroom	0.27
A.44.05.2B Bedroom	0.27
A.44.06.1B Bedroom	0.25
A.44.07.1B Bedroom	0.25
A.44.08.2B Bedroom	0.30
A.44.08.2B Bedroom	0.30
A.44.09.2B Bedroom	0.27
A.44.09.2B Bedroom	0.27
A.44.10.2B Bedroom	0.30
A.44.10.2B Bedroom	0.25
A.45.01.3B Bedroom	0.68
A.45.01.3B Bedroom	0.35
A.45.01.3B Bedroom	0.30
A.45.02.3B Bedroom	0.27
A.45.02.3B Bedroom	0.30
A.45.02.3B Bedroom	0.27
A.45.03.3B Bedroom	0.27

Location	Operative Temperature > 26 (Max 1%)
A.45.03.3B Bedroom	0.22
A.45.03.3B Bedroom	0.27
A.45.04.3B Bedroom	0.30
A.45.04.3B Bedroom	0.33
A.45.04.3B Bedroom	0.65
A.45.05.3B Bedroom	0.27
A.45.05.3B Bedroom	0.25
A.45.05.3B Bedroom	0.25
A.45.06.3B Bedroom	0.30
A.45.06.3B Bedroom	0.30
A.45.06.3B Bedroom	0.30

12.0 Appendix 6: DSY2: TM52 Criterion 1 Living Block A

Location	Operative Temperature > 26 (Max 1%)
A.02.01.1BKLD	0.85
A.02.02.1BKLD	0.70
A.02.03.2BKLD	3.27
A.02.04.2BKLD	1.61
A.02.05.2BKLD	3.12
A.02.06.1BKLD	0.70
A.02.07.1BKLD	0.85
A.02.08.2BKLD	1.31
A.02.09.2BKLD	1.21
A.02.10.2BKLD	0.80
A.03.01.1BKLD	0.90
A.03.02.1BKLD	0.80
A.03.03.2BKLD	3.57
A.03.04.2BKLD	1.71
A.03.05.2BKLD	3.37
A.03.06.1BKLD	0.80
A.03.07.1BKLD	0.90
A.03.08.2BKLD	1.36
A.03.09.2BKLD	1.21
A.03.10.2BKLD	0.85
A.04.01.1BKLD	0.90
A.04.02.1BKLD	0.75
A.04.03.2BKLD	3.37
A.04.04.2BKLD	1.66
A.04.05.2BKLD	3.22
A.04.06.1BKLD	0.80
A.04.07.1BKLD	0.90
A.04.08.2BKLD	1.36
A.04.09.2BKLD	1.31
A.04.10.2BKLD	0.80
A.05.01.1BKLD	0.90
A.05.02.1BKLD	0.75
A.05.03.2BKLD	3.37
A.05.04.2BKLD	1.66
A.05.05.2BKLD	3.22
A.05.06.1BKLD	0.80
A.05.07.1BKLD	0.90
A.05.08.2BKLD	1.36
A.05.09.2BKLD	1.31
A.05.10.2BKLD	0.80
A.06.01.1BKLD	0.90
A.06.02.1BKLD	0.75
A.06.03.2BKLD	3.37
A.06.04.2BKLD	1.66
A.06.05.2BKLD	3.22
A.06.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.06.07.1BKLD	0.90
A.06.08.2BKLD	1.36
A.06.09.2BKLD	1.31
A.06.10.2BKLD	0.80
A.07.01.1BKLD	0.90
A.07.02.1BKLD	0.75
A.07.03.2BKLD	3.37
A.07.04.2BKLD	1.66
A.07.05.2BKLD	3.22
A.07.06.1BKLD	0.80
A.07.07.1BKLD	0.90
A.07.08.2BKLD	1.36
A.07.09.2BKLD	1.36
A.07.10.2BKLD	0.80
A.08.01.1BKLD	0.90
A.08.02.1BKLD	0.75
A.08.03.2BKLD	3.42
A.08.04.2BKLD	1.66
A.08.05.2BKLD	3.22
A.08.06.1BKLD	0.80
A.08.07.1BKLD	0.90
A.08.08.2BKLD	1.36
A.08.09.2BKLD	1.36
A.08.10.2BKLD	0.80
A.09.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.09.02.1BKLD	0.75
A.09.03.2BKLD	3.42
A.09.04.2BKLD	1.66
A.09.05.2BKLD	3.22
A.09.06.1BKLD	0.80
A.09.07.1BKLD	0.90
A.09.08.2BKLD	1.36
A.09.09.2BKLD	1.36
A.09.10.2BKLD	0.80
A.10.01.1BKLD	0.90
A.10.02.1BKLD	0.75
A.10.03.2BKLD	3.42
A.10.04.2BKLD	1.66
A.10.05.2BKLD	3.22
A.10.06.1BKLD	0.80
A.10.07.1BKLD	0.90
A.10.08.2BKLD	1.36
A.10.09.2BKLD	1.36
A.10.10.2BKLD	0.80
A.11.01.1BKLD	0.90
A.11.02.1BKLD	0.75
A.11.03.2BKLD	3.42
A.11.04.2BKLD	1.71
A.11.05.2BKLD	3.22
A.11.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.11.07.1BKLD	0.90
A.11.08.2BKLD	1.41
A.11.09.2BKLD	1.36
A.11.10.2BKLD	0.80
A.12.01.1BKLD	0.90
A.12.02.1BKLD	0.75
A.12.03.2BKLD	3.57
A.12.04.2BKLD	1.71
A.12.05.2BKLD	3.37
A.12.06.1BKLD	0.80
A.12.07.1BKLD	0.90
A.12.08.2BKLD	1.41
A.12.09.2BKLD	1.36
A.12.10.2BKLD	0.85
A.13.01.1BKLD	0.96
A.13.02.1BKLD	0.70
A.13.03.2BKLD	3.82
A.13.05.2BKLD	3.57
A.13.06.1BKLD	0.70
A.13.07.1BKLD	0.96
A.13.08.2BKLD	2.56
A.13.09.2BKLD	1.71
A.13.10.2BKLD	0.90
A.13.13.2BKLD	1.81
A.14.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.14.02.1BKLD	0.75
A.14.03.2BKLD	3.32
A.14.04.2BKLD	1.61
A.14.05.2BKLD	3.12
A.14.06.1BKLD	0.80
A.14.07.1BKLD	0.90
A.14.08.2BKLD	1.36
A.14.09.2BKLD	1.31
A.14.10.2BKLD	0.80
A.15.01.1BKLD	0.90
A.15.02.1BKLD	0.75
A.15.03.2BKLD	3.32
A.15.04.2BKLD	1.56
A.15.05.2BKLD	3.12
A.15.06.1BKLD	0.80
A.15.07.1BKLD	0.90
A.15.08.2BKLD	1.36
A.15.09.2BKLD	1.31
A.15.10.2BKLD	0.80
A.16.01.1BKLD	0.90
A.16.02.1BKLD	0.75
A.16.03.2BKLD	3.32
A.16.04.2BKLD	1.56
A.16.05.2BKLD	3.17
A.16.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.16.07.1BKLD	0.90
A.16.08.2BKLD	1.36
A.16.09.2BKLD	1.31
A.16.10.2BKLD	0.80
A.17.01.1BKLD	0.90
A.17.02.1BKLD	0.75
A.17.03.2BKLD	3.32
A.17.04.2BKLD	1.56
A.17.05.2BKLD	3.17
A.17.06.1BKLD	0.80
A.17.07.1BKLD	0.90
A.17.08.2BKLD	1.36
A.17.09.2BKLD	1.31
A.17.10.2BKLD	0.80
A.18.01.1BKLD	0.90
A.18.02.1BKLD	0.75
A.18.03.2BKLD	3.32
A.18.04.2BKLD	1.56
A.18.05.2BKLD	3.17
A.18.06.1BKLD	0.80
A.18.07.1BKLD	0.90
A.18.08.2BKLD	1.36
A.18.09.2BKLD	1.31
A.18.10.2BKLD	0.80
A.19.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.19.02.1BKLD	0.75
A.19.03.2BKLD	3.32
A.19.04.2BKLD	1.56
A.19.05.2BKLD	3.17
A.19.06.1BKLD	0.80
A.19.07.1BKLD	0.90
A.19.08.2BKLD	1.36
A.19.09.2BKLD	1.31
A.19.10.2BKLD	0.80
A.20.01.1BKLD	0.90
A.20.02.1BKLD	0.75
A.20.03.2BKLD	3.32
A.20.04.2BKLD	1.56
A.20.05.2BKLD	3.17
A.20.06.1BKLD	0.80
A.20.07.1BKLD	0.90
A.20.08.2BKLD	1.36
A.20.09.2BKLD	1.31
A.20.10.2BKLD	0.80
A.21.01.1BKLD	0.90
A.21.02.1BKLD	0.75
A.21.03.2BKLD	3.32
A.21.04.2BKLD	1.56
A.21.05.2BKLD	3.17
A.21.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.21.07.1BKLD	0.90
A.21.08.2BKLD	1.36
A.21.09.2BKLD	1.31
A.21.10.2BKLD	0.80
A.22.01.1BKLD	0.90
A.22.02.1BKLD	0.80
A.22.03.2BKLD	3.07
A.22.04.2BKLD	1.56
A.22.05.2BKLD	3.02
A.22.06.1BKLD	0.80
A.22.07.1BKLD	0.90
A.22.08.2BKLD	1.26
A.22.09.2BKLD	1.21
A.22.10.2BKLD	0.80
A.23.01.1BKLD	0.90
A.23.02.1BKLD	0.80
A.23.03.2BKLD	3.07
A.23.04.2BKLD	1.61
A.23.05.2BKLD	3.02
A.23.06.1BKLD	0.80
A.23.07.1BKLD	0.90
A.23.08.2BKLD	1.26
A.23.09.2BKLD	1.21
A.23.10.2BKLD	0.80
A.24.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.24.02.1BKLD	0.80
A.24.03.2BKLD	3.07
A.24.04.2BKLD	1.56
A.24.05.2BKLD	3.02
A.24.06.1BKLD	0.80
A.24.07.1BKLD	0.90
A.24.08.2BKLD	1.26
A.24.09.2BKLD	1.21
A.24.10.2BKLD	0.80
A.25.01.1BKLD	0.90
A.25.02.1BKLD	0.80
A.25.03.2BKLD	3.07
A.25.04.2BKLD	1.56
A.25.05.2BKLD	3.02
A.25.06.1BKLD	0.80
A.25.07.1BKLD	0.90
A.25.08.2BKLD	1.26
A.25.09.2BKLD	1.21
A.25.10.2BKLD	0.80
A.26.01.1BKLD	0.90
A.26.02.1BKLD	0.80
A.26.03.2BKLD	3.07
A.26.04.2BKLD	1.56
A.26.05.2BKLD	3.02
A.26.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.26.07.1BKLD	0.90
A.26.08.2BKLD	1.26
A.26.09.2BKLD	1.21
A.26.10.2BKLD	0.80
A.27.01.1BKLD	0.90
A.27.02.1BKLD	0.80
A.27.03.2BKLD	3.07
A.27.04.2BKLD	1.56
A.27.05.2BKLD	3.02
A.27.06.1BKLD	0.80
A.27.07.1BKLD	0.90
A.27.08.2BKLD	1.26
A.27.09.2BKLD	1.21
A.27.10.2BKLD	0.80
A.28.01.1BKLD	0.90
A.28.02.1BKLD	0.80
A.28.03.2BKLD	3.07
A.28.04.2BKLD	1.56
A.28.05.2BKLD	3.02
A.28.06.1BKLD	0.80
A.28.07.1BKLD	0.90
A.28.08.2BKLD	1.26
A.28.09.2BKLD	1.21
A.28.10.2BKLD	0.80
A.29.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.29.02.1BKLD	0.80
A.29.03.2BKLD	3.07
A.29.04.2BKLD	1.56
A.29.05.2BKLD	3.02
A.29.06.1BKLD	0.80
A.29.07.1BKLD	0.90
A.29.08.2BKLD	1.26
A.29.09.2BKLD	1.21
A.29.10.2BKLD	0.80
A.30.01.1BKLD	0.90
A.30.02.1BKLD	0.80
A.30.03.2BKLD	3.07
A.30.04.2BKLD	1.56
A.30.05.2BKLD	3.02
A.30.06.1BKLD	0.80
A.30.07.1BKLD	0.90
A.30.08.2BKLD	1.26
A.30.09.2BKLD	1.21
A.30.10.2BKLD	0.80
A.31.01.1BKLD	0.90
A.31.02.1BKLD	0.80
A.31.03.2BKLD	3.07
A.31.04.2BKLD	1.56
A.31.05.2BKLD	2.87
A.31.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.31.07.1BKLD	0.90
A.31.08.2BKLD	1.26
A.31.09.2BKLD	1.21
A.31.10.2BKLD	0.80
A.32.01.1BKLD	0.90
A.32.02.1BKLD	0.80
A.32.03.2BKLD	3.07
A.32.04.2BKLD	1.56
A.32.05.2BKLD	2.87
A.32.06.1BKLD	0.80
A.32.07.1BKLD	0.90
A.32.08.2BKLD	1.26
A.32.09.2BKLD	1.21
A.32.10.2BKLD	0.80
A.33.01.1BKLD	0.90
A.33.02.1BKLD	0.80
A.33.03.2BKLD	3.07
A.33.04.2BKLD	1.56
A.33.05.2BKLD	2.87
A.33.06.1BKLD	0.80
A.33.07.1BKLD	0.90
A.33.08.2BKLD	1.26
A.33.09.2BKLD	1.21
A.33.10.2BKLD	0.80
A.34.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.34.02.1BKLD	0.80
A.34.03.2BKLD	3.07
A.34.04.2BKLD	1.56
A.34.05.2BKLD	2.87
A.34.06.1BKLD	0.80
A.34.07.1BKLD	0.90
A.34.08.2BKLD	1.26
A.34.09.2BKLD	1.21
A.34.10.2BKLD	0.80
A.35.01.1BKLD	0.90
A.35.02.1BKLD	0.80
A.35.03.2BKLD	3.07
A.35.04.2BKLD	1.56
A.35.05.2BKLD	2.87
A.35.06.1BKLD	0.80
A.35.07.1BKLD	0.90
A.35.08.2BKLD	1.26
A.35.09.2BKLD	1.21
A.35.10.2BKLD	0.80
A.36.01.1BKLD	0.90
A.36.02.1BKLD	0.80
A.36.03.2BKLD	3.07
A.36.04.2BKLD	1.56
A.36.05.2BKLD	2.87
A.36.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.36.07.1BKLD	0.90
A.36.08.2BKLD	1.26
A.36.09.2BKLD	1.21
A.36.10.2BKLD	0.80
A.37.01.1BKLD	0.90
A.37.02.1BKLD	0.80
A.37.03.2BKLD	3.07
A.37.04.2BKLD	1.56
A.37.05.2BKLD	2.87
A.37.06.1BKLD	0.80
A.37.07.1BKLD	0.90
A.37.08.2BKLD	1.26
A.37.09.2BKLD	1.21
A.37.10.2BKLD	0.80
A.38.01.1BKLD	0.90
A.38.02.1BKLD	0.80
A.38.03.2BKLD	3.07
A.38.04.2BKLD	1.56
A.38.05.2BKLD	2.87
A.38.06.1BKLD	0.80
A.38.07.1BKLD	0.90
A.38.08.2BKLD	1.26
A.38.09.2BKLD	1.21
A.38.10.2BKLD	0.80
A.39.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.39.02.1BKLD	0.80
A.39.03.2BKLD	3.07
A.39.04.2BKLD	1.56
A.39.05.2BKLD	2.87
A.39.06.1BKLD	0.80
A.39.07.1BKLD	0.90
A.39.08.2BKLD	1.26
A.39.09.2BKLD	1.21
A.39.10.2BKLD	0.80
A.40.01.1BKLD	0.90
A.40.02.1BKLD	0.75
A.40.03.2BKLD	3.32
A.40.04.2BKLD	1.56
A.40.05.2BKLD	3.17
A.40.06.1BKLD	0.75
A.40.07.1BKLD	0.90
A.40.08.2BKLD	1.36
A.40.09.2BKLD	1.31
A.40.10.2BKLD	0.80
A.41.01.1BKLD	0.90
A.41.02.1BKLD	0.75
A.41.03.2BKLD	3.32
A.41.04.2BKLD	1.56
A.41.05.2BKLD	3.17
A.41.06.1BKLD	0.75

Location	Operative Temperature > 26 (Max 1%)
A.41.07.1BKLD	0.90
A.41.08.2BKLD	1.36
A.41.09.2BKLD	1.31
A.41.10.2BKLD	0.80
A.42.01.1BKLD	0.90
A.42.02.1BKLD	0.75
A.42.03.2BKLD	3.32
A.42.04.2BKLD	1.56
A.42.05.2BKLD	3.17
A.42.06.1BKLD	0.75
A.42.07.1BKLD	0.90
A.42.08.2BKLD	1.36
A.42.09.2BKLD	1.31
A.42.10.2BKLD	0.80
A.43.01.1BKLD	0.90
A.43.02.1BKLD	0.75
A.43.03.2BKLD	3.32
A.43.04.2BKLD	1.56
A.43.05.2BKLD	3.17
A.43.06.1BKLD	0.75
A.43.07.1BKLD	0.90
A.43.08.2BKLD	1.36
A.43.09.2BKLD	1.31
A.43.10.2BKLD	0.80
A.44.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.44.02.1BKLD	0.75
A.44.03.2BKLD	3.32
A.44.04.2BKLD	1.56
A.44.05.2BKLD	3.17
A.44.06.1BKLD	0.75
A.44.07.1BKLD	0.90
A.44.08.2BKLD	1.31
A.44.09.2BKLD	1.31
A.44.10.2BKLD	0.80
A.45.01.3BKLD	0.96
A.45.02.3BKLD	2.87
A.45.03.3BKLD	2.66
A.45.04.3BKLD	0.75
A.45.05.3BKLD	1.11
A.45.06.3BKLD	1.21

13.0 Appendix 7: DSY3: TM52 Criterion 1 Bedroom Block A

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.02.01.1B Bedroom	0.90
A.02.02.1B Bedroom	0.65
A.02.03.2B Bedroom	2.21
A.02.03.2B Bedroom	1.55
A.02.04.2B Bedroom	1.96
A.02.04.2B Bedroom	2.40
A.02.05.2B Bedroom	2.02
A.02.05.2B Bedroom	1.25
A.02.06.1B Bedroom	0.52
A.02.07.1B Bedroom	0.95
A.02.08.2B Bedroom	0.44
A.02.08.2B Bedroom	1.01
A.02.09.2B Bedroom	0.27
A.02.09.2B Bedroom	0.52
A.02.10.2B Bedroom	0.44
A.02.10.2B Bedroom	0.19
A.03.01.1B Bedroom	1.25
A.03.02.1B Bedroom	1.06
A.03.03.2B Bedroom	1.74
A.03.03.2B Bedroom	2.37
A.03.04.2B Bedroom	2.59
A.03.04.2B Bedroom	2.07
A.03.05.2B Bedroom	1.53
A.03.05.2B Bedroom	2.23
A.03.06.1B Bedroom	0.87
A.03.07.1B Bedroom	1.23
A.03.08.2B Bedroom	0.65
A.03.08.2B Bedroom	1.33
A.03.09.2B Bedroom	0.44
A.03.09.2B Bedroom	0.98
A.03.10.2B Bedroom	0.49
A.03.10.2B Bedroom	0.30
A.04.01.1B Bedroom	1.25
A.04.02.1B Bedroom	1.03
A.04.03.2B Bedroom	2.26
A.04.03.2B Bedroom	1.72
A.04.04.2B Bedroom	2.04
A.04.04.2B Bedroom	2.53
A.04.05.2B Bedroom	2.10
A.04.05.2B Bedroom	1.53
A.04.06.1B Bedroom	0.87
A.04.07.1B Bedroom	1.17
A.04.08.2B Bedroom	0.65
A.04.08.2B Bedroom	1.39
A.04.09.2B Bedroom	0.41
A.04.09.2B Bedroom	0.95

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.04.10.2B Bedroom	0.57
A.04.10.2B Bedroom	0.38
A.05.01.1B Bedroom	1.25
A.05.02.1B Bedroom	1.03
A.05.03.2B Bedroom	2.26
A.05.03.2B Bedroom	1.72
A.05.04.2B Bedroom	2.04
A.05.04.2B Bedroom	2.53
A.05.05.2B Bedroom	2.10
A.05.05.2B Bedroom	1.53
A.05.06.1B Bedroom	0.87
A.05.07.1B Bedroom	1.20
A.05.08.2B Bedroom	0.65
A.05.08.2B Bedroom	1.39
A.05.09.2B Bedroom	0.95
A.05.09.2B Bedroom	0.41
A.05.10.2B Bedroom	0.57
A.05.10.2B Bedroom	0.38
A.06.01.1B Bedroom	1.28
A.06.02.1B Bedroom	1.03
A.06.03.2B Bedroom	2.26
A.06.03.2B Bedroom	1.72
A.06.04.2B Bedroom	2.04
A.06.04.2B Bedroom	2.53
A.06.05.2B Bedroom	2.10

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.06.05.2B Bedroom	1.55
A.06.06.1B Bedroom	0.87
A.06.07.1B Bedroom	1.23
A.06.08.2B Bedroom	1.39
A.06.08.2B Bedroom	0.68
A.06.09.2B Bedroom	0.95
A.06.09.2B Bedroom	0.41
A.06.10.2B Bedroom	0.38
A.06.10.2B Bedroom	0.57
A.07.01.1B Bedroom	1.28
A.07.02.1B Bedroom	1.03
A.07.03.2B Bedroom	1.72
A.07.03.2B Bedroom	2.26
A.07.04.2B Bedroom	2.53
A.07.04.2B Bedroom	2.04
A.07.05.2B Bedroom	2.10
A.07.05.2B Bedroom	1.55
A.07.06.1B Bedroom	0.90
A.07.07.1B Bedroom	1.23
A.07.08.2B Bedroom	0.68
A.07.08.2B Bedroom	1.39
A.07.09.2B Bedroom	0.95
A.07.09.2B Bedroom	0.44
A.07.10.2B Bedroom	0.38
A.07.10.2B Bedroom	0.57

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.08.01.1B Bedroom	1.28
A.08.02.1B Bedroom	1.03
A.08.03.2B Bedroom	2.29
A.08.03.2B Bedroom	1.77
A.08.04.2B Bedroom	2.04
A.08.04.2B Bedroom	2.53
A.08.05.2B Bedroom	1.55
A.08.05.2B Bedroom	2.10
A.08.06.1B Bedroom	0.90
A.08.07.1B Bedroom	1.23
A.08.08.2B Bedroom	0.68
A.08.08.2B Bedroom	1.39
A.08.09.2B Bedroom	0.95
A.08.09.2B Bedroom	0.44
A.08.10.2B Bedroom	0.38
A.08.10.2B Bedroom	0.57
A.09.01.1B Bedroom	1.28
A.09.02.1B Bedroom	1.03
A.09.03.2B Bedroom	1.77
A.09.03.2B Bedroom	2.29
A.09.04.2B Bedroom	2.53
A.09.04.2B Bedroom	2.04
A.09.05.2B Bedroom	2.10
A.09.05.2B Bedroom	1.55
A.09.06.1B Bedroom	0.90

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.09.07.1B Bedroom	1.25
A.09.08.2B Bedroom	0.68
A.09.08.2B Bedroom	1.39
A.09.09.2B Bedroom	0.95
A.09.09.2B Bedroom	0.44
A.09.10.2B Bedroom	0.57
A.09.10.2B Bedroom	0.38
A.10.01.1B Bedroom	1.28
A.10.02.1B Bedroom	1.03
A.10.03.2B Bedroom	2.29
A.10.03.2B Bedroom	1.80
A.10.04.2B Bedroom	2.53
A.10.04.2B Bedroom	2.04
A.10.05.2B Bedroom	1.55
A.10.05.2B Bedroom	2.10
A.10.06.1B Bedroom	0.93
A.10.07.1B Bedroom	1.25
A.10.08.2B Bedroom	1.39
A.10.08.2B Bedroom	0.68
A.10.09.2B Bedroom	0.44
A.10.09.2B Bedroom	0.95
A.10.10.2B Bedroom	0.60
A.10.10.2B Bedroom	0.38
A.11.01.1B Bedroom	1.36
A.11.02.1B Bedroom	1.06

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.11.03.2B Bedroom	2.29
A.11.03.2B Bedroom	1.80
A.11.04.2B Bedroom	2.53
A.11.04.2B Bedroom	2.04
A.11.05.2B Bedroom	1.55
A.11.05.2B Bedroom	2.12
A.11.06.1B Bedroom	0.93
A.11.07.1B Bedroom	1.25
A.11.08.2B Bedroom	0.68
A.11.08.2B Bedroom	1.47
A.11.09.2B Bedroom	0.98
A.11.09.2B Bedroom	0.46
A.11.10.2B Bedroom	0.38
A.11.10.2B Bedroom	0.60
A.12.01.1B Bedroom	1.31
A.12.02.1B Bedroom	1.12
A.12.03.2B Bedroom	2.29
A.12.03.2B Bedroom	1.91
A.12.04.2B Bedroom	2.59
A.12.04.2B Bedroom	2.07
A.12.05.2B Bedroom	1.55
A.12.05.2B Bedroom	2.12
A.12.06.1B Bedroom	0.95
A.12.07.1B Bedroom	1.23
A.12.08.2B Bedroom	1.36

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.12.08.2B Bedroom	0.68
A.12.09.2B Bedroom	0.98
A.12.09.2B Bedroom	0.44
A.12.10.2B Bedroom	0.60
A.12.10.2B Bedroom	0.38
A.13.01.1B Bedroom	2.02
A.13.02.1B Bedroom	1.09
A.13.03.2B Bedroom	2.15
A.13.03.2B Bedroom	2.40
A.13.05.2B Bedroom	2.07
A.13.05.2B Bedroom	1.55
A.13.06.1B Bedroom	0.93
A.13.07.1B Bedroom	2.34
A.13.08.2B Bedroom	2.34
A.13.08.2B Bedroom	0.82
A.13.09.2B Bedroom	1.06
A.13.09.2B Bedroom	0.52
A.13.10.2B Bedroom	0.33
A.13.10.2B Bedroom	0.68
A.13.13.2B Bedroom	2.78
A.13.13.2B Bedroom	2.12
A.14.01.1B Bedroom	1.28
A.14.02.1B Bedroom	1.01
A.14.03.2B Bedroom	1.74
A.14.03.2B Bedroom	2.26

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.14.04.2B Bedroom	2.48
A.14.04.2B Bedroom	1.96
A.14.05.2B Bedroom	1.55
A.14.05.2B Bedroom	2.02
A.14.06.1B Bedroom	0.90
A.14.07.1B Bedroom	1.23
A.14.08.2B Bedroom	0.65
A.14.08.2B Bedroom	1.39
A.14.09.2B Bedroom	0.44
A.14.09.2B Bedroom	0.95
A.14.10.2B Bedroom	0.38
A.14.10.2B Bedroom	0.60
A.15.01.1B Bedroom	1.25
A.15.02.1B Bedroom	1.01
A.15.03.2B Bedroom	1.74
A.15.03.2B Bedroom	2.23
A.15.04.2B Bedroom	2.48
A.15.04.2B Bedroom	1.96
A.15.05.2B Bedroom	2.02
A.15.05.2B Bedroom	1.55
A.15.06.1B Bedroom	0.90
A.15.07.1B Bedroom	1.20
A.15.08.2B Bedroom	1.31
A.15.08.2B Bedroom	0.63
A.15.09.2B Bedroom	0.95

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.15.09.2B Bedroom	0.44
A.15.10.2B Bedroom	0.33
A.15.10.2B Bedroom	0.57
A.16.01.1B Bedroom	1.25
A.16.02.1B Bedroom	1.01
A.16.03.2B Bedroom	2.23
A.16.03.2B Bedroom	1.74
A.16.04.2B Bedroom	2.48
A.16.04.2B Bedroom	1.96
A.16.05.2B Bedroom	2.02
A.16.05.2B Bedroom	1.53
A.16.06.1B Bedroom	0.87
A.16.07.1B Bedroom	1.20
A.16.08.2B Bedroom	1.31
A.16.08.2B Bedroom	0.63
A.16.09.2B Bedroom	0.44
A.16.09.2B Bedroom	0.93
A.16.10.2B Bedroom	0.57
A.16.10.2B Bedroom	0.33
A.17.01.1B Bedroom	1.25
A.17.02.1B Bedroom	1.01
A.17.03.2B Bedroom	1.74
A.17.03.2B Bedroom	2.23
A.17.04.2B Bedroom	1.96
A.17.04.2B Bedroom	2.48

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.17.05.2B Bedroom	2.02
A.17.05.2B Bedroom	1.53
A.17.06.1B Bedroom	0.87
A.17.07.1B Bedroom	1.20
A.17.08.2B Bedroom	1.31
A.17.08.2B Bedroom	0.63
A.17.09.2B Bedroom	0.93
A.17.09.2B Bedroom	0.44
A.17.10.2B Bedroom	0.57
A.17.10.2B Bedroom	0.33
A.18.01.1B Bedroom	1.25
A.18.02.1B Bedroom	1.01
A.18.03.2B Bedroom	2.23
A.18.03.2B Bedroom	1.74
A.18.04.2B Bedroom	2.48
A.18.04.2B Bedroom	1.96
A.18.05.2B Bedroom	2.02
A.18.05.2B Bedroom	1.55
A.18.06.1B Bedroom	0.87
A.18.07.1B Bedroom	1.20
A.18.08.2B Bedroom	0.63
A.18.08.2B Bedroom	1.31
A.18.09.2B Bedroom	0.93
A.18.09.2B Bedroom	0.44
A.18.10.2B Bedroom	0.33

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.18.10.2B Bedroom	0.57
A.19.01.1B Bedroom	1.25
A.19.02.1B Bedroom	1.01
A.19.03.2B Bedroom	1.74
A.19.03.2B Bedroom	2.23
A.19.04.2B Bedroom	1.96
A.19.04.2B Bedroom	2.48
A.19.05.2B Bedroom	2.02
A.19.05.2B Bedroom	1.55
A.19.06.1B Bedroom	0.87
A.19.07.1B Bedroom	1.20
A.19.08.2B Bedroom	1.31
A.19.08.2B Bedroom	0.63
A.19.09.2B Bedroom	0.44
A.19.09.2B Bedroom	0.93
A.19.10.2B Bedroom	0.57
A.19.10.2B Bedroom	0.33
A.20.01.1B Bedroom	1.25
A.20.02.1B Bedroom	1.01
A.20.03.2B Bedroom	1.74
A.20.03.2B Bedroom	2.23
A.20.04.2B Bedroom	1.96
A.20.04.2B Bedroom	2.48
A.20.05.2B Bedroom	2.02
A.20.05.2B Bedroom	1.55

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.20.06.1B Bedroom	0.87
A.20.07.1B Bedroom	1.20
A.20.08.2B Bedroom	1.31
A.20.08.2B Bedroom	0.63
A.20.09.2B Bedroom	0.93
A.20.09.2B Bedroom	0.44
A.20.10.2B Bedroom	0.33
A.20.10.2B Bedroom	0.57
A.21.01.1B Bedroom	1.25
A.21.02.1B Bedroom	0.98
A.21.03.2B Bedroom	1.74
A.21.03.2B Bedroom	2.23
A.21.04.2B Bedroom	1.96
A.21.04.2B Bedroom	2.48
A.21.05.2B Bedroom	1.50
A.21.05.2B Bedroom	2.02
A.21.06.1B Bedroom	0.87
A.21.07.1B Bedroom	1.17
A.21.08.2B Bedroom	1.31
A.21.08.2B Bedroom	0.63
A.21.09.2B Bedroom	0.44
A.21.09.2B Bedroom	0.93
A.21.10.2B Bedroom	0.33
A.21.10.2B Bedroom	0.57
A.22.01.1B Bedroom	1.23

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.22.02.1B Bedroom	0.98
A.22.03.2B Bedroom	1.74
A.22.03.2B Bedroom	2.21
A.22.04.2B Bedroom	2.40
A.22.04.2B Bedroom	1.96
A.22.05.2B Bedroom	1.99
A.22.05.2B Bedroom	1.50
A.22.06.1B Bedroom	0.87
A.22.07.1B Bedroom	1.14
A.22.08.2B Bedroom	0.63
A.22.08.2B Bedroom	1.28
A.22.09.2B Bedroom	0.93
A.22.09.2B Bedroom	0.41
A.22.10.2B Bedroom	0.27
A.22.10.2B Bedroom	0.57
A.23.01.1B Bedroom	1.23
A.23.02.1B Bedroom	0.98
A.23.03.2B Bedroom	2.18
A.23.03.2B Bedroom	1.72
A.23.04.2B Bedroom	1.93
A.23.04.2B Bedroom	2.40
A.23.05.2B Bedroom	1.99
A.23.05.2B Bedroom	1.50
A.23.06.1B Bedroom	0.87
A.23.07.1B Bedroom	1.14

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.23.08.2B Bedroom	0.63
A.23.08.2B Bedroom	1.25
A.23.09.2B Bedroom	0.41
A.23.09.2B Bedroom	0.93
A.23.10.2B Bedroom	0.57
A.23.10.2B Bedroom	0.27
A.24.01.1B Bedroom	1.23
A.24.02.1B Bedroom	0.98
A.24.03.2B Bedroom	2.21
A.24.03.2B Bedroom	1.74
A.24.04.2B Bedroom	2.40
A.24.04.2B Bedroom	1.93
A.24.05.2B Bedroom	1.99
A.24.05.2B Bedroom	1.50
A.24.06.1B Bedroom	0.87
A.24.07.1B Bedroom	1.14
A.24.08.2B Bedroom	1.25
A.24.08.2B Bedroom	0.63
A.24.09.2B Bedroom	0.41
A.24.09.2B Bedroom	0.93
A.24.10.2B Bedroom	0.57
A.24.10.2B Bedroom	0.27
A.25.01.1B Bedroom	1.23
A.25.02.1B Bedroom	0.98
A.25.03.2B Bedroom	2.21

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.25.03.2B Bedroom	1.74
A.25.04.2B Bedroom	1.93
A.25.04.2B Bedroom	2.40
A.25.05.2B Bedroom	1.99
A.25.05.2B Bedroom	1.50
A.25.06.1B Bedroom	0.87
A.25.07.1B Bedroom	1.14
A.25.08.2B Bedroom	1.25
A.25.08.2B Bedroom	0.63
A.25.09.2B Bedroom	0.93
A.25.09.2B Bedroom	0.41
A.25.10.2B Bedroom	0.57
A.25.10.2B Bedroom	0.27
A.26.01.1B Bedroom	1.23
A.26.02.1B Bedroom	0.98
A.26.03.2B Bedroom	1.74
A.26.03.2B Bedroom	2.21
A.26.04.2B Bedroom	1.93
A.26.04.2B Bedroom	2.40
A.26.05.2B Bedroom	1.50
A.26.05.2B Bedroom	1.99
A.26.06.1B Bedroom	0.87
A.26.07.1B Bedroom	1.14
A.26.08.2B Bedroom	0.63
A.26.08.2B Bedroom	1.25

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.26.09.2B Bedroom	0.41
A.26.09.2B Bedroom	0.93
A.26.10.2B Bedroom	0.27
A.26.10.2B Bedroom	0.57
A.27.01.1B Bedroom	1.23
A.27.02.1B Bedroom	0.98
A.27.03.2B Bedroom	1.74
A.27.03.2B Bedroom	2.21
A.27.04.2B Bedroom	2.40
A.27.04.2B Bedroom	1.93
A.27.05.2B Bedroom	1.50
A.27.05.2B Bedroom	1.99
A.27.06.1B Bedroom	0.87
A.27.07.1B Bedroom	1.14
A.27.08.2B Bedroom	1.25
A.27.08.2B Bedroom	0.63
A.27.09.2B Bedroom	0.93
A.27.09.2B Bedroom	0.41
A.27.10.2B Bedroom	0.27
A.27.10.2B Bedroom	0.57
A.28.01.1B Bedroom	1.23
A.28.02.1B Bedroom	0.98
A.28.03.2B Bedroom	2.21
A.28.03.2B Bedroom	1.74
A.28.04.2B Bedroom	2.40

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.28.04.2B Bedroom	1.93
A.28.05.2B Bedroom	1.99
A.28.05.2B Bedroom	1.50
A.28.06.1B Bedroom	0.87
A.28.07.1B Bedroom	1.14
A.28.08.2B Bedroom	1.25
A.28.08.2B Bedroom	0.63
A.28.09.2B Bedroom	0.93
A.28.09.2B Bedroom	0.41
A.28.10.2B Bedroom	0.27
A.28.10.2B Bedroom	0.57
A.29.01.1B Bedroom	1.23
A.29.02.1B Bedroom	0.98
A.29.03.2B Bedroom	2.21
A.29.03.2B Bedroom	1.74
A.29.04.2B Bedroom	1.93
A.29.04.2B Bedroom	2.40
A.29.05.2B Bedroom	1.50
A.29.05.2B Bedroom	1.99
A.29.06.1B Bedroom	0.87
A.29.07.1B Bedroom	1.14
A.29.08.2B Bedroom	0.63
A.29.08.2B Bedroom	1.25
A.29.09.2B Bedroom	0.93
A.29.09.2B Bedroom	0.41

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.29.10.2B Bedroom	0.27
A.29.10.2B Bedroom	0.57
A.30.01.1B Bedroom	1.23
A.30.02.1B Bedroom	0.98
A.30.03.2B Bedroom	1.74
A.30.03.2B Bedroom	2.21
A.30.04.2B Bedroom	2.40
A.30.04.2B Bedroom	1.93
A.30.05.2B Bedroom	1.50
A.30.05.2B Bedroom	1.99
A.30.06.1B Bedroom	0.87
A.30.07.1B Bedroom	1.14
A.30.08.2B Bedroom	0.60
A.30.08.2B Bedroom	1.25
A.30.09.2B Bedroom	0.93
A.30.09.2B Bedroom	0.41
A.30.10.2B Bedroom	0.57
A.30.10.2B Bedroom	0.27
A.31.01.1B Bedroom	1.20
A.31.02.1B Bedroom	0.98
A.31.03.2B Bedroom	1.69
A.31.03.2B Bedroom	2.18
A.31.04.2B Bedroom	2.37
A.31.04.2B Bedroom	1.91
A.31.05.2B Bedroom	1.50

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.31.05.2B Bedroom	1.99
A.31.06.1B Bedroom	0.84
A.31.07.1B Bedroom	1.12
A.31.08.2B Bedroom	1.25
A.31.08.2B Bedroom	0.57
A.31.09.2B Bedroom	0.90
A.31.09.2B Bedroom	0.41
A.31.10.2B Bedroom	0.57
A.31.10.2B Bedroom	0.27
A.32.01.1B Bedroom	1.20
A.32.02.1B Bedroom	0.98
A.32.03.2B Bedroom	1.69
A.32.03.2B Bedroom	2.18
A.32.04.2B Bedroom	2.37
A.32.04.2B Bedroom	1.91
A.32.05.2B Bedroom	1.99
A.32.05.2B Bedroom	1.50
A.32.06.1B Bedroom	0.82
A.32.07.1B Bedroom	1.12
A.32.08.2B Bedroom	0.54
A.32.08.2B Bedroom	1.25
A.32.09.2B Bedroom	0.41
A.32.09.2B Bedroom	0.90
A.32.10.2B Bedroom	0.57
A.32.10.2B Bedroom	0.27

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.33.01.1B Bedroom	1.20
A.33.02.1B Bedroom	0.98
A.33.03.2B Bedroom	2.18
A.33.03.2B Bedroom	1.69
A.33.04.2B Bedroom	2.37
A.33.04.2B Bedroom	1.91
A.33.05.2B Bedroom	1.50
A.33.05.2B Bedroom	1.99
A.33.06.1B Bedroom	0.82
A.33.07.1B Bedroom	1.12
A.33.08.2B Bedroom	0.54
A.33.08.2B Bedroom	1.25
A.33.09.2B Bedroom	0.90
A.33.09.2B Bedroom	0.41
A.33.10.2B Bedroom	0.57
A.33.10.2B Bedroom	0.27
A.34.01.1B Bedroom	1.20
A.34.02.1B Bedroom	0.98
A.34.03.2B Bedroom	1.69
A.34.03.2B Bedroom	2.18
A.34.04.2B Bedroom	1.91
A.34.04.2B Bedroom	2.37
A.34.05.2B Bedroom	1.50
A.34.05.2B Bedroom	1.99
A.34.06.1B Bedroom	0.82

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.34.07.1B Bedroom	1.12
A.34.08.2B Bedroom	0.54
A.34.08.2B Bedroom	1.25
A.34.09.2B Bedroom	0.90
A.34.09.2B Bedroom	0.41
A.34.10.2B Bedroom	0.57
A.34.10.2B Bedroom	0.27
A.35.01.1B Bedroom	1.20
A.35.02.1B Bedroom	0.98
A.35.03.2B Bedroom	2.18
A.35.03.2B Bedroom	1.69
A.35.04.2B Bedroom	2.37
A.35.04.2B Bedroom	1.91
A.35.05.2B Bedroom	1.50
A.35.05.2B Bedroom	1.99
A.35.06.1B Bedroom	0.82
A.35.07.1B Bedroom	1.12
A.35.08.2B Bedroom	0.54
A.35.08.2B Bedroom	1.25
A.35.09.2B Bedroom	0.90
A.35.09.2B Bedroom	0.41
A.35.10.2B Bedroom	0.27
A.35.10.2B Bedroom	0.57
A.36.01.1B Bedroom	1.20
A.36.02.1B Bedroom	0.98

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.36.03.2B Bedroom	2.18
A.36.03.2B Bedroom	1.69
A.36.04.2B Bedroom	2.37
A.36.04.2B Bedroom	1.91
A.36.05.2B Bedroom	1.99
A.36.05.2B Bedroom	1.50
A.36.06.1B Bedroom	0.82
A.36.07.1B Bedroom	1.12
A.36.08.2B Bedroom	0.54
A.36.08.2B Bedroom	1.25
A.36.09.2B Bedroom	0.41
A.36.09.2B Bedroom	0.90
A.36.10.2B Bedroom	0.57
A.36.10.2B Bedroom	0.27
A.37.01.1B Bedroom	1.20
A.37.02.1B Bedroom	0.98
A.37.03.2B Bedroom	1.69
A.37.03.2B Bedroom	2.18
A.37.04.2B Bedroom	1.91
A.37.04.2B Bedroom	2.37
A.37.05.2B Bedroom	1.50
A.37.05.2B Bedroom	1.99
A.37.06.1B Bedroom	0.82
A.37.07.1B Bedroom	1.12
A.37.08.2B Bedroom	0.54

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.37.08.2B Bedroom	1.25
A.37.09.2B Bedroom	0.90
A.37.09.2B Bedroom	0.41
A.37.10.2B Bedroom	0.27
A.37.10.2B Bedroom	0.57
A.38.01.1B Bedroom	1.20
A.38.02.1B Bedroom	0.98
A.38.03.2B Bedroom	1.69
A.38.03.2B Bedroom	2.18
A.38.04.2B Bedroom	1.91
A.38.04.2B Bedroom	2.37
A.38.05.2B Bedroom	1.50
A.38.05.2B Bedroom	1.99
A.38.06.1B Bedroom	0.84
A.38.07.1B Bedroom	1.12
A.38.08.2B Bedroom	0.54
A.38.08.2B Bedroom	1.25
A.38.09.2B Bedroom	0.41
A.38.09.2B Bedroom	0.90
A.38.10.2B Bedroom	0.27
A.38.10.2B Bedroom	0.57
A.39.01.1B Bedroom	1.20
A.39.02.1B Bedroom	0.98
A.39.03.2B Bedroom	2.18
A.39.03.2B Bedroom	1.69

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.39.04.2B Bedroom	1.91
A.39.04.2B Bedroom	2.37
A.39.05.2B Bedroom	1.50
A.39.05.2B Bedroom	1.99
A.39.06.1B Bedroom	0.84
A.39.07.1B Bedroom	1.12
A.39.08.2B Bedroom	0.57
A.39.08.2B Bedroom	1.25
A.39.09.2B Bedroom	0.41
A.39.09.2B Bedroom	0.90
A.39.10.2B Bedroom	0.57
A.39.10.2B Bedroom	0.27
A.40.01.1B Bedroom	1.25
A.40.02.1B Bedroom	0.98
A.40.03.2B Bedroom	2.23
A.40.03.2B Bedroom	1.77
A.40.04.2B Bedroom	2.40
A.40.04.2B Bedroom	1.91
A.40.05.2B Bedroom	2.02
A.40.05.2B Bedroom	1.53
A.40.06.1B Bedroom	0.87
A.40.07.1B Bedroom	1.17
A.40.08.2B Bedroom	0.57
A.40.08.2B Bedroom	1.31
A.40.09.2B Bedroom	0.93

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.40.09.2B Bedroom	0.44
A.40.10.2B Bedroom	0.27
A.40.10.2B Bedroom	0.60
A.41.01.1B Bedroom	1.28
A.41.02.1B Bedroom	1.01
A.41.03.2B Bedroom	2.26
A.41.03.2B Bedroom	1.80
A.41.04.2B Bedroom	2.40
A.41.04.2B Bedroom	1.91
A.41.05.2B Bedroom	1.53
A.41.05.2B Bedroom	2.02
A.41.06.1B Bedroom	0.87
A.41.07.1B Bedroom	1.17
A.41.08.2B Bedroom	0.60
A.41.08.2B Bedroom	1.33
A.41.09.2B Bedroom	0.44
A.41.09.2B Bedroom	0.93
A.41.10.2B Bedroom	0.60
A.41.10.2B Bedroom	0.27
A.42.01.1B Bedroom	1.28
A.42.02.1B Bedroom	1.01
A.42.03.2B Bedroom	1.80
A.42.03.2B Bedroom	2.26
A.42.04.2B Bedroom	1.91
A.42.04.2B Bedroom	2.40

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.42.05.2B Bedroom	1.53
A.42.05.2B Bedroom	2.02
A.42.06.1B Bedroom	0.87
A.42.07.1B Bedroom	1.17
A.42.08.2B Bedroom	0.60
A.42.08.2B Bedroom	1.36
A.42.09.2B Bedroom	0.93
A.42.09.2B Bedroom	0.44
A.42.10.2B Bedroom	0.27
A.42.10.2B Bedroom	0.60
A.43.01.1B Bedroom	1.28
A.43.02.1B Bedroom	1.01
A.43.03.2B Bedroom	2.26
A.43.03.2B Bedroom	1.80
A.43.04.2B Bedroom	2.40
A.43.04.2B Bedroom	1.91
A.43.05.2B Bedroom	2.02
A.43.05.2B Bedroom	1.53
A.43.06.1B Bedroom	0.87
A.43.07.1B Bedroom	1.17
A.43.08.2B Bedroom	1.33
A.43.08.2B Bedroom	0.60
A.43.09.2B Bedroom	0.44
A.43.09.2B Bedroom	0.93
A.43.10.2B Bedroom	0.60

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.43.10.2B Bedroom	0.27
A.44.01.1B Bedroom	1.31
A.44.02.1B Bedroom	1.06
A.44.03.2B Bedroom	2.26
A.44.03.2B Bedroom	1.77
A.44.04.2B Bedroom	2.40
A.44.04.2B Bedroom	1.88
A.44.05.2B Bedroom	2.02
A.44.05.2B Bedroom	1.53
A.44.06.1B Bedroom	0.84
A.44.07.1B Bedroom	1.17
A.44.08.2B Bedroom	0.57
A.44.08.2B Bedroom	1.28
A.44.09.2B Bedroom	0.44
A.44.09.2B Bedroom	0.93
A.44.10.2B Bedroom	0.27
A.44.10.2B Bedroom	0.60
A.45.01.3B Bedroom	1.25
A.45.01.3B Bedroom	0.63
A.45.01.3B Bedroom	2.37
A.45.02.3B Bedroom	2.23
A.45.02.3B Bedroom	1.53
A.45.02.3B Bedroom	2.10
A.45.03.3B Bedroom	1.96
A.45.03.3B Bedroom	1.53

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
A.45.03.3B Bedroom	1.12
A.45.04.3B Bedroom	1.28
A.45.04.3B Bedroom	0.25
A.45.04.3B Bedroom	0.68
A.45.05.3B Bedroom	0.44
A.45.05.3B Bedroom	0.41
A.45.05.3B Bedroom	0.22
A.45.06.3B Bedroom	0.84
A.45.06.3B Bedroom	0.54
A.45.06.3B Bedroom	0.38

14.0 Appendix 8: DSY 3: Bedroom Night-time Temperature Test Block A

Location	Operative Temperature > 26 (Max 1%)
A.02.01.1B Bedroom	0.57
A.02.02.1B Bedroom	0.46
A.02.03.2B Bedroom	0.52
A.02.03.2B Bedroom	0.49
A.02.04.2B Bedroom	0.65
A.02.04.2B Bedroom	0.60
A.02.05.2B Bedroom	0.57
A.02.05.2B Bedroom	0.57
A.02.06.1B Bedroom	0.49
A.02.07.1B Bedroom	0.46
A.02.08.2B Bedroom	0.44
A.02.08.2B Bedroom	0.52
A.02.09.2B Bedroom	0.33
A.02.09.2B Bedroom	0.49
A.02.10.2B Bedroom	0.41
A.02.10.2B Bedroom	0.49
A.03.01.1B Bedroom	0.54
A.03.02.1B Bedroom	0.65
A.03.03.2B Bedroom	0.65
A.03.03.2B Bedroom	0.74
A.03.04.2B Bedroom	0.74
A.03.04.2B Bedroom	0.84
A.03.05.2B Bedroom	0.76
A.03.05.2B Bedroom	0.74
A.03.06.1B Bedroom	0.63
A.03.07.1B Bedroom	0.63
A.03.08.2B Bedroom	0.63
A.03.08.2B Bedroom	0.71
A.03.09.2B Bedroom	0.54
A.03.09.2B Bedroom	0.68
A.03.10.2B Bedroom	0.57
A.03.10.2B Bedroom	0.65
A.04.01.1B Bedroom	0.57
A.04.02.1B Bedroom	0.65
A.04.03.2B Bedroom	0.71
A.04.03.2B Bedroom	0.65
A.04.04.2B Bedroom	0.79
A.04.04.2B Bedroom	0.68
A.04.05.2B Bedroom	0.65
A.04.05.2B Bedroom	0.74
A.04.06.1B Bedroom	0.60
A.04.07.1B Bedroom	0.60
A.04.08.2B Bedroom	0.57

Location	Operative Temperature > 26 (Max 1%)
A.04.08.2B Bedroom	0.68
A.04.09.2B Bedroom	0.52
A.04.09.2B Bedroom	0.68
A.04.10.2B Bedroom	0.46
A.04.10.2B Bedroom	0.54
A.05.01.1B Bedroom	0.57
A.05.02.1B Bedroom	0.65
A.05.03.2B Bedroom	0.71
A.05.03.2B Bedroom	0.65
A.05.04.2B Bedroom	0.79
A.05.04.2B Bedroom	0.68
A.05.05.2B Bedroom	0.65
A.05.05.2B Bedroom	0.74
A.05.06.1B Bedroom	0.60
A.05.07.1B Bedroom	0.60
A.05.08.2B Bedroom	0.57
A.05.08.2B Bedroom	0.68
A.05.09.2B Bedroom	0.68
A.05.09.2B Bedroom	0.52
A.05.10.2B Bedroom	0.46
A.05.10.2B Bedroom	0.54
A.06.01.1B Bedroom	0.57
A.06.02.1B Bedroom	0.65
A.06.03.2B Bedroom	0.68
A.06.03.2B Bedroom	0.65

Location	Operative Temperature > 26 (Max 1%)
A.06.04.2B Bedroom	0.79
A.06.04.2B Bedroom	0.68
A.06.05.2B Bedroom	0.65
A.06.05.2B Bedroom	0.74
A.06.06.1B Bedroom	0.60
A.06.07.1B Bedroom	0.63
A.06.08.2B Bedroom	0.68
A.06.08.2B Bedroom	0.57
A.06.09.2B Bedroom	0.68
A.06.09.2B Bedroom	0.52
A.06.10.2B Bedroom	0.54
A.06.10.2B Bedroom	0.46
A.07.01.1B Bedroom	0.57
A.07.02.1B Bedroom	0.65
A.07.03.2B Bedroom	0.65
A.07.03.2B Bedroom	0.71
A.07.04.2B Bedroom	0.68
A.07.04.2B Bedroom	0.79
A.07.05.2B Bedroom	0.65
A.07.05.2B Bedroom	0.74
A.07.06.1B Bedroom	0.60
A.07.07.1B Bedroom	0.63
A.07.08.2B Bedroom	0.57
A.07.08.2B Bedroom	0.68
A.07.09.2B Bedroom	0.68

Location	Operative Temperature > 26 (Max 1%)
A.07.09.2B Bedroom	0.52
A.07.10.2B Bedroom	0.54
A.07.10.2B Bedroom	0.46
A.08.01.1B Bedroom	0.57
A.08.02.1B Bedroom	0.65
A.08.03.2B Bedroom	0.71
A.08.03.2B Bedroom	0.65
A.08.04.2B Bedroom	0.79
A.08.04.2B Bedroom	0.68
A.08.05.2B Bedroom	0.74
A.08.05.2B Bedroom	0.65
A.08.06.1B Bedroom	0.60
A.08.07.1B Bedroom	0.63
A.08.08.2B Bedroom	0.57
A.08.08.2B Bedroom	0.68
A.08.09.2B Bedroom	0.68
A.08.09.2B Bedroom	0.52
A.08.10.2B Bedroom	0.57
A.08.10.2B Bedroom	0.49
A.09.01.1B Bedroom	0.57
A.09.02.1B Bedroom	0.65
A.09.03.2B Bedroom	0.65
A.09.03.2B Bedroom	0.71
A.09.04.2B Bedroom	0.68
A.09.04.2B Bedroom	0.79

Location	Operative Temperature > 26 (Max 1%)
A.09.05.2B Bedroom	0.65
A.09.05.2B Bedroom	0.74
A.09.06.1B Bedroom	0.60
A.09.07.1B Bedroom	0.63
A.09.08.2B Bedroom	0.57
A.09.08.2B Bedroom	0.68
A.09.09.2B Bedroom	0.68
A.09.09.2B Bedroom	0.52
A.09.10.2B Bedroom	0.46
A.09.10.2B Bedroom	0.57
A.10.01.1B Bedroom	0.57
A.10.02.1B Bedroom	0.65
A.10.03.2B Bedroom	0.71
A.10.03.2B Bedroom	0.65
A.10.04.2B Bedroom	0.68
A.10.04.2B Bedroom	0.79
A.10.05.2B Bedroom	0.74
A.10.05.2B Bedroom	0.65
A.10.06.1B Bedroom	0.63
A.10.07.1B Bedroom	0.63
A.10.08.2B Bedroom	0.68
A.10.08.2B Bedroom	0.57
A.10.09.2B Bedroom	0.54
A.10.09.2B Bedroom	0.68
A.10.10.2B Bedroom	0.46

Location	Operative Temperature > 26 (Max 1%)
A.10.10.2B Bedroom	0.57
A.11.01.1B Bedroom	0.57
A.11.02.1B Bedroom	0.65
A.11.03.2B Bedroom	0.71
A.11.03.2B Bedroom	0.65
A.11.04.2B Bedroom	0.68
A.11.04.2B Bedroom	0.79
A.11.05.2B Bedroom	0.74
A.11.05.2B Bedroom	0.65
A.11.06.1B Bedroom	0.63
A.11.07.1B Bedroom	0.68
A.11.08.2B Bedroom	0.60
A.11.08.2B Bedroom	0.74
A.11.09.2B Bedroom	0.68
A.11.09.2B Bedroom	0.54
A.11.10.2B Bedroom	0.57
A.11.10.2B Bedroom	0.49
A.12.01.1B Bedroom	0.57
A.12.02.1B Bedroom	0.65
A.12.03.2B Bedroom	0.71
A.12.03.2B Bedroom	0.68
A.12.04.2B Bedroom	0.68
A.12.04.2B Bedroom	0.79
A.12.05.2B Bedroom	0.74
A.12.05.2B Bedroom	0.65

Location	Operative Temperature > 26 (Max 1%)
A.12.06.1B Bedroom	0.63
A.12.07.1B Bedroom	0.65
A.12.08.2B Bedroom	0.74
A.12.08.2B Bedroom	0.57
A.12.09.2B Bedroom	0.68
A.12.09.2B Bedroom	0.54
A.12.10.2B Bedroom	0.52
A.12.10.2B Bedroom	0.60
A.13.01.1B Bedroom	0.65
A.13.02.1B Bedroom	0.68
A.13.03.2B Bedroom	0.71
A.13.03.2B Bedroom	0.74
A.13.05.2B Bedroom	0.65
A.13.05.2B Bedroom	0.82
A.13.06.1B Bedroom	0.74
A.13.07.1B Bedroom	0.82
A.13.08.2B Bedroom	0.84
A.13.08.2B Bedroom	0.71
A.13.09.2B Bedroom	0.68
A.13.09.2B Bedroom	0.57
A.13.10.2B Bedroom	0.74
A.13.10.2B Bedroom	0.65
A.13.13.2B Bedroom	0.74
A.13.13.2B Bedroom	0.90
A.14.01.1B Bedroom	0.57

Location	Operative Temperature > 26 (Max 1%)
A.14.02.1B Bedroom	0.63
A.14.03.2B Bedroom	0.65
A.14.03.2B Bedroom	0.65
A.14.04.2B Bedroom	0.63
A.14.04.2B Bedroom	0.76
A.14.05.2B Bedroom	0.71
A.14.05.2B Bedroom	0.63
A.14.06.1B Bedroom	0.60
A.14.07.1B Bedroom	0.63
A.14.08.2B Bedroom	0.57
A.14.08.2B Bedroom	0.71
A.14.09.2B Bedroom	0.46
A.14.09.2B Bedroom	0.65
A.14.10.2B Bedroom	0.54
A.14.10.2B Bedroom	0.46
A.15.01.1B Bedroom	0.49
A.15.02.1B Bedroom	0.63
A.15.03.2B Bedroom	0.65
A.15.03.2B Bedroom	0.65
A.15.04.2B Bedroom	0.63
A.15.04.2B Bedroom	0.76
A.15.05.2B Bedroom	0.63
A.15.05.2B Bedroom	0.71
A.15.06.1B Bedroom	0.60
A.15.07.1B Bedroom	0.60

Location	Operative Temperature > 26 (Max 1%)
A.15.08.2B Bedroom	0.68
A.15.08.2B Bedroom	0.54
A.15.09.2B Bedroom	0.65
A.15.09.2B Bedroom	0.44
A.15.10.2B Bedroom	0.54
A.15.10.2B Bedroom	0.46
A.16.01.1B Bedroom	0.49
A.16.02.1B Bedroom	0.63
A.16.03.2B Bedroom	0.65
A.16.03.2B Bedroom	0.65
A.16.04.2B Bedroom	0.63
A.16.04.2B Bedroom	0.76
A.16.05.2B Bedroom	0.63
A.16.05.2B Bedroom	0.71
A.16.06.1B Bedroom	0.60
A.16.07.1B Bedroom	0.60
A.16.08.2B Bedroom	0.68
A.16.08.2B Bedroom	0.54
A.16.09.2B Bedroom	0.41
A.16.09.2B Bedroom	0.65
A.16.10.2B Bedroom	0.46
A.16.10.2B Bedroom	0.54
A.17.01.1B Bedroom	0.49
A.17.02.1B Bedroom	0.63
A.17.03.2B Bedroom	0.65

Location	Operative Temperature > 26 (Max 1%)
A.17.03.2B Bedroom	0.65
A.17.04.2B Bedroom	0.76
A.17.04.2B Bedroom	0.63
A.17.05.2B Bedroom	0.63
A.17.05.2B Bedroom	0.71
A.17.06.1B Bedroom	0.60
A.17.07.1B Bedroom	0.60
A.17.08.2B Bedroom	0.68
A.17.08.2B Bedroom	0.54
A.17.09.2B Bedroom	0.65
A.17.09.2B Bedroom	0.41
A.17.10.2B Bedroom	0.46
A.17.10.2B Bedroom	0.54
A.18.01.1B Bedroom	0.49
A.18.02.1B Bedroom	0.63
A.18.03.2B Bedroom	0.65
A.18.03.2B Bedroom	0.65
A.18.04.2B Bedroom	0.63
A.18.04.2B Bedroom	0.76
A.18.05.2B Bedroom	0.63
A.18.05.2B Bedroom	0.71
A.18.06.1B Bedroom	0.60
A.18.07.1B Bedroom	0.60
A.18.08.2B Bedroom	0.54
A.18.08.2B Bedroom	0.68

Location	Operative Temperature > 26 (Max 1%)
A.18.09.2B Bedroom	0.65
A.18.09.2B Bedroom	0.41
A.18.10.2B Bedroom	0.54
A.18.10.2B Bedroom	0.46
A.19.01.1B Bedroom	0.49
A.19.02.1B Bedroom	0.63
A.19.03.2B Bedroom	0.65
A.19.03.2B Bedroom	0.65
A.19.04.2B Bedroom	0.76
A.19.04.2B Bedroom	0.63
A.19.05.2B Bedroom	0.63
A.19.05.2B Bedroom	0.71
A.19.06.1B Bedroom	0.60
A.19.07.1B Bedroom	0.60
A.19.08.2B Bedroom	0.68
A.19.08.2B Bedroom	0.54
A.19.09.2B Bedroom	0.41
A.19.09.2B Bedroom	0.65
A.19.10.2B Bedroom	0.46
A.19.10.2B Bedroom	0.54
A.20.01.1B Bedroom	0.49
A.20.02.1B Bedroom	0.63
A.20.03.2B Bedroom	0.65
A.20.03.2B Bedroom	0.65
A.20.04.2B Bedroom	0.76

Location	Operative Temperature > 26 (Max 1%)
A.20.04.2B Bedroom	0.63
A.20.05.2B Bedroom	0.63
A.20.05.2B Bedroom	0.71
A.20.06.1B Bedroom	0.60
A.20.07.1B Bedroom	0.60
A.20.08.2B Bedroom	0.68
A.20.08.2B Bedroom	0.54
A.20.09.2B Bedroom	0.65
A.20.09.2B Bedroom	0.44
A.20.10.2B Bedroom	0.54
A.20.10.2B Bedroom	0.46
A.21.01.1B Bedroom	0.49
A.21.02.1B Bedroom	0.63
A.21.03.2B Bedroom	0.65
A.21.03.2B Bedroom	0.63
A.21.04.2B Bedroom	0.76
A.21.04.2B Bedroom	0.63
A.21.05.2B Bedroom	0.71
A.21.05.2B Bedroom	0.63
A.21.06.1B Bedroom	0.60
A.21.07.1B Bedroom	0.60
A.21.08.2B Bedroom	0.68
A.21.08.2B Bedroom	0.54
A.21.09.2B Bedroom	0.41
A.21.09.2B Bedroom	0.65

Location	Operative Temperature > 26 (Max 1%)
A.21.10.2B Bedroom	0.54
A.21.10.2B Bedroom	0.46
A.22.01.1B Bedroom	0.49
A.22.02.1B Bedroom	0.57
A.22.03.2B Bedroom	0.63
A.22.03.2B Bedroom	0.63
A.22.04.2B Bedroom	0.63
A.22.04.2B Bedroom	0.68
A.22.05.2B Bedroom	0.60
A.22.05.2B Bedroom	0.63
A.22.06.1B Bedroom	0.60
A.22.07.1B Bedroom	0.52
A.22.08.2B Bedroom	0.46
A.22.08.2B Bedroom	0.63
A.22.09.2B Bedroom	0.60
A.22.09.2B Bedroom	0.38
A.22.10.2B Bedroom	0.54
A.22.10.2B Bedroom	0.44
A.23.01.1B Bedroom	0.49
A.23.02.1B Bedroom	0.57
A.23.03.2B Bedroom	0.60
A.23.03.2B Bedroom	0.63
A.23.04.2B Bedroom	0.68
A.23.04.2B Bedroom	0.63
A.23.05.2B Bedroom	0.60

Location	Operative Temperature > 26 (Max 1%)
A.23.05.2B Bedroom	0.63
A.23.06.1B Bedroom	0.60
A.23.07.1B Bedroom	0.52
A.23.08.2B Bedroom	0.46
A.23.08.2B Bedroom	0.63
A.23.09.2B Bedroom	0.38
A.23.09.2B Bedroom	0.60
A.23.10.2B Bedroom	0.44
A.23.10.2B Bedroom	0.54
A.24.01.1B Bedroom	0.49
A.24.02.1B Bedroom	0.57
A.24.03.2B Bedroom	0.60
A.24.03.2B Bedroom	0.63
A.24.04.2B Bedroom	0.63
A.24.04.2B Bedroom	0.68
A.24.05.2B Bedroom	0.60
A.24.05.2B Bedroom	0.63
A.24.06.1B Bedroom	0.60
A.24.07.1B Bedroom	0.52
A.24.08.2B Bedroom	0.63
A.24.08.2B Bedroom	0.46
A.24.09.2B Bedroom	0.38
A.24.09.2B Bedroom	0.60
A.24.10.2B Bedroom	0.44
A.24.10.2B Bedroom	0.54

Location	Operative Temperature > 26 (Max 1%)
A.25.01.1B Bedroom	0.49
A.25.02.1B Bedroom	0.57
A.25.03.2B Bedroom	0.60
A.25.03.2B Bedroom	0.63
A.25.04.2B Bedroom	0.68
A.25.04.2B Bedroom	0.63
A.25.05.2B Bedroom	0.60
A.25.05.2B Bedroom	0.63
A.25.06.1B Bedroom	0.60
A.25.07.1B Bedroom	0.52
A.25.08.2B Bedroom	0.63
A.25.08.2B Bedroom	0.46
A.25.09.2B Bedroom	0.60
A.25.09.2B Bedroom	0.38
A.25.10.2B Bedroom	0.44
A.25.10.2B Bedroom	0.54
A.26.01.1B Bedroom	0.49
A.26.02.1B Bedroom	0.57
A.26.03.2B Bedroom	0.63
A.26.03.2B Bedroom	0.60
A.26.04.2B Bedroom	0.68
A.26.04.2B Bedroom	0.63
A.26.05.2B Bedroom	0.63
A.26.05.2B Bedroom	0.60
A.26.06.1B Bedroom	0.60

Location	Operative Temperature > 26 (Max 1%)
A.26.07.1B Bedroom	0.52
A.26.08.2B Bedroom	0.46
A.26.08.2B Bedroom	0.63
A.26.09.2B Bedroom	0.38
A.26.09.2B Bedroom	0.60
A.26.10.2B Bedroom	0.54
A.26.10.2B Bedroom	0.44
A.27.01.1B Bedroom	0.49
A.27.02.1B Bedroom	0.57
A.27.03.2B Bedroom	0.63
A.27.03.2B Bedroom	0.60
A.27.04.2B Bedroom	0.63
A.27.04.2B Bedroom	0.68
A.27.05.2B Bedroom	0.63
A.27.05.2B Bedroom	0.60
A.27.06.1B Bedroom	0.60
A.27.07.1B Bedroom	0.52
A.27.08.2B Bedroom	0.63
A.27.08.2B Bedroom	0.46
A.27.09.2B Bedroom	0.60
A.27.09.2B Bedroom	0.38
A.27.10.2B Bedroom	0.54
A.27.10.2B Bedroom	0.44
A.28.01.1B Bedroom	0.49
A.28.02.1B Bedroom	0.57

Location	Operative Temperature > 26 (Max 1%)
A.28.03.2B Bedroom	0.60
A.28.03.2B Bedroom	0.63
A.28.04.2B Bedroom	0.63
A.28.04.2B Bedroom	0.68
A.28.05.2B Bedroom	0.60
A.28.05.2B Bedroom	0.63
A.28.06.1B Bedroom	0.60
A.28.07.1B Bedroom	0.52
A.28.08.2B Bedroom	0.63
A.28.08.2B Bedroom	0.46
A.28.09.2B Bedroom	0.60
A.28.09.2B Bedroom	0.38
A.28.10.2B Bedroom	0.54
A.28.10.2B Bedroom	0.44
A.29.01.1B Bedroom	0.49
A.29.02.1B Bedroom	0.57
A.29.03.2B Bedroom	0.63
A.29.03.2B Bedroom	0.63
A.29.04.2B Bedroom	0.68
A.29.04.2B Bedroom	0.63
A.29.05.2B Bedroom	0.63
A.29.05.2B Bedroom	0.60
A.29.06.1B Bedroom	0.60
A.29.07.1B Bedroom	0.52
A.29.08.2B Bedroom	0.46

Location	Operative Temperature > 26 (Max 1%)
A.29.08.2B Bedroom	0.63
A.29.09.2B Bedroom	0.60
A.29.09.2B Bedroom	0.38
A.29.10.2B Bedroom	0.54
A.29.10.2B Bedroom	0.44
A.30.01.1B Bedroom	0.49
A.30.02.1B Bedroom	0.57
A.30.03.2B Bedroom	0.63
A.30.03.2B Bedroom	0.60
A.30.04.2B Bedroom	0.63
A.30.04.2B Bedroom	0.68
A.30.05.2B Bedroom	0.63
A.30.05.2B Bedroom	0.60
A.30.06.1B Bedroom	0.60
A.30.07.1B Bedroom	0.52
A.30.08.2B Bedroom	0.46
A.30.08.2B Bedroom	0.63
A.30.09.2B Bedroom	0.60
A.30.09.2B Bedroom	0.38
A.30.10.2B Bedroom	0.44
A.30.10.2B Bedroom	0.54
A.31.01.1B Bedroom	0.49
A.31.02.1B Bedroom	0.54
A.31.03.2B Bedroom	0.63
A.31.03.2B Bedroom	0.54

Location	Operative Temperature > 26 (Max 1%)
A.31.04.2B Bedroom	0.63
A.31.04.2B Bedroom	0.65
A.31.05.2B Bedroom	0.63
A.31.05.2B Bedroom	0.60
A.31.06.1B Bedroom	0.54
A.31.07.1B Bedroom	0.52
A.31.08.2B Bedroom	0.60
A.31.08.2B Bedroom	0.46
A.31.09.2B Bedroom	0.60
A.31.09.2B Bedroom	0.38
A.31.10.2B Bedroom	0.44
A.31.10.2B Bedroom	0.52
A.32.01.1B Bedroom	0.49
A.32.02.1B Bedroom	0.54
A.32.03.2B Bedroom	0.63
A.32.03.2B Bedroom	0.54
A.32.04.2B Bedroom	0.63
A.32.04.2B Bedroom	0.65
A.32.05.2B Bedroom	0.60
A.32.05.2B Bedroom	0.63
A.32.06.1B Bedroom	0.54
A.32.07.1B Bedroom	0.52
A.32.08.2B Bedroom	0.46
A.32.08.2B Bedroom	0.60
A.32.09.2B Bedroom	0.38

Location	Operative Temperature > 26 (Max 1%)
A.32.09.2B Bedroom	0.57
A.32.10.2B Bedroom	0.44
A.32.10.2B Bedroom	0.52
A.33.01.1B Bedroom	0.49
A.33.02.1B Bedroom	0.54
A.33.03.2B Bedroom	0.54
A.33.03.2B Bedroom	0.63
A.33.04.2B Bedroom	0.63
A.33.04.2B Bedroom	0.65
A.33.05.2B Bedroom	0.63
A.33.05.2B Bedroom	0.60
A.33.06.1B Bedroom	0.54
A.33.07.1B Bedroom	0.52
A.33.08.2B Bedroom	0.46
A.33.08.2B Bedroom	0.60
A.33.09.2B Bedroom	0.57
A.33.09.2B Bedroom	0.38
A.33.10.2B Bedroom	0.44
A.33.10.2B Bedroom	0.52
A.34.01.1B Bedroom	0.49
A.34.02.1B Bedroom	0.54
A.34.03.2B Bedroom	0.63
A.34.03.2B Bedroom	0.54
A.34.04.2B Bedroom	0.65
A.34.04.2B Bedroom	0.63

Location	Operative Temperature > 26 (Max 1%)
A.34.05.2B Bedroom	0.63
A.34.05.2B Bedroom	0.60
A.34.06.1B Bedroom	0.54
A.34.07.1B Bedroom	0.52
A.34.08.2B Bedroom	0.46
A.34.08.2B Bedroom	0.60
A.34.09.2B Bedroom	0.57
A.34.09.2B Bedroom	0.38
A.34.10.2B Bedroom	0.44
A.34.10.2B Bedroom	0.52
A.35.01.1B Bedroom	0.49
A.35.02.1B Bedroom	0.54
A.35.03.2B Bedroom	0.54
A.35.03.2B Bedroom	0.63
A.35.04.2B Bedroom	0.63
A.35.04.2B Bedroom	0.65
A.35.05.2B Bedroom	0.63
A.35.05.2B Bedroom	0.60
A.35.06.1B Bedroom	0.54
A.35.07.1B Bedroom	0.52
A.35.08.2B Bedroom	0.46
A.35.08.2B Bedroom	0.60
A.35.09.2B Bedroom	0.57
A.35.09.2B Bedroom	0.38
A.35.10.2B Bedroom	0.52

Location	Operative Temperature > 26 (Max 1%)
A.35.10.2B Bedroom	0.44
A.36.01.1B Bedroom	0.49
A.36.02.1B Bedroom	0.54
A.36.03.2B Bedroom	0.54
A.36.03.2B Bedroom	0.63
A.36.04.2B Bedroom	0.63
A.36.04.2B Bedroom	0.65
A.36.05.2B Bedroom	0.60
A.36.05.2B Bedroom	0.63
A.36.06.1B Bedroom	0.54
A.36.07.1B Bedroom	0.52
A.36.08.2B Bedroom	0.46
A.36.08.2B Bedroom	0.60
A.36.09.2B Bedroom	0.38
A.36.09.2B Bedroom	0.57
A.36.10.2B Bedroom	0.44
A.36.10.2B Bedroom	0.52
A.37.01.1B Bedroom	0.49
A.37.02.1B Bedroom	0.54
A.37.03.2B Bedroom	0.63
A.37.03.2B Bedroom	0.54
A.37.04.2B Bedroom	0.65
A.37.04.2B Bedroom	0.63
A.37.05.2B Bedroom	0.63
A.37.05.2B Bedroom	0.60

Location	Operative Temperature > 26 (Max 1%)
A.37.06.1B Bedroom	0.54
A.37.07.1B Bedroom	0.52
A.37.08.2B Bedroom	0.46
A.37.08.2B Bedroom	0.60
A.37.09.2B Bedroom	0.57
A.37.09.2B Bedroom	0.38
A.37.10.2B Bedroom	0.52
A.37.10.2B Bedroom	0.44
A.38.01.1B Bedroom	0.49
A.38.02.1B Bedroom	0.54
A.38.03.2B Bedroom	0.63
A.38.03.2B Bedroom	0.54
A.38.04.2B Bedroom	0.65
A.38.04.2B Bedroom	0.63
A.38.05.2B Bedroom	0.63
A.38.05.2B Bedroom	0.60
A.38.06.1B Bedroom	0.54
A.38.07.1B Bedroom	0.52
A.38.08.2B Bedroom	0.46
A.38.08.2B Bedroom	0.60
A.38.09.2B Bedroom	0.38
A.38.09.2B Bedroom	0.57
A.38.10.2B Bedroom	0.52
A.38.10.2B Bedroom	0.44
A.39.01.1B Bedroom	0.49

Location	Operative Temperature > 26 (Max 1%)
A.39.02.1B Bedroom	0.54
A.39.03.2B Bedroom	0.54
A.39.03.2B Bedroom	0.63
A.39.04.2B Bedroom	0.65
A.39.04.2B Bedroom	0.63
A.39.05.2B Bedroom	0.63
A.39.05.2B Bedroom	0.60
A.39.06.1B Bedroom	0.54
A.39.07.1B Bedroom	0.52
A.39.08.2B Bedroom	0.46
A.39.08.2B Bedroom	0.63
A.39.09.2B Bedroom	0.38
A.39.09.2B Bedroom	0.60
A.39.10.2B Bedroom	0.44
A.39.10.2B Bedroom	0.52
A.40.01.1B Bedroom	0.52
A.40.02.1B Bedroom	0.63
A.40.03.2B Bedroom	0.65
A.40.03.2B Bedroom	0.65
A.40.04.2B Bedroom	0.63
A.40.04.2B Bedroom	0.74
A.40.05.2B Bedroom	0.60
A.40.05.2B Bedroom	0.71
A.40.06.1B Bedroom	0.60
A.40.07.1B Bedroom	0.63

Location	Operative Temperature > 26 (Max 1%)
A.40.08.2B Bedroom	0.54
A.40.08.2B Bedroom	0.71
A.40.09.2B Bedroom	0.63
A.40.09.2B Bedroom	0.41
A.40.10.2B Bedroom	0.54
A.40.10.2B Bedroom	0.46
A.41.01.1B Bedroom	0.54
A.41.02.1B Bedroom	0.63
A.41.03.2B Bedroom	0.65
A.41.03.2B Bedroom	0.65
A.41.04.2B Bedroom	0.63
A.41.04.2B Bedroom	0.74
A.41.05.2B Bedroom	0.71
A.41.05.2B Bedroom	0.63
A.41.06.1B Bedroom	0.60
A.41.07.1B Bedroom	0.63
A.41.08.2B Bedroom	0.54
A.41.08.2B Bedroom	0.71
A.41.09.2B Bedroom	0.41
A.41.09.2B Bedroom	0.63
A.41.10.2B Bedroom	0.46
A.41.10.2B Bedroom	0.57
A.42.01.1B Bedroom	0.54
A.42.02.1B Bedroom	0.63
A.42.03.2B Bedroom	0.65

Location	Operative Temperature > 26 (Max 1%)
A.42.03.2B Bedroom	0.65
A.42.04.2B Bedroom	0.74
A.42.04.2B Bedroom	0.63
A.42.05.2B Bedroom	0.71
A.42.05.2B Bedroom	0.63
A.42.06.1B Bedroom	0.60
A.42.07.1B Bedroom	0.63
A.42.08.2B Bedroom	0.54
A.42.08.2B Bedroom	0.71
A.42.09.2B Bedroom	0.63
A.42.09.2B Bedroom	0.41
A.42.10.2B Bedroom	0.57
A.42.10.2B Bedroom	0.46
A.43.01.1B Bedroom	0.57
A.43.02.1B Bedroom	0.63
A.43.03.2B Bedroom	0.65
A.43.03.2B Bedroom	0.65
A.43.04.2B Bedroom	0.63
A.43.04.2B Bedroom	0.74
A.43.05.2B Bedroom	0.63
A.43.05.2B Bedroom	0.71
A.43.06.1B Bedroom	0.60
A.43.07.1B Bedroom	0.63
A.43.08.2B Bedroom	0.71
A.43.08.2B Bedroom	0.54

Location	Operative Temperature > 26 (Max 1%)
A.43.09.2B Bedroom	0.41
A.43.09.2B Bedroom	0.63
A.43.10.2B Bedroom	0.46
A.43.10.2B Bedroom	0.57
A.44.01.1B Bedroom	0.57
A.44.02.1B Bedroom	0.63
A.44.03.2B Bedroom	0.65
A.44.03.2B Bedroom	0.65
A.44.04.2B Bedroom	0.63
A.44.04.2B Bedroom	0.71
A.44.05.2B Bedroom	0.63
A.44.05.2B Bedroom	0.71
A.44.06.1B Bedroom	0.60
A.44.07.1B Bedroom	0.57
A.44.08.2B Bedroom	0.54
A.44.08.2B Bedroom	0.71
A.44.09.2B Bedroom	0.41
A.44.09.2B Bedroom	0.63
A.44.10.2B Bedroom	0.54
A.44.10.2B Bedroom	0.46
A.45.01.3B Bedroom	2.70
A.45.01.3B Bedroom	0.84
A.45.01.3B Bedroom	0.90
A.45.02.3B Bedroom	0.54
A.45.02.3B Bedroom	0.68

Location	Operative Temperature > 26 (Max 1%)
A.45.02.3B Bedroom	0.65
A.45.03.3B Bedroom	0.60
A.45.03.3B Bedroom	0.46
A.45.03.3B Bedroom	0.71
A.45.04.3B Bedroom	0.76
A.45.04.3B Bedroom	0.84
A.45.04.3B Bedroom	2.42
A.45.05.3B Bedroom	0.65
A.45.05.3B Bedroom	0.41
A.45.05.3B Bedroom	0.27
A.45.06.3B Bedroom	0.63
A.45.06.3B Bedroom	0.44
A.45.06.3B Bedroom	0.49

15.0 Appendix 9: DSY3: TM52 Criterion 1 Living Block A

Location	Operative Temperature > 26 (Max 1%)
A.02.01.1BKLD	0.45
A.02.02.1BKLD	0.55
A.02.03.2BKLD	5.58
A.02.04.2BKLD	2.97
A.02.05.2BKLD	5.53
A.02.06.1BKLD	0.35
A.02.07.1BKLD	0.30
A.02.08.2BKLD	3.37
A.02.09.2BKLD	2.11
A.02.10.2BKLD	0.45
A.03.01.1BKLD	0.80
A.03.02.1BKLD	0.80
A.03.03.2BKLD	6.03
A.03.04.2BKLD	3.67
A.03.05.2BKLD	5.83
A.03.06.1BKLD	0.75
A.03.07.1BKLD	0.75
A.03.08.2BKLD	4.47
A.03.09.2BKLD	2.77
A.03.10.2BKLD	0.65
A.04.01.1BKLD	0.85
A.04.02.1BKLD	0.85
A.04.03.2BKLD	5.88
A.04.04.2BKLD	3.62
A.04.05.2BKLD	5.83
A.04.06.1BKLD	0.80
A.04.07.1BKLD	0.85
A.04.08.2BKLD	4.42
A.04.09.2BKLD	2.82
A.04.10.2BKLD	0.75
A.05.01.1BKLD	0.85
A.05.02.1BKLD	0.85
A.05.03.2BKLD	5.88
A.05.04.2BKLD	3.62
A.05.05.2BKLD	5.83
A.05.06.1BKLD	0.80
A.05.07.1BKLD	0.85
A.05.08.2BKLD	4.47
A.05.09.2BKLD	2.82
A.05.10.2BKLD	0.75
A.06.01.1BKLD	0.85
A.06.02.1BKLD	0.85
A.06.03.2BKLD	5.88
A.06.04.2BKLD	3.62
A.06.05.2BKLD	5.83
A.06.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.06.07.1BKLD	0.85
A.06.08.2BKLD	4.47
A.06.09.2BKLD	2.82
A.06.10.2BKLD	0.80
A.07.01.1BKLD	0.85
A.07.02.1BKLD	0.90
A.07.03.2BKLD	5.93
A.07.04.2BKLD	3.62
A.07.05.2BKLD	5.83
A.07.06.1BKLD	0.80
A.07.07.1BKLD	0.85
A.07.08.2BKLD	4.47
A.07.09.2BKLD	2.82
A.07.10.2BKLD	0.80
A.08.01.1BKLD	0.85
A.08.02.1BKLD	0.90
A.08.03.2BKLD	5.93
A.08.04.2BKLD	3.62
A.08.05.2BKLD	5.83
A.08.06.1BKLD	0.80
A.08.07.1BKLD	0.85
A.08.08.2BKLD	4.47
A.08.09.2BKLD	2.82
A.08.10.2BKLD	0.80
A.09.01.1BKLD	0.85

Location	Operative Temperature > 26 (Max 1%)
A.09.02.1BKLD	0.90
A.09.03.2BKLD	5.93
A.09.04.2BKLD	3.62
A.09.05.2BKLD	5.83
A.09.06.1BKLD	0.80
A.09.07.1BKLD	0.85
A.09.08.2BKLD	4.52
A.09.09.2BKLD	2.82
A.09.10.2BKLD	0.80
A.10.01.1BKLD	0.85
A.10.02.1BKLD	0.90
A.10.03.2BKLD	5.93
A.10.04.2BKLD	3.62
A.10.05.2BKLD	5.88
A.10.06.1BKLD	0.80
A.10.07.1BKLD	0.85
A.10.08.2BKLD	4.52
A.10.09.2BKLD	2.82
A.10.10.2BKLD	0.80
A.11.01.1BKLD	0.85
A.11.02.1BKLD	0.90
A.11.03.2BKLD	6.03
A.11.04.2BKLD	3.62
A.11.05.2BKLD	5.88
A.11.06.1BKLD	0.80

Location	Operative Temperature > 26 (Max 1%)
A.11.07.1BKLD	0.90
A.11.08.2BKLD	4.58
A.11.09.2BKLD	2.87
A.11.10.2BKLD	0.96
A.12.01.1BKLD	0.85
A.12.02.1BKLD	0.90
A.12.03.2BKLD	6.18
A.12.04.2BKLD	3.67
A.12.05.2BKLD	5.93
A.12.06.1BKLD	0.80
A.12.07.1BKLD	0.85
A.12.08.2BKLD	4.63
A.12.09.2BKLD	2.87
A.12.10.2BKLD	0.80
A.13.01.1BKLD	1.01
A.13.02.1BKLD	0.70
A.13.03.2BKLD	6.69
A.13.05.2BKLD	6.18
A.13.06.1BKLD	0.85
A.13.07.1BKLD	0.96
A.13.08.2BKLD	5.68
A.13.09.2BKLD	3.57
A.13.10.2BKLD	0.96
A.13.13.2BKLD	4.12
A.14.01.1BKLD	0.90

Location	Operative Temperature > 26 (Max 1%)
A.14.02.1BKLD	0.85
A.14.03.2BKLD	5.88
A.14.04.2BKLD	3.57
A.14.05.2BKLD	5.88
A.14.06.1BKLD	0.75
A.14.07.1BKLD	0.90
A.14.08.2BKLD	4.42
A.14.09.2BKLD	2.97
A.14.10.2BKLD	0.80
A.15.01.1BKLD	0.85
A.15.02.1BKLD	0.85
A.15.03.2BKLD	5.78
A.15.04.2BKLD	3.57
A.15.05.2BKLD	5.88
A.15.06.1BKLD	0.80
A.15.07.1BKLD	0.85
A.15.08.2BKLD	4.37
A.15.09.2BKLD	2.87
A.15.10.2BKLD	0.75
A.16.01.1BKLD	0.85
A.16.02.1BKLD	0.85
A.16.03.2BKLD	5.78
A.16.04.2BKLD	3.57
A.16.05.2BKLD	5.88
A.16.06.1BKLD	0.75

Location	Operative Temperature > 26 (Max 1%)
A.16.07.1BKLD	0.85
A.16.08.2BKLD	4.37
A.16.09.2BKLD	2.87
A.16.10.2BKLD	0.75
A.17.01.1BKLD	0.85
A.17.02.1BKLD	0.85
A.17.03.2BKLD	5.78
A.17.04.2BKLD	3.57
A.17.05.2BKLD	5.88
A.17.06.1BKLD	0.75
A.17.07.1BKLD	0.85
A.17.08.2BKLD	4.37
A.17.09.2BKLD	2.87
A.17.10.2BKLD	0.75
A.18.01.1BKLD	0.85
A.18.02.1BKLD	0.85
A.18.03.2BKLD	5.78
A.18.04.2BKLD	3.57
A.18.05.2BKLD	5.88
A.18.06.1BKLD	0.75
A.18.07.1BKLD	0.85
A.18.08.2BKLD	4.37
A.18.09.2BKLD	2.87
A.18.10.2BKLD	0.75
A.19.01.1BKLD	0.85

Location	Operative Temperature > 26 (Max 1%)
A.19.02.1BKLD	0.85
A.19.03.2BKLD	5.78
A.19.04.2BKLD	3.57
A.19.05.2BKLD	5.88
A.19.06.1BKLD	0.75
A.19.07.1BKLD	0.85
A.19.08.2BKLD	4.37
A.19.09.2BKLD	2.87
A.19.10.2BKLD	0.75
A.20.01.1BKLD	0.85
A.20.02.1BKLD	0.85
A.20.03.2BKLD	5.78
A.20.04.2BKLD	3.57
A.20.05.2BKLD	5.88
A.20.06.1BKLD	0.75
A.20.07.1BKLD	0.85
A.20.08.2BKLD	4.37
A.20.09.2BKLD	2.87
A.20.10.2BKLD	0.75
A.21.01.1BKLD	0.85
A.21.02.1BKLD	0.85
A.21.03.2BKLD	5.78
A.21.04.2BKLD	3.57
A.21.05.2BKLD	5.88
A.21.06.1BKLD	0.75

Location	Operative Temperature > 26 (Max 1%)
A.21.07.1BKLD	0.85
A.21.08.2BKLD	4.37
A.21.09.2BKLD	2.87
A.21.10.2BKLD	0.75
A.22.01.1BKLD	0.85
A.22.02.1BKLD	0.85
A.22.03.2BKLD	5.68
A.22.04.2BKLD	3.42
A.22.05.2BKLD	5.88
A.22.06.1BKLD	0.70
A.22.07.1BKLD	0.85
A.22.08.2BKLD	4.12
A.22.09.2BKLD	2.77
A.22.10.2BKLD	0.75
A.23.01.1BKLD	0.85
A.23.02.1BKLD	0.85
A.23.03.2BKLD	5.68
A.23.04.2BKLD	3.52
A.23.05.2BKLD	5.88
A.23.06.1BKLD	0.70
A.23.07.1BKLD	0.85
A.23.08.2BKLD	4.12
A.23.09.2BKLD	2.71
A.23.10.2BKLD	0.75
A.24.01.1BKLD	0.85

Location	Operative Temperature > 26 (Max 1%)
A.24.02.1BKLD	0.85
A.24.03.2BKLD	5.68
A.24.04.2BKLD	3.42
A.24.05.2BKLD	5.88
A.24.06.1BKLD	0.70
A.24.07.1BKLD	0.85
A.24.08.2BKLD	4.12
A.24.09.2BKLD	2.71
A.24.10.2BKLD	0.75
A.25.01.1BKLD	0.85
A.25.02.1BKLD	0.85
A.25.03.2BKLD	5.68
A.25.04.2BKLD	3.42
A.25.05.2BKLD	5.88
A.25.06.1BKLD	0.70
A.25.07.1BKLD	0.85
A.25.08.2BKLD	4.12
A.25.09.2BKLD	2.71
A.25.10.2BKLD	0.75
A.26.01.1BKLD	0.85
A.26.02.1BKLD	0.85
A.26.03.2BKLD	5.68
A.26.04.2BKLD	3.42
A.26.05.2BKLD	5.88
A.26.06.1BKLD	0.70

Location	Operative Temperature > 26 (Max 1%)
A.26.07.1BKLD	0.85
A.26.08.2BKLD	4.12
A.26.09.2BKLD	2.71
A.26.10.2BKLD	0.75
A.27.01.1BKLD	0.85
A.27.02.1BKLD	0.85
A.27.03.2BKLD	5.68
A.27.04.2BKLD	3.42
A.27.05.2BKLD	5.88
A.27.06.1BKLD	0.70
A.27.07.1BKLD	0.85
A.27.08.2BKLD	4.12
A.27.09.2BKLD	2.71
A.27.10.2BKLD	0.75
A.28.01.1BKLD	0.85
A.28.02.1BKLD	0.85
A.28.03.2BKLD	5.68
A.28.04.2BKLD	3.42
A.28.05.2BKLD	5.88
A.28.06.1BKLD	0.70
A.28.07.1BKLD	0.85
A.28.08.2BKLD	4.12
A.28.09.2BKLD	2.71
A.28.10.2BKLD	0.75
A.29.01.1BKLD	0.85

Location	Operative Temperature > 26 (Max 1%)
A.29.02.1BKLD	0.85
A.29.03.2BKLD	5.68
A.29.04.2BKLD	3.42
A.29.05.2BKLD	5.88
A.29.06.1BKLD	0.70
A.29.07.1BKLD	0.85
A.29.08.2BKLD	4.12
A.29.09.2BKLD	2.71
A.29.10.2BKLD	0.75
A.30.01.1BKLD	0.85
A.30.02.1BKLD	0.85
A.30.03.2BKLD	5.68
A.30.04.2BKLD	3.42
A.30.05.2BKLD	5.88
A.30.06.1BKLD	0.70
A.30.07.1BKLD	0.85
A.30.08.2BKLD	4.12
A.30.09.2BKLD	2.71
A.30.10.2BKLD	0.75
A.31.01.1BKLD	0.85
A.31.02.1BKLD	0.85
A.31.03.2BKLD	5.53
A.31.04.2BKLD	3.42
A.31.05.2BKLD	5.88
A.31.06.1BKLD	0.70

Location	Operative Temperature > 26 (Max 1%)
A.31.07.1BKLD	0.85
A.31.08.2BKLD	3.92
A.31.09.2BKLD	2.66
A.31.10.2BKLD	0.75
A.32.01.1BKLD	0.85
A.32.02.1BKLD	0.85
A.32.03.2BKLD	5.53
A.32.04.2BKLD	3.42
A.32.05.2BKLD	5.88
A.32.06.1BKLD	0.70
A.32.07.1BKLD	0.85
A.32.08.2BKLD	3.92
A.32.09.2BKLD	2.66
A.32.10.2BKLD	0.75
A.33.01.1BKLD	0.85
A.33.02.1BKLD	0.85
A.33.03.2BKLD	5.53
A.33.04.2BKLD	3.42
A.33.05.2BKLD	5.88
A.33.06.1BKLD	0.70
A.33.07.1BKLD	0.85
A.33.08.2BKLD	3.92
A.33.09.2BKLD	2.66
A.33.10.2BKLD	0.75
A.34.01.1BKLD	0.85

Location	Operative Temperature > 26 (Max 1%)
A.34.02.1BKLD	0.85
A.34.03.2BKLD	5.53
A.34.04.2BKLD	3.42
A.34.05.2BKLD	5.88
A.34.06.1BKLD	0.70
A.34.07.1BKLD	0.85
A.34.08.2BKLD	3.92
A.34.09.2BKLD	2.66
A.34.10.2BKLD	0.75
A.35.01.1BKLD	0.85
A.35.02.1BKLD	0.85
A.35.03.2BKLD	5.53
A.35.04.2BKLD	3.42
A.35.05.2BKLD	5.88
A.35.06.1BKLD	0.70
A.35.07.1BKLD	0.85
A.35.08.2BKLD	3.92
A.35.09.2BKLD	2.66
A.35.10.2BKLD	0.75
A.36.01.1BKLD	0.85
A.36.02.1BKLD	0.85
A.36.03.2BKLD	5.53
A.36.04.2BKLD	3.42
A.36.05.2BKLD	5.88
A.36.06.1BKLD	0.70

Location	Operative Temperature > 26 (Max 1%)
A.36.07.1BKLD	0.85
A.36.08.2BKLD	3.92
A.36.09.2BKLD	2.66
A.36.10.2BKLD	0.75
A.37.01.1BKLD	0.85
A.37.02.1BKLD	0.85
A.37.03.2BKLD	5.53
A.37.04.2BKLD	3.42
A.37.05.2BKLD	5.88
A.37.06.1BKLD	0.70
A.37.07.1BKLD	0.85
A.37.08.2BKLD	3.92
A.37.09.2BKLD	2.66
A.37.10.2BKLD	0.75
A.38.01.1BKLD	0.85
A.38.02.1BKLD	0.85
A.38.03.2BKLD	5.53
A.38.04.2BKLD	3.42
A.38.05.2BKLD	5.88
A.38.06.1BKLD	0.70
A.38.07.1BKLD	0.85
A.38.08.2BKLD	3.92
A.38.09.2BKLD	2.66
A.38.10.2BKLD	0.75
A.39.01.1BKLD	0.85

Location	Operative Temperature > 26 (Max 1%)
A.39.02.1BKLD	0.85
A.39.03.2BKLD	5.58
A.39.04.2BKLD	3.42
A.39.05.2BKLD	5.88
A.39.06.1BKLD	0.70
A.39.07.1BKLD	0.85
A.39.08.2BKLD	3.92
A.39.09.2BKLD	2.66
A.39.10.2BKLD	0.75
A.40.01.1BKLD	0.85
A.40.02.1BKLD	0.90
A.40.03.2BKLD	5.78
A.40.04.2BKLD	3.47
A.40.05.2BKLD	5.88
A.40.06.1BKLD	0.70
A.40.07.1BKLD	0.80
A.40.08.2BKLD	4.42
A.40.09.2BKLD	2.87
A.40.10.2BKLD	0.75
A.41.01.1BKLD	0.85
A.41.02.1BKLD	0.90
A.41.03.2BKLD	5.83
A.41.04.2BKLD	3.47
A.41.05.2BKLD	5.88
A.41.06.1BKLD	0.70

Location	Operative Temperature > 26 (Max 1%)
A.41.07.1BKLD	0.80
A.41.08.2BKLD	4.42
A.41.09.2BKLD	2.92
A.41.10.2BKLD	0.75
A.42.01.1BKLD	0.85
A.42.02.1BKLD	0.90
A.42.03.2BKLD	5.83
A.42.04.2BKLD	3.47
A.42.05.2BKLD	5.88
A.42.06.1BKLD	0.70
A.42.07.1BKLD	0.85
A.42.08.2BKLD	4.42
A.42.09.2BKLD	2.92
A.42.10.2BKLD	0.75
A.43.01.1BKLD	0.85
A.43.02.1BKLD	0.90
A.43.03.2BKLD	5.83
A.43.04.2BKLD	3.47
A.43.05.2BKLD	5.88
A.43.06.1BKLD	0.70
A.43.07.1BKLD	0.90
A.43.08.2BKLD	4.42
A.43.09.2BKLD	2.92
A.43.10.2BKLD	0.75
A.44.01.1BKLD	1.01

Location	Operative Temperature > 26 (Max 1%)
A.44.02.1BKLD	0.90
A.44.03.2BKLD	5.83
A.44.04.2BKLD	3.47
A.44.05.2BKLD	5.88
A.44.06.1BKLD	0.80
A.44.07.1BKLD	0.90
A.44.08.2BKLD	4.42
A.44.09.2BKLD	2.87
A.44.10.2BKLD	0.70
A.45.01.3BKLD	1.31
A.45.02.3BKLD	5.43
A.45.03.3BKLD	5.08
A.45.04.3BKLD	0.80
A.45.05.3BKLD	1.96
A.45.06.3BKLD	2.92

16.0 Appendix 10: DSY1: TM52 Criterion 1 Bedroom Block B

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.00.001 2B Apt Bedroom 1	0.00
B.00.001 2B Apt Bedroom 2	0.00
B.00.007 3B Apt Bedroom 1	0.00
B.00.007 3B Apt Bedroom 2	1.03
B.00.007 3B Apt Bedroom 3	1.14
B.00.008 2B Apt Bedroom 1	0.71
B.00.009 2B Apt Bedroom 1	0.03
B.00.009 2B Apt Bedroom 2	0.68
B.00.010 2B Apt Bedroom 1	0.00
B.00.011 1B Apt Bedroom 1	0.00
B.00.013 2B Apt 13 Bedroom 2	1.01
B.01.001 2B Apt Bedroom 2	0.00
B.01.001 2B Apt Bedroom 2	0.00
B.01.002 2B Apt Bedroom 1	0.00
B.01.002 2B Apt Bedroom 2	0.00
B.01.003 2B Apt Bedroom 1	0.00
B.01.004 1B Apt Bedroom	0.00
B.01.005 2B Apt Bedroom 1	0.00
B.01.005 2B Apt Bedroom 2	0.00
B.01.006 2B Apt Bedroom 1	0.00
B.01.006 2B Apt Bedroom 2	0.11
B.01.007 2B Apt Bedroom 1	0.00
B.01.007 2B Apt Bedroom 2	0.08
B.01.008 2B Apt Bedroom 1	0.00
B.01.008 2B Apt Bedroom 2	0.08
B.01.009 2B Apt Bedroom 1	0.00
B.01.009 2B Apt Bedroom 2	0.00
B.01.010 1B Apt Bedroom 1	0.00
B.01.011 1B Apt Bedroom	0.00
B.01.012 3B Apt Bedroom 1	0.79
B.01.012 3B Apt Bedroom 2	1.61
B.01.012 3B Apt Bedroom 3	1.61
B.01.013 2B Apt Bedroom 1	0.46
B.01.013 2B Apt Bedroom 2	0.57
B.01.014 2B Apt Bedroom 1	0.44
B.01.014 2B Apt Bedroom 2	0.57
B.01.015 2B Apt Bedroom 1	0.05
B.01.015 2B Apt Bedroom 2	0.79
B.01.016 2B Apt Bedroom 1	0.00
B.01.016 2B Apt Bedroom 2	0.00
B.01.017 3B Apt Bedroom 1	0.00
B.01.017 3B Apt Bedroom 2	0.00
B.01.017 3B Apt Bedroom 3	0.00
B.01.018 2B Apt Bedroom 1	0.00
B.01.018 2B Apt Bedroom 2	0.00
B.01.019 2B Apt Bedroom 1	0.00
B.01.019 2B Apt Bedroom 2	0.00
B.01.020 2B Apt Bedroom 1	0.00
B.01.020 2B Apt Bedroom 2	0.03
B.01.021 3B Apt Bedroom 1	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.01.021 3B Apt Bedroom 2	0.22
B.01.021 3B Apt Bedroom 3	0.16
B.01.022 2B Apt Bedroom 1	0.00
B.01.022 2B Apt Bedroom 2	0.14
B.02.001 2B Apt Bedroom 2	0.00
B.02.001 2B Apt Bedroom 2	0.00
B.02.002 2B Apt Bedroom 1	0.00
B.02.002 2B Apt Bedroom 2	0.00
B.02.003 2B Apt Bedroom 1	0.00
B.02.004 1B Apt Bedroom	0.00
B.02.005 2B Apt Bedroom 1	0.00
B.02.005 2B Apt Bedroom 2	0.05
B.02.006 2B Apt Bedroom 1	0.00
B.02.006 2B Apt Bedroom 2	0.16
B.02.007 2B Apt Bedroom 1	0.00
B.02.007 2B Apt Bedroom 2	0.11
B.02.008 2B Apt Bedroom 1	0.00
B.02.008 2B Apt Bedroom 2	0.11
B.02.009 2B Apt Bedroom 1	0.00
B.02.009 2B Apt Bedroom 2	0.00
B.02.010 1B Apt Bedroom 1	0.00
B.02.011 1B Apt Bedroom	0.00
B.02.012 3B Apt Bedroom 1	0.98
B.02.012 3B Apt Bedroom 2	1.80
B.02.012 3B Apt Bedroom 3	1.88
B.02.013 2B Apt Bedroom 1	0.46
B.02.013 2B Apt Bedroom 2	0.60

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.02.014 2B Apt Bedroom 1	0.46
B.02.014 2B Apt Bedroom 2	0.60
B.02.015 2B Apt Bedroom 1	0.08
B.02.015 2B Apt Bedroom 2	0.79
B.02.016 2B Apt Bedroom 1	0.00
B.02.016 2B Apt Bedroom 2	0.00
B.02.017 3B Apt Bedroom 1	0.00
B.02.017 3B Apt Bedroom 2	0.00
B.02.017 3B Apt Bedroom 3	0.00
B.02.018 2B Apt Bedroom 1	0.00
B.02.018 2B Apt Bedroom 2	0.00
B.02.019 2B Apt Bedroom 1	0.00
B.02.019 2B Apt Bedroom 2	0.00
B.02.020 2B Apt Bedroom 1	0.00
B.02.020 2B Apt Bedroom 2	0.03
B.02.021 3B Apt Bedroom 1	0.00
B.02.021 3B Apt Bedroom 2	0.30
B.02.021 3B Apt Bedroom 3	0.30
B.02.022 2B Apt Bedroom 1	0.00
B.02.022 2B Apt Bedroom 2	0.22
B.03.001 2B Apt Bedroom 2	0.00
B.03.001 2B Apt Bedroom 2	0.00
B.03.002 1B Apt Bedroom 1	0.00
B.03.003 1B Apt Bedroom 1	0.00
B.03.004 1B Apt Bedroom	0.00
B.03.005 2B Apt Bedroom 1	0.00
B.03.005 2B Apt Bedroom 2	0.08

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.03.006 2B Apt Bedroom 1	0.00
B.03.006 2B Apt Bedroom 2	0.08
B.03.007 2B Apt Bedroom 1	0.00
B.03.007 2B Apt Bedroom 2	0.08
B.03.008 2B Apt Bedroom 1	0.00
B.03.008 2B Apt Bedroom 2	0.00
B.03.009 2B Apt Bedroom 1	0.00
B.03.009 2B Apt Bedroom 2	0.00
B.03.010 3B Apt Bedroom 1	0.52
B.03.011 1B Apt Bedroom 1	1.47
B.03.012 2B Apt Bedroom 1	1.66
B.03.012 2B Apt Bedroom 2	1.66
B.03.013 2B Apt Bedroom 1	1.23
B.03.013 2B Apt Bedroom 2	1.74
B.03.014 2B Apt Bedroom 1	1.25
B.03.014 2B Apt Bedroom 2	1.72
B.03.015 2B Apt Bedroom 1	0.08
B.03.015 2B Apt Bedroom 2	0.82
B.03.016 2B Apt Bedroom 1	0.00
B.03.016 2B Apt Bedroom 2	0.00
B.03.017 3B Apt Bedroom 1	0.00
B.03.017 3B Apt Bedroom 2	0.00
B.03.017 3B Apt Bedroom 3	0.00
B.03.018 2B Apt Bedroom 1	0.00
B.03.018 2B Apt Bedroom 2	0.00
B.03.019 2B Apt Bedroom 1	0.00
B.03.019 2B Apt Bedroom 2	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.03.020 2B Apt Bedroom 1	0.00
B.03.020 2B Apt Bedroom 2	0.08
B.03.021 3B Apt Bedroom 1	0.00
B.03.021 3B Apt Bedroom 2	0.33
B.03.021 3B Apt Bedroom 3	0.44
B.03.022 2B Apt Bedroom 1	0.00
B.03.022 2B Apt Bedroom 2	0.22
B.04.001 2B Apt Bedroom 2	0.00
B.04.001 2B Apt Bedroom 2	0.00
B.04.002 1B Apt Bedroom 1	0.00
B.04.003 1B Apt Bedroom 1	0.00
B.04.004 1B Apt Bedroom	0.00
B.04.005 2B Apt Bedroom 1	0.00
B.04.005 2B Apt Bedroom 2	0.08
B.04.006 2B Apt Bedroom 1	0.00
B.04.006 2B Apt Bedroom 2	0.08
B.04.007 2B Apt Bedroom 1	0.00
B.04.007 2B Apt Bedroom 2	0.11
B.04.008 2B Apt Bedroom 1	0.00
B.04.008 2B Apt Bedroom 2	0.00
B.04.009 2B Apt Bedroom 1	0.00
B.04.009 2B Apt Bedroom 2	0.00
B.04.010 3B Apt Bedroom 1	0.54
B.04.011 1B Apt Bedroom 1	1.50
B.04.012 2B Apt Bedroom 1	1.66
B.04.012 2B Apt Bedroom 2	1.63
B.04.013 2B Apt Bedroom 1	1.23

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.04.013 2B Apt Bedroom 2	1.85
B.04.014 2B Apt Bedroom 1	1.31
B.04.014 2B Apt Bedroom 2	1.77
B.04.015 2B Apt Bedroom 1	0.08
B.04.015 2B Apt Bedroom 2	0.82
B.04.016 2B Apt Bedroom 1	0.00
B.04.016 2B Apt Bedroom 2	0.00
B.04.017 3B Apt Bedroom 1	0.00
B.04.017 3B Apt Bedroom 2	0.00
B.04.017 3B Apt Bedroom 3	0.00
B.04.018 2B Apt Bedroom 1	0.00
B.04.018 2B Apt Bedroom 2	0.00
B.04.019 2B Apt Bedroom 1	0.00
B.04.019 2B Apt Bedroom 2	0.00
B.04.020 2B Apt Bedroom 1	0.00
B.04.020 2B Apt Bedroom 2	0.33
B.04.021 3B Apt Bedroom 1	0.00
B.04.021 3B Apt Bedroom 2	0.33
B.04.021 3B Apt Bedroom 3	0.44
B.04.022 2B Apt Bedroom 1	0.00
B.04.022 2B Apt Bedroom 2	0.22
B.05.001 2B Apt Bedroom 2	0.00
B.05.001 2B Apt Bedroom 2	0.00
B.05.002 1B Apt Bedroom 1	0.00
B.05.003 1B Apt Bedroom 1	0.00
B.05.004 1B Apt Bedroom	0.00
B.05.005 2B Apt Bedroom 1	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.05.005 2B Apt Bedroom 2	0.08
B.05.006 2B Apt Bedroom 1	0.00
B.05.006 2B Apt Bedroom 2	0.08
B.05.007 2B Apt Bedroom 1	0.00
B.05.007 2B Apt Bedroom 2	0.11
B.05.008 2B Apt Bedroom 1	0.00
B.05.008 2B Apt Bedroom 2	0.00
B.05.009 2B Apt Bedroom 1	0.00
B.05.009 2B Apt Bedroom 2	0.00
B.05.010 3B Apt Bedroom 1	0.54
B.05.011 1B Apt Bedroom 1	1.50
B.05.012 2B Apt Bedroom 1	2.04
B.05.012 2B Apt Bedroom 2	2.07
B.05.013 2B Apt Bedroom 1	1.31
B.05.013 2B Apt Bedroom 2	1.85
B.05.014 2B Apt Bedroom 1	1.31
B.05.014 2B Apt Bedroom 2	1.77
B.05.015 2B Apt Bedroom 1	0.08
B.05.015 2B Apt Bedroom 2	0.79
B.05.016 2B Apt Bedroom 1	0.00
B.05.016 2B Apt Bedroom 2	0.00
B.05.017 3B Apt Bedroom 1	0.00
B.05.017 3B Apt Bedroom 2	0.00
B.05.017 3B Apt Bedroom 3	0.00
B.05.018 2B Apt Bedroom 1	0.00
B.05.018 2B Apt Bedroom 2	0.00
B.05.019 2B Apt Bedroom 1	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.05.019 2B Apt Bedroom 2	0.00
B.05.020 2B Apt Bedroom 1	0.11
B.05.020 2B Apt Bedroom 2	0.52
B.05.021 3B Apt Bedroom 1	0.00
B.05.021 3B Apt Bedroom 2	0.33
B.05.021 3B Apt Bedroom 3	0.44
B.05.022 2B Apt Bedroom 1	0.00
B.05.022 2B Apt Bedroom 2	0.22
B.06.001 2B Apt Bedroom 2	0.00
B.06.001 2B Apt Bedroom 2	0.00
B.06.002 1B Apt Bedroom 1	0.00
B.06.003 1B Apt Bedroom 1	0.00
B.06.004 1B Apt Bedroom	0.00
B.06.005 2B Apt Bedroom 1	0.00
B.06.005 2B Apt Bedroom 2	0.00
B.06.006 2B Apt Bedroom 1	0.00
B.06.006 2B Apt Bedroom 2	0.00
B.06.007 2B Apt Bedroom 1	0.00
B.06.007 2B Apt Bedroom 2	0.00
B.06.008 2B Apt Bedroom 1	0.00
B.06.008 2B Apt Bedroom 2	0.00
B.06.009 2B Apt Bedroom 1	0.00
B.06.009 2B Apt Bedroom 2	0.00
B.06.010 3B Apt Bedroom 1	0.52
B.06.011 1B Apt Bedroom 1	1.42
B.06.012 2B Apt Bedroom 1	1.96
B.06.012 2B Apt Bedroom 2	2.02

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.06.013 2B Apt Bedroom 1	1.14
B.06.013 2B Apt Bedroom 2	1.69
B.06.014 2B Apt Bedroom 1	1.17
B.06.014 2B Apt Bedroom 2	1.61
B.06.015 2B Apt Bedroom 1	0.05
B.06.015 2B Apt Bedroom 2	0.74
B.06.016 2B Apt Bedroom 1	0.00
B.06.016 2B Apt Bedroom 2	0.00
B.06.017 3B Apt Bedroom 1	0.00
B.06.017 3B Apt Bedroom 2	0.00
B.06.017 3B Apt Bedroom 3	0.00
B.06.018 2B Apt Bedroom 1	0.00
B.06.018 2B Apt Bedroom 2	0.00
B.06.019 2B Apt Bedroom 1	0.00
B.06.019 2B Apt Bedroom 2	0.00
B.06.020 2B Apt Bedroom 1	0.33
B.06.020 2B Apt Bedroom 2	0.52
B.06.021 3B Apt Bedroom 1	0.00
B.06.021 3B Apt Bedroom 2	0.30
B.06.021 3B Apt Bedroom 3	0.44
B.06.022 2B Apt Bedroom 1	0.00
B.06.022 2B Apt Bedroom 2	0.16
B.07.001 4B Apt Bedroom 1	0.00
B.07.002 4B Bedroom 1	0.00
B.07.004 4B Bedroom 1	0.00
B.07.005 4B Bedroom 1	0.00
B.07.007 4B Bedroom 1	0.35

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.07.008 4B Bedroom 1	0.27
B.07.009 4B Bedroom 1	0.30
B.07.010 4B Bedroom 1	0.46
B.07.011 4B Bedroom 1	0.00
B.07.013 4B Bedroom 1	0.00
B.07.015 4B Bedroom	0.00
B.07.016 4B Bedroom	0.05
B.07.017 4B Bedroom 1	0.33
B.08.001 4B Apt Bedroom 1	0.00
B.08.001 4B Apt Bedroom 2	0.00
B.08.001 4B Apt Bedroom 3	0.00
B.08.003 4B Bedroom 2	0.00
B.08.003 4B Bedroom 3	0.00
B.08.003 4B Bedroom 4	0.30
B.08.004 4B Apt Bedroom 2	0.25
B.08.004 4B Apt Bedroom 3	0.00
B.08.004 4B Apt Bedroom 4	0.00
B.08.005 4B Apt Bedroom 2	0.05
B.08.005 4B Apt Bedroom 3	0.00
B.08.005 4B Apt Bedroom 4	0.00
B.08.006 3B Apt Bedroom 3	0.00
B.08.006 3B Bedroom 1	0.00
B.08.006 3B Bedroom 2	0.00
B.08.007 4B Bedroom 2	0.11
B.08.007 4B Bedroom 3	1.01
B.08.007 4B Bedroom 4	1.23
B.08.008 4B Apt Bedroom 2	0.71

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.08.008 4B Apt Bedroom 3	1.06
B.08.008 4B Apt Bedroom 4	0.60
B.08.009 4B Apt Bedroom 2	0.60
B.08.009 4B Apt Bedroom 3	0.82
B.08.009 4B Apt Bedroom 4	1.31
B.08.010 4B Apt Bedroom 2	2.12
B.08.010 4B Apt Bedroom 3	1.47
B.08.010 4B Apt Bedroom 4	0.38
B.08.011 4B Apt Bedroom 2	0.03
B.08.011 4B Apt Bedroom 3	0.03
B.08.011 4B Apt Bedroom 4	0.00
B.08.012 3B Apt Bedroom 1	0.00
B.08.012 3B Apt Bedroom 2	0.00
B.08.012 3B Apt Bedroom 3	0.00
B.08.013 4B Apt Bedroom 2	0.00
B.08.013 4B Apt Bedroom 3	0.00
B.08.013 4B Apt Bedroom 4	0.08
B.08.014 2B Apt Bedroom 1	0.05
B.08.014 2B Apt Bedroom 2	0.54
B.08.015 4B Apt Bedroom 2	0.08
B.08.015 4B Apt Bedroom 3	0.57
B.08.015 4B Apt Bedroom 4	0.76
B.08.016 4B Apt Bedroom 2	0.65
B.08.016 4B Apt Bedroom 3	0.71
B.08.016 4B Apt Bedroom 4	0.74
B.08.017 4B Apt Bedroom 2	0.74
B.08.017 4B Apt Bedroom 3	0.33

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.08.017 4B Apt Bedroom 4	0.05
B.08.0024B Bedroom	0.00
B.08.0024B Bedroom	0.00
B.08.0024B Bedroom	0.00

17.0 Appendix 11: DSY 1: Bedroom Night-time Temperature Test Block B

Location	Operative Temperature >26 (Max 1%)
B.00.001 2B Apt Bedroom 1	0.57
B.00.001 2B Apt Bedroom 2	0.11
B.00.007 3B Apt Bedroom 1	0.30
B.00.007 3B Apt Bedroom 2	0.63
B.00.007 3B Apt Bedroom 3	0.68
B.00.008 2B Apt Bedroom 1	0.65
B.00.009 2B Apt Bedroom 1	0.38
B.00.009 2B Apt Bedroom 2	0.63
B.00.010 2B Apt Bedroom 1	0.16
B.00.011 1B Apt Bedroom 1	0.19
B.00.013 2B Apt 13 Bedroom 2	0.68
B.01.001 2B Apt Bedroom 2	0.14
B.01.001 2B Apt Bedroom 2	0.16
B.01.002 2B Apt Bedroom 1	0.14
B.01.002 2B Apt Bedroom 2	0.16
B.01.003 2B Apt Bedroom 1	0.11
B.01.004 1B Apt Bedroom	0.11
B.01.005 2B Apt Bedroom 1	0.60
B.01.005 2B Apt Bedroom 2	0.54
B.01.006 2B Apt Bedroom 1	0.63
B.01.006 2B Apt Bedroom 2	0.57
B.01.007 2B Apt Bedroom 1	0.63
B.01.007 2B Apt Bedroom 2	0.57
B.01.008 2B Apt Bedroom 1	0.63
B.01.008 2B Apt Bedroom 2	0.63
B.01.009 2B Apt Bedroom 1	0.38
B.01.009 2B Apt Bedroom 2	0.46
B.01.010 1B Apt Bedroom 1	0.19
B.01.011 1B Apt Bedroom	0.27
B.01.012 3B Apt Bedroom 1	0.35
B.01.012 3B Apt Bedroom 2	0.60
B.01.012 3B Apt Bedroom 3	0.65
B.01.013 2B Apt Bedroom 1	0.54
B.01.013 2B Apt Bedroom 2	0.49
B.01.014 2B Apt Bedroom 1	0.49
B.01.014 2B Apt Bedroom 2	0.46
B.01.015 2B Apt Bedroom 1	0.30
B.01.015 2B Apt Bedroom 2	0.52
B.01.016 2B Apt Bedroom 1	0.22
B.01.016 2B Apt Bedroom 2	0.14
B.01.017 3B Apt Bedroom 1	0.19
B.01.017 3B Apt Bedroom 2	0.27
B.01.017 3B Apt Bedroom 3	0.27
B.01.018 2B Apt Bedroom 1	0.16
B.01.018 2B Apt Bedroom 2	0.25
B.01.019 2B Apt Bedroom 1	0.35
B.01.019 2B Apt Bedroom 2	0.14
B.01.020 2B Apt Bedroom 1	0.30
B.01.020 2B Apt Bedroom 2	0.22

Location	Operative Temperature >26 (Max 1%)
B.01.021 3B Apt Bedroom 1	0.27
B.01.021 3B Apt Bedroom 2	0.33
B.01.021 3B Apt Bedroom 3	0.33
B.01.022 2B Apt Bedroom 1	0.19
B.01.022 2B Apt Bedroom 2	0.25
B.02.001 2B Apt Bedroom 2	0.16
B.02.001 2B Apt Bedroom 2	0.14
B.02.002 2B Apt Bedroom 1	0.16
B.02.002 2B Apt Bedroom 2	0.22
B.02.003 2B Apt Bedroom 1	0.16
B.02.004 1B Apt Bedroom	0.14
B.02.005 2B Apt Bedroom 1	0.65
B.02.005 2B Apt Bedroom 2	0.57
B.02.006 2B Apt Bedroom 1	0.68
B.02.006 2B Apt Bedroom 2	0.63
B.02.007 2B Apt Bedroom 1	0.63
B.02.007 2B Apt Bedroom 2	0.63
B.02.008 2B Apt Bedroom 1	0.65
B.02.008 2B Apt Bedroom 2	0.60
B.02.009 2B Apt Bedroom 1	0.49
B.02.009 2B Apt Bedroom 2	0.49
B.02.010 1B Apt Bedroom 1	0.33
B.02.011 1B Apt Bedroom	0.49
B.02.012 3B Apt Bedroom 1	0.90
B.02.012 3B Apt Bedroom 2	0.84
B.02.012 3B Apt Bedroom 3	0.87
B.02.013 2B Apt Bedroom 1	0.60

Location	Operative Temperature >26 (Max 1%)
B.02.013 2B Apt Bedroom 2	0.54
B.02.014 2B Apt Bedroom 1	0.52
B.02.014 2B Apt Bedroom 2	0.52
B.02.015 2B Apt Bedroom 1	0.30
B.02.015 2B Apt Bedroom 2	0.46
B.02.016 2B Apt Bedroom 1	0.22
B.02.016 2B Apt Bedroom 2	0.11
B.02.017 3B Apt Bedroom 1	0.11
B.02.017 3B Apt Bedroom 2	0.27
B.02.017 3B Apt Bedroom 3	0.30
B.02.018 2B Apt Bedroom 1	0.27
B.02.018 2B Apt Bedroom 2	0.27
B.02.019 2B Apt Bedroom 1	0.41
B.02.019 2B Apt Bedroom 2	0.22
B.02.020 2B Apt Bedroom 1	0.38
B.02.020 2B Apt Bedroom 2	0.38
B.02.021 3B Apt Bedroom 1	0.35
B.02.021 3B Apt Bedroom 2	0.41
B.02.021 3B Apt Bedroom 3	0.41
B.02.022 2B Apt Bedroom 1	0.22
B.02.022 2B Apt Bedroom 2	0.33
B.03.001 2B Apt Bedroom 2	0.16
B.03.001 2B Apt Bedroom 2	0.14
B.03.002 1B Apt Bedroom 1	0.14
B.03.003 1B Apt Bedroom 1	0.14
B.03.004 1B Apt Bedroom	0.19
B.03.005 2B Apt Bedroom 1	0.65

Location	Operative Temperature >26 (Max 1%)
B.03.005 2B Apt Bedroom 2	0.65
B.03.006 2B Apt Bedroom 1	0.63
B.03.006 2B Apt Bedroom 2	0.65
B.03.007 2B Apt Bedroom 1	0.63
B.03.007 2B Apt Bedroom 2	0.65
B.03.008 2B Apt Bedroom 1	0.60
B.03.008 2B Apt Bedroom 2	0.54
B.03.009 2B Apt Bedroom 1	0.60
B.03.009 2B Apt Bedroom 2	0.63
B.03.010 3B Apt Bedroom 1	0.33
B.03.011 1B Apt Bedroom 1	0.68
B.03.012 2B Apt Bedroom 1	0.71
B.03.012 2B Apt Bedroom 2	0.71
B.03.013 2B Apt Bedroom 1	0.84
B.03.013 2B Apt Bedroom 2	0.82
B.03.014 2B Apt Bedroom 1	0.84
B.03.014 2B Apt Bedroom 2	0.82
B.03.015 2B Apt Bedroom 1	0.30
B.03.015 2B Apt Bedroom 2	0.52
B.03.016 2B Apt Bedroom 1	0.22
B.03.016 2B Apt Bedroom 2	0.14
B.03.017 3B Apt Bedroom 1	0.08
B.03.017 3B Apt Bedroom 2	0.35
B.03.017 3B Apt Bedroom 3	0.38
B.03.018 2B Apt Bedroom 1	0.19
B.03.018 2B Apt Bedroom 2	0.33
B.03.019 2B Apt Bedroom 1	0.52

Location	Operative Temperature >26 (Max 1%)
B.03.019 2B Apt Bedroom 2	0.46
B.03.020 2B Apt Bedroom 1	0.38
B.03.020 2B Apt Bedroom 2	0.38
B.03.021 3B Apt Bedroom 1	0.35
B.03.021 3B Apt Bedroom 2	0.41
B.03.021 3B Apt Bedroom 3	0.44
B.03.022 2B Apt Bedroom 1	0.19
B.03.022 2B Apt Bedroom 2	0.33
B.04.001 2B Apt Bedroom 2	0.14
B.04.001 2B Apt Bedroom 2	0.14
B.04.002 1B Apt Bedroom 1	0.14
B.04.003 1B Apt Bedroom 1	0.14
B.04.004 1B Apt Bedroom	0.14
B.04.005 2B Apt Bedroom 1	0.63
B.04.005 2B Apt Bedroom 2	0.60
B.04.006 2B Apt Bedroom 1	0.60
B.04.006 2B Apt Bedroom 2	0.63
B.04.007 2B Apt Bedroom 1	0.60
B.04.007 2B Apt Bedroom 2	0.63
B.04.008 2B Apt Bedroom 1	0.60
B.04.008 2B Apt Bedroom 2	0.57
B.04.009 2B Apt Bedroom 1	0.65
B.04.009 2B Apt Bedroom 2	0.63
B.04.010 3B Apt Bedroom 1	0.35
B.04.011 1B Apt Bedroom 1	0.68
B.04.012 2B Apt Bedroom 1	0.71
B.04.012 2B Apt Bedroom 2	0.71

Location	Operative Temperature >26 (Max 1%)
B.04.013 2B Apt Bedroom 1	0.84
B.04.013 2B Apt Bedroom 2	0.84
B.04.014 2B Apt Bedroom 1	0.84
B.04.014 2B Apt Bedroom 2	0.84
B.04.015 2B Apt Bedroom 1	0.27
B.04.015 2B Apt Bedroom 2	0.46
B.04.016 2B Apt Bedroom 1	0.22
B.04.016 2B Apt Bedroom 2	0.14
B.04.017 3B Apt Bedroom 1	0.08
B.04.017 3B Apt Bedroom 2	0.35
B.04.017 3B Apt Bedroom 3	0.38
B.04.018 2B Apt Bedroom 1	0.19
B.04.018 2B Apt Bedroom 2	0.30
B.04.019 2B Apt Bedroom 1	0.52
B.04.019 2B Apt Bedroom 2	0.44
B.04.020 2B Apt Bedroom 1	0.38
B.04.020 2B Apt Bedroom 2	0.38
B.04.021 3B Apt Bedroom 1	0.35
B.04.021 3B Apt Bedroom 2	0.41
B.04.021 3B Apt Bedroom 3	0.41
B.04.022 2B Apt Bedroom 1	0.16
B.04.022 2B Apt Bedroom 2	0.33
B.05.001 2B Apt Bedroom 2	0.14
B.05.001 2B Apt Bedroom 2	0.14
B.05.002 1B Apt Bedroom 1	0.14
B.05.003 1B Apt Bedroom 1	0.14
B.05.004 1B Apt Bedroom	0.19

Location	Operative Temperature >26 (Max 1%)
B.05.005 2B Apt Bedroom 1	0.63
B.05.005 2B Apt Bedroom 2	0.60
B.05.006 2B Apt Bedroom 1	0.60
B.05.006 2B Apt Bedroom 2	0.63
B.05.007 2B Apt Bedroom 1	0.60
B.05.007 2B Apt Bedroom 2	0.63
B.05.008 2B Apt Bedroom 1	0.60
B.05.008 2B Apt Bedroom 2	0.57
B.05.009 2B Apt Bedroom 1	0.65
B.05.009 2B Apt Bedroom 2	0.63
B.05.010 3B Apt Bedroom 1	0.35
B.05.011 1B Apt Bedroom 1	0.74
B.05.012 2B Apt Bedroom 1	0.84
B.05.012 2B Apt Bedroom 2	0.84
B.05.013 2B Apt Bedroom 1	0.87
B.05.013 2B Apt Bedroom 2	0.84
B.05.014 2B Apt Bedroom 1	0.87
B.05.014 2B Apt Bedroom 2	0.84
B.05.015 2B Apt Bedroom 1	0.27
B.05.015 2B Apt Bedroom 2	0.46
B.05.016 2B Apt Bedroom 1	0.22
B.05.016 2B Apt Bedroom 2	0.14
B.05.017 3B Apt Bedroom 1	0.08
B.05.017 3B Apt Bedroom 2	0.35
B.05.017 3B Apt Bedroom 3	0.38
B.05.018 2B Apt Bedroom 1	0.19
B.05.018 2B Apt Bedroom 2	0.30

Location	Operative Temperature >26 (Max 1%)
B.05.019 2B Apt Bedroom 1	0.54
B.05.019 2B Apt Bedroom 2	0.46
B.05.020 2B Apt Bedroom 1	0.41
B.05.020 2B Apt Bedroom 2	0.44
B.05.021 3B Apt Bedroom 1	0.35
B.05.021 3B Apt Bedroom 2	0.41
B.05.021 3B Apt Bedroom 3	0.41
B.05.022 2B Apt Bedroom 1	0.19
B.05.022 2B Apt Bedroom 2	0.33
B.06.001 2B Apt Bedroom 2	0.11
B.06.001 2B Apt Bedroom 2	0.11
B.06.002 1B Apt Bedroom 1	0.14
B.06.003 1B Apt Bedroom 1	0.14
B.06.004 1B Apt Bedroom	0.14
B.06.005 2B Apt Bedroom 1	0.57
B.06.005 2B Apt Bedroom 2	0.54
B.06.006 2B Apt Bedroom 1	0.60
B.06.006 2B Apt Bedroom 2	0.60
B.06.007 2B Apt Bedroom 1	0.54
B.06.007 2B Apt Bedroom 2	0.57
B.06.008 2B Apt Bedroom 1	0.57
B.06.008 2B Apt Bedroom 2	0.52
B.06.009 2B Apt Bedroom 1	0.57
B.06.009 2B Apt Bedroom 2	0.60
B.06.010 3B Apt Bedroom 1	0.30
B.06.011 1B Apt Bedroom 1	0.63
B.06.012 2B Apt Bedroom 1	0.82

Location	Operative Temperature >26 (Max 1%)
B.06.012 2B Apt Bedroom 2	0.82
B.06.013 2B Apt Bedroom 1	0.84
B.06.013 2B Apt Bedroom 2	0.79
B.06.014 2B Apt Bedroom 1	0.84
B.06.014 2B Apt Bedroom 2	0.79
B.06.015 2B Apt Bedroom 1	0.27
B.06.015 2B Apt Bedroom 2	0.46
B.06.016 2B Apt Bedroom 1	0.22
B.06.016 2B Apt Bedroom 2	0.14
B.06.017 3B Apt Bedroom 1	0.08
B.06.017 3B Apt Bedroom 2	0.33
B.06.017 3B Apt Bedroom 3	0.38
B.06.018 2B Apt Bedroom 1	0.19
B.06.018 2B Apt Bedroom 2	0.25
B.06.019 2B Apt Bedroom 1	0.57
B.06.019 2B Apt Bedroom 2	0.46
B.06.020 2B Apt Bedroom 1	0.41
B.06.020 2B Apt Bedroom 2	0.41
B.06.021 3B Apt Bedroom 1	0.35
B.06.021 3B Apt Bedroom 2	0.41
B.06.021 3B Apt Bedroom 3	0.41
B.06.022 2B Apt Bedroom 1	0.19
B.06.022 2B Apt Bedroom 2	0.25
B.07.001 4B Apt Bedroom 1	0.05
B.07.002 4B Bedroom 1	0.14
B.07.004 4B Bedroom 1	0.11
B.07.005 4B Bedroom 1	0.11

Location	Operative Temperature >26 (Max 1%)
B.07.007 4B Bedroom 1	0.08
B.07.008 4B Bedroom 1	0.14
B.07.009 4B Bedroom 1	0.84
B.07.010 4B Bedroom 1	0.14
B.07.011 4B Bedroom 1	0.08
B.07.013 4B Bedroom 1	0.11
B.07.015 4B Bedroom	0.25
B.07.016 4B Bedroom	0.14
B.07.017 4B Bedroom 1	0.14
B.08.001 4B Apt Bedroom 1	0.03
B.08.001 4B Apt Bedroom 2	0.03
B.08.001 4B Apt Bedroom 3	0.08
B.08.003 4B Bedroom 2	0.03
B.08.003 4B Bedroom 3	0.11
B.08.003 4B Bedroom 4	0.25
B.08.004 4B Apt Bedroom 2	0.11
B.08.004 4B Apt Bedroom 3	0.11
B.08.004 4B Apt Bedroom 4	0.11
B.08.005 4B Apt Bedroom 2	0.05
B.08.005 4B Apt Bedroom 3	0.05
B.08.005 4B Apt Bedroom 4	0.16
B.08.006 3B Apt Bedroom 3	0.27
B.08.006 3B Bedroom 1	0.11
B.08.006 3B Bedroom 2	0.16
B.08.007 4B Bedroom 2	0.11
B.08.007 4B Bedroom 3	0.08
B.08.007 4B Bedroom 4	0.05

Location	Operative Temperature >26 (Max 1%)
B.08.008 4B Apt Bedroom 2	0.35
B.08.008 4B Apt Bedroom 3	0.14
B.08.008 4B Apt Bedroom 4	0.19
B.08.009 4B Apt Bedroom 2	0.33
B.08.009 4B Apt Bedroom 3	0.16
B.08.009 4B Apt Bedroom 4	0.19
B.08.010 4B Apt Bedroom 2	0.25
B.08.010 4B Apt Bedroom 3	0.25
B.08.010 4B Apt Bedroom 4	0.14
B.08.011 4B Apt Bedroom 2	0.05
B.08.011 4B Apt Bedroom 3	0.11
B.08.011 4B Apt Bedroom 4	0.05
B.08.012 3B Apt Bedroom 1	0.11
B.08.012 3B Apt Bedroom 2	0.11
B.08.012 3B Apt Bedroom 3	0.16
B.08.013 4B Apt Bedroom 2	0.14
B.08.013 4B Apt Bedroom 3	0.08
B.08.013 4B Apt Bedroom 4	0.11
B.08.014 2B Apt Bedroom 1	0.05
B.08.014 2B Apt Bedroom 2	0.30
B.08.015 4B Apt Bedroom 2	0.11
B.08.015 4B Apt Bedroom 3	0.14
B.08.015 4B Apt Bedroom 4	0.14
B.08.016 4B Apt Bedroom 2	0.30
B.08.016 4B Apt Bedroom 3	0.16
B.08.016 4B Apt Bedroom 4	0.19
B.08.017 4B Apt Bedroom 2	0.14

Location	Operative Temperature >26 (Max 1%)
B.08.017 4B Apt Bedroom 3	0.05
B.08.017 4B Apt Bedroom 4	0.08
B.08.0024B Bedroom	0.11
B.08.0024B Bedroom	0.11
B.08.0024B Bedroom	0.11

18.0 Appendix 12: DSY1: TM52 Criterion 1 Living Block B

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.00.001 2B Apt KLD	0.00
B.00.002 2B Apt KLD	0.00
B.00.003 2B Apt KLD	0.00
B.00.004 2B Apt KLD	0.00
B.00.005 2B Apt KLD	0.00
B.00.006 2B Apt KLD	0.00
B.00.007 3B Apt KLD	0.65
B.00.008 2B Apt KLD	0.60
B.00.009 2B Apt KLD	1.41
B.00.010 2B Apt KLD	0.00
B.00.011 1B Apt KLD	0.00
B.01.001 2B Apt KLD	0.00
B.01.002 2B Apt KLD	0.00
B.01.003 2B Apt KLD	0.00
B.01.004 1B Apt KLD	0.00
B.01.010 1B Apt KLD	0.00
B.01.011 1B Apt KLD	0.00
B.01.012 3B Apt KLD	2.16
B.01.013 2B Apt KLD	0.80
B.01.014 2B Apt KLD	0.70
B.01.015 2B Apt KLD	1.61
B.01.016 2B Apt KLD	0.05
B.01.017 3B Apt KLD	0.00
B.01.018 2B Apt KLD	0.00
B.01.019 2B Apt KLD	0.00
B.01.020 2B Apt KLD	0.05
B.01.021 3B Apt KLD	0.10
B.01.022 2B Apt KLD	0.15
B.02.001 2B Apt KLD	0.00
B.02.002 2B Apt KLD	0.00
B.02.003 2B Apt KLD	0.00
B.02.004 1B Apt KLD	0.00
B.02.010 1B Apt KLD	0.00
B.02.011 1B Apt KLD	0.00
B.02.012 3B Apt KLD	2.51
B.02.013 2B Apt KLD	0.80
B.02.014 2B Apt KLD	0.75
B.02.015 2B Apt KLD	1.61
B.02.016 2B Apt KLD	0.05
B.02.017 3B Apt KLD	0.00
B.02.018 2B Apt KLD	0.00
B.02.019 2B Apt KLD	0.00
B.02.020 2B Apt KLD	0.20
B.02.021 3B Apt KLD	0.30
B.02.022 2B Apt KLD	0.15
B.03.001 2B Apt KLD	0.00
B.03.002 1B Apt KLD	0.00
B.03.003 1B Apt KLD	0.00
B.03.004 1B Apt KLD	0.00
B.03.005 2B Apt KLD	0.25

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.03.006 2B Apt KLD	0.30
B.03.007 2B Apt KLD	0.20
B.03.008 2B Apt KLD	0.00
B.03.009 2B Apt KLD	0.00
B.03.010 3B Apt KLD	1.11
B.03.010 3B Apt KLD	1.06
B.03.010 3B Apt KLD	0.96
B.03.011 1B Apt KLD	1.26
B.03.012 2B Apt KLD	2.01
B.03.013 2B Apt KLD	2.21
B.03.014 2B Apt KLD	1.96
B.03.015 2B Apt KLD	1.61
B.03.016 2B Apt KLD	0.05
B.03.017 3B Apt KLD	0.00
B.03.018 2B Apt KLD	0.00
B.03.019 2B Apt KLD	0.00
B.03.020 2B Apt KLD	0.30
B.03.021 3B Apt KLD	0.40
B.03.022 2B Apt KLD	0.15
B.04.001 2B Apt KLD	0.00
B.04.002 1B Apt KLD	0.00
B.04.003 1B Apt KLD	0.00
B.04.004 1B Apt KLD	0.00
B.04.005 2B Apt KLD	0.25
B.04.006 2B Apt KLD	0.30
B.04.007 2B Apt KLD	0.25
B.04.008 2B Apt KLD	0.05

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.04.009 2B Apt KLD	0.00
B.04.010 3B Apt KLD	1.16
B.04.010 3B Apt KLD	1.06
B.04.010 3B Apt KLD	1.01
B.04.011 1B Apt KLD	1.41
B.04.012 2B Apt KLD	1.96
B.04.013 2B Apt KLD	2.41
B.04.014 2B Apt KLD	2.01
B.04.015 2B Apt KLD	1.56
B.04.016 2B Apt KLD	0.10
B.04.017 3B Apt KLD	0.00
B.04.018 2B Apt KLD	0.00
B.04.019 2B Apt KLD	0.00
B.04.020 2B Apt KLD	0.45
B.04.021 3B Apt KLD	0.40
B.04.022 2B Apt KLD	0.15
B.05.001 2B Apt KLD	0.00
B.05.002 1B Apt KLD	0.00
B.05.003 1B Apt KLD	0.00
B.05.004 1B Apt KLD	0.00
B.05.005 2B Apt KLD	0.25
B.05.006 2B Apt KLD	0.30
B.05.007 2B Apt KLD	0.25
B.05.008 2B Apt KLD	0.05
B.05.009 2B Apt KLD	0.00
B.05.010 3B Apt KLD	1.01
B.05.010 3B Apt KLD	1.16

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.05.010 3B Apt KLD	1.06
B.05.011 1B Apt KLD	1.41
B.05.012 2B Apt KLD	2.66
B.05.012 2B Apt KLD	2.46
B.05.013 2B Apt KLD	2.46
B.05.014 2B Apt KLD	2.01
B.05.015 2B Apt KLD	1.56
B.05.016 2B Apt KLD	0.15
B.05.017 3B Apt KLD	0.00
B.05.018 2B Apt KLD	0.00
B.05.019 2B Apt KLD	0.00
B.05.020 2B Apt KLD	0.60
B.05.021 3B Apt KLD	0.45
B.05.022 2B Apt KLD	0.15
B.06.001 2B Apt KLD	0.00
B.06.002 1B Apt KLD	0.00
B.06.003 1B Apt KLD	0.00
B.06.004 1B Apt KLD	0.00
B.06.005 2B Apt KLD	0.15
B.06.006 2B Apt KLD	0.15
B.06.007 2B Apt KLD	0.15
B.06.008 2B Apt KLD	0.00
B.06.009 2B Apt KLD	0.00
B.06.010 3B Apt KLD	0.90
B.06.010 3B Apt KLD	0.96
B.06.010 3B Apt KLD	1.01
B.06.011 1B Apt KLD	1.41

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.06.012 2B Apt KLD	2.36
B.06.012 2B Apt KLD	2.61
B.06.013 2B Apt KLD	2.21
B.06.014 2B Apt KLD	1.76
B.06.015 2B Apt KLD	1.31
B.06.016 2B Apt KLD	0.05
B.06.017 3B Apt KLD	0.00
B.06.018 2B Apt KLD	0.00
B.06.019 2B Apt KLD	0.00
B.06.020 2B Apt KLD	0.55
B.06.021 3B Apt KLD	0.40
B.06.022 2B Apt KLD	0.15
B.07.001 4B Apt KLD	0.00
B.07.002 3B Apt KLD	0.00
B.07.003 4B Apt KLD	0.00
B.07.004 4B KLD	0.00
B.07.005 4B KLD	0.00
B.07.006 3B KLD	0.00
B.07.007 4B KLD	0.35
B.07.008 4B KLD	0.85
B.07.009 4B KLD	1.31
B.07.010 4B KLD	0.65
B.07.011 4B KLD 1	0.00
B.07.012 3B KLD	0.00
B.07.013 4B KLD	0.00
B.07.014 2B KLD	0.20
B.07.015 4B KLD	0.25

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.07.016 4B KLD	0.70
B.07.017 4B KLD	0.00

19.0 Appendix 13: DSY2: TM52 Criterion 1 Bedroom Block B

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.00.001 2B Apt Bedroom 1	0.57
B.00.001 2B Apt Bedroom 2	0.35
B.00.007 3B Apt Bedroom 1	0.35
B.00.007 3B Apt Bedroom 2	0.54
B.00.007 3B Apt Bedroom 3	0.60
B.00.008 2B Apt Bedroom 1	0.60
B.00.009 2B Apt Bedroom 1	0.44
B.00.009 2B Apt Bedroom 2	0.52
B.00.010 2B Apt Bedroom 1	0.30
B.00.011 1B Apt Bedroom 1	0.30
B.00.013 2B Apt 13 Bedroom 2	0.57
B.01.001 2B Apt Bedroom 2	0.41
B.01.001 2B Apt Bedroom 2	0.33
B.01.002 2B Apt Bedroom 1	0.35
B.01.002 2B Apt Bedroom 2	0.38
B.01.003 2B Apt Bedroom 1	0.35
B.01.004 1B Apt Bedroom	0.33
B.01.005 2B Apt Bedroom 1	0.49
B.01.005 2B Apt Bedroom 2	0.49
B.01.006 2B Apt Bedroom 1	0.54
B.01.006 2B Apt Bedroom 2	0.52
B.01.007 2B Apt Bedroom 1	0.52
B.01.007 2B Apt Bedroom 2	0.52
B.01.008 2B Apt Bedroom 1	0.54
B.01.008 2B Apt Bedroom 2	0.52
B.01.009 2B Apt Bedroom 1	0.52
B.01.009 2B Apt Bedroom 2	0.46
B.01.010 1B Apt Bedroom 1	0.38
B.01.011 1B Apt Bedroom	0.30
B.01.012 3B Apt Bedroom 1	0.41
B.01.012 3B Apt Bedroom 2	0.54
B.01.012 3B Apt Bedroom 3	0.60
B.01.013 2B Apt Bedroom 1	0.57
B.01.013 2B Apt Bedroom 2	0.49
B.01.014 2B Apt Bedroom 1	0.54
B.01.014 2B Apt Bedroom 2	0.49
B.01.015 2B Apt Bedroom 1	0.46
B.01.015 2B Apt Bedroom 2	0.54
B.01.016 2B Apt Bedroom 1	0.38
B.01.016 2B Apt Bedroom 2	0.33
B.01.017 3B Apt Bedroom 1	0.35
B.01.017 3B Apt Bedroom 2	0.38
B.01.017 3B Apt Bedroom 3	0.41
B.01.018 2B Apt Bedroom 1	0.25
B.01.018 2B Apt Bedroom 2	0.27
B.01.019 2B Apt Bedroom 1	0.35
B.01.019 2B Apt Bedroom 2	0.33
B.01.020 2B Apt Bedroom 1	0.35
B.01.020 2B Apt Bedroom 2	0.33
B.01.021 3B Apt Bedroom 1	0.33

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.01.021 3B Apt Bedroom 2	0.38
B.01.021 3B Apt Bedroom 3	0.38
B.01.022 2B Apt Bedroom 1	0.33
B.01.022 2B Apt Bedroom 2	0.35
B.02.001 2B Apt Bedroom 2	0.33
B.02.001 2B Apt Bedroom 2	0.41
B.02.002 2B Apt Bedroom 1	0.46
B.02.002 2B Apt Bedroom 2	0.46
B.02.003 2B Apt Bedroom 1	0.49
B.02.004 1B Apt Bedroom	0.46
B.02.005 2B Apt Bedroom 1	0.60
B.02.005 2B Apt Bedroom 2	0.57
B.02.006 2B Apt Bedroom 1	0.60
B.02.006 2B Apt Bedroom 2	0.57
B.02.007 2B Apt Bedroom 1	0.60
B.02.007 2B Apt Bedroom 2	0.60
B.02.008 2B Apt Bedroom 1	0.54
B.02.008 2B Apt Bedroom 2	0.57
B.02.009 2B Apt Bedroom 1	0.52
B.02.009 2B Apt Bedroom 2	0.54
B.02.010 1B Apt Bedroom 1	0.49
B.02.011 1B Apt Bedroom	0.52
B.02.012 3B Apt Bedroom 1	0.76
B.02.012 3B Apt Bedroom 2	0.71
B.02.012 3B Apt Bedroom 3	0.71
B.02.013 2B Apt Bedroom 1	0.57
B.02.013 2B Apt Bedroom 2	0.57

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.02.014 2B Apt Bedroom 1	0.57
B.02.014 2B Apt Bedroom 2	0.57
B.02.015 2B Apt Bedroom 1	0.44
B.02.015 2B Apt Bedroom 2	0.57
B.02.016 2B Apt Bedroom 1	0.38
B.02.016 2B Apt Bedroom 2	0.35
B.02.017 3B Apt Bedroom 1	0.30
B.02.017 3B Apt Bedroom 2	0.41
B.02.017 3B Apt Bedroom 3	0.44
B.02.018 2B Apt Bedroom 1	0.33
B.02.018 2B Apt Bedroom 2	0.33
B.02.019 2B Apt Bedroom 1	0.41
B.02.019 2B Apt Bedroom 2	0.41
B.02.020 2B Apt Bedroom 1	0.46
B.02.020 2B Apt Bedroom 2	0.41
B.02.021 3B Apt Bedroom 1	0.44
B.02.021 3B Apt Bedroom 2	0.46
B.02.021 3B Apt Bedroom 3	0.52
B.02.022 2B Apt Bedroom 1	0.35
B.02.022 2B Apt Bedroom 2	0.41
B.03.001 2B Apt Bedroom 2	0.33
B.03.001 2B Apt Bedroom 2	0.41
B.03.002 1B Apt Bedroom 1	0.44
B.03.003 1B Apt Bedroom 1	0.46
B.03.004 1B Apt Bedroom	0.46
B.03.005 2B Apt Bedroom 1	0.60
B.03.005 2B Apt Bedroom 2	0.57

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.03.006 2B Apt Bedroom 1	0.60
B.03.006 2B Apt Bedroom 2	0.60
B.03.007 2B Apt Bedroom 1	0.60
B.03.007 2B Apt Bedroom 2	0.60
B.03.008 2B Apt Bedroom 1	0.54
B.03.008 2B Apt Bedroom 2	0.54
B.03.009 2B Apt Bedroom 1	0.54
B.03.009 2B Apt Bedroom 2	0.54
B.03.010 3B Apt Bedroom 1	0.44
B.03.011 1B Apt Bedroom 1	0.57
B.03.012 2B Apt Bedroom 1	0.60
B.03.012 2B Apt Bedroom 2	0.60
B.03.013 2B Apt Bedroom 1	0.65
B.03.013 2B Apt Bedroom 2	0.68
B.03.014 2B Apt Bedroom 1	0.65
B.03.014 2B Apt Bedroom 2	0.68
B.03.015 2B Apt Bedroom 1	0.44
B.03.015 2B Apt Bedroom 2	0.57
B.03.016 2B Apt Bedroom 1	0.38
B.03.016 2B Apt Bedroom 2	0.33
B.03.017 3B Apt Bedroom 1	0.22
B.03.017 3B Apt Bedroom 2	0.41
B.03.017 3B Apt Bedroom 3	0.41
B.03.018 2B Apt Bedroom 1	0.33
B.03.018 2B Apt Bedroom 2	0.35
B.03.019 2B Apt Bedroom 1	0.46
B.03.019 2B Apt Bedroom 2	0.46

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.03.020 2B Apt Bedroom 1	0.38
B.03.020 2B Apt Bedroom 2	0.44
B.03.021 3B Apt Bedroom 1	0.44
B.03.021 3B Apt Bedroom 2	0.46
B.03.021 3B Apt Bedroom 3	0.52
B.03.022 2B Apt Bedroom 1	0.35
B.03.022 2B Apt Bedroom 2	0.41
B.04.001 2B Apt Bedroom 2	0.33
B.04.001 2B Apt Bedroom 2	0.41
B.04.002 1B Apt Bedroom 1	0.44
B.04.003 1B Apt Bedroom 1	0.44
B.04.004 1B Apt Bedroom	0.46
B.04.005 2B Apt Bedroom 1	0.60
B.04.005 2B Apt Bedroom 2	0.57
B.04.006 2B Apt Bedroom 1	0.57
B.04.006 2B Apt Bedroom 2	0.60
B.04.007 2B Apt Bedroom 1	0.60
B.04.007 2B Apt Bedroom 2	0.60
B.04.008 2B Apt Bedroom 1	0.54
B.04.008 2B Apt Bedroom 2	0.54
B.04.009 2B Apt Bedroom 1	0.57
B.04.009 2B Apt Bedroom 2	0.54
B.04.010 3B Apt Bedroom 1	0.49
B.04.011 1B Apt Bedroom 1	0.60
B.04.012 2B Apt Bedroom 1	0.60
B.04.012 2B Apt Bedroom 2	0.60
B.04.013 2B Apt Bedroom 1	0.68

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.04.013 2B Apt Bedroom 2	0.71
B.04.014 2B Apt Bedroom 1	0.68
B.04.014 2B Apt Bedroom 2	0.71
B.04.015 2B Apt Bedroom 1	0.41
B.04.015 2B Apt Bedroom 2	0.57
B.04.016 2B Apt Bedroom 1	0.38
B.04.016 2B Apt Bedroom 2	0.35
B.04.017 3B Apt Bedroom 1	0.22
B.04.017 3B Apt Bedroom 2	0.38
B.04.017 3B Apt Bedroom 3	0.41
B.04.018 2B Apt Bedroom 1	0.33
B.04.018 2B Apt Bedroom 2	0.35
B.04.019 2B Apt Bedroom 1	0.46
B.04.019 2B Apt Bedroom 2	0.46
B.04.020 2B Apt Bedroom 1	0.38
B.04.020 2B Apt Bedroom 2	0.46
B.04.021 3B Apt Bedroom 1	0.44
B.04.021 3B Apt Bedroom 2	0.46
B.04.021 3B Apt Bedroom 3	0.52
B.04.022 2B Apt Bedroom 1	0.35
B.04.022 2B Apt Bedroom 2	0.41
B.05.001 2B Apt Bedroom 2	0.41
B.05.001 2B Apt Bedroom 2	0.33
B.05.002 1B Apt Bedroom 1	0.44
B.05.003 1B Apt Bedroom 1	0.46
B.05.004 1B Apt Bedroom	0.46
B.05.005 2B Apt Bedroom 1	0.60

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.05.005 2B Apt Bedroom 2	0.57
B.05.006 2B Apt Bedroom 1	0.57
B.05.006 2B Apt Bedroom 2	0.60
B.05.007 2B Apt Bedroom 1	0.60
B.05.007 2B Apt Bedroom 2	0.60
B.05.008 2B Apt Bedroom 1	0.54
B.05.008 2B Apt Bedroom 2	0.54
B.05.009 2B Apt Bedroom 1	0.57
B.05.009 2B Apt Bedroom 2	0.54
B.05.010 3B Apt Bedroom 1	0.49
B.05.011 1B Apt Bedroom 1	0.63
B.05.012 2B Apt Bedroom 1	0.71
B.05.012 2B Apt Bedroom 2	0.71
B.05.013 2B Apt Bedroom 1	0.68
B.05.013 2B Apt Bedroom 2	0.71
B.05.014 2B Apt Bedroom 1	0.68
B.05.014 2B Apt Bedroom 2	0.71
B.05.015 2B Apt Bedroom 1	0.41
B.05.015 2B Apt Bedroom 2	0.57
B.05.016 2B Apt Bedroom 1	0.38
B.05.016 2B Apt Bedroom 2	0.35
B.05.017 3B Apt Bedroom 1	0.22
B.05.017 3B Apt Bedroom 2	0.38
B.05.017 3B Apt Bedroom 3	0.41
B.05.018 2B Apt Bedroom 1	0.33
B.05.018 2B Apt Bedroom 2	0.35
B.05.019 2B Apt Bedroom 1	0.52

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.05.019 2B Apt Bedroom 2	0.46
B.05.020 2B Apt Bedroom 1	0.41
B.05.020 2B Apt Bedroom 2	0.46
B.05.021 3B Apt Bedroom 1	0.44
B.05.021 3B Apt Bedroom 2	0.46
B.05.021 3B Apt Bedroom 3	0.52
B.05.022 2B Apt Bedroom 1	0.35
B.05.022 2B Apt Bedroom 2	0.41
B.06.001 2B Apt Bedroom 2	0.33
B.06.001 2B Apt Bedroom 2	0.41
B.06.002 1B Apt Bedroom 1	0.41
B.06.003 1B Apt Bedroom 1	0.41
B.06.004 1B Apt Bedroom	0.46
B.06.005 2B Apt Bedroom 1	0.57
B.06.005 2B Apt Bedroom 2	0.57
B.06.006 2B Apt Bedroom 1	0.54
B.06.006 2B Apt Bedroom 2	0.57
B.06.007 2B Apt Bedroom 1	0.54
B.06.007 2B Apt Bedroom 2	0.57
B.06.008 2B Apt Bedroom 1	0.52
B.06.008 2B Apt Bedroom 2	0.52
B.06.009 2B Apt Bedroom 1	0.57
B.06.009 2B Apt Bedroom 2	0.52
B.06.010 3B Apt Bedroom 1	0.49
B.06.011 1B Apt Bedroom 1	0.57
B.06.012 2B Apt Bedroom 1	0.65
B.06.012 2B Apt Bedroom 2	0.68

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.06.013 2B Apt Bedroom 1	0.65
B.06.013 2B Apt Bedroom 2	0.65
B.06.014 2B Apt Bedroom 1	0.65
B.06.014 2B Apt Bedroom 2	0.65
B.06.015 2B Apt Bedroom 1	0.41
B.06.015 2B Apt Bedroom 2	0.49
B.06.016 2B Apt Bedroom 1	0.38
B.06.016 2B Apt Bedroom 2	0.33
B.06.017 3B Apt Bedroom 1	0.22
B.06.017 3B Apt Bedroom 2	0.38
B.06.017 3B Apt Bedroom 3	0.41
B.06.018 2B Apt Bedroom 1	0.30
B.06.018 2B Apt Bedroom 2	0.33
B.06.019 2B Apt Bedroom 1	0.54
B.06.019 2B Apt Bedroom 2	0.46
B.06.020 2B Apt Bedroom 1	0.41
B.06.020 2B Apt Bedroom 2	0.44
B.06.021 3B Apt Bedroom 1	0.44
B.06.021 3B Apt Bedroom 2	0.44
B.06.021 3B Apt Bedroom 3	0.52
B.06.022 2B Apt Bedroom 1	0.33
B.06.022 2B Apt Bedroom 2	0.38
B.07.001 4B Apt Bedroom 1	0.25
B.07.002 4B Bedroom 1	0.25
B.07.004 4B Bedroom 1	0.27
B.07.005 4B Bedroom 1	0.25
B.07.007 4B Bedroom 1	0.27

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.07.008 4B Bedroom 1	0.25
B.07.009 4B Bedroom 1	0.68
B.07.010 4B Bedroom 1	0.27
B.07.011 4B Bedroom 1	0.25
B.07.013 4B Bedroom 1	0.25
B.07.015 4B Bedroom	0.46
B.07.016 4B Bedroom	0.27
B.07.017 4B Bedroom 1	0.25
B.08.001 4B Apt Bedroom 1	0.22
B.08.001 4B Apt Bedroom 2	0.25
B.08.001 4B Apt Bedroom 3	0.30
B.08.003 4B Bedroom 2	0.14
B.08.003 4B Bedroom 3	0.25
B.08.003 4B Bedroom 4	0.27
B.08.004 4B Apt Bedroom 2	0.25
B.08.004 4B Apt Bedroom 3	0.25
B.08.004 4B Apt Bedroom 4	0.25
B.08.005 4B Apt Bedroom 2	0.19
B.08.005 4B Apt Bedroom 3	0.22
B.08.005 4B Apt Bedroom 4	0.27
B.08.006 3B Apt Bedroom 3	0.35
B.08.006 3B Bedroom 1	0.25
B.08.006 3B Bedroom 2	0.27
B.08.007 4B Bedroom 2	0.25
B.08.007 4B Bedroom 3	0.19
B.08.007 4B Bedroom 4	0.30
B.08.008 4B Apt Bedroom 2	0.44

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.08.008 4B Apt Bedroom 3	0.27
B.08.008 4B Apt Bedroom 4	0.27
B.08.009 4B Apt Bedroom 2	0.33
B.08.009 4B Apt Bedroom 3	0.27
B.08.009 4B Apt Bedroom 4	0.30
B.08.010 4B Apt Bedroom 2	0.38
B.08.010 4B Apt Bedroom 3	0.46
B.08.010 4B Apt Bedroom 4	0.25
B.08.011 4B Apt Bedroom 2	0.22
B.08.011 4B Apt Bedroom 3	0.27
B.08.011 4B Apt Bedroom 4	0.27
B.08.012 3B Apt Bedroom 1	0.25
B.08.012 3B Apt Bedroom 2	0.25
B.08.012 3B Apt Bedroom 3	0.27
B.08.013 4B Apt Bedroom 2	0.27
B.08.013 4B Apt Bedroom 3	0.27
B.08.013 4B Apt Bedroom 4	0.27
B.08.014 2B Apt Bedroom 1	0.22
B.08.014 2B Apt Bedroom 2	0.30
B.08.015 4B Apt Bedroom 2	0.27
B.08.015 4B Apt Bedroom 3	0.27
B.08.015 4B Apt Bedroom 4	0.27
B.08.016 4B Apt Bedroom 2	0.38
B.08.016 4B Apt Bedroom 3	0.27
B.08.016 4B Apt Bedroom 4	0.27
B.08.017 4B Apt Bedroom 2	0.27
B.08.017 4B Apt Bedroom 3	0.25

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.08.017 4B Apt Bedroom 4	0.25
B.08.0024B Bedroom	0.22
B.08.0024B Bedroom	0.25
B.08.0024B Bedroom	0.25

20.0 Appendix 14: DSY2: Bedroom Night-time Temperature Test Block B

Location	Operative Temperature >26 (Max 1%)
B.00.001 2B Apt Bedroom 1	0.41
B.00.001 2B Apt Bedroom 2	0.41
B.00.007 3B Apt Bedroom 1	0.33
B.00.007 3B Apt Bedroom 2	1.42
B.00.007 3B Apt Bedroom 3	1.47
B.00.008 2B Apt Bedroom 1	1.03
B.00.009 2B Apt Bedroom 1	0.44
B.00.009 2B Apt Bedroom 2	1.23
B.00.010 2B Apt Bedroom 1	0.00
B.00.011 1B Apt Bedroom 1	0.38
B.00.013 2B Apt 13 Bedroom 2	1.39
B.01.001 2B Apt Bedroom 2	0.52
B.01.001 2B Apt Bedroom 2	0.44
B.01.002 2B Apt Bedroom 1	0.49
B.01.002 2B Apt Bedroom 2	0.52
B.01.003 2B Apt Bedroom 1	0.44
B.01.004 1B Apt Bedroom	0.46
B.01.005 2B Apt Bedroom 1	0.60
B.01.005 2B Apt Bedroom 2	0.63
B.01.006 2B Apt Bedroom 1	0.60
B.01.006 2B Apt Bedroom 2	0.63
B.01.007 2B Apt Bedroom 1	0.60
B.01.007 2B Apt Bedroom 2	0.63
B.01.008 2B Apt Bedroom 1	0.60
B.01.008 2B Apt Bedroom 2	0.63
B.01.009 2B Apt Bedroom 1	0.54
B.01.009 2B Apt Bedroom 2	0.63
B.01.010 1B Apt Bedroom 1	0.49
B.01.011 1B Apt Bedroom	0.44
B.01.012 3B Apt Bedroom 1	1.25
B.01.012 3B Apt Bedroom 2	1.91
B.01.012 3B Apt Bedroom 3	1.93
B.01.013 2B Apt Bedroom 1	1.09
B.01.013 2B Apt Bedroom 2	1.28
B.01.014 2B Apt Bedroom 1	1.06
B.01.014 2B Apt Bedroom 2	1.28
B.01.015 2B Apt Bedroom 1	0.54
B.01.015 2B Apt Bedroom 2	1.47
B.01.016 2B Apt Bedroom 1	0.44
B.01.016 2B Apt Bedroom 2	0.46
B.01.017 3B Apt Bedroom 1	0.30
B.01.017 3B Apt Bedroom 2	0.44
B.01.017 3B Apt Bedroom 3	0.44
B.01.018 2B Apt Bedroom 1	0.16
B.01.018 2B Apt Bedroom 2	0.30

Location	Operative Temperature >26 (Max 1%)
B.01.019 2B Apt Bedroom 1	0.41
B.01.019 2B Apt Bedroom 2	0.41
B.01.020 2B Apt Bedroom 1	0.44
B.01.020 2B Apt Bedroom 2	0.49
B.01.021 3B Apt Bedroom 1	0.44
B.01.021 3B Apt Bedroom 2	0.60
B.01.021 3B Apt Bedroom 3	0.65
B.01.022 2B Apt Bedroom 1	0.44
B.01.022 2B Apt Bedroom 2	0.54
B.02.001 2B Apt Bedroom 2	0.44
B.02.001 2B Apt Bedroom 2	0.60
B.02.002 2B Apt Bedroom 1	0.49
B.02.002 2B Apt Bedroom 2	0.60
B.02.003 2B Apt Bedroom 1	0.49
B.02.004 1B Apt Bedroom	0.60
B.02.005 2B Apt Bedroom 1	0.60
B.02.005 2B Apt Bedroom 2	0.68
B.02.006 2B Apt Bedroom 1	0.60
B.02.006 2B Apt Bedroom 2	0.71
B.02.007 2B Apt Bedroom 1	0.60
B.02.007 2B Apt Bedroom 2	0.65
B.02.008 2B Apt Bedroom 1	0.60
B.02.008 2B Apt Bedroom 2	0.63
B.02.009 2B Apt Bedroom 1	0.57
B.02.009 2B Apt Bedroom 2	0.63

Location	Operative Temperature >26 (Max 1%)
B.02.010 1B Apt Bedroom 1	0.57
B.02.011 1B Apt Bedroom	0.54
B.02.012 3B Apt Bedroom 1	1.47
B.02.012 3B Apt Bedroom 2	2.02
B.02.012 3B Apt Bedroom 3	2.10
B.02.013 2B Apt Bedroom 1	1.09
B.02.013 2B Apt Bedroom 2	1.36
B.02.014 2B Apt Bedroom 1	1.09
B.02.014 2B Apt Bedroom 2	1.36
B.02.015 2B Apt Bedroom 1	0.57
B.02.015 2B Apt Bedroom 2	1.53
B.02.016 2B Apt Bedroom 1	0.46
B.02.016 2B Apt Bedroom 2	0.49
B.02.017 3B Apt Bedroom 1	0.00
B.02.017 3B Apt Bedroom 2	0.49
B.02.017 3B Apt Bedroom 3	0.49
B.02.018 2B Apt Bedroom 1	0.25
B.02.018 2B Apt Bedroom 2	0.33
B.02.019 2B Apt Bedroom 1	0.46
B.02.019 2B Apt Bedroom 2	0.46
B.02.020 2B Apt Bedroom 1	0.46
B.02.020 2B Apt Bedroom 2	0.52
B.02.021 3B Apt Bedroom 1	0.44
B.02.021 3B Apt Bedroom 2	0.71
B.02.021 3B Apt Bedroom 3	0.74

Location	Operative Temperature >26 (Max 1%)
B.02.022 2B Apt Bedroom 1	0.44
B.02.022 2B Apt Bedroom 2	0.54
B.03.001 2B Apt Bedroom 2	0.44
B.03.001 2B Apt Bedroom 2	0.60
B.03.002 1B Apt Bedroom 1	0.52
B.03.003 1B Apt Bedroom 1	0.49
B.03.004 1B Apt Bedroom	0.60
B.03.005 2B Apt Bedroom 1	0.65
B.03.005 2B Apt Bedroom 2	0.65
B.03.006 2B Apt Bedroom 1	0.63
B.03.006 2B Apt Bedroom 2	0.65
B.03.007 2B Apt Bedroom 1	0.60
B.03.007 2B Apt Bedroom 2	0.65
B.03.008 2B Apt Bedroom 1	0.60
B.03.008 2B Apt Bedroom 2	0.60
B.03.009 2B Apt Bedroom 1	0.60
B.03.009 2B Apt Bedroom 2	0.60
B.03.010 3B Apt Bedroom 1	1.12
B.03.011 1B Apt Bedroom 1	1.74
B.03.012 2B Apt Bedroom 1	1.99
B.03.012 2B Apt Bedroom 2	1.99
B.03.013 2B Apt Bedroom 1	1.66
B.03.013 2B Apt Bedroom 2	2.02
B.03.014 2B Apt Bedroom 1	1.66
B.03.014 2B Apt Bedroom 2	1.99

Location	Operative Temperature >26 (Max 1%)
B.03.015 2B Apt Bedroom 1	0.57
B.03.015 2B Apt Bedroom 2	1.53
B.03.016 2B Apt Bedroom 1	0.46
B.03.016 2B Apt Bedroom 2	0.46
B.03.017 3B Apt Bedroom 1	0.00
B.03.017 3B Apt Bedroom 2	0.35
B.03.017 3B Apt Bedroom 3	0.41
B.03.018 2B Apt Bedroom 1	0.27
B.03.018 2B Apt Bedroom 2	0.35
B.03.019 2B Apt Bedroom 1	0.46
B.03.019 2B Apt Bedroom 2	0.44
B.03.020 2B Apt Bedroom 1	0.44
B.03.020 2B Apt Bedroom 2	0.57
B.03.021 3B Apt Bedroom 1	0.44
B.03.021 3B Apt Bedroom 2	0.71
B.03.021 3B Apt Bedroom 3	0.79
B.03.022 2B Apt Bedroom 1	0.44
B.03.022 2B Apt Bedroom 2	0.54
B.04.001 2B Apt Bedroom 2	0.44
B.04.001 2B Apt Bedroom 2	0.60
B.04.002 1B Apt Bedroom 1	0.52
B.04.003 1B Apt Bedroom 1	0.49
B.04.004 1B Apt Bedroom	0.60
B.04.005 2B Apt Bedroom 1	0.63
B.04.005 2B Apt Bedroom 2	0.65

Location	Operative Temperature >26 (Max 1%)
B.04.006 2B Apt Bedroom 1	0.63
B.04.006 2B Apt Bedroom 2	0.65
B.04.007 2B Apt Bedroom 1	0.60
B.04.007 2B Apt Bedroom 2	0.65
B.04.008 2B Apt Bedroom 1	0.60
B.04.008 2B Apt Bedroom 2	0.60
B.04.009 2B Apt Bedroom 1	0.65
B.04.009 2B Apt Bedroom 2	0.60
B.04.010 3B Apt Bedroom 1	1.20
B.04.011 1B Apt Bedroom 1	1.77
B.04.012 2B Apt Bedroom 1	1.99
B.04.012 2B Apt Bedroom 2	1.99
B.04.013 2B Apt Bedroom 1	1.63
B.04.013 2B Apt Bedroom 2	2.07
B.04.014 2B Apt Bedroom 1	1.66
B.04.014 2B Apt Bedroom 2	2.04
B.04.015 2B Apt Bedroom 1	0.52
B.04.015 2B Apt Bedroom 2	1.53
B.04.016 2B Apt Bedroom 1	0.46
B.04.016 2B Apt Bedroom 2	0.46
B.04.017 3B Apt Bedroom 1	0.00
B.04.017 3B Apt Bedroom 2	0.35
B.04.017 3B Apt Bedroom 3	0.41
B.04.018 2B Apt Bedroom 1	0.30
B.04.018 2B Apt Bedroom 2	0.38

Location	Operative Temperature >26 (Max 1%)
B.04.019 2B Apt Bedroom 1	0.46
B.04.019 2B Apt Bedroom 2	0.44
B.04.020 2B Apt Bedroom 1	0.46
B.04.020 2B Apt Bedroom 2	0.84
B.04.021 3B Apt Bedroom 1	0.44
B.04.021 3B Apt Bedroom 2	0.71
B.04.021 3B Apt Bedroom 3	0.79
B.04.022 2B Apt Bedroom 1	0.44
B.04.022 2B Apt Bedroom 2	0.57
B.05.001 2B Apt Bedroom 2	0.60
B.05.001 2B Apt Bedroom 2	0.44
B.05.002 1B Apt Bedroom 1	0.52
B.05.003 1B Apt Bedroom 1	0.49
B.05.004 1B Apt Bedroom	0.60
B.05.005 2B Apt Bedroom 1	0.63
B.05.005 2B Apt Bedroom 2	0.65
B.05.006 2B Apt Bedroom 1	0.60
B.05.006 2B Apt Bedroom 2	0.65
B.05.007 2B Apt Bedroom 1	0.60
B.05.007 2B Apt Bedroom 2	0.65
B.05.008 2B Apt Bedroom 1	0.60
B.05.008 2B Apt Bedroom 2	0.60
B.05.009 2B Apt Bedroom 1	0.65
B.05.009 2B Apt Bedroom 2	0.60
B.05.010 3B Apt Bedroom 1	1.20

Location	Operative Temperature >26 (Max 1%)
B.05.011 1B Apt Bedroom 1	1.91
B.05.012 2B Apt Bedroom 1	2.23
B.05.012 2B Apt Bedroom 2	2.26
B.05.013 2B Apt Bedroom 1	1.66
B.05.013 2B Apt Bedroom 2	2.07
B.05.014 2B Apt Bedroom 1	1.66
B.05.014 2B Apt Bedroom 2	2.04
B.05.015 2B Apt Bedroom 1	0.52
B.05.015 2B Apt Bedroom 2	1.53
B.05.016 2B Apt Bedroom 1	0.46
B.05.016 2B Apt Bedroom 2	0.46
B.05.017 3B Apt Bedroom 1	0.00
B.05.017 3B Apt Bedroom 2	0.35
B.05.017 3B Apt Bedroom 3	0.41
B.05.018 2B Apt Bedroom 1	0.30
B.05.018 2B Apt Bedroom 2	0.38
B.05.019 2B Apt Bedroom 1	0.46
B.05.019 2B Apt Bedroom 2	0.44
B.05.020 2B Apt Bedroom 1	0.63
B.05.020 2B Apt Bedroom 2	1.03
B.05.021 3B Apt Bedroom 1	0.44
B.05.021 3B Apt Bedroom 2	0.71
B.05.021 3B Apt Bedroom 3	0.79
B.05.022 2B Apt Bedroom 1	0.44
B.05.022 2B Apt Bedroom 2	0.57

Location	Operative Temperature >26 (Max 1%)
B.06.001 2B Apt Bedroom 2	0.44
B.06.001 2B Apt Bedroom 2	0.54
B.06.002 1B Apt Bedroom 1	0.49
B.06.003 1B Apt Bedroom 1	0.49
B.06.004 1B Apt Bedroom	0.60
B.06.005 2B Apt Bedroom 1	0.60
B.06.005 2B Apt Bedroom 2	0.65
B.06.006 2B Apt Bedroom 1	0.60
B.06.006 2B Apt Bedroom 2	0.65
B.06.007 2B Apt Bedroom 1	0.60
B.06.007 2B Apt Bedroom 2	0.63
B.06.008 2B Apt Bedroom 1	0.60
B.06.008 2B Apt Bedroom 2	0.60
B.06.009 2B Apt Bedroom 1	0.60
B.06.009 2B Apt Bedroom 2	0.60
B.06.010 3B Apt Bedroom 1	1.14
B.06.011 1B Apt Bedroom 1	1.66
B.06.012 2B Apt Bedroom 1	2.18
B.06.012 2B Apt Bedroom 2	2.18
B.06.013 2B Apt Bedroom 1	1.63
B.06.013 2B Apt Bedroom 2	1.96
B.06.014 2B Apt Bedroom 1	1.63
B.06.014 2B Apt Bedroom 2	1.96
B.06.015 2B Apt Bedroom 1	0.49
B.06.015 2B Apt Bedroom 2	1.42

Location	Operative Temperature >26 (Max 1%)
B.06.016 2B Apt Bedroom 1	0.46
B.06.016 2B Apt Bedroom 2	0.46
B.06.017 3B Apt Bedroom 1	0.00
B.06.017 3B Apt Bedroom 2	0.38
B.06.017 3B Apt Bedroom 3	0.41
B.06.018 2B Apt Bedroom 1	0.30
B.06.018 2B Apt Bedroom 2	0.38
B.06.019 2B Apt Bedroom 1	0.49
B.06.019 2B Apt Bedroom 2	0.44
B.06.020 2B Apt Bedroom 1	0.76
B.06.020 2B Apt Bedroom 2	1.03
B.06.021 3B Apt Bedroom 1	0.44
B.06.021 3B Apt Bedroom 2	0.68
B.06.021 3B Apt Bedroom 3	0.76
B.06.022 2B Apt Bedroom 1	0.44
B.06.022 2B Apt Bedroom 2	0.54
B.07.001 4B Apt Bedroom 1	0.46
B.07.002 4B Bedroom 1	0.54
B.07.004 4B Bedroom 1	0.49
B.07.005 4B Bedroom 1	0.49
B.07.007 4B Bedroom 1	0.79
B.07.008 4B Bedroom 1	0.68
B.07.009 4B Bedroom 1	0.76
B.07.010 4B Bedroom 1	0.79
B.07.011 4B Bedroom 1	0.46

Location	Operative Temperature >26 (Max 1%)
B.07.013 4B Bedroom 1	0.41
B.07.015 4B Bedroom	0.46
B.07.016 4B Bedroom	0.46
B.07.017 4B Bedroom 1	0.65
B.08.001 4B Apt Bedroom 1	0.46
B.08.001 4B Apt Bedroom 2	0.57
B.08.001 4B Apt Bedroom 3	0.60
B.08.003 4B Bedroom 2	0.52
B.08.003 4B Bedroom 3	0.54
B.08.003 4B Bedroom 4	0.90
B.08.004 4B Apt Bedroom 2	0.82
B.08.004 4B Apt Bedroom 3	0.54
B.08.004 4B Apt Bedroom 4	0.54
B.08.005 4B Apt Bedroom 2	0.57
B.08.005 4B Apt Bedroom 3	0.52
B.08.005 4B Apt Bedroom 4	0.57
B.08.006 3B Apt Bedroom 3	0.63
B.08.006 3B Bedroom 1	0.60
B.08.006 3B Bedroom 2	0.54
B.08.007 4B Bedroom 2	0.54
B.08.007 4B Bedroom 3	1.77
B.08.007 4B Bedroom 4	1.80
B.08.008 4B Apt Bedroom 2	1.20
B.08.008 4B Apt Bedroom 3	1.53
B.08.008 4B Apt Bedroom 4	1.06

Location	Operative Temperature >26 (Max 1%)
B.08.009 4B Apt Bedroom 2	1.09
B.08.009 4B Apt Bedroom 3	1.23
B.08.009 4B Apt Bedroom 4	1.63
B.08.010 4B Apt Bedroom 2	2.40
B.08.010 4B Apt Bedroom 3	1.99
B.08.010 4B Apt Bedroom 4	0.74
B.08.011 4B Apt Bedroom 2	0.46
B.08.011 4B Apt Bedroom 3	0.68
B.08.011 4B Apt Bedroom 4	0.63
B.08.012 3B Apt Bedroom 1	0.44
B.08.012 3B Apt Bedroom 2	0.44
B.08.012 3B Apt Bedroom 3	0.41
B.08.013 4B Apt Bedroom 2	0.38
B.08.013 4B Apt Bedroom 3	0.41
B.08.013 4B Apt Bedroom 4	0.46
B.08.014 2B Apt Bedroom 1	0.49
B.08.014 2B Apt Bedroom 2	0.90
B.08.015 4B Apt Bedroom 2	0.49
B.08.015 4B Apt Bedroom 3	1.01
B.08.015 4B Apt Bedroom 4	1.33
B.08.016 4B Apt Bedroom 2	1.17
B.08.016 4B Apt Bedroom 3	1.20
B.08.016 4B Apt Bedroom 4	1.23
B.08.017 4B Apt Bedroom 2	1.28
B.08.017 4B Apt Bedroom 3	0.82

Location	Operative Temperature >26 (Max 1%)
B.08.017 4B Apt Bedroom 4	0.46
B.08.0024B Bedroom	0.54
B.08.0024B Bedroom	0.54
B.08.0024B Bedroom	0.54

21.0 Appendix 15: DSY2: TM52 Criterion 1 Living Block B

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.00.001 2B Apt KLD	0.85
B.00.002 2B Apt KLD	0.40
B.00.003 2B Apt KLD	0.70
B.00.004 2B Apt KLD	1.01
B.00.005 2B Apt KLD	1.01
B.00.006 2B Apt KLD	0.65
B.00.007 3B Apt KLD	1.56
B.00.008 2B Apt KLD	1.46
B.00.009 2B Apt KLD	2.21
B.00.010 2B Apt KLD	0.80
B.00.011 1B Apt KLD	0.80
B.01.001 2B Apt KLD	0.90
B.01.002 2B Apt KLD	0.80
B.01.003 2B Apt KLD	0.75
B.01.004 1B Apt KLD	0.85
B.01.010 1B Apt KLD	0.90
B.01.011 1B Apt KLD	0.50
B.01.012 3B Apt KLD	2.61
B.01.013 2B Apt KLD	1.71
B.01.014 2B Apt KLD	1.66
B.01.015 2B Apt KLD	2.56
B.01.016 2B Apt KLD	1.01
B.01.017 3B Apt KLD	0.75
B.01.018 2B Apt KLD	0.55
B.01.019 2B Apt KLD	0.65
B.01.020 2B Apt KLD	0.80
B.01.021 3B Apt KLD	0.90
B.01.022 2B Apt KLD	1.01
B.02.001 2B Apt KLD	0.90
B.02.002 2B Apt KLD	0.80
B.02.003 2B Apt KLD	0.85
B.02.004 1B Apt KLD	1.06
B.02.010 1B Apt KLD	0.96
B.02.011 1B Apt KLD	0.85
B.02.012 3B Apt KLD	2.87
B.02.013 2B Apt KLD	1.76
B.02.014 2B Apt KLD	1.71
B.02.015 2B Apt KLD	2.36
B.02.016 2B Apt KLD	1.01
B.02.017 3B Apt KLD	0.75
B.02.018 2B Apt KLD	0.60
B.02.019 2B Apt KLD	0.75
B.02.020 2B Apt KLD	1.06
B.02.021 3B Apt KLD	1.11
B.02.022 2B Apt KLD	1.01
B.03.001 2B Apt KLD	0.96

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.03.002 1B Apt KLD	0.85
B.03.003 1B Apt KLD	0.80
B.03.004 1B Apt KLD	1.06
B.03.005 2B Apt KLD	1.11
B.03.006 2B Apt KLD	1.11
B.03.007 2B Apt KLD	1.06
B.03.008 2B Apt KLD	0.96
B.03.009 2B Apt KLD	0.90
B.03.010 3B Apt KLD	2.97
B.03.010 3B Apt KLD	2.41
B.03.010 3B Apt KLD	2.31
B.03.011 1B Apt KLD	1.86
B.03.012 2B Apt KLD	2.71
B.03.013 2B Apt KLD	2.66
B.03.014 2B Apt KLD	2.61
B.03.015 2B Apt KLD	2.36
B.03.016 2B Apt KLD	1.01
B.03.017 3B Apt KLD	0.55
B.03.018 2B Apt KLD	0.55
B.03.019 2B Apt KLD	0.75
B.03.020 2B Apt KLD	1.21
B.03.021 3B Apt KLD	1.21
B.03.022 2B Apt KLD	1.01
B.04.001 2B Apt KLD	0.90
B.04.002 1B Apt KLD	0.85

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.04.003 1B Apt KLD	0.80
B.04.004 1B Apt KLD	1.06
B.04.005 2B Apt KLD	1.11
B.04.006 2B Apt KLD	1.11
B.04.007 2B Apt KLD	1.11
B.04.008 2B Apt KLD	0.96
B.04.009 2B Apt KLD	0.96
B.04.010 3B Apt KLD	3.02
B.04.010 3B Apt KLD	2.61
B.04.010 3B Apt KLD	2.46
B.04.011 1B Apt KLD	2.01
B.04.012 2B Apt KLD	2.61
B.04.013 2B Apt KLD	2.71
B.04.014 2B Apt KLD	2.66
B.04.015 2B Apt KLD	2.46
B.04.016 2B Apt KLD	1.01
B.04.017 3B Apt KLD	0.55
B.04.018 2B Apt KLD	0.55
B.04.019 2B Apt KLD	0.75
B.04.020 2B Apt KLD	1.26
B.04.021 3B Apt KLD	1.26
B.04.022 2B Apt KLD	1.01
B.05.001 2B Apt KLD	0.90
B.05.002 1B Apt KLD	0.85
B.05.003 1B Apt KLD	0.80

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.05.004 1B Apt KLD	1.06
B.05.005 2B Apt KLD	1.11
B.05.006 2B Apt KLD	1.11
B.05.007 2B Apt KLD	1.06
B.05.008 2B Apt KLD	0.96
B.05.009 2B Apt KLD	0.96
B.05.010 3B Apt KLD	2.46
B.05.010 3B Apt KLD	3.02
B.05.010 3B Apt KLD	2.61
B.05.011 1B Apt KLD	2.06
B.05.012 2B Apt KLD	3.02
B.05.012 2B Apt KLD	2.92
B.05.013 2B Apt KLD	2.82
B.05.014 2B Apt KLD	2.66
B.05.015 2B Apt KLD	2.41
B.05.016 2B Apt KLD	1.01
B.05.017 3B Apt KLD	0.55
B.05.018 2B Apt KLD	0.55
B.05.019 2B Apt KLD	0.75
B.05.020 2B Apt KLD	1.51
B.05.021 3B Apt KLD	1.26
B.05.022 2B Apt KLD	1.01
B.06.001 2B Apt KLD	0.90
B.06.002 1B Apt KLD	0.85
B.06.003 1B Apt KLD	0.80

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.06.004 1B Apt KLD	1.06
B.06.005 2B Apt KLD	1.11
B.06.006 2B Apt KLD	1.06
B.06.007 2B Apt KLD	1.06
B.06.008 2B Apt KLD	0.96
B.06.009 2B Apt KLD	0.90
B.06.010 3B Apt KLD	2.21
B.06.010 3B Apt KLD	2.16
B.06.010 3B Apt KLD	2.51
B.06.011 1B Apt KLD	2.01
B.06.012 2B Apt KLD	2.66
B.06.012 2B Apt KLD	2.97
B.06.013 2B Apt KLD	2.66
B.06.014 2B Apt KLD	2.56
B.06.015 2B Apt KLD	2.31
B.06.016 2B Apt KLD	1.01
B.06.017 3B Apt KLD	0.60
B.06.018 2B Apt KLD	0.55
B.06.019 2B Apt KLD	0.75
B.06.020 2B Apt KLD	1.46
B.06.021 3B Apt KLD	1.26
B.06.022 2B Apt KLD	1.01
B.07.001 4B Apt KLD	0.90
B.07.002 3B Apt KLD	0.80
B.07.003 4B Apt KLD	0.90

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.07.004 4B KLD	0.96
B.07.005 4B KLD	0.96
B.07.006 3B KLD	0.96
B.07.007 4B KLD	1.06
B.07.008 4B KLD	1.51
B.07.009 4B KLD	1.91
B.07.010 4B KLD	1.41
B.07.011 4B KLD 1	0.90
B.07.012 3B KLD	0.80
B.07.013 4B KLD	0.70
B.07.014 2B KLD	1.11
B.07.015 4B KLD	1.01
B.07.016 4B KLD	1.31
B.07.017 4B KLD	0.85

22.0 Appendix 16: DSY3: TM52 Criterion 1 Bedroom Block B

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.00.001 2B Apt Bedroom 1	0.05
B.00.001 2B Apt Bedroom 2	0.27
B.00.007 3B Apt Bedroom 1	0.41
B.00.007 3B Apt Bedroom 2	2.64
B.00.007 3B Apt Bedroom 3	2.81
B.00.008 2B Apt Bedroom 1	2.23
B.00.009 2B Apt Bedroom 1	0.71
B.00.009 2B Apt Bedroom 2	2.42
B.00.010 2B Apt Bedroom 1	0.00
B.00.011 1B Apt Bedroom 1	0.03
B.00.013 2B Apt 13 Bedroom 2	2.59
B.01.001 2B Apt Bedroom 2	0.52
B.01.001 2B Apt Bedroom 2	0.25
B.01.002 2B Apt Bedroom 1	0.33
B.01.002 2B Apt Bedroom 2	0.46
B.01.003 2B Apt Bedroom 1	0.22
B.01.004 1B Apt Bedroom	0.41
B.01.005 2B Apt Bedroom 1	0.76
B.01.005 2B Apt Bedroom 2	1.33
B.01.006 2B Apt Bedroom 1	0.82
B.01.006 2B Apt Bedroom 2	1.91
B.01.007 2B Apt Bedroom 1	0.79
B.01.007 2B Apt Bedroom 2	1.69
B.01.008 2B Apt Bedroom 1	0.76
B.01.008 2B Apt Bedroom 2	1.66
B.01.009 2B Apt Bedroom 1	0.16
B.01.009 2B Apt Bedroom 2	1.09
B.01.010 1B Apt Bedroom 1	0.46
B.01.011 1B Apt Bedroom	0.00
B.01.012 3B Apt Bedroom 1	2.07
B.01.012 3B Apt Bedroom 2	3.19
B.01.012 3B Apt Bedroom 3	3.19
B.01.013 2B Apt Bedroom 1	1.85
B.01.013 2B Apt Bedroom 2	2.18
B.01.014 2B Apt Bedroom 1	1.85
B.01.014 2B Apt Bedroom 2	2.12
B.01.015 2B Apt Bedroom 1	1.12
B.01.015 2B Apt Bedroom 2	2.56
B.01.016 2B Apt Bedroom 1	0.57
B.01.016 2B Apt Bedroom 2	0.41
B.01.017 3B Apt Bedroom 1	0.00
B.01.017 3B Apt Bedroom 2	0.11
B.01.017 3B Apt Bedroom 3	0.16
B.01.018 2B Apt Bedroom 1	0.00
B.01.018 2B Apt Bedroom 2	0.00
B.01.019 2B Apt Bedroom 1	0.00

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.01.019 2B Apt Bedroom 2	0.05
B.01.020 2B Apt Bedroom 1	0.08
B.01.020 2B Apt Bedroom 2	0.49
B.01.021 3B Apt Bedroom 1	0.30
B.01.021 3B Apt Bedroom 2	1.31
B.01.021 3B Apt Bedroom 3	1.25
B.01.022 2B Apt Bedroom 1	0.11
B.01.022 2B Apt Bedroom 2	1.36
B.02.001 2B Apt Bedroom 2	0.27
B.02.001 2B Apt Bedroom 2	0.63
B.02.002 2B Apt Bedroom 1	0.38
B.02.002 2B Apt Bedroom 2	0.46
B.02.003 2B Apt Bedroom 1	0.30
B.02.004 1B Apt Bedroom	0.46
B.02.005 2B Apt Bedroom 1	1.31
B.02.005 2B Apt Bedroom 2	1.85
B.02.006 2B Apt Bedroom 1	1.42
B.02.006 2B Apt Bedroom 2	2.18
B.02.007 2B Apt Bedroom 1	1.25
B.02.007 2B Apt Bedroom 2	2.04
B.02.008 2B Apt Bedroom 1	0.90
B.02.008 2B Apt Bedroom 2	1.74
B.02.009 2B Apt Bedroom 1	0.33
B.02.009 2B Apt Bedroom 2	1.39
B.02.010 1B Apt Bedroom 1	0.57

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.02.011 1B Apt Bedroom	0.35
B.02.012 3B Apt Bedroom 1	2.64
B.02.012 3B Apt Bedroom 2	3.40
B.02.012 3B Apt Bedroom 3	3.51
B.02.013 2B Apt Bedroom 1	1.99
B.02.013 2B Apt Bedroom 2	2.34
B.02.014 2B Apt Bedroom 1	1.88
B.02.014 2B Apt Bedroom 2	2.31
B.02.015 2B Apt Bedroom 1	1.09
B.02.015 2B Apt Bedroom 2	2.53
B.02.016 2B Apt Bedroom 1	0.60
B.02.016 2B Apt Bedroom 2	0.46
B.02.017 3B Apt Bedroom 1	0.00
B.02.017 3B Apt Bedroom 2	0.16
B.02.017 3B Apt Bedroom 3	0.19
B.02.018 2B Apt Bedroom 1	0.00
B.02.018 2B Apt Bedroom 2	0.00
B.02.019 2B Apt Bedroom 1	0.08
B.02.019 2B Apt Bedroom 2	0.33
B.02.020 2B Apt Bedroom 1	0.49
B.02.020 2B Apt Bedroom 2	1.01
B.02.021 3B Apt Bedroom 1	0.52
B.02.021 3B Apt Bedroom 2	1.47
B.02.021 3B Apt Bedroom 3	1.61
B.02.022 2B Apt Bedroom 1	0.22

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.02.022 2B Apt Bedroom 2	1.42
B.03.001 2B Apt Bedroom 2	0.27
B.03.001 2B Apt Bedroom 2	0.63
B.03.002 1B Apt Bedroom 1	0.44
B.03.003 1B Apt Bedroom 1	0.30
B.03.004 1B Apt Bedroom	0.52
B.03.005 2B Apt Bedroom 1	1.61
B.03.005 2B Apt Bedroom 2	1.93
B.03.006 2B Apt Bedroom 1	1.55
B.03.006 2B Apt Bedroom 2	1.93
B.03.007 2B Apt Bedroom 1	1.39
B.03.007 2B Apt Bedroom 2	1.91
B.03.008 2B Apt Bedroom 1	0.63
B.03.008 2B Apt Bedroom 2	1.12
B.03.009 2B Apt Bedroom 1	1.50
B.03.009 2B Apt Bedroom 2	0.84
B.03.010 3B Apt Bedroom 1	2.40
B.03.011 1B Apt Bedroom 1	3.00
B.03.012 2B Apt Bedroom 1	3.27
B.03.012 2B Apt Bedroom 2	3.30
B.03.013 2B Apt Bedroom 1	3.00
B.03.013 2B Apt Bedroom 2	3.38
B.03.014 2B Apt Bedroom 1	3.05
B.03.014 2B Apt Bedroom 2	3.35
B.03.015 2B Apt Bedroom 1	1.14

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.03.015 2B Apt Bedroom 2	2.61
B.03.016 2B Apt Bedroom 1	0.60
B.03.016 2B Apt Bedroom 2	0.44
B.03.017 3B Apt Bedroom 1	0.00
B.03.017 3B Apt Bedroom 2	0.11
B.03.017 3B Apt Bedroom 3	0.16
B.03.018 2B Apt Bedroom 1	0.00
B.03.018 2B Apt Bedroom 2	0.00
B.03.019 2B Apt Bedroom 1	0.25
B.03.019 2B Apt Bedroom 2	0.27
B.03.020 2B Apt Bedroom 1	0.63
B.03.020 2B Apt Bedroom 2	1.36
B.03.021 3B Apt Bedroom 1	0.54
B.03.021 3B Apt Bedroom 2	1.55
B.03.021 3B Apt Bedroom 3	1.66
B.03.022 2B Apt Bedroom 1	0.22
B.03.022 2B Apt Bedroom 2	1.42
B.04.001 2B Apt Bedroom 2	0.27
B.04.001 2B Apt Bedroom 2	0.63
B.04.002 1B Apt Bedroom 1	0.44
B.04.003 1B Apt Bedroom 1	0.27
B.04.004 1B Apt Bedroom	0.49
B.04.005 2B Apt Bedroom 1	1.61
B.04.005 2B Apt Bedroom 2	1.93
B.04.006 2B Apt Bedroom 1	1.55

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.04.006 2B Apt Bedroom 2	1.93
B.04.007 2B Apt Bedroom 1	1.50
B.04.007 2B Apt Bedroom 2	1.93
B.04.008 2B Apt Bedroom 1	0.71
B.04.008 2B Apt Bedroom 2	1.33
B.04.009 2B Apt Bedroom 1	1.66
B.04.009 2B Apt Bedroom 2	1.09
B.04.010 3B Apt Bedroom 1	2.48
B.04.011 1B Apt Bedroom 1	3.10
B.04.012 2B Apt Bedroom 1	3.21
B.04.012 2B Apt Bedroom 2	3.24
B.04.013 2B Apt Bedroom 1	3.02
B.04.013 2B Apt Bedroom 2	3.40
B.04.014 2B Apt Bedroom 1	3.05
B.04.014 2B Apt Bedroom 2	3.38
B.04.015 2B Apt Bedroom 1	1.12
B.04.015 2B Apt Bedroom 2	2.61
B.04.016 2B Apt Bedroom 1	0.60
B.04.016 2B Apt Bedroom 2	0.49
B.04.017 3B Apt Bedroom 1	0.00
B.04.017 3B Apt Bedroom 2	0.14
B.04.017 3B Apt Bedroom 3	0.16
B.04.018 2B Apt Bedroom 1	0.00
B.04.018 2B Apt Bedroom 2	0.00
B.04.019 2B Apt Bedroom 1	0.49

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.04.019 2B Apt Bedroom 2	0.44
B.04.020 2B Apt Bedroom 1	0.79
B.04.020 2B Apt Bedroom 2	1.72
B.04.021 3B Apt Bedroom 1	0.54
B.04.021 3B Apt Bedroom 2	1.50
B.04.021 3B Apt Bedroom 3	1.77
B.04.022 2B Apt Bedroom 1	0.22
B.04.022 2B Apt Bedroom 2	1.42
B.05.001 2B Apt Bedroom 2	0.63
B.05.001 2B Apt Bedroom 2	0.27
B.05.002 1B Apt Bedroom 1	0.44
B.05.003 1B Apt Bedroom 1	0.27
B.05.004 1B Apt Bedroom	0.52
B.05.005 2B Apt Bedroom 1	1.61
B.05.005 2B Apt Bedroom 2	1.93
B.05.006 2B Apt Bedroom 1	1.55
B.05.006 2B Apt Bedroom 2	1.93
B.05.007 2B Apt Bedroom 1	1.42
B.05.007 2B Apt Bedroom 2	1.93
B.05.008 2B Apt Bedroom 1	0.71
B.05.008 2B Apt Bedroom 2	1.33
B.05.009 2B Apt Bedroom 1	1.66
B.05.009 2B Apt Bedroom 2	1.06
B.05.010 3B Apt Bedroom 1	2.48
B.05.011 1B Apt Bedroom 1	3.16

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.05.012 2B Apt Bedroom 1	3.95
B.05.012 2B Apt Bedroom 2	3.98
B.05.013 2B Apt Bedroom 1	3.05
B.05.013 2B Apt Bedroom 2	3.43
B.05.014 2B Apt Bedroom 1	3.05
B.05.014 2B Apt Bedroom 2	3.35
B.05.015 2B Apt Bedroom 1	1.14
B.05.015 2B Apt Bedroom 2	2.61
B.05.016 2B Apt Bedroom 1	0.60
B.05.016 2B Apt Bedroom 2	0.60
B.05.017 3B Apt Bedroom 1	0.00
B.05.017 3B Apt Bedroom 2	0.14
B.05.017 3B Apt Bedroom 3	0.19
B.05.018 2B Apt Bedroom 1	0.00
B.05.018 2B Apt Bedroom 2	0.00
B.05.019 2B Apt Bedroom 1	0.76
B.05.019 2B Apt Bedroom 2	0.60
B.05.020 2B Apt Bedroom 1	1.20
B.05.020 2B Apt Bedroom 2	2.07
B.05.021 3B Apt Bedroom 1	0.54
B.05.021 3B Apt Bedroom 2	1.50
B.05.021 3B Apt Bedroom 3	1.82
B.05.022 2B Apt Bedroom 1	0.22
B.05.022 2B Apt Bedroom 2	1.42
B.06.001 2B Apt Bedroom 2	0.27

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.06.001 2B Apt Bedroom 2	0.60
B.06.002 1B Apt Bedroom 1	0.41
B.06.003 1B Apt Bedroom 1	0.27
B.06.004 1B Apt Bedroom	0.52
B.06.005 2B Apt Bedroom 1	1.20
B.06.005 2B Apt Bedroom 2	1.85
B.06.006 2B Apt Bedroom 1	1.28
B.06.006 2B Apt Bedroom 2	1.88
B.06.007 2B Apt Bedroom 1	0.95
B.06.007 2B Apt Bedroom 2	1.74
B.06.008 2B Apt Bedroom 1	0.63
B.06.008 2B Apt Bedroom 2	1.03
B.06.009 2B Apt Bedroom 1	1.36
B.06.009 2B Apt Bedroom 2	0.76
B.06.010 3B Apt Bedroom 1	2.31
B.06.011 1B Apt Bedroom 1	2.91
B.06.012 2B Apt Bedroom 1	3.68
B.06.012 2B Apt Bedroom 2	3.76
B.06.013 2B Apt Bedroom 1	2.91
B.06.013 2B Apt Bedroom 2	3.27
B.06.014 2B Apt Bedroom 1	2.97
B.06.014 2B Apt Bedroom 2	3.21
B.06.015 2B Apt Bedroom 1	1.06
B.06.015 2B Apt Bedroom 2	2.45
B.06.016 2B Apt Bedroom 1	0.60

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.06.016 2B Apt Bedroom 2	0.57
B.06.017 3B Apt Bedroom 1	0.00
B.06.017 3B Apt Bedroom 2	0.14
B.06.017 3B Apt Bedroom 3	0.19
B.06.018 2B Apt Bedroom 1	0.00
B.06.018 2B Apt Bedroom 2	0.00
B.06.019 2B Apt Bedroom 1	0.84
B.06.019 2B Apt Bedroom 2	0.76
B.06.020 2B Apt Bedroom 1	1.47
B.06.020 2B Apt Bedroom 2	2.04
B.06.021 3B Apt Bedroom 1	0.54
B.06.021 3B Apt Bedroom 2	1.44
B.06.021 3B Apt Bedroom 3	1.74
B.06.022 2B Apt Bedroom 1	0.22
B.06.022 2B Apt Bedroom 2	1.39
B.07.001 4B Apt Bedroom 1	0.35
B.07.002 4B Bedroom 1	0.46
B.07.004 4B Bedroom 1	0.30
B.07.005 4B Bedroom 1	0.30
B.07.007 4B Bedroom 1	1.80
B.07.008 4B Bedroom 1	1.58
B.07.009 4B Bedroom 1	1.63
B.07.010 4B Bedroom 1	1.80
B.07.011 4B Bedroom 1	0.35
B.07.013 4B Bedroom 1	0.03

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.07.015 4B Bedroom	0.79
B.07.016 4B Bedroom	0.95
B.07.017 4B Bedroom 1	1.50
B.08.001 4B Apt Bedroom 1	0.52
B.08.001 4B Apt Bedroom 2	0.71
B.08.001 4B Apt Bedroom 3	0.71
B.08.003 4B Bedroom 2	0.90
B.08.003 4B Bedroom 3	0.71
B.08.003 4B Bedroom 4	2.23
B.08.004 4B Apt Bedroom 2	2.02
B.08.004 4B Apt Bedroom 3	0.79
B.08.004 4B Apt Bedroom 4	0.60
B.08.005 4B Apt Bedroom 2	1.23
B.08.005 4B Apt Bedroom 3	0.60
B.08.005 4B Apt Bedroom 4	0.74
B.08.006 3B Apt Bedroom 3	0.87
B.08.006 3B Bedroom 1	1.14
B.08.006 3B Bedroom 2	0.44
B.08.007 4B Bedroom 2	1.55
B.08.007 4B Bedroom 3	3.21
B.08.007 4B Bedroom 4	3.16
B.08.008 4B Apt Bedroom 2	2.34
B.08.008 4B Apt Bedroom 3	2.72
B.08.008 4B Apt Bedroom 4	2.15
B.08.009 4B Apt Bedroom 2	2.15

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.08.009 4B Apt Bedroom 3	2.42
B.08.009 4B Apt Bedroom 4	2.81
B.08.010 4B Apt Bedroom 2	3.73
B.08.010 4B Apt Bedroom 3	3.16
B.08.010 4B Apt Bedroom 4	1.99
B.08.011 4B Apt Bedroom 2	0.87
B.08.011 4B Apt Bedroom 3	1.47
B.08.011 4B Apt Bedroom 4	1.36
B.08.012 3B Apt Bedroom 1	0.22
B.08.012 3B Apt Bedroom 2	0.16
B.08.012 3B Apt Bedroom 3	0.05
B.08.013 4B Apt Bedroom 2	0.03
B.08.013 4B Apt Bedroom 3	0.30
B.08.013 4B Apt Bedroom 4	0.90
B.08.014 2B Apt Bedroom 1	0.76
B.08.014 2B Apt Bedroom 2	1.82
B.08.015 4B Apt Bedroom 2	0.87
B.08.015 4B Apt Bedroom 3	1.93
B.08.015 4B Apt Bedroom 4	2.51
B.08.016 4B Apt Bedroom 2	2.18
B.08.016 4B Apt Bedroom 3	2.31
B.08.016 4B Apt Bedroom 4	2.31
B.08.017 4B Apt Bedroom 2	2.21
B.08.017 4B Apt Bedroom 3	1.61
B.08.017 4B Apt Bedroom 4	1.03

Location	Degrees > Max. adaptive temp > 1 (Max 3%)
B.08.0024B Bedroom	0.57
B.08.0024B Bedroom	0.52
B.08.0024B Bedroom	0.46

23.0 Appendix 17: DSY3: Bedroom Night-time Temperature Test Block B

Location	Operative Temperature >26 (Max 1%)
B.00.001 2B Apt Bedroom 1	0.57
B.00.001 2B Apt Bedroom 2	0.76
B.00.007 3B Apt Bedroom 1	1.09
B.00.007 3B Apt Bedroom 2	1.50
B.00.007 3B Apt Bedroom 3	1.63
B.00.008 2B Apt Bedroom 1	1.69
B.00.009 2B Apt Bedroom 1	1.17
B.00.009 2B Apt Bedroom 2	1.42
B.00.010 2B Apt Bedroom 1	0.74
B.00.011 1B Apt Bedroom 1	0.82
B.00.013 2B Apt 13 Bedroom 2	1.63
B.01.001 2B Apt Bedroom 2	0.82
B.01.001 2B Apt Bedroom 2	0.79
B.01.002 2B Apt Bedroom 1	0.76
B.01.002 2B Apt Bedroom 2	0.76
B.01.003 2B Apt Bedroom 1	0.76
B.01.004 1B Apt Bedroom	0.74
B.01.005 2B Apt Bedroom 1	1.44
B.01.005 2B Apt Bedroom 2	1.31
B.01.006 2B Apt Bedroom 1	1.55
B.01.006 2B Apt Bedroom 2	1.31
B.01.007 2B Apt Bedroom 1	1.50
B.01.007 2B Apt Bedroom 2	1.39
B.01.008 2B Apt Bedroom 1	1.74
B.01.008 2B Apt Bedroom 2	1.50
B.01.009 2B Apt Bedroom 1	1.12
B.01.009 2B Apt Bedroom 2	1.25
B.01.010 1B Apt Bedroom 1	0.76
B.01.011 1B Apt Bedroom	0.95
B.01.012 3B Apt Bedroom 1	0.98
B.01.012 3B Apt Bedroom 2	1.44
B.01.012 3B Apt Bedroom 3	1.55
B.01.013 2B Apt Bedroom 1	1.58
B.01.013 2B Apt Bedroom 2	1.44
B.01.014 2B Apt Bedroom 1	1.42
B.01.014 2B Apt Bedroom 2	1.39
B.01.015 2B Apt Bedroom 1	0.95
B.01.015 2B Apt Bedroom 2	1.20
B.01.016 2B Apt Bedroom 1	0.79
B.01.016 2B Apt Bedroom 2	0.71
B.01.017 3B Apt Bedroom 1	0.84
B.01.017 3B Apt Bedroom 2	0.82
B.01.017 3B Apt Bedroom 3	0.82
B.01.018 2B Apt Bedroom 1	0.68
B.01.018 2B Apt Bedroom 2	0.79

Location	Operative Temperature >26 (Max 1%)
B.01.019 2B Apt Bedroom 1	0.93
B.01.019 2B Apt Bedroom 2	0.79
B.01.020 2B Apt Bedroom 1	0.95
B.01.020 2B Apt Bedroom 2	0.87
B.01.021 3B Apt Bedroom 1	1.01
B.01.021 3B Apt Bedroom 2	1.14
B.01.021 3B Apt Bedroom 3	1.17
B.01.022 2B Apt Bedroom 1	0.82
B.01.022 2B Apt Bedroom 2	1.01
B.02.001 2B Apt Bedroom 2	0.79
B.02.001 2B Apt Bedroom 2	0.82
B.02.002 2B Apt Bedroom 1	0.76
B.02.002 2B Apt Bedroom 2	0.93
B.02.003 2B Apt Bedroom 1	0.98
B.02.004 1B Apt Bedroom	0.84
B.02.005 2B Apt Bedroom 1	1.77
B.02.005 2B Apt Bedroom 2	1.50
B.02.006 2B Apt Bedroom 1	1.82
B.02.006 2B Apt Bedroom 2	1.50
B.02.007 2B Apt Bedroom 1	1.80
B.02.007 2B Apt Bedroom 2	1.58
B.02.008 2B Apt Bedroom 1	1.72
B.02.008 2B Apt Bedroom 2	1.47
B.02.009 2B Apt Bedroom 1	1.25
B.02.009 2B Apt Bedroom 2	1.31

Location	Operative Temperature >26 (Max 1%)
B.02.010 1B Apt Bedroom 1	1.01
B.02.011 1B Apt Bedroom	1.39
B.02.012 3B Apt Bedroom 1	1.88
B.02.012 3B Apt Bedroom 2	1.77
B.02.012 3B Apt Bedroom 3	1.88
B.02.013 2B Apt Bedroom 1	1.58
B.02.013 2B Apt Bedroom 2	1.47
B.02.014 2B Apt Bedroom 1	1.50
B.02.014 2B Apt Bedroom 2	1.44
B.02.015 2B Apt Bedroom 1	0.98
B.02.015 2B Apt Bedroom 2	1.23
B.02.016 2B Apt Bedroom 1	0.82
B.02.016 2B Apt Bedroom 2	0.71
B.02.017 3B Apt Bedroom 1	0.63
B.02.017 3B Apt Bedroom 2	0.82
B.02.017 3B Apt Bedroom 3	0.90
B.02.018 2B Apt Bedroom 1	0.84
B.02.018 2B Apt Bedroom 2	0.93
B.02.019 2B Apt Bedroom 1	1.14
B.02.019 2B Apt Bedroom 2	1.01
B.02.020 2B Apt Bedroom 1	1.20
B.02.020 2B Apt Bedroom 2	1.09
B.02.021 3B Apt Bedroom 1	1.31
B.02.021 3B Apt Bedroom 2	1.36
B.02.021 3B Apt Bedroom 3	1.42

Location	Operative Temperature >26 (Max 1%)
B.02.022 2B Apt Bedroom 1	0.87
B.02.022 2B Apt Bedroom 2	1.03
B.03.001 2B Apt Bedroom 2	0.79
B.03.001 2B Apt Bedroom 2	0.82
B.03.002 1B Apt Bedroom 1	0.82
B.03.003 1B Apt Bedroom 1	0.84
B.03.004 1B Apt Bedroom	0.87
B.03.005 2B Apt Bedroom 1	1.69
B.03.005 2B Apt Bedroom 2	1.61
B.03.006 2B Apt Bedroom 1	1.53
B.03.006 2B Apt Bedroom 2	1.69
B.03.007 2B Apt Bedroom 1	1.58
B.03.007 2B Apt Bedroom 2	1.63
B.03.008 2B Apt Bedroom 1	1.50
B.03.008 2B Apt Bedroom 2	1.55
B.03.009 2B Apt Bedroom 1	1.61
B.03.009 2B Apt Bedroom 2	1.66
B.03.010 3B Apt Bedroom 1	1.23
B.03.011 1B Apt Bedroom 1	1.61
B.03.012 2B Apt Bedroom 1	1.63
B.03.012 2B Apt Bedroom 2	1.63
B.03.013 2B Apt Bedroom 1	1.85
B.03.013 2B Apt Bedroom 2	1.80
B.03.014 2B Apt Bedroom 1	1.85
B.03.014 2B Apt Bedroom 2	1.77

Location	Operative Temperature >26 (Max 1%)
B.03.015 2B Apt Bedroom 1	0.98
B.03.015 2B Apt Bedroom 2	1.25
B.03.016 2B Apt Bedroom 1	0.82
B.03.016 2B Apt Bedroom 2	0.74
B.03.017 3B Apt Bedroom 1	0.63
B.03.017 3B Apt Bedroom 2	0.82
B.03.017 3B Apt Bedroom 3	0.93
B.03.018 2B Apt Bedroom 1	0.98
B.03.018 2B Apt Bedroom 2	1.01
B.03.019 2B Apt Bedroom 1	1.55
B.03.019 2B Apt Bedroom 2	1.47
B.03.020 2B Apt Bedroom 1	1.14
B.03.020 2B Apt Bedroom 2	1.14
B.03.021 3B Apt Bedroom 1	1.33
B.03.021 3B Apt Bedroom 2	1.36
B.03.021 3B Apt Bedroom 3	1.44
B.03.022 2B Apt Bedroom 1	0.87
B.03.022 2B Apt Bedroom 2	1.03
B.04.001 2B Apt Bedroom 2	0.76
B.04.001 2B Apt Bedroom 2	0.74
B.04.002 1B Apt Bedroom 1	0.82
B.04.003 1B Apt Bedroom 1	0.82
B.04.004 1B Apt Bedroom	0.87
B.04.005 2B Apt Bedroom 1	1.63
B.04.005 2B Apt Bedroom 2	1.55

Location	Operative Temperature >26 (Max 1%)
B.04.006 2B Apt Bedroom 1	1.44
B.04.006 2B Apt Bedroom 2	1.61
B.04.007 2B Apt Bedroom 1	1.47
B.04.007 2B Apt Bedroom 2	1.61
B.04.008 2B Apt Bedroom 1	1.47
B.04.008 2B Apt Bedroom 2	1.55
B.04.009 2B Apt Bedroom 1	1.69
B.04.009 2B Apt Bedroom 2	1.63
B.04.010 3B Apt Bedroom 1	1.33
B.04.011 1B Apt Bedroom 1	1.61
B.04.012 2B Apt Bedroom 1	1.58
B.04.012 2B Apt Bedroom 2	1.61
B.04.013 2B Apt Bedroom 1	1.85
B.04.013 2B Apt Bedroom 2	1.77
B.04.014 2B Apt Bedroom 1	1.85
B.04.014 2B Apt Bedroom 2	1.77
B.04.015 2B Apt Bedroom 1	0.95
B.04.015 2B Apt Bedroom 2	1.23
B.04.016 2B Apt Bedroom 1	0.82
B.04.016 2B Apt Bedroom 2	0.71
B.04.017 3B Apt Bedroom 1	0.60
B.04.017 3B Apt Bedroom 2	0.82
B.04.017 3B Apt Bedroom 3	0.90
B.04.018 2B Apt Bedroom 1	0.93
B.04.018 2B Apt Bedroom 2	0.98

Location	Operative Temperature >26 (Max 1%)
B.04.019 2B Apt Bedroom 1	1.58
B.04.019 2B Apt Bedroom 2	1.47
B.04.020 2B Apt Bedroom 1	1.14
B.04.020 2B Apt Bedroom 2	1.14
B.04.021 3B Apt Bedroom 1	1.25
B.04.021 3B Apt Bedroom 2	1.33
B.04.021 3B Apt Bedroom 3	1.42
B.04.022 2B Apt Bedroom 1	0.82
B.04.022 2B Apt Bedroom 2	1.03
B.05.001 2B Apt Bedroom 2	0.74
B.05.001 2B Apt Bedroom 2	0.76
B.05.002 1B Apt Bedroom 1	0.82
B.05.003 1B Apt Bedroom 1	0.82
B.05.004 1B Apt Bedroom	0.87
B.05.005 2B Apt Bedroom 1	1.53
B.05.005 2B Apt Bedroom 2	1.55
B.05.006 2B Apt Bedroom 1	1.42
B.05.006 2B Apt Bedroom 2	1.61
B.05.007 2B Apt Bedroom 1	1.44
B.05.007 2B Apt Bedroom 2	1.61
B.05.008 2B Apt Bedroom 1	1.47
B.05.008 2B Apt Bedroom 2	1.55
B.05.009 2B Apt Bedroom 1	1.69
B.05.009 2B Apt Bedroom 2	1.63
B.05.010 3B Apt Bedroom 1	1.31

Location	Operative Temperature >26 (Max 1%)
B.05.011 1B Apt Bedroom 1	1.61
B.05.012 2B Apt Bedroom 1	1.74
B.05.012 2B Apt Bedroom 2	1.77
B.05.013 2B Apt Bedroom 1	1.91
B.05.013 2B Apt Bedroom 2	1.80
B.05.014 2B Apt Bedroom 1	1.88
B.05.014 2B Apt Bedroom 2	1.77
B.05.015 2B Apt Bedroom 1	0.95
B.05.015 2B Apt Bedroom 2	1.23
B.05.016 2B Apt Bedroom 1	0.82
B.05.016 2B Apt Bedroom 2	0.74
B.05.017 3B Apt Bedroom 1	0.60
B.05.017 3B Apt Bedroom 2	0.82
B.05.017 3B Apt Bedroom 3	0.93
B.05.018 2B Apt Bedroom 1	0.93
B.05.018 2B Apt Bedroom 2	0.98
B.05.019 2B Apt Bedroom 1	1.63
B.05.019 2B Apt Bedroom 2	1.55
B.05.020 2B Apt Bedroom 1	1.20
B.05.020 2B Apt Bedroom 2	1.20
B.05.021 3B Apt Bedroom 1	1.25
B.05.021 3B Apt Bedroom 2	1.33
B.05.021 3B Apt Bedroom 3	1.42
B.05.022 2B Apt Bedroom 1	0.82
B.05.022 2B Apt Bedroom 2	1.03

Location	Operative Temperature >26 (Max 1%)
B.06.001 2B Apt Bedroom 2	0.76
B.06.001 2B Apt Bedroom 2	0.71
B.06.002 1B Apt Bedroom 1	0.79
B.06.003 1B Apt Bedroom 1	0.82
B.06.004 1B Apt Bedroom	0.84
B.06.005 2B Apt Bedroom 1	1.42
B.06.005 2B Apt Bedroom 2	1.42
B.06.006 2B Apt Bedroom 1	1.42
B.06.006 2B Apt Bedroom 2	1.42
B.06.007 2B Apt Bedroom 1	1.39
B.06.007 2B Apt Bedroom 2	1.42
B.06.008 2B Apt Bedroom 1	1.42
B.06.008 2B Apt Bedroom 2	1.44
B.06.009 2B Apt Bedroom 1	1.55
B.06.009 2B Apt Bedroom 2	1.58
B.06.010 3B Apt Bedroom 1	1.28
B.06.011 1B Apt Bedroom 1	1.53
B.06.012 2B Apt Bedroom 1	1.72
B.06.012 2B Apt Bedroom 2	1.74
B.06.013 2B Apt Bedroom 1	1.80
B.06.013 2B Apt Bedroom 2	1.74
B.06.014 2B Apt Bedroom 1	1.80
B.06.014 2B Apt Bedroom 2	1.69
B.06.015 2B Apt Bedroom 1	0.95
B.06.015 2B Apt Bedroom 2	1.14

Location	Operative Temperature >26 (Max 1%)
B.06.016 2B Apt Bedroom 1	0.82
B.06.016 2B Apt Bedroom 2	0.74
B.06.017 3B Apt Bedroom 1	0.65
B.06.017 3B Apt Bedroom 2	0.82
B.06.017 3B Apt Bedroom 3	0.90
B.06.018 2B Apt Bedroom 1	0.87
B.06.018 2B Apt Bedroom 2	0.95
B.06.019 2B Apt Bedroom 1	1.63
B.06.019 2B Apt Bedroom 2	1.58
B.06.020 2B Apt Bedroom 1	1.20
B.06.020 2B Apt Bedroom 2	1.12
B.06.021 3B Apt Bedroom 1	1.20
B.06.021 3B Apt Bedroom 2	1.28
B.06.021 3B Apt Bedroom 3	1.33
B.06.022 2B Apt Bedroom 1	0.82
B.06.022 2B Apt Bedroom 2	1.01
B.07.001 4B Apt Bedroom 1	0.44
B.07.002 4B Bedroom 1	0.57
B.07.004 4B Bedroom 1	0.54
B.07.005 4B Bedroom 1	0.54
B.07.007 4B Bedroom 1	0.54
B.07.008 4B Bedroom 1	0.65
B.07.009 4B Bedroom 1	1.85
B.07.010 4B Bedroom 1	0.63
B.07.011 4B Bedroom 1	0.46

Location	Operative Temperature >26 (Max 1%)
B.07.013 4B Bedroom 1	0.44
B.07.015 4B Bedroom	1.25
B.07.016 4B Bedroom	0.60
B.07.017 4B Bedroom 1	0.46
B.08.001 4B Apt Bedroom 1	0.38
B.08.001 4B Apt Bedroom 2	0.30
B.08.001 4B Apt Bedroom 3	0.57
B.08.003 4B Bedroom 2	0.27
B.08.003 4B Bedroom 3	0.52
B.08.003 4B Bedroom 4	0.87
B.08.004 4B Apt Bedroom 2	0.52
B.08.004 4B Apt Bedroom 3	0.52
B.08.004 4B Apt Bedroom 4	0.52
B.08.005 4B Apt Bedroom 2	0.33
B.08.005 4B Apt Bedroom 3	0.41
B.08.005 4B Apt Bedroom 4	0.84
B.08.006 3B Apt Bedroom 3	0.95
B.08.006 3B Bedroom 1	0.49
B.08.006 3B Bedroom 2	0.79
B.08.007 4B Bedroom 2	0.41
B.08.007 4B Bedroom 3	0.35
B.08.007 4B Bedroom 4	0.82
B.08.008 4B Apt Bedroom 2	1.01
B.08.008 4B Apt Bedroom 3	0.68
B.08.008 4B Apt Bedroom 4	0.79

Location	Operative Temperature >26 (Max 1%)
B.08.009 4B Apt Bedroom 2	0.95
B.08.009 4B Apt Bedroom 3	0.74
B.08.009 4B Apt Bedroom 4	0.76
B.08.010 4B Apt Bedroom 2	0.79
B.08.010 4B Apt Bedroom 3	0.90
B.08.010 4B Apt Bedroom 4	0.54
B.08.011 4B Apt Bedroom 2	0.44
B.08.011 4B Apt Bedroom 3	0.65
B.08.011 4B Apt Bedroom 4	0.52
B.08.012 3B Apt Bedroom 1	0.49
B.08.012 3B Apt Bedroom 2	0.49
B.08.012 3B Apt Bedroom 3	0.79
B.08.013 4B Apt Bedroom 2	0.68
B.08.013 4B Apt Bedroom 3	0.65
B.08.013 4B Apt Bedroom 4	0.74
B.08.014 2B Apt Bedroom 1	0.41
B.08.014 2B Apt Bedroom 2	0.90
B.08.015 4B Apt Bedroom 2	0.79
B.08.015 4B Apt Bedroom 3	0.63
B.08.015 4B Apt Bedroom 4	0.63
B.08.016 4B Apt Bedroom 2	0.95
B.08.016 4B Apt Bedroom 3	0.76
B.08.016 4B Apt Bedroom 4	0.79
B.08.017 4B Apt Bedroom 2	0.65
B.08.017 4B Apt Bedroom 3	0.41

Location	Operative Temperature >26 (Max 1%)
B.08.017 4B Apt Bedroom 4	0.46
B.08.0024B Bedroom	0.44
B.08.0024B Bedroom	0.46
B.08.0024B Bedroom	0.49

24.0 Appendix 18: DSY3: TM52 Criterion 1 Living Block B

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.00.001 2B Apt KLD	0.85
B.00.002 2B Apt KLD	0.40
B.00.003 2B Apt KLD	0.70
B.00.004 2B Apt KLD	1.01
B.00.005 2B Apt KLD	1.01
B.00.006 2B Apt KLD	0.65
B.00.007 3B Apt KLD	1.56
B.00.008 2B Apt KLD	1.46
B.00.009 2B Apt KLD	2.21
B.00.010 2B Apt KLD	0.80
B.00.011 1B Apt KLD	0.80
B.01.001 2B Apt KLD	0.90
B.01.002 2B Apt KLD	0.80
B.01.003 2B Apt KLD	0.75
B.01.004 1B Apt KLD	0.85
B.01.010 1B Apt KLD	0.90
B.01.011 1B Apt KLD	0.50
B.01.012 3B Apt KLD	2.61
B.01.013 2B Apt KLD	1.71
B.01.014 2B Apt KLD	1.66
B.01.015 2B Apt KLD	2.56
B.01.016 2B Apt KLD	1.01
B.01.017 3B Apt KLD	0.75
B.01.018 2B Apt KLD	0.55
B.01.019 2B Apt KLD	0.65
B.01.020 2B Apt KLD	0.80
B.01.021 3B Apt KLD	0.90
B.01.022 2B Apt KLD	1.01
B.02.001 2B Apt KLD	0.90
B.02.002 2B Apt KLD	0.80
B.02.003 2B Apt KLD	0.85
B.02.004 1B Apt KLD	1.06
B.02.010 1B Apt KLD	0.96
B.02.011 1B Apt KLD	0.85
B.02.012 3B Apt KLD	2.87
B.02.013 2B Apt KLD	1.76
B.02.014 2B Apt KLD	1.71
B.02.015 2B Apt KLD	2.36
B.02.016 2B Apt KLD	1.01
B.02.017 3B Apt KLD	0.75
B.02.018 2B Apt KLD	0.60
B.02.019 2B Apt KLD	0.75
B.02.020 2B Apt KLD	1.06
B.02.021 3B Apt KLD	1.11
B.02.022 2B Apt KLD	1.01
B.03.001 2B Apt KLD	0.96

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.03.002 1B Apt KLD	0.85
B.03.003 1B Apt KLD	0.80
B.03.004 1B Apt KLD	1.06
B.03.005 2B Apt KLD	1.11
B.03.006 2B Apt KLD	1.11
B.03.007 2B Apt KLD	1.06
B.03.008 2B Apt KLD	0.96
B.03.009 2B Apt KLD	0.90
B.03.010 3B Apt KLD	2.97
B.03.010 3B Apt KLD	2.41
B.03.010 3B Apt KLD	2.31
B.03.011 1B Apt KLD	1.86
B.03.012 2B Apt KLD	2.71
B.03.013 2B Apt KLD	2.66
B.03.014 2B Apt KLD	2.61
B.03.015 2B Apt KLD	2.36
B.03.016 2B Apt KLD	1.01
B.03.017 3B Apt KLD	0.55
B.03.018 2B Apt KLD	0.55
B.03.019 2B Apt KLD	0.75
B.03.020 2B Apt KLD	1.21
B.03.021 3B Apt KLD	1.21
B.03.022 2B Apt KLD	1.01
B.04.001 2B Apt KLD	0.90
B.04.002 1B Apt KLD	0.85

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.04.003 1B Apt KLD	0.80
B.04.004 1B Apt KLD	1.06
B.04.005 2B Apt KLD	1.11
B.04.006 2B Apt KLD	1.11
B.04.007 2B Apt KLD	1.11
B.04.008 2B Apt KLD	0.96
B.04.009 2B Apt KLD	0.96
B.04.010 3B Apt KLD	3.02
B.04.010 3B Apt KLD	2.61
B.04.010 3B Apt KLD	2.46
B.04.011 1B Apt KLD	2.01
B.04.012 2B Apt KLD	2.61
B.04.013 2B Apt KLD	2.71
B.04.014 2B Apt KLD	2.66
B.04.015 2B Apt KLD	2.46
B.04.016 2B Apt KLD	1.01
B.04.017 3B Apt KLD	0.55
B.04.018 2B Apt KLD	0.55
B.04.019 2B Apt KLD	0.75
B.04.020 2B Apt KLD	1.26
B.04.021 3B Apt KLD	1.26
B.04.022 2B Apt KLD	1.01
B.05.001 2B Apt KLD	0.90
B.05.002 1B Apt KLD	0.85
B.05.003 1B Apt KLD	0.80

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.05.004 1B Apt KLD	1.06
B.05.005 2B Apt KLD	1.11
B.05.006 2B Apt KLD	1.11
B.05.007 2B Apt KLD	1.06
B.05.008 2B Apt KLD	0.96
B.05.009 2B Apt KLD	0.96
B.05.010 3B Apt KLD	2.46
B.05.010 3B Apt KLD	3.02
B.05.010 3B Apt KLD	2.61
B.05.011 1B Apt KLD	2.06
B.05.012 2B Apt KLD	3.02
B.05.012 2B Apt KLD	2.92
B.05.013 2B Apt KLD	2.82
B.05.014 2B Apt KLD	2.66
B.05.015 2B Apt KLD	2.41
B.05.016 2B Apt KLD	1.01
B.05.017 3B Apt KLD	0.55
B.05.018 2B Apt KLD	0.55
B.05.019 2B Apt KLD	0.75
B.05.020 2B Apt KLD	1.51
B.05.021 3B Apt KLD	1.26
B.05.022 2B Apt KLD	1.01
B.06.001 2B Apt KLD	0.90
B.06.002 1B Apt KLD	0.85
B.06.003 1B Apt KLD	0.80

Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.06.004 1B Apt KLD	1.06
B.06.005 2B Apt KLD	1.11
B.06.006 2B Apt KLD	1.06
B.06.007 2B Apt KLD	1.06
B.06.008 2B Apt KLD	0.96
B.06.009 2B Apt KLD	0.90
B.06.010 3B Apt KLD	2.21
B.06.010 3B Apt KLD	2.16
B.06.010 3B Apt KLD	2.51
B.06.011 1B Apt KLD	2.01
B.06.012 2B Apt KLD	2.66
B.06.012 2B Apt KLD	2.97
B.06.013 2B Apt KLD	2.66
B.06.014 2B Apt KLD	2.56
B.06.015 2B Apt KLD	2.31
B.06.016 2B Apt KLD	1.01
B.06.017 3B Apt KLD	0.60
B.06.018 2B Apt KLD	0.55
B.06.019 2B Apt KLD	0.75
B.06.020 2B Apt KLD	1.46
B.06.021 3B Apt KLD	1.26
B.06.022 2B Apt KLD	1.01
B.07.001 4B Apt KLD	0.90
B.07.002 3B Apt KLD	0.80
B.07.003 4B Apt KLD	0.90


Location	Degrees > Max. adaptive temp >1 (Max 3%)
B.07.004 4B KLD	0.96
B.07.005 4B KLD	0.96
B.07.006 3B KLD	0.96
B.07.007 4B KLD	1.06
B.07.008 4B KLD	1.51
B.07.009 4B KLD	1.91
B.07.010 4B KLD	1.41
B.07.011 4B KLD 1	0.90
B.07.012 3B KLD	0.80
B.07.013 4B KLD	0.70
B.07.014 2B KLD	1.11
B.07.015 4B KLD	1.01
B.07.016 4B KLD	1.31
B.07.017 4B KLD	0.85

13.0 Appendix 4: Whole Life Carbon Analysis

Upfront and Life Cycle Embodied Carbon Report
One Castlefield
Manchester

Site: 44153 – No. 1 Castlefield
Contact: Matthew Holland
Date: 16/06/2026

First Issue



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

Table of Contents

SECTION 1.0 – EXECUTIVE SUMMARY & INTRODUCTION 3

SECTION 2.0 - SCOPE & METHODOLOGY 5

2.1 METHODOLOGICAL FRAMEWORK 5

2.2 DATA SOURCES 5

2.3 – GMCA REPORTING 6

SECTION 3.0 – BLOCK A (THE TOWER) PROJECT DESCRIPTION 7

SECTION 4.0 - EMBODIED CARBON RESULTS (CRADLE TO GRAVE A1-C4) & TOP CONTRIBUTING MATERIALS 7

4.1 – UPFRONT & LIFE CYCLE EMBODIED CARBON RESULTS 7

4.2 – TOP CONTRIBUTING MATERIALS – BLOCK A (THE TOWER), ONE CASTLEFIELD, 436 APARTMENTS 8

SECTION 5.0 – BLOCK B (THE STREET BLOCK) PROJECT DESCRIPTION 11

SECTION 6.0 - EMBODIED CARBON RESULTS (CRADLE TO GRAVE A1-C4) & TOP CONTRIBUTING MATERIALS 12

6.1 – UPFRONT & LIFE CYCLE EMBODIED CARBON RESULTS 12

6.2 - TOP CONTRIBUTING MATERIALS – BLOCK B (THE STREET BLOCK) ONE CASTLEFIELD- 157 APARTMENTS 12

SECTION 7.0 – DATA ASSUMPTIONS, UNCERTAINTY & TOP-UP FACTOR 15

SECTION 8.0 - CONCLUSION & GMCA COMPLIANCE STATEMENT 16

APPENDIX 1 – THE TOWER (BLOCK A) PLANS, SECTIONS & ELEVATIONS, STRUCTURAL DESIGN 17

APPENDIX 2 – BLOCK B (THE STREET BLOCK) PLANS, SECTIONS & ELEVATIONS, STRUCTURAL DESIGN 27

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

Section 1.0 – Executive Summary & Introduction

This report presents the upfront and life cycle embodied carbon (A1-C4) for the proposed residential development at One Castlefield, Manchester. This report contains reporting on models for both Block A (The Tower) and Block B (The Street) buildings, for the same development.

The assessment has been undertaken using One Click LCA, in accordance with the RICS Whole Life Carbon Assessment for the Built Environment methodology and prepared in support of the carbon reduction objectives set out within the GMCA policies.

The proposed scheme comprises a 46-storey residential development delivering 436 apartments (Block A, The Tower) and a 9-storey residential development delivering 157 apartments (Block B, The Street Block).

The structural strategy for both blocks comprises piled foundations and reinforced concrete substructures. Block A comprises a reinforced concrete frame and core with an aluminium-framed glazed curtain wall façade, whilst Block B comprises a reinforced concrete flat slab frame with a brick-faced precast cladding façade system. This report focuses on both upfront embodied carbon (Modules A1-A5) as well as the Whole Life Carbon/Life Cycle Carbon (A1-C4) as is appropriate to the size of the development (see section 2.3)

- A1-A3: Product stage (material manufacture)
- A4: Transport to site
- A5: Construction/installation processes
- B1-B5: In-use stage
- C1-C4: End of life stage

Upfront and Life Cycle Embodied Carbon Results:

including 15% top-up factor, see section 7.0 for full breakdown

Upfront & Life Cycle Embodied Carbon (A1-C4)			
Block	**GIFA (m2)**	**Total kgco2e - (A1-C4)**	**Kgco2/m2 - (A1-C4)**
Block A (The Tower)	36,846	20,195,168.22	548.10
Block B (The Street Block)	16,825	9,130,11.16	542.65

Upfront Embodied Carbon (A1-A5)			
Block	**GIFA (m2)**	**Total kgco2e - (A1-A5)**	**Kgco2/m2 - (A1-A5)**
Block A (The Tower)	36,846	14,079,576.25	382.12
Block B (The Street Block)	16,825	6,597,344.44	392.12

- The embodied carbon intensity of Block A is 548.10 $kgCO_2e/m^2$, which is below the GMCA target of 600 $kgCO_2e/m^2$.
- The embodied carbon intensity of Block B is 542.65 $kgCO_2e/m^2$, which is below the GMCA target of 600 $kgCO_2e/m^2$.

Top Contributing Materials (highest upfront & life cycle embodied carbon emissions)

see section 4.1 for full breakdown

BLOCK A (The Tower)

Material 1: Ready-Mix Concrete (C50/60 50% GGBS)

Material 2: Reinforcement Steel (Rebar)

Material 3: Aluminium Framed Curtain Wall System

Block B (The Street Block)

Material 1: Ready-Mix Concrete (C50/60 50% GGBS)

Material 2: Reinforcement Steel (Rebar)

Material 3: Brick-faced precast cladding

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

Section 2.0 - Scope & Methodology

2.1 Methodological Framework

This assessment applies the RICS Whole Life Carbon Assessment for the Built Environment (2023). The assessment has been undertaken using One Click LCA software and covers the following life-cycle modules:

Scope Included:

- A1 – Raw material supply
- A2 – Transport of materials
- A3 – Manufacturing
- A4 – Transport to site
- A5 – Construction/installation stage
- B-stage emissions (use, maintenance, repair, replacement)
- C-stage emissions (end of life)

GMCA guidance requires Large Major Developments to report both upfront and life-cycle embodied carbon (A1-C4).

2.2 Data Sources

- Environmental Product Declarations (EPDs) where available
- OneClick LCA Generic Data Inputs
- Typical construction assemblies for high-rise & mid-rise apartments, respectively.
- Structural drawings (see appendix)
- Architectural drawings (see appendix)

2.3 – GMCA Reporting

For the purposes of assessing energy and carbon performance under the GMCA Submission Guidance (2025), this scheme is classified as a Large Major Development. The residential thresholds set out in the guidance define:

- Major Development: *10–149 homes*
- Large Major Development: *150+ homes*

Block A (The Tower) comprises of **436 residential dwellings** and Block B (The Street Blocks) comprises of **157 residential dwellings.** Both projects are placed within the Large Major Development category. Hence, upfront AND life cycle embodied carbon model has been reported. The results will also be reported against the ≤600kgco2e/m2 limit for flats.




Figure 1 – Submission Guidance for Places for Everyone policies JP-S2 and JP-S3, GMCA, March 2025 (pg. 14)

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

Section 3.0 – Block A (The Tower) Project Description

The development comprises 436 apartments, of which the entire development has been included in the modelling carried out within the OneClick LCA Software




Figure 2 – Proposed south elevation




Figure 3 – Proposed ground floor plan

Section 4.0 - Embodied Carbon Results (Cradle to Grave A1-C4) & Top Contributing Materials

4.1 – Upfront & Life Cycle Embodied Carbon Results

Upfront & Life Cycle Embodied Carbon (A1-C4)		
GIFA (m2)	**Total kgco2e - (A1-C4)**	**Kgco2/m2 - (A1-C4)**
36,846	20,195,168.22	548.10

Upfront Embodied Carbon (A1-A5)		
GIFA (m2)	**Total kgco2e - (A1-A5)**	**Kgco2/m2 - (A1-A5)**
36,846	14,079,576.25	382.12

The above calculations both include the 15% top up & 2% data uncertainty factor (see section 7.0)

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

4.2 – Top Contributing Materials – Block A (The Tower), One Castlefield, 436 apartments

Material 1: Ready-Mix Concrete (C50/60 50% GGBS)

- **165.06 kgco2e/m2** *(53.1% of total upfront embodied carbon A1-A3)*

Ready-mix concrete arises primarily from the reinforced concrete frame and substructure, including the piled foundations, raft foundation, core walls, columns, transfer elements and floor slabs. Concrete forms the principal structural material within the development and represents the largest contributor to embodied carbon due to the extensive use of reinforced concrete throughout the tower

Material 2: Reinforcement Steel (Rebar)

- **33.19 kgCO_2e/m²** *(10.7% of total upfront embodied carbon A1-A3)*

Reinforcement steel emissions arise from the reinforced concrete structural frame, including foundations, core walls, columns, beams and floor slabs. Reinforcement is required throughout the structure to provide tensile capacity and structural resilience, making it the second largest contributor to the upfront embodied carbon impact

Material 3: Aluminium Framed Curtain Wall System

- **17.26 kgCO_2e/m²** *(5.6% of total upfront embodied carbon A1-A3)*

Curtain wall emissions arise primarily from the aluminium framed glazed façade system, including double-glazed vision panels and associated framing components. The embodied carbon impact is driven by the use of aluminium framing and high-performance insulated glazing units, which form a significant proportion of the external envelope.

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk




Figure 4 – Pie chart showing global warming potential per resource type (OneClick LCA)

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk




Figure 5 – Bubble Chart showing the top-contributing materials to the One Castlefield – Block A (The Tower) development

Section 5.0 – Block B (The Street Block) Project Description

The development comprises 157 apartments, of which the entire development has been included in the modelling carried out within the OneClick LCA Software




Figure 6 – Proposed ground floor plan



Figure 7 – Proposed west elevation

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

Section 6.0 - Embodied Carbon Results (Cradle to Grave A1-C4) & Top Contributing Materials

6.1 – Upfront & Life Cycle Embodied Carbon Results

Upfront & Life Cycle Embodied Carbon (A1-C4)		
GIFA (m2)	**Total kgco2e - (A1-C4)**	**Kgco2/m2 - (A1-C4)**
16,825	9,130,111.16	542.65

Upfront Embodied Carbon (A1-A5)		
GIFA (m2)	**Total kgco2e - (A1-A5)**	**Kgco2/m2 - (A1-A5)**
16,825	6,597,344.44	392.12

The above calculations both include the 15% top up & 2% data uncertainty factor (see section 7.0)

6.2 - Top Contributing Materials – Block B (The Street Block) One Castlefield- 157 Apartments

Material 1: Ready-Mix Concrete (C50/60 50% GGBS)

- **169.57 kgco2e/m2** *(52.7% of upfront embodied carbon)*

Reinforced concrete is the primary embodied carbon contributor within the street block, driven by the piled foundations, structural frame, floor slabs and core walls. Despite the lower building height, the structural system remains material-intensive and accounts for the majority of upfront embodied carbon.

Material 2: Reinforcement Steel (Rebar)

- **34.18 kgCO_2e/m²** *(10.6% of upfront embodied carbon)*

Reinforcement steel is a key contributor due to its widespread use throughout the concrete frame. Steel reinforcement is required within the foundations, columns, slabs and cores to provide structural capacity and durability.

Material 3: Brick-faced precast cladding

- **31.03 kgCO_2e/m²** *(9.7% of total upfront embodied carbon)*

Brick-faced precast cladding is a significant contributor to embodied carbon due to the combination of concrete backing panels, brick finishes and associated manufacturing processes. As the predominant façade material, it represents a substantial proportion of the building envelope impact.




Figure 8 – Pie Chart showing the global warming potential per stage to the One Castlefield – Block B (The Street Block) development (OneClick LCA)

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk




Figure 9 – Bubble Chart showing the top-contributing materials to the One Castlefield – Block B (The Street Block) development (OneClick LCA)

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

Section 7.0 – Data assumptions, uncertainty & top-up factor

At the time of undertaking these assessments, detailed construction information and fully quantified schedules were not available. Material quantities and specifications have therefore been estimated based on concept design information, typical high-rise residential construction practices and mid-rise residential construction practices (respectively) as well as industry benchmark data within One Click LCA.

To reflect this level of early-stage uncertainty, the RICS-compliant uncertainty top-up factor of 15% for early design stage assumptions has been applied within the software. This ensures that the reported upfront and life cycle embodied carbon figure remains appropriately conservative and proportionate for a planning-stage submission.

As well as the top-up factor a 2% data uncertainty factor has been applied to the life cycle and upfront embodied carbon assessment to account for the conceptual stage of design development, assumptions regarding material specifications, and the use of generic datasets where project-specific information was unavailable.

Material quantities have been derived from the latest available architectural and structural drawings, with floor areas, façade extents, structural depths and internal layouts measured directly from drawings where detailed schedules were not available.

It is recommended that the assessment is updated at later design stages (RIBA Stage 4 and post-construction) once detailed structural calculations, coordinated services information and confirmed product specifications are available, to provide improved accuracy.

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

Section 8.0 - Conclusion & GMCA Compliance Statement

This report provides a complete assessment of upfront and life cycle embodied carbon (A1–C4) for the proposed developments at One Castlefield for both Block A (The Tower) and Block B (The Street Block) The report identifies the three materials with the highest embodied carbon contributions in full compliance with the **GMCA Submission Guidance (2025)** for both assessments.


The project is fully compliant with GMCA requirements for embodied carbon reporting, having:

- Reported A1–C4 (cradle to grave) embodied carbon using RICS 2023 methodology *(section 4.1 & 6.1)*
- Both Block A and Block B achieve embodied carbon intensities below the GMCA target of 600 $kgCO_2e/m^2$ GIFA for residential developments.
- Identified the top three contributing materials per development *(section 4.2 & 6.2)*


These assessments establish a clear baseline for embodied carbon performance at design stage and provide a solid foundation for future refinement as the projects progress.

1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

Appendix 1 – The Tower (Block A) Plans, Sections & Elevations, Structural Design




1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk




1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

COMPLETE SUSTAINABILITY SOLUTIONS ™



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk



General Notes:

PRT
REV
STATUS
S3
Work In Progress
DESCRIPTION
ISSUE
WIP S3-3 Drawings
DATE
04/09/2020
CHK
SL
APP
MM

DeSimone
Suite 3, Unit 8
Pioneer Industrial Park
Hebden Bridge
HX7 7BZ
+44(0) 16227 50070
info@desimone.com
www.desimone.com

CLIENT: Kirkbidalam 8 Limited


PROJECT: No. 1 Castlefield

DRAWING TITLE: Level 02 to 04


PROJECT No.: 250288
DRAWN BY: SL
CHECKED BY: MM
DRAWING No.: 001020
APPROVED BY: MM
DATE: 04/09/20
SCALE: As indicated
REVISION: P01
NTC-DCE-BA-ZZ-DS-0001020

© 2020 DESIMONE CONSULTING ENGINEERS LTD


1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk




1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk




1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk




1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk


1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

COMPLETE SUSTAINABILITY SOLUTIONS ™

Appendix 2 – Block B (The Street Block) Plans, Sections & Elevations, Structural Design



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk


COMPLETE SUSTAINABILITY SOLUTIONS ™

COMPLETE SUSTAINABILITY SOLUTIONS TM

FACADE MATERIALS

1 RED / ORANGE STOCK BRICKWORK
2 FULL HEIGHT CLEAR VISION GLAZING
3 ANODISED ALUMINIUM PERFORATED PANEL - COLOUR: RED COPPER FINISH
4 ANODISED ALUMINIUM METAL PANEL - COLOUR: RED COPPER FINISH
5 ANODISED ALUMINIUM METAL PANEL - COLOUR: BLACK
6 ANODISED ALUMINIUM LOUVRE - COLOUR BLACK
7 ANODISED ALUMINIUM EXPRESSED FINS - COLOUR: BLACK
8 METAL STANDING SEAM ROOF - COLOUR: BLACK
9 LOUVRED METAL DOOR - COLOUR: BLACK
10 GLAZED METAL DOOR - COLOUR: BLACK
11 METAL RAILING - COLOUR: BLACK PPC FINISH
12 ANODISED ALUMINIUM DECORATIVE PERFORATED METAL PANELLING - COLOUR: BLACK
13 METAL DOOR WITH GLAZED VISION PANEL - COLOUR: RED COPPER FINISH
14 ENTRANCE CANOPY
15 FULL HEIGHT GLAZED CURTAIN WALLING
16 FULL HEIGHT GLAZED REVOLVING DOOR

KEY PLAN



BLOCK B NORTH ELEVATION- REFER TO:
N1C-DCM-BBE-E-EL-A-50054



1 BLOCK B - COURTYARD - WEST ELEVATION
ELEVATION 1 : 100

2 BLOCK B - COURTYARD - EAST ELEVATION
ELEVATION 1 : 100

No	Date	Dwn	Chk	App	Revision or reason for issue
P01.01	30.10.25	MM	GS	GS	Rev1Issue
P01.02	12.02.26	AF	GS	GS	Draft Issue for Comment
P01.03	25.02.26	NM	GS	GS	ISSUED FOR PLANNING

General Notes
Do not scale from drawing. Use marked dimensions.
To be read in conjunction with all other Consultant's drawings.
The Architect to be immediately notified of any discrepancies.
Copyright on this drawing retained by the Architect.

DRAFT

Client: KIRINDOLAM 8 LIMITED

DENTON CORKER MARSHALL

Architect
Denton Corker Marshall LLP
Level 3, 1 Bartholomew Lane, London, EC2N 2AX
Old Exchange, 6 St. Ann's Passage, Manchester, M2 4WH
Telephone +44 (0)20 7553 2020 / +44 (0)161 834 3011
Email mail@dentoncorkermarshall.co.uk

Project Title: NO. 1 CASTLEFIELD


Scale / North Point
1:100 @ A1
1:200 @ A3
0 1 2 3 5M

Drawing Title: BLOCK B (STREET BLOCK) EAST & WEST (COURTYARD) GA ELEVATION

Drawing Number: N1C-DCM-BBZ-ZZ-EL-A-50053


Drawing Purpose: PLANNING
CDE Status / Revision: S0 P01.03

COMPLETE SUSTAINABILITY SOLUTIONS TM
1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk




1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

COMPLETE SUSTAINABILITY SOLUTIONS ™



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk

BLOCK B LEVEL 01
1 : 100
General Notes:
COLUMN SCHEDULE
REF
SIZE (mm)
WIDTH W
DEPTH D
MATERIAL GRADE
C1
C4
C5
400
500
250
600
1000
500
C50/60
C50/60
C50/60
VERTICAL B.E.B. (RC) CONCRETE GRADE
= C40/50
= C50/60
BLOCK B
BLOCK A
DeSimone
Work in Progress
S3
WIP-04 Drawings
Kirkbolam B Limited
No. 1 Castlefield
Block B Level 01
250288
001010
P01
NTC-DCE-BB-01-D-S-001010
1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk



1 Balloon Street
Manchester
M2 4NH
office@completesustainability.co.uk