OUR TOWN HALL PROJECT

Document Name: Condensate Pump Schedule

Document Ref: OTH-HAK-TH-ZZ-SCH-V-0003

Status: S4 – Suitable for Construction

Document Type: Schedules

Revision History:

REV.	DATE	DESCRIPTION OF CHANGE
P01	23/08/2019	Issue For Comment
P02	30/08/2019	Issue For Tender
P03	21/02/2023	Issued For Construction

Condensate Pump Schedule

Project :	**Manchester Town Hall Catering Works**	Project No :	**50801**	Schedule Ref :	**OTH-HAK-TH-ZZ-SCH-V-0003**
		Area Served :	**Multiple Level**	Purpose of Issue :	**Suitable for Construction**
		Issue Date :	**21 February 2023**	Revision :	**P03**

Pump Details		
Manufacturer		Apen Pumps or Equal and Approved
Model		Hi-Lift 1L & 2L
Quanity		7
Pump References		CP-01 to CP-07
Max. Flow		11 L/h @ 0 Head
Max. Head		12 m
Tank Capacity		1L & 2L
Sound Level @ 1m		51dB(A)
Rated		Continuously
Max. Water Temperature		40°C
Inlet/Outlet		x3 25mm in, 6mm out
IP Protection		IP20
Safety Switch		3.0A Normally Closed
Thermal Protection		Yes
Power Supply		230 VAC, 0.4A, 50/60Hz

General Specification

- Key Features:
  - High Head
  - Easy Fit & Maintenance
  - Easy Access Clean Tray
  - Built in Spirit Level
- Suitability:

Ducted unit; FIlor Standing & Chassis Units; Cassette Units; Refrigerated Units / Cold Store

Revision	Revision Notes	Revision Date
P01	Tender - For Comment	23 August 2019
P02	Issue For Tender	30 August 2019
P03	Suitable for Construction	21 February 2023